

# Adeptia Suite 5.1

# **Developer Guide**

Release Date September 1, 2010

Adeptia Inc. 443 North Clark Ave, Suite 350 Chicago, IL 60654, USA



## Copyright

Copyright © 2000-2010 Adeptia, Inc. All rights reserved.

## **Trademarks**

The Adeptia<sup>TM</sup> is a trademark of Adeptia, Inc.

### **Statement of Conditions**

Adeptia, Inc. provides this publication "as is" without warranty of any kind, either express or implied. In no event shall Adeptia be liable for any loss of profits, loss of business, loss of use or data, interruption of business, or for indirect, special, punitive, incidental, or consequential damages of any kind.

No part of this work covered by copyright herein may be reproduced in any form or by any means—graphic, electronic or mechanical—including photocopying, recording, taping, or storage in an information retrieval system, without prior written permission of the copyright owner.

This publication is subject to replacement by a later edition. To determine if a later edition exists, contact <u>www.adeptia.com.</u>

### **Document Conventions**

Convention	Description				
Text Matter in font Verdana and font size 9 point.	Explains the installation guide.				
Text matter	Click on link to reach target.				
Ø	Note:				

### Abbreviations Used

Abbreviation	Description
WebDAV	Web-based Distributed Authoring and Versioning



## **Contact Information**

In case of any queries, please contact us at:

Contact For	Email ID				
Sales	sales@adeptia.com				
Support	support@adeptia.com				

For latest updates and information, please visit us at <u>www.adeptia.com</u> .

# **Table of Contents**

1	ABOUT THIS GUIDE TARGET AUDIENCE	
2 3	DESIGNING WEB FORMS	
3	CREATING A WEB FORM	
	Creating Web Form Using Template	
	Creating Web Form Manually	
	Integrating Custom Web Application in Human WorkFlow	
	Creating Web Form Using Rich Form	
	Activating a Web Form	
4	DESIGNING WORKFLOW TASK	
	EXECUTING HUMAN WORKFLOW TASK	
5	CREATING DATA DICTIONARY Creating Positional Data Dictionary	
	Creating EDI Data Dictionary	50
6	CREATING SOURCE ACTIVITY	
	CREATING ADVANCED DATABASE SOURCE ACTIVITY	
	CREATING DATABASE SOURCE ACTIVITY	
	CREATING FILE SOURCE ACTIVITY	
	CREATING FTP SOURCE ACTIVITY	60
	CREATING HTTP SOURCE ACTIVITY	
	CREATING JMS SOURCE ACTIVITY	
	CREATING LAN FILE SOURCE ACTIVITY	
	Creating Mail Source Activity	71
	CREATING WEBDAV SOURCE ACTIVITY	74
7	CREATING SCHEMA ACTIVITY	
	CREATING ADVANCE DATABASE SCHEMA ACTIVITY	
	Special Usage Scenario	
	Delete Records from target table	
	Enable RollBackOn Error Attribute	
	CREATING ADVANCE POSITIONAL SCHEMA ACTIVITY	
	Viewing Print-Friendly Page	
	Special Usage Scenario	
	Enable IsRemoveHeader Attribute	
	CREATING ADVANCE TEXT SCHEMA ACTIVITY	
	CREATING DATABASE SCHEMA ACTIVITY	
	Special Usage Scenario	
	Delete Target Records	
	CREATING EDI SCHEMA ACTIVITY	121
	Manipulating EDI Schema Hierarchy	
	Creating Excel Schema Activity	



	CREATING POSITIONAL SCHEMA ACTIVITY	143
	CREATING TEXT SCHEMA ACTIVITY	148
	CREATING WORD SCHEMA ACTIVITY	152
	CREATING XML SCHEMA ACTIVITY	155
	Testing Schema Activity	158
	CREATING XML VALIDATOR ACTIVITY	
8	CREATING TARGET ACTIVITY	
	CREATING ADVANCED DATABASE TARGET ACTIVITY	
	Understanding Record Count in Process Flow Logs	
	CREATING DATABASE TARGET ACTIVITY	
	CREATING FILE TARGET ACTIVITY	
	CREATING FTP TARGET ACTIVITY	
	CREATING HTTP TARGET ACTIVITY	
	CREATING JMS TARGET ACTIVITY	
	CREATING LAN FILE TARGET ACTIVITY	
	Creating Mail Target Activity	
	CREATING WEBDAV TARGET ACTIVITY	
9	CREATING WEB SERVICES	
	CREATING SECURITY POLICY ACTIVITY FOR WEB SERVICES	
	CREATING WEB SERVICE CONSUMER ACTIVITY	
	Creating Web Services Consumer Activity using UDDI	
	Creating Web Services Consumer Activity using URI	
	Using Web Service Addressing	
	CREATING WEB SERVICE PROVIDER ACTIVITY	
10		
	Accessing Data Mapper	
	Understanding Data Mapper Applet	
	Mapping Elements	
	Load Source and Target Schemas	
	Search Element in Source or Target Schema Tree	
	Map Source and Target Elements	
	Map Elements Using Drag and Drop Approach	
	Map Elements using Buttons on the Tool Bar	
	Using Custom Auto Map Options	
	Using Add Value Map Options	
	Copy/Paste Mapping	
	Mapping Functions	
	Save Mapping and Exit Data Mapper	
	View and Validate Generated Mapping XSL	
	View Mapping XML	
	View and Validate Mapping Output	



Using Data Viewer	258
Viewing Mapping in PDF format	264
View Mapping in Read-Only Mode	266
Splitting Source Data	268
Set Splitter XPath	270
Enabling Quick Splitting	272
Set Merger XPath	274
Assign Data Streams	275
Remove Mapping of an Element	277
Using Context Schema	278
Create Context Schema Definition	278
Load Context Variable	281
Map Schema Elements	281
Modify Streaming Properties of Mapping Activity	282
Using Mapping Functions	283
Adding a Constant	283
Using Math Function	284
Using String Function	287
Using Date Function	291
Using Aggregation Functions	294
Using Conditional Function	297
Using Axis Function	307
Using Boolean Function	310
Using Context Functions	311
Using DB Function	320
Using Textual Rules	324
Using Namespace	326
Adding Namespace	326
Editing Namespace	327
Using XSL Template	328
Add XSL Template	328
Map Elements using XSL Template	331
Using Global Variable	333
Using Local Variable	339
Using Custom Methods	344
Dynamically Loading Custom Methods	349
Using Key Function	352
Usage Scenario	353
Creating a Key	353
Mapping the Key with Target Element	356
Declaring Connection Info Variable	358
Setting Target Element Properties	360
Setting For Each Property	362



	Adding Comments to Target Schema Elements	
	Setting Sorting Rules	
	Filtering of Elements/Attributes in Target Data	
	Using Apply Filter Checkbox	
	Creating Clone of Target Element	
	Removing Clone of Target Element	
	Removing Schema	
	Adding Custom XSL	
	Select Root	
	Adding Namespace Prefix	
	Populating extension type element	
	USING RECORD TO RECORD SERVICE	
11	CREATING EXTENSIONS	
	CREATING CUSTOM PLUGIN	
	CREATING NATIVE CALL ACTIVITY	
12	CREATING POLLING SERVICE ACTIVITY	
	CREATING DATABASE POLLING ACTIVITY	
	CREATING FILE POLLING ACTIVITY	
	CREATING FTP POLLING ACTIVITY	
	CREATING MAIL POLLING ACTIVITY	
13	CREATING DATABASE CONNECTORS	
	CREATING DATABASE DRIVER	
	CREATING DATABASE INFO.	
	Using MLLP	
	Configuring MLLP Server	
	Configuring MLLP Client	
	Activating MLLP Activity	
14	MISCELLANEOUS	
14	CREATING CONTEXT DOWNLOAD ACTIVITY	
	CREATING CONTEXT UPLOAD ACTIVITY	
	Creating Stored Procedure	
	CREATING NOTIFICATION ACTIVITY	
	Creating Mail Notification Activity	
	Creating Notification to Send User Defined Message	
	Creating Notification to Send Process Flow Summary	
15	USING REPORTS & DASHBOARD	
-	CREATING CUSTOM REPORT	
	CREATING DASHBOARD COMPONENT ACTIVITY	
	Creating Bar Chart Activity	
	Creating String Chart Activity	
	Creating Table Chart Activity	
	Creating PIE Chart Activity	
	CREATING DASHBOARD DESIGN ACTIVITY	



	Executing DashBoard Design	460
16	MANAGING ACTIVITIES	462
	Searching an Activity	462
	Using Wild Cards in Search	463
	VIEWING ACTIVITY PROPERTIES	464
	Editing an Activity	465
	Deleting an Activity	467
	VIEWING REVISION HISTORY	468
	VIEWING DEPENDENT ACTIVITIES	468
	Changing Advanced Properties	470
17	WORKING WITH PROCESS FLOW	472
	Understanding Process Designer	474
	Creating Process Flow	483
	Designing Process Flow using BPMN Graphical Elements	483
	Attaching Adeptia Server activities with the BPMN elements	490
	Save Process Flow on Local Hard Disk	494
	Changing Transformer Type	495
	Activating/De-activating Process Flow	496
	Testing a Process Flow	497
	UNDERSTANDING VALIDATION	499
	Disabling Validation	500
	Using Undo Redo	502
	USING MULTIPLE SELECTIONS	502
	USING ZOOM IN AND ZOOM OUT	503
	USING ACTIONS IN PROCESS FLOW	504
	CREATING PROCESS FLOW VARIABLE	510
	CREATING CONTEXT VARIABLE	512
	USING CONTEXT SOURCE AND CONTEXT TARGET	517
	Overriding Process Flow Description at Runtime	519
	OVERRIDING ACTIVITY OF A PROCESS FLOW AT RUNTIME	520
	Overriding an activity using Custom Plugin	521
	Overriding an activity using put-context-var	522
	Activities that can be overridden	524
	Source Activity	524
	Target Activity	525
	Schema Activity	525
	Polling Activity	526
	Other Activities	526
	Overriding subject and body of email sent for a Human Workflow Tasi	k 527
	Overriding Assignee User of a Human Workflow Task	528
	Processing Record Queue	529
	Adding Conditions in Process Flow	534
	Process Flow Variable Condition	534



	Adding Condition Using Process Flow Activity Attributes	534
	Adding Condition Using Process Flow Variable Other Condition	537
	Java Condition	538
	Adding Condition Using Java Condition	539
	Expression Condition Builder	540
	Adding Condition Using Expression Builder	540
	DEFINING SEQUENCE FLOW ORDERING	546
	CREATING MULTIPLE STREAMS	547
	USING STREAM SELECTOR	554
	Using Repeater Node	555
	Using Error Intermediate Event	558
	CREATING EXCEPTION HANDLER SCRIPT	559
	Creating Global Exception Handler Script	560
	Creating Activity Exception Handler Script	561
	USING COMPRESSION/DECOMPRESSION	562
	USING CUSTOM REPORT IN PROCESS FLOW	563
	ATTACHING END PROCESS (MAIL NOTIFICATION) TO PROCESS FLOW	564
	GENERATING PDF FILE OF PROCESS FLOW	565
	Working with Process Designer in Offline and Online Modes	567
	Executing a Process Flow	569
	Executing a Process Flow Manually	569
	Executing a Process Flow Automatically	570
	USAGE RECOMMENDATION	571
18	CREATING TRIGGER AND EVENTS	573
	Creating Calendar Event	
	Creating Database Event	575
	CREATING EVENT REGISTRY	580
	Creating File Event	582
	CREATING FTP EVENT	586
	CREATING HTTP TRIGGER	
	Usage Recommendation	
	CREATING JMS EVENT	593
	Creating Mail Event	596
	Creating Timer Event	600
	TRIGGERING PROCESS FLOW USING WEB SERVICE TRIGGER	602
	Activating Trigger Events	604
	TRIGGERING PROCESS FLOWS IN SEQUENCE	604
19	RECOVERY	
	RECOVERABLE PROCESS FLOWS	
	Enabling Implicit Recovery	
	Using Checkpoints	
	Using Human Workflow Activity	
	How Recovery Works	607



	ENABLING RECOVERY	
20	ABOUT ADEPTIA INC	608
	TABLE OF FIGURES	
22	TABLE OF TABLES	621

# **1** ABOUT THIS GUIDE

This document covers a detailed description of all activities and services of Adeptia Suite that are available to a developer. It acts as a guideline to use these services seamlessly and use them in a design environment using Adeptia Suite.

A developer also has access to the other features of the Adeptia Suite. For details, refer to the Business User Guide, Process Modeling and Simulation Guide and Administrator Guide.

#### Pre-Requisite:

• It is important to read the *Getting Started* guide before reading this guide.

This document is divided into the following sections:

- Forms
  - Designing Web Forms
- Workflow
  - Designing Workflow Task
- Services
  - Creating Data Dictionary
  - Creating Source Activity
  - Creating Schema Activity
  - Creating Target Activity
  - Creating Web Services Activity
  - Creating Data Transformation Activities
  - Creating Extensions
  - Creating Native Service Activity
  - Creating Notification Activity
  - Creating Polling Activity
  - Creating Database Connectors
  - Creating Miscellaneous Activities
- Reports and Dashboards
  - Creating Custom Report
  - Creating Dashboard Component
  - Creating Dashboard Design



Process Flow

- Working with a Process Flow
- Events and Triggers
  - Creating Calendar Event
  - Creating Database Event
  - Creating Event Registry
  - Creating File Event
  - Creating FTP Event
  - Creating HTTP Trigger
  - Creating JMS Event
  - Creating Mail Event
  - Creating Timer Event
  - Creating Web Service Trigger



# **2** TARGET AUDIENCE

Even though all these features are available to all users, they are primarily performed by a developer. Thus, this document is intended for developers. They can use these details to seamlessly perform all design features of Adeptia Suite.



# FORMS



# **3** DESIGNING WEB FORMS

Web forms can be used for two purposes in Adeptia Suite. It can be used in the Workflow task or as a form, which is added as a link in the Workspace Menu.

You can create web forms and trigger process flows or customize using the web forms. Adeptia Suite also allows you to integrate a custom application into the Adeptia Suite using its graphical user interface. You can upload any custom JSP or HTML file, written to serve a specific purpose. This feature facilitates smooth management of multiple JSPs and HTML files, saves time and allows seamless integration into the Adeptia Suite.

In the Adeptia Suite this feature is available in:

BPM Suite	Integration Suite	ETL Suite
$\checkmark$		

This chapter describes the following tasks:

- <u>Creating a Web Form</u>
- Activating a Web Form

# **CREATING A WEB FORM**

A web form can be created in three ways:

- Using Template
- Entering HTML Code manually
- Using Rich Form

#### Steps to create web form

- 1. In the Adeptia Suite homepage menu, click **[+]** Configure to expand the tree. All the items in the Configure category are displayed.
- 2. Click **[+]** Forms to expand the tree and then click **Web** Forms. The Manage Web Forms screen is displayed (see Figure 3.1).



This feature is visible to only those users who have *Write* and *Execute* permissions.



[+]	My Tasks Configure > Forms > Web Forms									
[+]	My Documents									
[+]	My Solutions	Ne	New   Edit   Delete   Revisions   Dependencies							Search
[+]	My Monitor									
[+]	History	Act	tivate	e						
		#		())	Name	Des	cription	Owner	Perm.	Modified 🔻
[+]	Design	1	0	103	ApprovePurchaseRequisition	approval form for requisit	tion	demouser	RWX	08/08/09 16:36
[-]	Configure	2	0	-02	CorrectPurchaseRequisition	make corrections to the	requisition	demouser	RWX	08/08/09 15:51
	[-] Forms	3	0	165	ReviewPurchaseRequisition	supervisor review form		demouser	BWX	08/08/09 15:39
	ee Web Forms		~	100			and an all and a second states			
	[+] WorkFlow	4	~	0		Form that allows user to	send purchase requisition	demouser	RWX	08/08/09 15:26
	[+] Services	5	$\circ$	-02	InventoryCorrectionForm	correct inventory data		demouser	RWX	08/08/09 10:36
	[+] Reports & Dashboards									
[+]	Deploy									
[+]	Administer									
• •										

Figure 3.1: Manage Web Forms

3. Click the **New** link. The Create Web Forms screen is displayed (see Figure 3.2).

Configure > Forms > Web Forms	
[-] Standard properties	
Name *	
Description *	
Application Type *	Form
Form Type	Template Create Form
Add as Link	
MajorLevel Category Name	My Solutions
MinorLevel Category Name	
Link Name	
Action	
Trigger Process	Select Process Flow
Customize	Add/Remove File(s)
[+] Advanced properties * Mandatory fields. Save Cancel	

Figure 3.2: Create Web Form

- 4. Enter the name and description of the web form in the *Name* and *Description* fields respectively.
- 5. Select *Form* from the *Application Type* drop-down list. By default, *Form* is selected.

6. Select the method to create the form from the *Form Type* drop-down list. The methods used to create forms are described in the table below.

Form Type	Description
Template	When Template is selected, a <i>Form template</i> opens, where you can define the form.
Manual	When <i>Manual</i> is selected, you need to write complete HTML code for the form manually.
Rich Form	When <i>Rich Form</i> is selected, you can create and design a rich web form using the <i>Frevvo</i> tool.

Table 3.1: Form Types

- 7. To design the form using a template, select *Template* from the *Form Type* drop-down list. For details, refer to the Creating Web Form Using Template section.
- 8. To design the form manually, select *Manual* from the *Form Type* drop-down list. For details, refer to the Creating Web Form Manually section.
- 9. To design the form using a rich form, select *Rich Form* from the *Form Type* drop-down list. For details, refer to the Creating Web Form Using Rich Form section.
- 10. Click **Create Form** button. This displays the selected design form screen. Create the form as desired.
- 11. Select the *Add as Link* checkbox, if you want the custom form to appear as a link in the Workspace Menu.
- 12. Enter the major category name under which the link would appear in the Workspace Menu, in the *MajorLevel Category Name* field. By default, the link appears in **My Solutions** menu in the Workspace Menu. Thus, the major category name is already entered as My Solutions. You can edit it if required. However, if you edit this and enter another MajorLevel category Name (for example, *Customer*), then **Customer** appears as a link at the bottom of the Workspace Menu. The link is added in a hierarchical format. First the MajorLevel Category Name link is displayed. Under this, the MinorLevel Category Name is displayed, and under that is displayed the link name. The web form is uploaded under this link.
- 13. Enter the minor category name to in the *MinorLevel Category Name* field. For example, if you enter Insurance Policy in this field, it will be considered as a *MinorLevel Category Name*.
- 14. Enter the name of the link in the *Link Name* field. For example, you can enter the link name as *Claim Insurance Policy Form*. Under this link, you can upload the claim insurance form. Thus, the hierarchy for the above example will appear as *My Solutions -> Insurance Policy ->Claim Insurance Policy Form*, or *Customer ->Insurance Policy ->Claim Insurance Policy Form*.
- 15. Once you select the *Add as Link* option, the *Action* fields get activated. You can set an action once this web form is executed. You can either trigger a process flow or by uploading custom jsp files. To trigger a process flow, select the *Trigger Process* radio button and select the process flow that you want to trigger, from the drop-down list.



- 16. Alternately, to upload custom jsp files, select the *Customize* radio button.
- 17. Click **Add/Remove File(s)** button to upload the custom JSPs, HTMLs and support files. This displays the Add/Remove Files screen (see Figure 3.3).

Add/Remove	Files - Windows Internet Explorer	
		A
Choose File(s)	;)	
Click on Browse	outton to choose the file.	
Browse File	Browse	Add File
Select All   Ren	10ve File(s)	
Cust.html		
2 Click on Finis	sh button to complete the process.	
Finish		

Figure 3.3: Add/Remove Files

- 18. Click **Browse** button to select the file to be uploaded. Once it is selected, it appears in the *Browse File* field.
- 19. Click **Add File** button to add the selected file. This displays the file with a checkbox. Similarly, you can add multiple files to be uploaded (see Figure 3.4).

🖉 Add/Remove Files - Windows Internet Explorer	
	*
Choose File(s)	
Click on Browse button to choose the file.	
Browse File Browse Add File	
Select All   Remove File(s)	
Click on Finish button to complete the process.	
Finish	

Figure 3.4: Added File(s)

There is no limit to the number of files that you can upload into the Adeptia Suite.

- 20. To remove the uploaded file, mark the checkboxes of the files that you want to remove and click **Remove Files** link. To select all files, click **Select All**.
- 21. Click **Finish** button. This closes the Add/Remove Files screen and displays the selected files in the *Customize* field (see Figure 3.5).



Configure > Forms > Web Form	15
[-] Standard properties	
Name *	Customer
Description *	Customer
Application Type *	Form
Form Type	Template  Create Form
Add as Link	
MajorLevel Category Name	My Solutions
MinorLevel Category Name	Insurance Policy
Link Name	Claim Insurance Policy Form
Action	
C Trigger Process	Select Process Flow
Customize	Custm.html Select Main File 💌 Add/Remove File(s)
[+] Advanced properties	
* Mandatory fields.	
Save Cancel	

Figure 3.5: Uploaded File(s)



Ø	You can upload only JSP and HTML files and all their supported classes and jar files using this feature.
	Once the files are uploaded, if an error occurs due to the connection being disconnected, then the system displays an error message. When you upload the files, a folder is created with name as specified in <i>Link Name</i> field, in the//AdeptiaServer/AdeptiaServer-4.9/ServerKernel/web/custom folder and the uploaded file are copied into this directory. If your application is referring to any JS, CSS or image file, you need to mention the path of these files relative to custom folder. Following is the sample HTML file.
	<html> <title> Adeptia BPM Server </title> <script <br="" type="text/javascript">src="Custom/ErrorReports/calendar.js"></script> <body> <h1> Hi! </h1> <img src="Custom/ErrorReports/nature2.jpg"/> </body> </html>
	Here ErrorReports is the name of the link.

- 22. All the uploaded files are displayed in the *Main File* drop-down list. Select the file that you want to select as the main file from this list.
- 23. Click the **Save** button. A screen is displayed confirming that the web form has been created successfully. If the comments property is enabled, then clicking Save will display a screen where you need to enter comments related to creating the web form (see Figure 3.6).

Explorer User Prompt	×
Script Prompt: Add Comments	OK Cancel

#### Figure 3.6: Enter Comments

24. Enter the comments in the Add Comments field.



The comment should be at least 1 character in length.

25. Click **OK** to save the comments. This displays a screen confirming that the web form has been created successfully.



Ø
---

Ø

By default, the *Comments* property is disabled. To enable it, refer to the *Updating System Properties* section in *Administrator Guide*.

You can create a Custom Application too from the Create Web Form screen. Select *Custom* from the *Application Type* drop-down list in the Create Web Form screen. This deactivates the *Form Type* field and the *Trigger Process* option. Enter the details as required and upload the custom jsp files.

#### **Creating Web Form Using Template**

#### Steps to create web form using Template

- 1. Select *Template* from the *Form Type* drop-down list in the Create Web Form screen.
- 2. Click **Create Form** button. This displays the Design Form using Template screen (see Figure 3.7).

Design Form			
Define Header			
	Define FormHeader		
	Define Form		
Define LeftBar			Define RightBar
	1		
	Define FormFooter		
Define Footer			
Form Properties			
	Name	Value	
Open in New Window			
Cancel Preview	Submit		



Figure 3.7: Design Form using Template

3. To define header, click **Define Header** button. The following screen is displayed (see Figure 3.8).

		Html Area		
Add/Manage Image				X
Available Images :	No Image Available 💌			Add Image
Upload New Image :		Browse		Upload Image
Format				
Header/Paragraph:	Header One	Add	Add Font	
Add File Download/Upload				

- 4. To add an image into header, select the image from *Available Images* dropdown list and click **Add Image** button.
- 5. To upload any new image in the list of Available Images, browse the required image and click **Upload Image** button. The selected image is added to the *Available Images* list.
- 6. Select header type from *Header/Paragraph* drop-down list and click **Add** button. Tags for selected header are added into HTML area. Enter the required text between the header tags.
- 7. To change the fonts of the text, click **Add Font** button and select the required font and color.
- 8. To add link for File Download/Upload option, click Add File Download/Upload button.
- 9. Click Submit button to return to Design Form using Template screen.
- 10. Repeat step 3 to 8 to design other portion (except Form) of the web form.
- 11. To define the form, click **Define Form** button. The Define Form screen is displayed (see Figure 3.9).

Figure 3.8: Define Header







Figure 3.9: Define Form

- 12. Enter the name of the variable header in the Variable Header field.
- 13. Enter the name of the variable, which will be displayed in the HTML page, in the *Display Name* field.
- 14. Enter the name of the variable, corresponding to Display Name in the *Variable Name* field.
- 15. Select the type of the field from the *Type* drop-down list.
- 16. Select the property of the field whether Read Only or Editable from the *Property* drop-down list.
- 17. Enter the tokenizer (e.g. comma) in the *Tokenizer* field.

Workflow task will give an error.

- 18. Enter the possible values of the field separated by the tokenizer character in the *Values* field.
- 19. Check the *Mandatory* checkbox against the field that you want to define as mandatory entry field.



20. After defining variables for all required field, click **Submi**t button to return to the Design Form using Template screen.



Click **Preview** button to view a preview of the new HTML template, before submitting it.



By default, the new web form opens in the workspace area. To open it in a new screen, select the *Open in New Window* checkbox in the *Form Properties* section of the Design Form using Template screen.

21. Once you have created the template, click **Submit** button. This returns control to the Create Web Form screen.

### **Creating Web Form Manually**

#### Steps to create web form manually

- 1. Select *Manual* from the *Form Type* drop-down list in the Create Web Form screen.
- 2. Click **Create Form** button. This displays the Design Form manually screen (see Figure 3.10).

HTML Code	Design Form	
	HTML Code	

Figure 3.10: Design Form Manually

3. Enter the HTML code in *HTML Code* field to design the form. Sample HTML code which is used to design a form is displayed below (see Figure 3.11).

```
<TABLE height="90%" cellSpacing=0 cellPadding=0 width="100%" border=0>
<TBODY>
<TR height="15%">
```



```
<TD colSpan=3>
   <H1 align=center><FONT face="Times New Roman" color=brown
size=8>Adeptia
   BPM Server</FONT></H1></TD></TR>
 <TR height="70%">
  <TD width="15%">
     </TD>
  <TD width="70%">
   <TABLE height="100%" width="100%" border=0>
     <TBODY>
     <TR height=10>
      <TD>
       <H1 align=center><FONT face="Times New Roman" color=brown
       size=6>Employee Management Form </FONT></H1></TD></TR>
     <TR height=80>
      <TD>
       <FORM name=HTMLForm>
       <TABLE>
        <TBODY>
        <TR>
         <TD>Employee Id</TD>
         <TD><BR><INPUT name=Employeeid type=text></TD></TR>
        <TR>
         <TD>Employee Address</TD>
         <TD><BR><INPUT name=Employeeaddress type=text ></TD></TR>
        <TR>
         <TD>Employee Work Experience</TD>
         <TD><BR><SELECT name=Workexperience><OPTION value=1
           selected>One</OPTION><OPTION value=2>Two</OPTION><OPTION
           value=3>Three</OPTION><OPTION
        value=4>Four</OPTION></SELECT></TD></TR>
        <TR>
         <TD>Are these details are fine?</TD>
         <TD><BR><INPUT type=radio value=Yes
          name=Checkdetails>Yes<INPUT type=radio value=No
          name=Checkdetails>No</TD></TR>
        <TR>
         <TD colSpan=2><INPUT type=submit value="Save Task"
name=partialSubmit>
<INPUT type=submit value="Complete Task"
name=fullSubmit></TD></TR></TBODY></TABLE></FORM></TD></TR>
     <TR height=10>
      <TD>
       <H1 align=center><FONT face="Times New Roman" color=brown
       size=4>Press Save Task button to save this form </FONT>
       <H1 align=center><FONT face="Times New Roman" color=brown
       size=4>Press Complete Task button to complete this form
       </FONT>
```



Figure 3.11: Sample HTML Code

Ø	<i>Tips:</i> While creating a form, certain points need to be considered:
	<ul> <li>User must specify HTML Form Name.</li> </ul>
	<ul> <li>User must specify only one Complete Task button. There should not be any other action i.e. Cancel or Back etc.</li> </ul>
	<ul> <li>User can also specify Save Task button. Save button is used when user wants to save the partial completed task.</li> </ul>
	<ul> <li>User must specify <i>fullsubmit</i> and <i>partialsubmit</i> variable for Complete Task and Save Task button respectively.</li> </ul>
	<ul> <li>There could be any number of radio buttons.</li> </ul>
	<ul> <li>Variable defined in the HTML Code is automatically gets created in the Process flow.</li> </ul>

4. Once you have entered the HTML code, click **Submit** button. This returns control to the Create Web Form screen.

When writing the HTML code, at times some business scenarios cannot be addressed by simple HTML code. To implement these scenarios, you need more dynamic behavior of Human Workflow web pages and interaction with server end to get the required information. The Adeptia Suite allows you to integrate the custom web application that you have created using JSP or AJAX.

#### Integrating Custom Web Application in Human WorkFlow

To integrate the custom web application, you need to take care of the following points:

• While writing HTML code for a Workflow activity, you need to define a hidden variable named PID using following code:


<input Type=hidden name=PID readOnly>

This variable is used to pass the *Process Flow ID* (unique value generated for each execution of Process Flow) to the custom web application, which you have created.

 Create a hyperlink to call your custom web application and the corresponding Java script. The sample code (see Figure 3.12) creates a "Review" link in the Workflow page. Clicking the "Review" link calls the "review" function.

```
<a href='javascript:review();'>
<font color=blue>Review</font></a>
```

```
<script>
function review()
{
var pid=document.HTMLForm.PID.value;
var vWinTrans=window.open("custom/Review.jsp?PID="+pid
,"_blank","toolbar=yes,location=no,directories=no,status=no,menubar=
yes,scrollbars=yes,resizable=yes,copyhistory=no");
}
</script>
```



In the above mentioned code, *Review.jsp* is the custom jsp, which is called when you click the "Review" link in the Workflow page.

 In the custom web application, add the following code to access the value of Process Flow ID.

string pid=request.getParameter("PID");

• To create instance of class transactioninformation add the following code.

TransactionInformation ti=new TransactionInformation(request,session);

- A custom web application allows you to perform any kind of operation that is required. In addition, you can use Adeptia API to perform operations like logging information in process flow log, viewing variables, service objects etc. For Adeptia API documentation contact support@adeptia.com.
- Create a subfolder "custom" in ../../AdeptiaServer/AdeptiaServer-5.1/ServerKernel/web and copy your custom JSP in the "custom" folder.

#### **Creating Web Form Using Rich Form**

You can create a rich internet form and use it as an HTML page in an activity. This form can be used for a Human Workflow activity or a custom application. Adeptia supports an external tool, the **Frevvo** tool for creating a rich form. For details on a rich form by Frevvo, refer to http://docs.frevvo.com/docs/index.php/V3.0\_Main\_Page.

#### Steps to create a web form using a Rich Form

1. Select *Rich Form* from the *Form Type* drop-down list in the Create Web Form screen.

2. Click **Create Form** button. This displays theAdeptia Rich Form screen (see Figure 3.13).

http://localhost:8080/adeptia/DesignFrevvoForm.jsp?hiA	ctivityId=&frevvoFormId=&HIActivityname=C - Windows Internet Explorer
Info: -If you want to use this form as menu link then sele	ect a theme other than default theme(WorkFlowTaskTheme).Go to "Style(Tab)>Theme" to change the default theme.
▼ PALETTE	Contractor Energy Contractor
Dropdown Text	Customer FormForm
Radio     III TextArea	Image: Controls     Rules     Form Action     Doc Action     Finish     Cancel
Checkbox 🔂 Date	
Section M EMail	aprint and a second sec
Repeat de Money	
Tabs Phone	Drop Submit buttons from the palette to add to the form.
Panel 🥹 Quantity	
Message 🙉 Number	
🔛 Message 🥶 Multiber	
📽 Trigger 🎽 Video	
Upload Submit	
▼ PROPERTIES	
Settings Style Form Info	
Name Customer FormForm	
Description Edit the form to change this description	
Error page Save IV Printable IV	
Show Logo 🗖 Save/Load 🗖	
Captcha 🗖	
DATA SOURCES	

Figure 3.13: Adeptia Rich Form

- 3. This screen is divided into two parts. The left pane displays a palette of controls and their properties. The right pane displays a blank form. You can create a form by dragging the controls in the left pane and dropping them in the right pane. You can edit the control properties and also rearrange the controls.
- 4. When you drag and drop a control in the form canvas, it is displayed as a field with the control label. You can edit and customize the control by editing its properties that are displayed in the Properties section in the left pane. You can edit properties such as the control name or control type.
- 5. Additionally, you can add a name for the control in the *Name* property, which is created as a variable in the process flow context and used as a process flow variable. For example, if you add a text control and add var1 in the *Name* property, var1 is created as a process flow variable and used in the process flow, when required.
- 6. Furthermore, you can customize the control by defining its maximum length and hints, error or help messages. You can also manipulate its visibility and validations such as mandatory and password entries.



The properties can vary for each control. For details on each property, refer to

http://docs.frevvo.com/docs/index.php/V3.0\_Designing\_Forms#E diting\_Controls.



7. You can also customize the appearance and style of each control by editing the style properties displayed in the *Style* tab in the *Properties* section (see Figure 3.14).

	100000 C	2.4 C C C C C C C C C C C C C C C C C C C
Settings	Style	Advanced
Width		
Margin		
Padding		
Background		
Color		
Border Width		
Border Style	solid	•
Border Color		
Label Color		
Label Size		
Bo	ld 🗖	Italic 🗖
	DATA SOUR	CES

Figure 3.14: Style Properties

- 8. Additionally, you can also customize the style of the entire form by selecting the form and then clicking the *Style* tab.
- 9. A sample created rich form is displayed in Figure 3.15.



	CustomerForm	C		×
Preview Controls Rules			Finish	Cancel
🖨 print				
▼ Customer Details Form				
First Name				
Last Name				
Phone 9				
Email				
Browse.	Upload image			
Submit Reset				
Powered by <u>frevvo</u>				

Figure 3.15: Sample Rich Form

10. The **Submit** and **Reset** buttons are displayed as disabled. You can remove these buttons from the form by changing its *theme* property. To do this, select the form and click the *Style* tab. Then, select *ClearThemeWithHiddenSubmitButtons* in the *adeptia's themes*, from the *Theme* drop-down list.

Ø

If you want the form to trigger a process flow, then you need to select the *ClearThemeWithHiddenSubmitButtons* theme.

You can also edit other form properties such as enable print settings for the form, display **Powered by frevvo** logo in the form, etc. by selecting the form and clicking *Settings* tab.

 Before saving the form, you can preview it in HTML, by clicking the **Preview** button. You can also define rules to dynamically modify the behaviour of the form by clicking the Rules button. For more details on creating rules, refer to <u>http://docs.frevvo.com/docs/index.php/Form\_builder#Rules</u>.



- 12. Once you have completed the form, save the form by clicking the **Finish** button. It is saved in *C:\Program Files\AdeptiaServer\AdeptiaServer*. 4.9\ServerKernel\frevvo\WEB-INF\users\adeptia.
- 13. Once you save the form, the control is taken back to the Create Web Form screen.

## ACTIVATING A WEB FORM

By default, a web form is created in deactivate state. To access it, you need to activate it.

#### Steps to activate a web form

1. Select the web form you want to activate, in the Manage Web Forms screen, and click the **Activate** link. This activates the web form (see Figure 3.16).

[+]	My Tasks	Co	onfig	jure	> Forms > Web Forms				
[+]	My Documents								
[+]	My Solutions	Ne	wir	Edit	Delete   Revisions   Dependencies	Select Field to Searc	-h 🔽		Search
[+]	My Monitor								
[+]	History	Act	tivate	e -					
		#		(2)	Name	Description	Owner	Perm.	Modified <b>*</b>
[+]	Design	1	0	÷\$	ApprovePurchaseRequisition	approval form for requisition	demouser	RWX	08/08/09 16:36
[-]	Configure	2	$\bigcirc$	-@ł	CorrectPurchaseRequisition	make corrections to the requisition	demouser	RWX	08/08/09 15:51
	[-] Forms	з	0	-(j)	ReviewPurchaseRequisition	supervisor review form	demouser	RWX	08/08/09 15:39
	[+] WorkFlow	4	$\bigcirc$	۵	PurchaseRequisitionForm	Form that allows user to send purchase requisition	demouser	RWX	08/08/09 15:26
	[+] Services	5	0	÷\$2	InventoryCorrectionForm	correct inventory data	demouser	RWX	08/08/09 10:36
	[+] Reports & Dashboards								

Figure 3.16: Activated Web Form

Clicking **Deactivate** will deactivate the application and remove the link from the Workspace Menu.

M



# WORKFLOW

# 4 DESIGNING WORKFLOW TASK

A Workflow activity allows user(s) to interact with running process flows. It can provide data and/or get data from the process flows at runtime. Users can decide the execution path of the process flow based on the data processed.

For example, if a purchase order is issued for \$75,000, it may require approval from the Manager. The user can use a WorkFlow activity in such a case. The Workflow activity allows you to design an HTML page to perform this task. This HTML page can have all details of the purchase order and a button to **Approve** or **Reject**. Further, the activity allows you to assign this task to required person such as the manager, in this case. Once the Workflow activity is created, you can use this activity in the required process flow. When the process flow is executed, this activity gets listed as a task in the Manager's Task List. The Manager can open that task and click appropriate button to accept or reject the purchase order. If the manager accepts it, then the process flow will continue, else a rejection message will be sent to the user.

The Manager can enter input by clicking the **Open Task** link on the Task Manager screen. This displays the HTML form, where the Manager can enter input and click **Complete Task** or **Save Task** button.

Thus, users can use the Workflow service to perform various tasks such as:

- Design HTML page to show details of the task to be executed
- Assign tasks to other users and send them emails requesting for their necessary actions. These assigned tasks get listed in the Task Manager.
- Set Due date and Expiry date of the assigned task
- Defer the task to other users in not completed with due date



At times, the execution of tasks listed in the Task Manager, may get interrupted due to the kernel getting disconnected. To retain the executed data, the Human Workflow activity is equipped with the *Recovery Support* feature, which recovers all the executed data, at the next login.

In the Adeptia Suite this feature is available in:

BPM Suite	Integration Suite	ETL Suite
$\checkmark$		

This chapter describes the following tasks:

- Creating Workflow Task
- Executing Workflow Task



## **CREATING WORKFLOW TASK**

#### **Pre-Requisites**

• Web Form to be used in the Workflow Task must be created.

#### Steps to create a Workflow Task

- 1. In the Adeptia Suite homepage menu, click **[+] Configure** to expand the tree. All the items in the **Configure** category are displayed.
- 2. Click **[+] Workflow** to expand the tree and then click **Workflow Task**. The Manage Workflow Task screen is displayed (see Figure 4.1).

[+] [+]	My Tasks My Documents	Config	jure > WorkFlow > Workflow Task				
[+] [+]	My Solutions My Monitor	New	Edit   Delete   Revisions   Dependencies	Select Field	to Search 💌		Search
[+]	History	#	Name	Description	Owner	Perm.	Modified <b>•</b>
[+] [-]	Design Configure	1 () 2 ()	ReviewPRTask CorrectPRTask	review by supervisor make corrections to the requisition form	demouser demouser	RWX RWX	08/08/09 16:03 08/08/09 16:02
	[+] Forms [-] WorkFlow	3 () 4 ()	ApprovePRTask	approve requistion task to correct errors	demouser	RWX	08/08/09 16:02
		4 ()	InventoryCorrectionTask	task to correct errors	demouser	RWA	08/08/09 10:41
[+]	<ul> <li>[+] Reports &amp; Dashboards</li> <li>Deploy</li> </ul>						
[+]	Administer						

Figure 4.1: Manage Workflow Task

3. Click the **New** link. The Create Workflow Task screen is displayed (see Figure 4.2).



Standard properties	
Name *	
Description *	
User(s)	None admin (Default Administrator) demo_manager (demo manager) demo_supervisor (demo supervisor) 🔽
Role(s)	None
Task Priority *	Immediate 💌
Task Due for *	dd 00 • hh 00 • mm
Task Expires after *	Never dd 00 whh 00 wmm
Defer task to colleague upon Due date	
Defer task to manager upon Due date	
Documents Attach/View	Attach and View
Repository Folder	
Web Form *	SELECT
Email Body	
Advanced properties	
ndatory fields.	

Figure 4.2: Create Workflow Task

- 4. Enter the name and description of the Workflow task in the *Name* and *Description* fields respectively.
- 5. Select the user to whom you want to assign this task, from the *User ID* list box. You can override this user with another user dynamically, at the time of process flow execution. For details on how to override assignee during process flow execution, refer to <u>Overriding Assignee User of a Human Workflow Task</u> section.
- 6. To assign this task to Business Role, select the Business Role from the *Role(s)* list box.



To select more than one user or business role, press the **<Ctrl>** key and click on the user(s) or business role(s) with the mouse. To select no user or business role, select **None**. At least one user or business role should be



selected. To learn about Business Role, refer to the *Creating Business Roles* section in the *Administrator Guide*.

7. Select the priority of this task from the *Task Priority* drop-down list. By default, *Immediate* is selected.

Task priority does not have any direct impact on the task execution. It is just a flag so that user will be able to know that which task should be completed first.

- 8. Enter the due time for this task in days, hours and minutes, in the *Task Due for* drop-down lists.
- 9. Select the expiry time for this task in days, hours and minutes, from the *Task Expires after* drop-down lists.

Time entered into *Task Due for* and *Task Expires after* fields are counted after the task is listed in the Task Manager not from the creation of the task.
 If a task is not completed within its due time, it will be listed in the *Over Due* list in the Task Manager of the user. If it is not completed with in its expiry time, then it will be deleted from the Task Manager.

- 10. Check the *Defer task to colleague upon Due Date* check box, to defer the task to a colleague, if it is not completed within its due date.
- 11. Check the *Defer task to manager upon Due Date* check box, to defer the task to the Manager, if it is not completed within its due date.



Both the *Defer task to colleague* and *Defer task to manager* check boxes can be checked at the same time.

- 12. Select *Attach and View* to attach or view files from the *Documents Attach/View* drop-down list, if you want enable the option for attaching/viewing documents in the task manager.
- 13. Enter the name of folder, where the file attached with Workflow task is stored, in the *Repository Folder* field. This could be a WebDAV folder or process flow repository folder.

To specify, whether the defined folder is a WebDAV folder or a process flow repository folder, you need to change the abpm.hi.repository.type property. Refer to the *Administrator Guide* for details.
 If you set the *repository type* property as *WebDav* and leave the *Repository Folder* field blank, the files are saved into a default group folder created in "WebDAV folder" object. If files are stored in the default folder, its path would be *<group name folder\Process Flow name\Transaction Id>*.
 Here:
 *group name folder* is the folder of the group, the executor belongs to. *Process Flow name* is the name of the process flow, and *Transaction Id* is execution instance Id of the process flow.



- If you set the *repository type* property as *default* and leave the *Repository Folder* field blank, the files are saved into process flow repository.
- It is important to ensure that the folder path is correct and executor has write permissions to the folder; else the process flow will be created but will fail at runtime.
- 14. Select the web form that you want to attach to the task, from the *Web Form* drop-down list. All web forms that are created are listed in this drop-down field.
- 15. Enter your email message in the *Email Body* field. If you do not specify this message, then the default email with subject is sent. The subject of the email that is sent is defined in the code. You can override this subject and the first line of the email body by dynamically changing it. Refer to <u>Overriding</u> **Email Subject** for details.



To learn about Advanced Properties refer to section <u>Changing Advanced</u> <u>Properties</u> section.

16. Click **[+]** Advanced Properties to expand Advanced Properties. The Advanced Properties of the WorkFlow task are shown (see Figure 4.3).



[-]	Advanced properties					
	Send Email to user on addition of new task					
	Send reminder Email to user before due date of task	dd 00 Thh 00 Tmm				
	Send reminder Email to user before expiry date of task	dd 00 💌 hh 00 💌 mm				
	Email on Due Date	None User(s) Colleague(s) Manager(s)				
	Email on Expiry Date	None User(s) Colleague(s) Manager(s)				
	Screenflow					
	Screenflow in Parent					
	Screenflow in Child					
	Reassign Task					
	Owner*	admin (Default Administrator)				
		Read Write Execute				
	Permissions*	Owner 🔽 🔽				
	i ennissions	Group 🔽 🗖				
		Other 🗖 🗖				

Figure 4.3: Advanced Properties of Workflow Task

- 17. If you want to notify the user by email when the task is listed in user's task list, check *Send Email to User on addition of new task* check box.
- 18. If you want to send a reminder email to user, before the task's due date, check the *Send reminder email to user before due date of task* check box and specify the time in days, hours and minutes. For example if you specify 1 day, the reminder email is send 1 day before the due date of the task.
- 19. If you want to send a reminder email to user, before the task's expiry date, check the *Send reminder email to user before expiry date of task* check box and specify the time in days, hours and minutes.
- 20. Select the User(s), Colleague(s) or Manager(s) from the *Email on Due Date* list box, to send an email to a user, colleague or manager if the task is not completed by due date and time.

21. Select the User(s), Colleague(s) or Manager(s) from the Email on Expiry Date list box, to send an email to a user, colleague or manager if the task is expired.



Email sent to user(s), Colleague(s) or Manager(s), on Due Date or Expiry Date, contains URL of the Adeptia Suite Login Page (e.g. http://localhost:8080/adeptia/control).

To login into Adeptia Suite and to access task manager, replace 'localhost' with name or IP address of the machine, where Adeptia Suite is running.

22. Select Screenflow checkbox, to open the subsequent task in the same screen, once the previous task is executed, in case of multiple tasks being assigned to you.



- If you are setting multiple tasks to be executed one after another in a process flow, and the Screenflow feature is enabled, then you need to attach the same type of web forms. For example, a process flow has 3 tasks to be executed one after another. If the first task has a Manual web form attached, then the remaining two tasks should also have Manual web forms attached. Adeptia does not support multiple web form types in a single process flow.
- 23. Select Screenflow in Parent checkbox, to open the subsequent parent task in the same screen, once the previous parent task is executed, in case of multiple tasks being assigned to you.
- 24. Select Screenflow in Child checkbox, to open the subsequent child task in the same screen, once the previous child task is executed, in case of multiple tasks being assigned to you.
- 25. If you want to allow the user (to whom this task is assigned), to re-assing the t ask to any of its colleague, then check the *Reassign Task* checkbox.
- 26. Select the owner of the task in the Owner drop-down list.
- 27. Set the permissions by checking the appropriate checkbox(s) in the Permissions field.
- 28. Once you are done, click **Save** button. This displays a screen confirming that the workflow task has been created successfully. If the *Comments* property is enabled, then clicking Save will display a screen where you need to enter comments for creating the Workflow task (refer to Figure 3.6).
- 29. Enter the comments in the Add Comments field.



The comment should be at least 1 character in length.

30.

Click **OK** to save the comments. This displays a screen confirming that the workflow task has been created successfully.



By default, the Comments property is disabled. To enable it, refer to the Updating System Properties section in Administrator Guide.



# **EXECUTING HUMAN WORKFLOW TASK**

You can view a WorkFlow task assigned to you in your Task Manager and execute it by entering inputs.

In the Adeptia Suite, the Task Manager is available in:

BPM Suite	Integration Suite	ETL Suite
$\checkmark$		

#### Steps to execute a task assigned to a user

- 1. In the Adeptia Suite homepage menu, click **[+]** My Tasks to expand the tree. All the items in the My Tasks category are displayed.
- 2. Click **Task Manager**. The Task Manager screen is displayed with a list of tasks assigned to you (see Figure 4.4).

Task	Manager						
				-	-Select Field to Search	💌	Search
Ove	r Due						
# 🔺	Task Name		Task Subject	Action	Priority	Expiry Date	Comm.
			No over	due tasks			
Due	Today						
# 🔶	Task Name		Task Subject	Action	Priority	Due Date	Comm
	LossAdjustor	lossadjustor		Open Task	Immediate	07/01/2009 21:48	<b>a</b>
Due	within a Week						
# 🔺	Task Name		Task Subject	Action	Priority	Due Date	Comm
	ReviewClientDetails	task1		Open Task	Immediate	07/02/2009 17:35	
	ReviewClientDetails	task1		Open Task	Immediate	07/02/2009 17:36	
	Claim_Amount_review	review		Open Task	Normal	07/02/2009 17:41	<b>a</b>
Due	Later						
# 🗕	Task Name		Task Subject	Action	Priority	Due Date	Comm.

Figure 4.4: Task Manager

You can dynamically set the task description during execution of the process flow. While creating the process flow, this description is specified by using the *put-context-var* action. The *put-context-var* is connected in the process designer, before the Workflow activity. It is attached to the activity, by right-clicking the *put-context-var* action and selecting **View Properties**, and then selecting the name of the Workflow activity from the *Activity* dropdown list. The description is specified by selecting "taskDescription" from *Key* drop-down list, and entering the required description in the *Value* field. This description is displayed in the *Description* field of the assigned task in Task Manager. 3. Click the **Comments** icon (27) to add comments to your task. A dialog box is displayed to add the comments (see Figure 4.5).

	nments for the task 'ReviewClientDetails'
Properties	Value
Task Id	192168001002124644629039800015
Task Name	ReviewClientDetails
Task Description	task1
Process Flow Name	cust
Assign To	admin
Task Priority	Immediate
Task Creation Date	07/01/2009 16:34
Task Due Date	07/02/2009 17:35
Task Expiry Date	07/03/2009 18:36
Comments	
	Save Comments Cancel

Figure 4.5: Comments

- 4. Enter your comments and click **Save Comments**.
- 5. You can also re-assign the task to any user of your group. To re-assing the task, click *Reassign* link. The *Re-assign* task page is displayed (see Figure 4.6 ).



	7 1 5 1 1	
	Task Details	
Name	ReviewClaimDetails	
Description	Review Claim Detail:	5
Priority	Immediate	
Due Date	08/05/2010 15:14	(MM/dd/yyyy HH:mm)
Expiry Time	Never	(MM/dd/yyyy HH:mm)
	Reassign Task	
Users		Selected Users
demo_user demo_manager	admin	
Reassign Close		

Figure 4.6: Re-assign Task

- 6. Select the user to whom you want to re-assign the task, and click arrow to move it to selected user.
- 7. Click **Reassign**. The task is reassigned to selected user and removed from the current user.
- 8. Click **Open Task** link of the task you want to execute in the Task Manager screen. This opens the activity as displayed in the WorkFlow Task screen (see Figure 4.7).



		Task His
🚔 print		
Name		
Address		
	<u> </u>	
	<b>~</b> 1	
Mobile 🧕		
Email ID		
ocuments		
0		View Files
Attach Files File Name No files attached i	Size	Attached Documents No Files available

Figure 4.7: Workflow Task

- 9. Enter details as required.
- 10. Click the **Attach Files** link To attach the a file. This displays the File Upload screen (see Figure 4.8).

Human Workflow File Upload	
File Upload :	Browse
Upload File Cancel	

Figure 4.8: File Upload

- 11. Click **Browse** and select the file that you want to upload.
- 12. Click **Upload File**. This uploads the file and displays it in the *Attach Files* list in the Workflow Task screen (see Figure 4.9).



9	Attach Files			View Files
	File Name	Size		Attached Documents
1	source.bd	17 Byte (s)	delete	No Files available
2	ClaimManagementPF.xml	6 KB	delete	

Figure 4.9: File Uploaded

13. Click **Save Task** button. Reopen the task by clicking **Open Task** in the Task Manager screen. This displays the Workflow task screen, with the attached file in the *View Files* list (see Figure 4.10). Click **View/Download** link to view or download the file.

Attach Files			View Files		
File Name Size Attached Documents					
None			ClaimManagementPF.xml	View/Download	
			source.txt	View/Download	

Figure 4.10: View Attached File



# SERVICES

# **5** CREATING DATA DICTIONARY

A data dictionary is a collection of record definitions that are commonly used when a schema is created. You can just select the data dictionary and display the required records. This feature avoids redundancy of information and reduces the additional effort for creating a schema. Adeptia supports the Data Dictionary feature for Positional and EDI schemas only. This section explains:

- <u>Creating Postional Data Dictionary</u>
- <u>Creating EDI Data Dictionary</u>

# **CREATING POSITIONAL DATA DICTIONARY**

When creating Positional schemas, some record definitions may be common across schemas. You can create and define the record definitions commonly used in Positional schemas in a Positional Data Dictionary. Thus, when creating a Positional Schema, you can select the data dictionary and display the required records. Later, you can also view or delete a record from the Positional schema screen itself.

In the Adeptia Suite this feature is available in:

BPM Suite	Integration Suite	ETL Suite
$\checkmark$	$\checkmark$	

Steps to create Positional Data Dictionary

- 1. In the Adeptia Suite homepage menu, click **[+]** Configure to expand the tree. All the items in the Configure category are displayed.
- 2. Click [+] Services to expand the tree. All the items in the Services category are displayed.
- 3. Click **[+]** Data Dictionary to expand the tree and then click Positional. The Manage Positional Data Dictionary screen is displayed (see Figure 5.1).



[+] My Tasks	Config	gure > Services > Data Dictionary >	Docitional			
[+] My Documents	Conne	gare > Services > Data Dictionary >	Positional			
[+] My Solutions	New Li	Edit   Delete   Revisions   Dependencies		-Select Field to Search 💙		Search
[+] My Monitor	New	Edit   Delete   Revisions   Dependencies		Select Field to Search**		Search
[+] History						
	#	Name	Description	Owner	Perm.	Modified 🔻
[+] Design	1 ()	AL3_PositionalDataDictionary	AL3_PositionalDataDictionary	demouser	RWX	02/13/08 13:34
[-] Configure						
[+] Forms						
[+] WorkFlow						
[-] Services						
[-] Data Dictionary						
C Positional						
EDI						

Figure 5.1: Manage Positional Data Dictionary

4. Click **New** link. The Create Positional Data Dictionary screen is displayed (see Figure 5.2).

Configure >	> Servic	es > Data Dictionary >	Positiona	I			
[-] Standa	ard prop	erties					
	Name *				]		
	Description *				]		
	Create Dictionary Definition* O Use Definition File O Define Records Manually						
				XSD Browse			
	Add Re	ecord					
[	#	Record Name		Descripti	on	Version	Action
[+] Advan	ced prop	oerties					
* Mandatory fiel	lds.						
Save C	ancel						

Figure 5.2: Create Positional Data Dictionary

5. Enter the name and description for Positional Data Dictionary in the *Name* and *Description* fields respectively.

You need to define records to be stored in the Data Dictionary. You can do this in two ways. These are outlined as:


- Use Definition file
- Define records manually
- 6. To define the records using <u>definition file</u> click the Use Definition File radio button, select the type of file from the drop-down list and click **Browse** button to select the required file. Alternately, to enter the records manually, click the Define Records Manually radio button and click **Add Record** button. This displays the Data Dictionary Record Builder screen (see Figure 5.3).



							Data Die	tiona	ary Record Builder
			Define Reco	rd					
Record I	identifier Name*							_	
Record I	identifier Value*								
Descript	tion								
Version									
		-							
Enter the	e Fields Sequentially Using	Field Lengt	h C Start & End Positio	ons					
#	FieldName Description	Туре	DateFormat	TimeFormat	Star	End	Length Ali	gn Skip	j
1	s	string 💌	mmddyyyy	hh:mm:ss	▼ 1		L	-	
2	s	string 💌	mmddyyyy	hh:mm:ss	Y		L		
3	s	string 💌	mmddyyyy 🔽	hh:mm:ss	<b>Y</b>		L	-	
4	s	string 💌	mmddyyyy	hh:mm:ss	-		L		
Numbe	r of Rows 1 at Pos	sition 5	Add Row	Remove Row					2
								Sav	cancel

Figure 5.3: Data Dictionary Record Builder

- 7. Enter the name of the Record Identifier in the *Record Identifier Name* field.
- 8. Enter the value of the Record Identifier in the *Record Identifier Value* field.
- 9. Enter the description and version of the record identifier in the *Description* and *Version* fields respectively.
- 10. You can now enter fields for the record. Enter the name and description of the field in the *Field Name* and *Description* fields respectively.
- 11. Select the type of data from *Type* drop-down list.
- 12. If data type is *Date*, select the format of date and time from the *DateFormat* and *TimeFormat* drop-down lists respectively.
- 13. To define field position select one of the following options:
  - Field Length
  - Start & End Positions
- 14. To define the field position using field length, select *Field Length* radio button and enter the length of the field in the *Length* field. Alternately, to define the field position using start and end position, select the *Start and End Positions* radio button and enter the start and end positions of the field in the *Start* and *End* fields respectively.



15. Select the alignment of the field from the Align drop-down list.

From *Align* field select

L if the field is left aligned.

**R** if the field is right aligned.


To insert rows, specify the number and position of the rows to be added in the *Number of Rows* and at *Position* fields respectively and click **Add Row** button. A maximum of 99 rows can be added at a time.

- 16. Check the *Skip* checkbox if you want to skip this field while generating the XML. This selection skips the fields that are not required for the data dictionary.
- 17. Click **Save** to save the records. The saved records are displayed on the Create Positional Data Dictionary screen (see Figure 5.4). You can view, edit or delete a record from this screen by clicking the appropriate button for that record.

Confi	igure :	> Servi	ces > Data Dictionary >	Position	al			
[-]	Standa	ard prop	perties					
		Name *		Custom	ier	]		
		Descrip	tion *	Custom	ler	]		
		Create I	Dictionary Definition*					
		O Use	Definition File	XSD		Browse		
		O Defi	ne Records Manually					
		Add F	lecord					
		#	Record Name		Description		Version	Action
		1	John		Name			View Edit Delete

Figure 5.4: Records created for the Positional Data Dictionary

- 18. Click **Save** to save the Positional Data Dictionary. If the *comments* property is enabled, then clicking **Save** will display a screen where you need to enter comments related to creating the data dictionary (refer to Figure 3.6).
- 19. Enter the comments in the Add Comments field.



- 20. Click **OK** to save the comments. This displays a screen confirming that the data dictionary has been created successfully.
- 21. Once you save the Data Dictionary, you can view, edit or delete the data dictionary definition by clicking **View**, **Edit** or **Delete** links respectively. Additionally, you can also *print* or *download* the definition.

22. Select the data dictionary in the Manage Positional Data Dictionary screen and click **Edit** link. This displays the data dictionary in edit mode (see Figure 5.5).

Services > Data Dictionar	ry > Positional > Customer			
[·] Standard properties				
Name *	Customer			
Description *	Customer			
Create Dictionary Definition*				
C Use Definition File	XSD 💌	Browse		
C Define Records Manually	1			
Add Record Print-	friendly Page Download			
	Record Name	Description	Version	Action
1	John	Name	1	View Edit Delete
[+] Advanced properties * Mandatory fields. Save Save As Cancel				



23. Click **Print-Friendly Page** button to view the dictionary definition in print mode in the web browser (see Figure 5.6). Alternately, click Download to download the XSD file of the selected dictionary definition (see Figure 5.7).

Positional Data	a Dictionary Na	me: Cust	omer						
l) Record Iden	tifier Name = 1	Name, Re	cord Identifier V	alue = John					
FieldName	Description	Туре	DateFormat	TimeFormat	StartPos	EndPos	Length	Alignment	Skip
Name	Name	string			1	25	25	L	F
Address	address	string			26	60	35	L	F
DateofBirth	dob	date	mmddyyyy	hh:mm:ss	61	70	10	L	F
Claim Amt	claim	number			71	76	6	L	F


Figure 5.6: Print Positional Data Dictionary Definition



🖉 Dov	vnload Schema Definition - Windows Internet Explorer	
Posi	vnload PositionalDataDictionary Definition File tionalDataDictionary Name: Customer ect Definition File XSD 💌	
xsd	<pre><?xml version="1.0" encoding="ISO-8859-1"?> <!-- W3C Schema generated by Adeptia Editor--> <xs:schema xmlns:xs="http://www.w3.org/2001/XMLSchema"></xs:schema></pre>	
Field	Name:John John,Name,Name,string,,,1,25,L,F John,Address,address,string,,,26,60,L,F John,DateofBirth,dob,date,MMddyyyy,HH:mm:ss,61,70,L,F John,Claim_Amt,claim,number,,,71,76,L,F	×
	Download Cancel	

Figure 5.7: Download Positional Data Dictionary Definition

# **CREATING EDI DATA DICTIONARY**



When creating EDI Schemas, some record definitions may be common across schemas. You can create and define the record definitions that are commonly used in EDI schemas in an EDI Data Dictionary. Thus, when creating an EDI Schema, you can select the EDI Data Dictionary and display the required records.

#### Steps to create EDI Data Dictionary

- 1. In the Adeptia Suite homepage menu, click **[+] Configure** to expand the tree. All the items in the **Configure** category are displayed.
- 2. Click [+] Services to expand the tree. All the items in the Services category are displayed.
- 3. Click **[+]** Data Dictionary to expand the tree, and then click **EDI**. The Manage EDI Data Dictionary screen is displayed (see Figure 5.8).



Configure > Services > Data Dictionary > EDI         New   Edit   Delete   Revisions   Dependencies        Select Field to Search Image: Contemport of the search	
New   Edit   Delete   Revisions   DependenciesSelect Field to Search	
New   Edit   Delete   Revisions   DependenciesSelect Field to Search 💌	
	Search
# Name Description Owner Perm.	Modified <b>T</b>
1 Č Invoice_810 Invoice v 4010 demouser RWX 08/0	8/09 12:36



4. Click the **New** link. The Create EDI Data Dictionary screen is displayed (see Figure 5.9).

Conf	igure	> Servi	ces > Data Dictionary >	EDI				
[-]	Stand	ard pro	perties					
		Upload	Zip File *			Upload Zip		
		Name *						
		Descrip	tion *					
		EDI Sta	ndard *					
		Respor	sible Agency Code *					
		EDI Sta	ndard Version *					
		Create	Dictionary Definition*					
		Add	Transaction					
		#	XSD File		Description	1	Transaction Set	Action
[+]	Advar	nced pro	perties					
* Mand	latory fie	elds.						
Save	e (	Cancel						

Figure 5.9: Create EDI Data Dictionary

5. Click **Upload Zip** button to select and upload the zip file. All XSD's and the values contained in the zip file are uploaded automatically. All the fields of the data dictionary are populated automatically. You need not enter or change any value in these fields.

Ø	•	Currently one data dictionary is already created for X12 004010 Version.
	•	To create the EDI Data Dictionary of any other version, the ZIP will be provided by Adeptia. To get the XSD's of any other version contact support@adeptia.com.



- 6. Click the **Save** button. This displays a screen confirming that the Data dictionary has been created successfully. If the *comments* property is enabled, then clicking **Save** will display a screen where you need to enter comments related to creating the EDI Data Dictionary (refer to Figure 3.6).
- 7. Enter the comments in the *Add Comments* field.



The comment should be at least 1 character in length.

8. Click **OK** to save the comments. This displays a screen confirming that the EDI Data Dictionary has been created successfully.



By default, the *Comments* property is disabled. To enable it, refer to the *Updating System Properties* section in *Administrator* Guide.



# 6 CREATING SOURCE ACTIVITY

The Source activity enables you to identify specific source data to be read, its location and the transport protocol that is used to retrieve data. The Adeptia Suite allows following types of Source activities:

- <u>Advance Database Source</u>
- Database Source
- File Source
- FTP Source
- HTTP Source
- JMS Source
- LAN File Source
- Mail Source
- WebDAV Source
- Context Source

Context Source is used to get the data from the process flow context. To know how to use Context Source refer to the section <u>Using Context Source and Context</u> <u>Target</u> activity.



When using a source activity in a process flow, the *eventContextEnabled* property is set to *True* by default. This implies that all variables are allowed to be passed from events to the source activity. For example, if a mail event has a file attached, its filename can be passed to the source activity easily.

# **CREATING ADVANCED DATABASE SOURCE ACTIVITY**

The Advanced Database Source activity provides the ability to specify multiple tables of a database as source.

In the Adeptia Suite this feature is available in:

BPM Suite	Integration Suite	ETL Suite
$\checkmark$	$\checkmark$	$\checkmark$

#### Prerequisites:



• *Database Info* activity and *Advance Database Schema* must be created before creating Advanced Database Source activity.

#### Steps to create an Advanced Database Source Activity

- 1. In the Adeptia Suite homepage menu, click **[+]** Configure to expand the tree. All the items in the Configure category are displayed.
- 2. Click [+] Services to expand the tree. All the items in the Services category are displayed.
- 3. Click **[+] Source** to expand the tree, and then click **Adv**. **Database**. The Manage Advanced Database Source screen is displayed (see Figure 6.1).

[+] My Tasks		Config	ure > Services > So	urce > Adv. Da	tabase				
[+] My Documen	ts								
[+] My Solutions		New	dit   Delete   Revisions	Dependencies		Sele	ct Field to Search 💙		Search
[+] My Monitor									
[+] History									
		#	Name	2		Description	Owner	Perm.	Modified 🔻
[+] Design		1 ()	DBSource		db source		demouser	RWX	08/06/09 10:34
[-] Configure									
[+] Forms									
[+] WorkFlov	v								
[-] Services									
[+] Data D	ictionary								
[-] Sourc	e								
<b>0</b> ∳ Adv	. Database								
0¢ Dat	abase								
🖹 File									

Figure 6.1: Manage Advanced Database Source

4. Click the **New** link. The Create Advanced Database Source screen is displayed (see Figure 6.2).

Configure > Services > Source > Ad	v. Database	
[-] Standard properties		
Name *		
Description *		
Database Info *	SELECT	•
Schema Name *	SELECT Edit Quevies	¥
[+] Advanced properties		
* Mandatory fields.		
Save Cancel		

Figure 6.2: Create Advanced Database Source


- 5. Enter the name and the description of the new Advanced Database Source in the *Name* and *Description* fields respectively.
- 6. Select the database info activity and advanced database schema activity from the Database *Info* and the *Schema Name* drop-down lists respectively.



To learn how to create Database Info activity, refer to the section *Creating Database Info* in *Administrator Guide*. To learn how to create the Schema activity, refer to Creating Advance Database Schema Activity section.

7. To edit the database query of the selected schema, click **Edit Queries** button. The Edit Query(s) screen is displayed (see Figure 6.3).

	Edit Query for Adv Schema Name	anced Database Source : adsc_sql (adsc_sql)	
Table Name	SQL Query	Where Clause	
08/sb4.eb7dbaR1_/	SELECT Name,age,salary,dob FROM dbo.[R1]		*



8. Edit the query and click **OK** button to submit the edited query and return to the Manage Advanced Database Source screen.

Ø	•	While creating Advanced Database Source, <i>Edit Query</i> button is disabled. You can edit the query only after saving the Advance Database Source activity. First you have to save the Advance Database Source and edit it to edit the query.
	•	You can edit the Query only for <i>Where</i> clause and not to change the table name or column names. To change the table name or select different columns, go to Advance Database Schema and edit the schema over there.
	•	If you specify where clause in Advance Database Source as well as in Advance Database Schema, the <i>Where</i> clause of Advance Database schema is used during execution.
	•	To learn about Advanced Properties refer to Changing Advanced Properties section.

- 9. Click [+] to expand Advanced Properties.
- 10. In *Query Definition* field, Database Query is displayed in XML form. If you edit this query, database query defined using Edit Query button is overwritten.
- 11. You can check the *Use Optimize Algorithm* checkbox. If this option is enabled, data fetching from the source database table becomes faster. Enable this option only if the database source is an SQL database.
- 12. You can check the *With (No Lock) Option* checkbox. If this option is enabled, records are fetched from the source database without any lock constraint. This option is applicable, only when *Use Optimize Algorithm* option is enabled.



To learn about Advanced Properties refer to <u>Changing Advanced</u> <u>Properties</u> section.

13. Click **Save** button. This displays a screen confirming that the Advanced Database source activity has been created successfully. If the *Comments* property is enabled, then clicking **Save** will display a screen where you need to enter comments related to creating the Advanced Database source (refer to Figure 3.6).



14. Enter the comments in the Add Comments field.

Ø

- The comment should be at least 1 character in length.
- 15. Click **OK** to save the comments. This displays a screen confirming that the Advanced Database source activity has been created successfully.



By default, the *Comments* property is disabled. To enable it, refer to the *Updating System Properties* section in *Administrator* Guide.

# **CREATING DATABASE SOURCE ACTIVITY**

The Database Source activity provides the ability to specify a database as source.

In the Adeptia Suite this feature is available in:

BPM Suite	Integration Suite	ETL Suite
$\checkmark$	$\checkmark$	$\checkmark$

#### Prerequisites:

• *Database Info* activity and *Database Schema* must be created before creating Database Source activity.

#### Steps to create a Database Source Activity

- 1. In the Adeptia Suite homepage menu, click **[+] Configure** to expand the tree. All the items in the **Configure** category are displayed.
- 2. Click [+] Services to expand the tree. All the items in the Services category are displayed.
- 3. Click **[+] Source** to expand the tree, and then click **Database**. The Manage Database Source screen is displayed (see Figure 6.4).



[+]	My Tasks —	Config	jure > Services > Source > Databas	ie .				
[+]								
[+]		New	Edit   Delete   Revisions   Dependencies	Select Field to S	earch 💙		Searc	h
[+]								
[+]	History							
		#	Name	Description	Owner	Perm.	Modified 🔻	
[+]		1 ()	EvalXform_DBSource	Database Source having insurance data	demouser	RWX	07/22/05 16:27	
[-]	Configure							
	[+] Forms							
	[+] WorkFlow							
	[-] Services							
	[+] Data Dictionary							
	[-] Source							
	<b>0</b> ⇒ Adv. Database							
	<b>0</b> ♦ Database							
	🖹 File							

Figure 6.4: Manage Database Source

4. Click the New link. The Create Database Source screen is displayed (see Figure 6.5).

Configure > Services > Source > Database					
[-] Standard properties					
Name *					
Description *					
Database Info *	SELECT	•			
Schema Name *	SELECT		•		
[+] Advanced properties					
* Mandatory fields.					
Save Cancel					



- Enter the name and the description of the new Database Source in the Name 5. and *Description* fields respectively.
- Select the database info activity and database schema activity from the 6. Database Info and the Schema Name drop-down lists respectively.



To learn how to create Database Info activity, refer to the section Creating Database Info in Administrator Guide. To learn how to create the Schema activity, refer to Creating Database Schema section.

To learn about Advanced Properties refer to section Changing Advanced Properties.

- Click **Save** button. This displays a screen confirming that the database source 7. activity has been created successfully. If the Comments property is enabled, then clicking Save will display a screen where you need to enter comments related to creating the database source (refer to Figure 3.6).
- Enter the comments in the Add Comments field. 8.



Ø	
	l

The comment should be at least 1 character in length.

9. Click **OK** to save the comments. This displays a screen confirming that the database source activity has been created successfully.



By default, the *Comments* property is disabled. To enable it, refer to the *Updating System Properties* section in *Administrator* Guide.

# **CREATING FILE SOURCE ACTIVITY**

The File Source activity provides the ability to specify any file that is located on the local hard disk, as a source.

In the Adeptia Suite this feature is available in:

BPM Suite	Integration Suite	ETL Suite
$\checkmark$		$\checkmark$

#### Steps to create a File Source Activity

- 1. In the Adeptia Suite homepage menu, click **[+]** Configure to expand the tree. All the items in the Configure category are displayed.
- 2. Click [+] Services to expand the tree. All the items in the Services category are displayed.
- 3. Click **[+] Source** to expand the tree, and then click **File**. The Manage File Source screen is displayed (see Figure 6.6).

[+] My Tasks	Confi	gure > Services > Source > File					
[+] My Documents							
[+] My Solutions [+] My Monitor	New	Edit   Delete   Revisions   Dependencies		Select Field to Se	arch 💌		Search
[+] My Monitor [+] History							
	#	Name	Descripti	on	Owner	Perm.	Modified 🔻
[+] Design	1 ()	GetPurchaseOrderDataFile	receive purchase orders		demouser	RWX	11/24/09 14:22
[-] Configure [+] Forms	2 🔘	GetEmployeeBenefitsFile	excel data as a source		demouser	RWX	11/24/09 14:22
[+] Forms [+] WorkFlow	3 ()	EvalScript_FileSource	File Source With Zipped Emplo	oyee Data Files	demouser	RWX	11/24/09 14:20
[-] Services	4 ()	EvalRec_FileSource	Positional File		demouser	RWX	11/24/09 14:20
[+] Data Dictionary	5 ()	EvalPD_FileSource	file source containing purchas	e order	demouser	RWX	11/24/09 14:20
[-] Source							
<b>0</b> ♦ Adv. Database							
<b>0</b> ⇔ Database							
E File							
€ <b>5</b> FTP							

Figure 6.6: Manage File Source

4. Click the **New** link. The Create File Source screen is displayed (see Figure 6.7).



Configure > Services > Source > File	
[-] Standard properties	
Name *	
Description *	
File Path *	
File Name *	
[+] Advanced properties	
* Mandatory fields.	
Save Cancel Test	

Figure 6.7: Create File Source

- 5. Enter the name and the description of the new File Source in the *Name* and *Description* fields respectively.
- 6. Specify the full path of the source file name in the *File Path* field. For example, if a file named sales.txt is stored in a directory Employee, on the host where Adeptia Suite is running, the File Path will be c:/Employee.
- 7. Specify the source file name in the *File Name* field. With respect to the above example, enter the file name sales.txt in this field.

To learn about Advanced Properties refer to <u>Changing Advanced</u> <u>Properties</u> section.

If you want to delete the source file after it is used in the process flow execution, you can check the *Delete File on Success* checkbox, while defining the Advanced Properties. This selection will delete the source file once the JTA block in which the source file exists, is executed successfully during the process flow execution.

- 8. Click **Save** button. This displays a screen confirming that the file source activity has been created successfully. If the *Comments* property is enabled, then clicking **Save** will display a screen where you need to enter comments related to creating the file source (refer to Figure 3.6).
- 9. Enter the comments in the Add Comments field.



The comment should be at least 1 character in length.

10. Click **OK** to save the comments. This displays a screen confirming that the file source activity has been created successfully.

By default, the *Comments* property is disabled. To enable it, refer to the *Updating System Properties* section in *Administrator* Guide.





You can verify the file source activity at design time. For this, click **Test**. This verifies the values in the *File Path* and *Filename* fields and checks whether the file actually exists in the specified location.

# **CREATING FTP SOURCE ACTIVITY**

The FTP Source provides the ability to specify a file as a source that is accessible via  $\ensuremath{\mathsf{FTP}}$  .

In the Adeptia Suite this feature is available in:

BPM Suite	Integration Suite	ETL Suite
$\checkmark$		

#### Steps to create a FTP Source Activity

- 1. In the Adeptia Suite homepage menu, click **[+]** Configure to expand the tree. All the items in the Configure category are displayed.
- 2. Click [+] Services to expand the tree. All the items in the Services category are displayed.
- 3. Click **[+] Source** to expand the tree, and then click **FTP**. The Manage FTP Source screen is displayed (see Figure 6.8).

[+]	My Tasks —	Config	ure > Services > Source > FTP					
[+]	My Documents							
[+]	My Solutions	New	dit   Delete   Revisions   Dependencies		Select Field to Sea	arch 🗙		Search
[+]	My Monitor							bearen
[+]	History							
		#	Name	Descripti	on	Owner	Perm.	Modified 🔻
[+]	Design	1 ()	GetInventoryItemsFile	get CSV data file from FTP		demouser	RWX	09/01/09 12:19
[-]	Configure							
	[+] Forms							
	[+] WorkFlow							
	[-] Services							
	[+] Data Dictionary							
	[-] Source							
	<b>0</b> ≱ Adv. Database							
	<b>0</b> ♦ Database							
	🖹 File							
	RS FTP							

Figure 6.8: Manage FTP Source

4. Click the **New** link. The Create FTP Source screen is displayed (see Figure 6.9).



Configure > Services > Source > FT	р
[-] Standard properties	
Name *	
Description *	
Host name *	
Port *	21
User Id *	
Password	
Confirm Password	
Remote File Path	
File Name *	
Transfer Mode *	BINARY 💌
Transfer Type *	PASSIVE -
SSH FTP (SFTP) *	
FTP Over TLS/SSL (FTPS) *	
FTPS Mode	Explicit 💌
Protection Level	Clear 💌
Validate Server	
Keystore Name	SELECT 💌
[+] Advanced properties	
* Mandatory fields.	
Save Cancel Test	

Figure 6.9: Create FTP Source

- 5. Enter the name and the description for FTP Source in the *Name* and *Description* fields respectively.
- 6. Enter the host name/IP address and port of the FTP Server in the *Host Name* and *Port* fields respectively.
- 7. Enter the username in the *User ID* field.



- 8. Enter the password, if required, in the *Password* field. Then re-enter the password in the *Confirm Password* field.
- 9. Enter the path of source file in the in the *Remote File Path* field.
- 10. Enter the name of the source file in the *File Name* field.
- 11. Select the transfer mode as either BINARY or ASCII from *Transfer Mode* drop-down list respectively. In BINARY mode a file is copied bit for bit from one machine to the other. Both files (the original and the transferred file) will contain exactly the same sequence of bytes. In ASCII mode a file may be changed slightly to maintain the meaning of EOL (End Of Line) characters.
- 12. Select the transfer type as either Active or Passive from the *Transfer Type* drop-down list. Active transfer is more secure since the client only initiates communication to the Server on one port whereas in case of Passive transfer the client initiates communication to the Server over two ports. Passive mode is useful when you are behind a firewall or a proxy.
- 13. Check the *SSH FTP (SFTP)* checkbox if the FTP Server specified in the *Host Name* field is an FTP Server over SSH.
- 14. Check the *FTP Over TLS/SSL (FTPS)* checkbox, if the FTP Server, specified in the *Host Name* field is an FTP Serevr over TLS/SSL.
- 15. Incase you have selected *FTP Over TLS/SSL (FTPS)*, checkbox, then select the FTPS mode from *FTPS Mode* drop-down list. It can be *Explicit* or *Implicit* depending on FTP Server that you are accessing.
- 16. Select the protection level supported by the FTP Server, from the *Protection Level* drop-down list. It can be *Clear* or *Private*.
- 17. If you want to validate the certificate sent by the FTPS Server, check the *Validate Server* check box.
- 18. Select keystore activity from the *Keystore Name* drop-down list. This option is applicable only when you have checked the *Validate Server* checkbox.

When *Validate* option is unchecked, it always accepts the certificate sent by FTPS Server.

When this option is checked, it validates the certificate sent by FTPS server against the certificate imported in Keystore.

Keystore is repository of security certificates.

To know how to create Keystore and import certificates, refer to *Creating Keystore* secton of *Administrator Guide*.

Ø	•	To learn about Advanced Properties refer to <u>Changing Advanced</u> <u>Properties</u> section.
	•	If you want to delete the FTP source file after it is used in the process flow execution, you can check the <i>Delete File on Success</i> checkbox, while defining the Advanced Properties. This selection will delete the FTP source file once the JTA block in which the FTP source file exists, is executed successfully during the process flow execution.
	•	At times, when the Adeptia Suite is connected with the FTP server,



there could be connectivity issues. This could result in an infinite loop with no output. This issue can be resolved by setting a time limit if no data is transferred between Adeptia and FTP servers. You can set this limit (in seconds) in the *Data Timeout* field. By default, this is set to 60 seconds. This implies that if there is no data transfer for 60 seconds between both servers, the connection is broken and an error message is displayed.

- 19. Click **Save** button. This displays a screen confirming that the FTP source activity has been created successfully. If the *Comments* property is enabled, then clicking **Save** will display a screen where you need to enter comments related to creating the FTP source (refer to Figure 3.6).
- 20. Enter the comments in the *Add Comments* field.



The comment should be at least 1 character in length.

21.

. Click **OK** to save the comments. This displays a screen confirming that the FTP source activity has been created successfully.



By default, the *Comments* property is disabled. To enable it, refer to the *Updating System Properties* section in *Administrator* Guide.



You can verify the FTP source activity at design time. For this, click **Test**. This verifies the values in the *Host Name*, *Port*, *User ID*, *Password* and *Secured* fields and checks whether the specified FTP Server exists or not.

# **CREATING HTTP SOURCE ACTIVITY**

The HTTP Source provides the ability to specify a file as a source that is accessible via HTTP.

In the Adeptia Suite this feature is available in:

 BPM Suite	Integration Suite	ETL Suite	
$\checkmark$	$\checkmark$	$\checkmark$	

#### Steps to create a HTTP Source Activity

- 1. In the Adeptia Suite homepage menu, click **[+] Configure** to expand the tree. All the items in the **Configure** category are displayed.
- 2. Click [+] Services to expand the tree. All the items in the Services category are displayed.
- 3. Click **[+] Source** to expand the tree, and then click **HTTP**. The Manage HTTP Source screen is displayed (see Figure 6.10).



[+] My Tasks —	Configure > Services > Source	2 > FTP	
[+] My Documents			
[+] My Solutions	New   Edit   Delete   Revisions   Dep	nendenciesSelect Fie	ald to Search
[+] My Monitor			
[+] History			
	# Name	Description	Owner Perm. Modified 🔻
[+] Design	1 O GetInventoryItemsFile	get CS∨ data file from FTP	demouser RWX 09/01/09 12:19
[-] Configure			
[+] Forms			
[+] WorkFlow			
[-] Services			
[+] Data Dictionary			
[-] Source			
<b>0</b> ♦ Adv. Database			
<b>0</b> ⇔ Database			
🗂 File			
€ <b>S</b> FTP			
E HTTP			

Figure 6.10: Manage HTTP Source

4. Click the **New** link. The Create HTTP Source screen is displayed (see Figure 6.11).

Configure > Services > Source > HTTP					
[-] Standard properties					
Name *					
Description *					
HTTP URL *					
Secure					
HTTP Login Id *					
Password					
Confirm Password					
[+] Advanced properties					
* Mandatory fields.					
Save Cancel Test					



- 5. Enter the name and description of the new HTTP Source in the *Name* and *Description* fields respectively.
- 6. Enter the URL of the HTTP Server in the HTTP URL field. For example, http://www.adeptia.com/Employee/sales.txt
- 7. If authentication is required to access the specified file then check the *Secure* checkbox.

8. Enter the username and password in the *HTTP Login Id* and *Password* fields respectively. Then, re-enter the password in the *Confirm Password* field.



To learn about Advanced Properties refer to <u>Changing Advanced</u> <u>Properties</u> section.

- 9. Click **Save** button. This displays a screen confirming that the HTTP source activity has been created successfully. If the *Comments* property is enabled, then clicking **Save** will display a screen where you need to enter comments related to creating the HTTP source (refer to Figure 3.6).
- 10. Enter the comments in the *Add Comments* field.



The comment should be at least 1 character in length.

11. Click **OK** to save the comments. This displays a screen confirming that the HTTP source activity has been created successfully.



By default, the *Comments* property is disabled. To enable it, refer to the *Updating System Properties* section in *Administrator* Guide.



You can verify the HTTP source activity at design time. For this, click **Test**. This verifies the values in the *HTTP URL* and *HTTP Login Id* fields and checks whether the source activity actually exists in the specified location.

# **CREATING JMS SOURCE ACTIVITY**

The JMS Source activity provides the ability to specify a message of a queue or topic of a JMS Server as a source.

In the Adeptia Suite this feature is available in:

BPM Suite	Integration Suite	ETL Suite	
	$\checkmark$		

#### Prerequisites:

• *JMS Provider* activity must be created before creating *JMS Source* Activity.

#### Steps to create a JMS Source Activity

1. In the Adeptia Suite homepage menu, click **[+] Configure** to expand the tree. All the items in the **Configure** category are displayed.

- 2. Click [+] Services to expand the tree. All the items in the Services category are displayed.
- 3. Click **[+] Source** to expand the tree, and then click **JMS**. The Manage JMS Source screen is displayed (see Figure 6.12).

[+] My 1	Tasks	Configure > Services > Source > JMS			
[+] My [	Documents				
[+] My :	Solutions	New   Edit   Delete   Revisions   Dependencies	Select Fi	eld to Search 💙	Search
[+] My I	Monitor				bearen
[+] Hist	ory				
		# Name	Description	Owner Perm.	Modified 🔻
[+] Des	ign		No records found		
[-] Con	figure				
[+]	Forms				
[+] \	WorkFlow				
[-]	Services				
[+]	Data Dictionary				
[-]	Source				
	<b>0</b> ♦ Adv. Database				
	<b>()</b> ♦ Database				
	🖹 File				
	양 FTP				
	🖹 HTTP				
	🖾 JMS				

Figure 6.12: Manage JMS Source

4. Click the **New** link. The Create JMS Source screen is displayed (see Figure 6.13).

Configure > Services > Source > JMS				
[-] Standard properties				
Name *				
Description *				
JMS Provider*	EvalRec_JMSProvider (JMS Provider to connect)			
Connection Type*	TOPIC			
Durable Subscriber				
SubscriberID				
Queue Or Topic Name *				
MessageSelector				
Time Out	Sec(s)			
UserName				
Password				
Confirm Password				
[+] Advanced properties				
* Mandatory fields.				
Save Cancel Test				

Figure 6.13: Create JMS Source

- 5. Enter the name and the description of the new JMS Source in the *Name* and *Description* fields respectively.
- 6. Select the JMS Provider activity from the *JMS Provider* drop-down list.



To learn how to create JMS Provider activity, refer to the section *Creating JMS Provider* in *Administrator Guide*.

- 7. Select the Connection Type as either Topic or Queue from the *Connection Type* drop-down list.
- 8. Check the *Durable Subscriber* check box if the JMS Subscriber is durable. If a client needs to receive all the messages published on a topic, including the ones published while the subscriber is inactive, it uses a Durable Subscriber. This is applicable only when the connection type is Topic.
- 9. Enter the subscriber ID in the Subscriber ID field.
- 10. Enter the name of queue or topic as configured in the JMS Server in the *Queue Or Topic Name* field.
- 11. If you want to select a specific message from the JMS Server, enter the message selector in the *Message Selector* field.

9	The message selector is used to specify the filter criterion to receive a message that the user is interested in. The messages can be filtered based on only header references and properties references of the message. The message selector uses SQL92 query syntax to define the filter criteria. SQL92 is widely used to query the entire standard databases i.e. Oracle, SQL Server. The only difference between the database query and the message selector query is that the message selector uses, only a part of the query which is after the where clause.
	The following message selector selects messages with a message type of car and color of blue and weight greater than 2500 pounds:
	JMSType = 'car' AND color = 'blue' AND weight > 2500
	The following message selector selects message with the property Sport has value either as Basketball or Football.
	Sport in ('Basketball','Football')

- 12. Enter the time in seconds in the *Time Out* field. If any message is not received in this interval, process flow execution will be stopped. If Time Out field is left blank, JMS Source activity checks for the specified message and if message is not available, process flow is aborted, without waiting for message.
- 13. Enter the username and password (if required) to connect to JMS Server in the *UserName* and *Password* fields respectively. Then, re-enter the password in the *Confirm Password* field.



To learn about Advanced Properties refer to <u>Changing Advanced</u> <u>Properties</u> section.



- 14. Click **Save** button. This displays a screen confirming that the JMS source activity has been created successfully. If the *Comments* property is enabled, then clicking **Save** will display a screen where you need to enter comments related to creating the JMS source (refer to Figure 3.6).
- 15. Enter the comments in the Add Comments field.



The comment should be at least 1 character in length.

16. Click **OK** to save the comments. This displays a screen confirming that the JMS source activity has been created successfully.

By default, the *Comments* property is disabled. To enable it, refer to the *Updating System Properties* section in *Administrator* Guide.



You can verify the JMS source activity at design time. For this, click **Test**. This verifies the values in the *JMS Provider, Connection Type* and *Queue/Topic Name* fields and checks whether the source activity actually exists in the specified location.

# **CREATING LAN FILE SOURCE ACTIVITY**

The LAN File Source provides the ability to specify a file location that is accessible on the network.

In the Adeptia Suite this feature is available in:

BPM Suite	Integration Suite	ETL Suite		
$\checkmark$		$\checkmark$		

#### Steps to create a LAN File Source Activity

- 1. In the Adeptia Suite homepage menu, click **[+]** Configure to expand the tree. All the items in the Configure category are displayed.
- 2. Click [+] Services to expand the tree. All the items in the Services category are displayed.
- 3. Click **[+]** Source to expand the tree, and then click LAN File. The Manage LAN File Source screen is displayed (see Figure 6.14).



[+]	My Tasks	Configure > Services > Source > JMS			
[+]	My Documents				
[+]	My Solutions	New   Edit   Delete   Revisions   Dependencies	Salast	Field to Search M	Search
[+]	My Monitor	New   con   Delete   Revisions   Dependencies	select	Field to Search-	Search
[+]	History				
		# Name	Description	Owner Perm.	Modified 🔻
[+]	Design		No records found		
[-]	Configure				
	[+] Forms				
	[+] WorkFlow				
	[-] Services				
	[+] Data Dictionary				
	[-] Source				
	🕒 Adv. Database				
	🕒 🕈 Database				
	🖹 File				
	🐮 FTP				
	🗈 НТТР				
	🖂 JMS				
	🖹 LAN File				

Figure 6.14: Manage LAN File Source

4. Click the **New** link. The Create LAN File Source screen is displayed (see Figure 6.15).

Configure > Services > Source > LAN File					
[-] Standard properties					
Name *					
Description *					
File Path *					
File Name *					
File System *	UNIX				
Use VFS *					
Secure	V				
User Id *					
Password					
Confirm Password					
[+] Advanced properties					
* Mandatory fields.					
Save Cancel Test					

Figure 6.15: Create LAN File Source

- 5. Enter the name and the description of the new LAN File Source in the *Name* and *Description* fields respectively.
- 6. Enter the network path of the source file in the *File Path* field in the following format:

#### \\hostname\folder name

For example, if a file named *sales.txt* is stored in a shared folder employee of a host Server. The File Path will be \\*Server\employee\* 

- 7. Enter the name of the source file in *File Name* field. For Example Sales.txt.
- 8. Select the file system whether Windows or Unix from the *File System* dropdown list.
- 9. When Adeptia Suite is installed on Windows, the LAN File Source uses windows service to connect to remote machine to access any file. It just connects once and uses the same connection with the same User ID and Password (which is stored in the cache) every time. If you want to enforce the validation of User ID and Password every time while accessing the file on a remote machine, check *Use VFS* checkbox.
- 10. If authentication is required to access the source file, check the *Secure* checkbox.
- 11. Enter the username in the User ID field.
- 12. Enter the password, if required, in the *Password* field. Then re-enter the password in the *Confirm Password* field.

٥			about section		Properties	refer	to	Changing	Advanced
	exe the the	cution, Advan JTA bl	you car ced Proj ock in v	n check the perties. This	<i>Delete File c</i> s selection w AN source f	on Succ vill dele	: <i>ess</i> ete t	used in the p checkbox, w he LAN sour is executed	hile defining ce file once

- 13. Click **Save** button. This displays a screen confirming that the LAN File Source activity has been created successfully. If the *Comments* property is enabled, then clicking **Save** will display a screen where you need to enter comments related to creating the LAN file source (refer to Figure 3.6).
- 14. Enter the comments in the Add Comments field.



The comment should be at least 1 character in length.

15. Click **OK** to save the comments. This displays a screen confirming that the LAN File Source activity has been created successfully.

By default, the *Comments* property is disabled. To enable it, refer to the *Updating System Properties* section in *Administrator* Guide.



You can verify the LAN file source activity at design time. For this, click **Test**. This verifies the values in the *File Path*, *User ID* and *Password* fields.



and checks whether the file actually exists in the specified location.

### **CREATING MAIL SOURCE ACTIVITY**

Mail Source provides the ability to specify a file as a source that is accessible via Mail.

In the Adeptia Suite this feature is available in:

BPM Suite	Integration Suite	ETL Suite		
$\checkmark$	$\checkmark$	$\checkmark$		

#### Steps to create a Mail Source Activity

- 1. In the Adeptia Suite homepage menu, click **[+]** Configure to expand the tree. All the items in the Configure category are displayed.
- 2. Click [+] Services to expand the tree. All the items in the Services category are displayed.
- 3. Click **[+] Source** to expand the tree, and then click **Mail**. The Manage Mail Source screen is displayed (see Figure 6.16).

[+]	My Tasks	Config	jure > Services > Source > Mail					
[+]	My Documents							
[+]	My Solutions	New	Edit   Delete   Revisions   Dependencies		Select Field to Search V			Search
[+]	My Monitor							
[+]	History							
		#	Name	Descripti	ion	Owner	Perm.	Modified 🔻
[+]	Design	1 ()	ReceiveCustomerOrders	get email with order data file in	n excel	demouser	RWX	09/01/09 12:28
[-]	Configure	2 ()	EvalPF_MailSource	mail source		demouser	RWX	08/23/05 13:53
	+] Forms							
	+] WorkFlow							
[	-] Services							
	[+] Data Dictionary							
	[-] Source							
	<b>0</b> ∳ Adv. Database							
	0+ Database							
	E File							
	₽ <mark>\$</mark> FTP							
	HTTP							
	🖾 JMS							
	🖹 LAN File							
	🖾 Mail							

#### Figure 6.16: Manage Mail Source

4. Click the **New** link. The Create Mail Source screen is displayed (see Figure 6.17).



Configure > Services > Source > Mail	
[-] Standard properties	
Name *	
Description *	
Protocol *	POP3 -
Incoming Mail Server *	
Domain	
CDO host machine	
Enable SSL	
Port	110
UserId	
Password	
Confirm Password	
Search based on following filter crite	eria *
Sender E-mail	
Subject	
Mail Content	
Data Location*	Attachment 💌
File Name	
Leave Copy On Server	
[+] Advanced properties	
* Mandatory fields.	
Save Cancel Test	

### Figure 6.17: Create Mail Source

5. Enter the name and the description of the new Mail Source in the *Name* and *Description* fields respectively.



- 6. Select the Internet standard protocol to be used for retrieving incoming mails, from the *Protocol* drop-down list. You can select either POP3, IMAP4 or MAPI protocol. Based on the selected protocol, the default port number for that protocol is displayed in the *Port* field.
- 7. Enter the incoming mail server address in *Incoming Mail Server* field.

To access mails from Microsoft Exchange Server use MAPI in the Protocol drop-down list. To connect Adeptia Suite with Microsoft Exchange Server, you need to buy a third party tool called *J-Integra for Exchange*. J-Integra for Exchange is a high performance middleware bridge that enables Java Exchange interoperability. If you want to retrieve mails from an Exchange Server using J-Integra, select MAPI in the Protocol drop-down list. If MAPI is selected in the Protocol drop-down list: Enter name of the exchange server in the Incoming Mail Server field Enter the domain name in the Domain field Enter the name of the CDO host machine in the CDO host machine field. CDOConfig.exe is a tool that comes with the J-Integra for Exchange SDK and is used for configuring CDO. Host where CDO is configured is called CDO host machine. For detailed information about Jintegra for Exchange, refer to http://j-integra.intrinsyc.com/products/exchange/.

- 8. Check the *Enable SSL* checkbox, if the specified incoming mail server requires a secure connection.
- 9. The default port number for the selected protocol is displayed in the *Port* field. If you want to change this port number, enter the new port number in the *Port* field.
- 10. Enter the username and password of Mail Server in the *User ID* and *Password* fields respectively. Then, re-enter the password in the *Confirm Password* field.
- 11. Select any of the following filter criteria:
- Sender E-mail
- Mail Subject
- Mail Content

You may select more than one filter criteria.

- 12. Enter the sender's email address and subject of email in the *Sender Email* and *Subject* fields respectively.
- 13. To define search based on mail content, enter the required content in *Mail Content* field.



You can also use asterisk and Wild Cards in *Mail Content* field.

- 🛕 ADEPTIA
- 14. Select the location of data in the mail whether it is in attachment or in email body from the *Data Location* drop-down list. This is mandatory.
- 15. If you select an Attachment in the Data Location field, enter the name of the file in the File Name field.

Ø Mai

Mail Source activity does not support more than one file attachment.

16. If you want to leave a copy of the mail on the Server, check the *Leave Copy On Server* checkbox.



To learn about Advanced Properties refer to **Changing Advanced Properties** section.

- 17. Click **Save** button. This displays a screen confirming that the Mail source activity has been created successfully. If the *Comments* property is enabled, then clicking **Save** will display a screen where you need to enter comments related to creating the Mail file source (refer to Figure 3.6).
- 18. Enter the comments in the Add Comments field.



The comment should be at least 1 character in length.

19. Click **OK** to save the comments. This displays a screen confirming that the Mail source activity has been created successfully.

M

By default, the *Comments* property is disabled. To enable it, refer to the *Updating System Properties* section in *Administrator* Guide.

You can verify the mail source activity at design time. For this, click **Test**. This verifies the values in the In*coming Mail (POP3) Server, Port, User ID* and *Password* fields and checks whether the source activity actually exists in the specified location.

۲	When a mail event triggers process flows, each process flow uses a mail
Ø	source. At times, when multiple process flows use a mail source, errors can
	occur. In such a case, you can retry the action before exiting the mail
	source. You can set the number of retries and the sleep time between each
	retry, in case an error occurs while using a mail box. To change the
	settings, refer to the <i>abpm.mailEvent.retry</i> property in the <i>Administrator</i>
	Guide.

# **CREATING WEBDAV SOURCE ACTIVITY**

The WebDAV Source activity provides the ability to specify files that is stored in a WebDAV Server, as a source.

In the Adeptia Suite this feature is available in:

BPM Suite	Integration Suite	ETL Suite
$\checkmark$	$\checkmark$	$\checkmark$

#### Steps to create WebDAV Source Activity

- 1. In the Adeptia Suite homepage menu, click **[+]** Configure to expand the tree. All the items in the Configure category are displayed.
- 2. Click [+] Services to expand the tree. All the items in the Services category are displayed.
- 3. Click **[+] Source** to expand the tree, and then click **WebDAV**. The Manage WebDAV Source screen is displayed (see Figure 6.18).

[+] My Tasks	Configure	> Services > Source > WebDAV			
[+] My Documents					
[+] My Solutions	New   Edit	Delete   Revisions   Dependencies	Select	Field to Search 🔽	Search
[+] My Monitor					
[+] History					
	#	Name	Description	Owner Perm.	Modified 🔻
[+] Design			No records found		
[-] Configure					
[+] Forms					
[+] WorkFlow					
[-] Services					
[+] Data Dictionary					
[-] Source					
🚺 🔶 Adv. Database					
<b>0</b> ♦ Database					
🗐 File					
C FTP					
🗄 НТТР					
🖾 JMS					
🗈 LAN File					
🖾 Mail					
🗄 WebDAV					

Figure 6.18: Manage WebDAV Source

4. Click the **New** link. The Create WebDAV Source screen is displayed (see Figure 6.19).



Configure > Services > Source > WebD	VAV				
[-] Standard properties					
Name *					
Description *					
Server Name *					
Server Port *	8080				
Secure					
User Id					
Password					
Confirm Password					
File Path *					
File Name *					
[+] Advanced properties					
* Mandatory fields.					
Save Cancel Test					

Figure 6.19: Create WebDAV Source

- 5. Enter the name and description of the new WebDAV Source in the *Name* and *Description* fields respectively.
- 6. Enter the name of the WebDAV Server and Server port on which WebDAV Server is running, in the *Server Name* and *Server Port* fields respectively.
- 7. If the WebDAV is secured i.e. username and password are required to access it, then check the *Secure* checkbox and enter the username and password of the WebDAV Server in the *User ID* and *Password* fields respectively. Re-enter the password in the *Confirm Password* field.



If you are using WebDAV Server, which is built in with Adeptia Suite, the default Username is "Administrator" and the password is "indigo".

8. Enter the source file with full path in the *File Name* (full path) field. For example, */slide/files/Documents/File.txt*, where Documents is name of the folder and *File.txt* is the name of the file.



To learn about Advanced Properties refer to **Changing Advanced Properties** section.



- 9. Click **Save** button. This displays a screen confirming that the WebDAV source activity has been created successfully. If the *Comments* property is enabled, then clicking **Save** will display a screen where you need to enter comments related to creating the WebDAV source (refer to Figure 3.6).
- 10. Enter the comments in the Add Comments field.



The comment should be at least 1 character in length.

11. Click **OK** to save the comments. This displays a screen confirming that the WebDAV source activity has been created successfully.

By default, the *Comments* property is disabled. To enable it, refer to the *Updating System Properties* section in *Administrator* Guide.



You can verify the WebDAV source activity at design time. For this, click **Test**. This verifies the values in the *Server Name* and *Server Port* fields and checks whether the source activity actually exists in the specified location.

# 7 CREATING SCHEMA ACTIVITY

Schema is the structure of a file format and it specifies information about different data fields and record types that a message or a data file may contain. Designing a schema is the process of providing metadata information. Schema can be used both at the source end and the target end. At the source end, it is used to read data from the source file and at the target end, it is used to write data to the target file. The Adeptia Suite provides following types of Schema activities:

- Advance Database Schema
- Advance Positional Schema
- <u>Advance Text Schema</u>
- Database Schema
- Excel Schema
- Positional Schema
- Text Schema
- Word Schema
- XML Schema
- XML Validator
- EDI Schema

Adeptia Suite allows you to create schema in two ways:

- Using Definition File
- Entering the Fields Sequentially

#### **Using Definition File**

You can create a schema using a Definition File in three ways:

- Using Data File
- Using Field File
- Using XSD File

These methods may vary across different schemas. Their compatibility with the schemas are outlined in the table below.

Table 7.1:	Definition	File	Methods	used for	Creating	Schemas
------------	------------	------	---------	----------	----------	---------

Schema	Data File	Field File	XSD File
Advance Database Schema	$\checkmark$		$\checkmark$



Advance Positional Schema		$\checkmark$	$\checkmark$
Advance Text Schema		$\checkmark$	
Database Schema			$\checkmark$
Excel Schema	$\checkmark$		
Positional Schema			
Text Schema	$\checkmark$		

#### Using Data File

Data file is the file, which contains the actual data used as source or target during execution of a process flow. It could be same file, which is used in the process flow or another sample file of same format.

#### **Using Field File**

Field file is Comma Separated Values (CSV) file, which contains names of the fields and their definition, separated by comma. This option is helpful in case the number of fields in source or target data is very large. All the field names are picked up from this CSV file. Each line of the CSV file should contain one field name and its definition separated by comma. If the data type is *Date*, format of the date must be specified after data type, separated by comma.

Incase a field is defined as *Date* type and date format and time format is not defined, the default date format will be mm/dd/yy and time format will be blank.

When copying a field file, you need to verify that the field format is correct and there are no extra lines in the document. Else, an error is generated when converting to HTML.

#### Field File format for Advance Positional Schema

The Field file format for Advance Positional Schema can be of two types:

- Based on Start Position and End Position
- Based on Field Length

# Field File format for Advance Positional Schema based on Start and End Position

<Record Identifier1>: <Value>, <Record Identifier2>: <Value> <RecordIdentifier Value>, <FieldName>, <Description>, <DataType>, [DateFormat], [TimeFormat], <Start Position>, <EndPosition>, <Alignment>, <Skip>



In case of Advance Positional Schema, Record Identifier and Value should be specified at the beginning of the CSV file as displayed below:

a: first,b: second first,a,first\_field,string,.,1,11,L,F first,name,name\_of\_employee,string,.,12,21,L,T first,empid,employee\_ID,int,.,22,36,L,F second,b,second\_field,string,.,1,11,L,F second,DOB,date birth,date,yyyy/dd/MM,HH: mm: ss,12,24,L,F second,Address,Address employee,string,.,25,44,L,T

where: L means left alignment R means right alignment

> T means True F means False

#### Field File format for Advance Positional Schema based on Field Length

<RecordIdentifier

*Value>,<FieldName>,<Description>,<DataType>,[DateFormat],[TimeFormat],<Leng th>,<Alignment>,<Skip>* 

In case of Advance Positional Schema, Record Identifier and Value should be specified at the beginning of the CSV file as displayed below:

a:first,b:second
first,a,first_field,string,,,11,L,F
first,name,name_of_employee,string,,,10,L,T
first,empid,employee_ID,int,,,15,L,F
second,b,second_field,string,,,11,L,F
second,DOB,date
birth,date,yyyy/dd/MM,HH:mm:ss,13,L,F
second,Address,Address employee,string,,,20,L,T

where: L means left alignment

R means right alignment

T means True F means False

#### Field File format for EDI Schema

~

<Field Separator>

<Segment Identifier>,<Field Name>,<Description>,<ID>,<Minimum Size>, <Maximum Size>

Field Separator should be specified at the beginning of the CSV file. Following is the content of sample CSV file used to create EDI schema:

ISA,Name,Employee Name,1,2,2 ISA,Age, Employee Age,2,10,10 ISA,DOB,Date of Birth,3,2,2 ISA,MaritalStatus,Employee Marital Status,4,10,10

#### Field File format for Excel and Text Schema

<Field Name>, <Data Type>, [Date Format], [Time Format]

NAME,string,, PHONE\_NO,number,, DOB,date,MM/dd/yy,hh:mm:ss DOJ,date,MM/dd/yy,

#### Field File format for Positional Schema

Field file format for Positional Schema can be of two types:

- Based on Start Position and End Position
- Based on Field Length

#### Field File format for Positional Schema based on Start and End Position

<Field Name>, <Description>, <Data Type>, [Date Format], [Time Format], <Start Position>, <End Position>, <Alignment>, <Skip>

Following is the content of sample CSV file used to create Positional schema:

name,name of employee,string,,,1,10,L,F empid,employee ID,int,,,11,30,L,T DOB,Dat of birth,date,yyyy-dd-MM,HH:mm,31,60,L,F where: L means left alignment R means right alignment

T means True F means False

#### Field File format for Positional Schema based on Field Length

<Field Name>, <Description>, <Data Type>, [Date Format], [Time Format], <Length>, <Alignment>, <Skip>

Following is the content of sample CSV file used to create Positional schema:

name,name of employee,string,,,10,L,F empid,employee ID,int,,,20,L,T DOB,Dat of birth,date,yyyy-dd-MM,HH:mm,30,L,F

where: L means left alignment R means right alignment

> T means True F means False

#### Using XSD File

XML Schema Definition (XSD) file describes the elements in an XML document. XSD file used to create the schema must be compliant to the Adeptia Suite format. To get the Adeptia Suite compliant XSD, you can edit any existing schema and download the XSD file. You can further edit the field in XSD file and use it to create the schema. For example you already created a schema with 100 fields and you want to create another schema with same 90 fields out of 100. You can download the XSD file and use that XSD file from existing schema, delete 10 additional field by editing the XSD file and use that XSD file to create another schema.

#### Entering Fields Sequentially

This is manual way of creating the schema. If you select this option, you have to enter the field's name, their data type manually in correct sequence.

When creating a schema (except XML schema), a *Record Number* attribute is automatically created at the record level. It is available for each record. If the schema is used at the source level, then this attribute will be populated in the intermediate XML file at the record level. It always starts at1. If an error is detected, then this attribute will be generated in the Error File. For example, if error is found at

record number 5 in the source file, then Record Number 5 is displayed in the Error File.

# **CREATING ADVANCE DATABASE SCHEMA ACTIVITY**

The Advance Database Schema activity is created to define how the data from multiple tables can be obtained or inserted into selected tables. The Advance Database schema uses the predefined *Database Info* to connect to the database.

In the Adeptia Suite this feature is available in:

BPM Suite	Integration Suite	ETL Suite
$\checkmark$	$\checkmark$	$\checkmark$

#### Prerequisites:

• *Database Info* activity must be created before creating Advance Database Schema activity.

#### Steps to create the Advance Database Schema

- 1. In the Adeptia Suite homepage menu, click **[+]** Configure to expand the tree. All the items in the Configure category are displayed.
- 2. Click [+] Services to expand the tree. All the items in the Services category are displayed.
- 3. Click **[+]** Schema to expand the tree, and then click Adv. Database. The Manage Adv. Database Schema screen is displayed (see Figure 7.1).

[-] Configure [+] Forms	Config	jure > Services > Schema > Adv. D	atabase				
[+] WorkFlow [-] Services	New   I	Edit   Delete   Revisions   Dependencies		Select Field to Sea	arch 💌		Search
[+] Data Dictionary	Refrest	h					
[+] Source	#	Name	Descriptio	on	Owner	Perm.	Modified <b>*</b>
[-] Schema	1 ()	PointofSalesDatabaseSchema	schema definition for Point of S	iales Db	demouser	RWX	08/06/09 14:30
28 Adv. Positional							

Figure 7.1: Manage Advance Database Schema

4. Click the **New** link. The Create Advance Database Schema screen is displayed (see Figure 7.2).



Configure > Services > Schema > Ad	v. Database		
[-] Standard properties			
Name *		]	
Description *		]	
Database Info	SELECT		•
Create Schema Definition*			
C Use XSD File		Browse	
Use Database Table     Add Root Table			
Query:	Browse Tables PK'S:	Remove	Add Child Table
[+] Advanced properties			
* Mandatory fields.			
Save Cancel			

Figure 7.2: Create Advance Database Schema

- 5. Enter the name and description for new Advance Database Schema in *Name* and *Description* fields respectively.
- 6. Select the database info activity from the Database Info Id drop-down list.



To learn how to create Database Info activity, refer to the *Creating Database Info* section in *Administrator Guide*.

- 7. To define schema definition, select one of the following options:
  - Use XSD File
  - Use Database Table
- 8. To select the XSD file, which contains schema information, select the *Use XSD File* radio button and click Browse.
- 9. To define schema using database table, select the Use *Database Table* radio button and click **Browse Tables**. The Select Schema screen is displayed with the list of RDBMS Schema in case of *SQL Server* and *DB2* Database Info (see Figure 7.3).





Figure 7.3: Select Schema



O dbo.[syscolumns]	
O dbo.[syscomments]	
O dbo.[sysdepends]	
O dbo.[sysfilegroups]	
C dbo.[sysfiles]	
O dbo.[sysfiles1]	
O dbo.[sysforeignkeys]	
O dbo.[sysfulltextcatalogs]	
C dbo.[sysfulltextnotify]	
O dbo.[sysindexes]	
C dbo.[sysindexkeys]	
C dbo.[sysmembers]	
C dbo.[sysobjects]	
O dbo.[syspermissions]	
C dbo.[sysproperties]	
C dbo.[sysprotects]	
0	
Get Columns	

10. Select the required RDBMS schema and click **Get Tables**. The Select Table screen is displayed with the list of tables (see Figure 7.4).

Figure 7.4: Select Tables



11. Select the required table and click **Get Columns** button. The following screen is displayed with the list of columns and their data types (see Figure 7.5).




Select Table	Select Columns	Query
C dbo[syscolumns]	Select All	
C dba (ayaconmenta)	Name(char)	
C dbs.[systepends]	C epelint)	
C dbo (systlegroups)	🖂 salary(numaric)	the second se
C dbs.[sysfles]	dob(datetime)	the second second
C dbo.[sysfiles1]		Clear Query
C dba[sysfereignkeys]		
C dbs.[syslalbastcatalogs]		
C dbo.(systulizextractify)		
C dbo.[sysindaxas]		
C dbs.[sysindaxkays]		
C dbo.[sysmembers]		Primary Keys
C dio [sysolpets]		
C dbs.[syspermissions]		
C dbo.(sysproperties)		
C dbo.[sysprotects]		
· · · · ·		
Get Columnia	Generate Query	
	Add Drimary Key	Clear Primary Keys

Figure 7.5: Select Columns and Primary Key

12. In *Select Columns*, select the required column(s) and click **Generate Query** button to generate the database query. The generated query is displayed in the *Query* field. You can also specify the where clause within the generated select query (see Figure 7.6).

Select Table			Select Columns	Query
C dbo.[syscolumes]	1 4	R	Select All	SELECT Name,age,salary,dob FROM
C dbo (syscomments)		5	Name(char)	dbo.[R1]
C dba[sysdepends]		R	age(int)	
C dbs[sysfiegroups]		P	salary(numeric)	
C dbs [systles]		R	dob(datetime)	
C dbs.[systies1]				Clear Query
C dbo.(sysforeignkeys)				
C dbo.[sysfulbastcatalogs]				
C dbo.[sysfeltextnetify]				
C dba[sysindexes]				
C dbs.[sysindenkeys]				
C dbo.(sysmembers)				Primary Keys
C dbo.[sysobjects]				07-070730-0
C dba.[syspermissions]				
C dbo.[sysproperties]				
C dbs [sysprotects]				
C++ + - +	-			
Get Colemns			Generate Query	1
Service Accommentation			Add Primary Key	Clear Primary Keys
			Statement Contract Contract	





	•	This query is validated, once you click the <b>Save</b> button.
Ŵ	-	In case some SQL function is used or some calculation is done over the Column Name(s), use the alias name for that Column Name(s).
		For example, for a query like:
		SELECT SID,Name+Dept,Salary FROM dbo.Employee
		You can use:
		SELECT SID, (Name+Dept) as AliasName,Salary FROM dbo.Employee
		Reason:



While getting the result set, you have to assign the output of (Name+Dept) to some new field.

13. To designate a column as Primary Key, select the required column(s) and click **Add Primary Key**. The selected column is displayed in the *Primary Key* field.



At times, you may not use the Primary Key in the query, but append it internally in the query. You need to ensure that the Primary Key name should be the same at both the places. Else, the schema will fetch the data twice for the Primary Key column and result in errors.

- 14. Click **OK** to return to the Create Advance Database Schema screen. The selected query and primary key are displayed in their respective fields.
- 15. To add the child table of the selected table, click **Add Child Table** in the Create Advance Database Schema screen. A child table is displayed under the root table (see Figure 7.7).

Design > Services > Schema > Adv. Database	
[-] Standard properties	
Name *	advdbschema1
Description *	advdbschema1
Database Info	dbi_sql (dbi_sql)
Create Schema Definition* Ô Use XSD File	Browse
© Use Database Table Add Root Table SELECT a Query: Name, age, salary, do Browse □ Query: Brow	Tables PK'S; Name 😰 Remove Add Child Table
[+] Advanced properties	
* Mandatory fields.	
Save Cancel	

Figure 7.7: Create Child Table

- 16. Click **Browse Tables** in the child table. The Select Schema screen is displayed with a list of RDBMS Schema in case of SQL Server and DB2 Database Info (refer to Figure 7.3). If HSQLDB Database Info is selected, then the Select Table screen is displayed (refer to Figure 7.4).
- 17. In the Select Schema screen, select the required RDBMS schema and click **Get Tables**. The Select Table screen is displayed with the list of tables (refer to Figure 7.4).



A **Close** button appears on the Select Table screen, in case of *SQL Server* or *DBO* Database Info. Clicking this button takes the control to the Select Schema screen.



18. Select the required table and click **Get Columns**. The following screen is displayed (see Figure 7.8).

C dba[syscolumns] C dba[syscomments] C dba[sysdagands]	Setect All Parent Table Column(s) Instant(char) Name	2
C dbo (syndapanda)	L Name(char) Plame	
	spe(int) Name 💌	
C dbs[sysHegroups]	T salary(int) Name	<u>×</u>
C dbs.(systles)	OOB(datetime) Name 💌	Clear Query
C dbs.[systles1]	Contraction of the Manual Contraction of the	Contraction of the
C dbo.[sysfareignkeya]		Related Keys
C dbo (systalbextcatalogs)		randos roys
C dbs[sysfulbactnotily]		
C dbo[sysindexes]		
C dba.(sysindeskeys)		
C dbs[sysmembers]		
C die.(sysshjects)		-
C dbs[syspamissions]		Cinar Rolated Keys
C dbo.(sysproperties)		Char Related Reys
C dbo.[sysprotects]		
c 🗳		Primary Keys
Cet Columns	Generate Query	
Cer Commis	Add Helated Key	
	Add Primary Key	
		-
		Clear Primary Keys

Figure 7.8: Select Column, Primary and Related Keys

19. In Select Columns, select the required column(s) and click **Generate Query** button to generate the database query. The generated query is displayed in the *Query* field. You can also specify the where clause within the generated select query.



A column name should not include any standard SQL keyword (for example, *Identity*), as it generates an error, when the Advance Database schema is used as a source or target database.

20. To designate a column as a Related Key, select the required column(s) and click **Add Related Key**. The selected column is displayed in the *Related Key* field (see Figure 7.9).

Select Table	Select Columns	Query
C dba[syscolumes]	Select All Parent Table Column(s)	SELECT Name, age, salary, DOB FROM dbo. [C1]
C dbo.[syscomments]	Vame(char) Name	db0.[C 1]
C dbo.[sysdepends]	🗖 age(int) Name 💌	
C dbs.[systlagroups]	🖂 salary(int) Name 💌	
C dbo(systles)	DOB(datatime) Name	Clear Query
C dbo.[availes1]		
C dbo.[sysforeigskays]		Related Keys
C dbs.[sysfaltextcatalogs]		Holatod Nojs
C dbs.[systaltestant/y]		
C dbs.[sysindexes]		Name~Name
C dbo.(sysindexkeys)		
C dbo (syamembers)		
C dbo [sysobjects]		
C dbo.[syspermissions]		Clear Helated Keys
C dbs [sysproparties]		Cour netated keys
C dbs.[syspretures]		Primary Keys
····	Generate Query	Primary Keys
Get Culumns	Add Kelated Key	Name
	Add Primary Rey	
		Clear Primary Keys
		Contract of the second division of the second

Figure 7.9: Add Related Key

- 21. To change the Primary Key, select the required column(s) and click **Add Primary Key**. The selected column is displayed in the Primary Key field.
- 22. Click **OK** to return to the Advance Database Schema screen.

23. To add another independent database table, click Add Root Table and repeat the steps from 8 to 13. Alternately, you can create a root table from the Create Advance Database Schema screen by clicking Add Root Table.

ADEPTIA

Ø	<ul> <li>At the Root level, the same table should not be used more than once.</li> </ul>
	<ul> <li>To learn about Advanced Properties refer to <u>Changing</u> <u>Advanced Properties</u> section.</li> </ul>
	<ul> <li>There are some Unicode Characters, which are reserved characters in XML. You can filter these characters by enabling Filter Unicode Character option.To enable Filter Unicode Character option, mark the <i>Filter Unicode Character</i> checkbox as checked in Advanced Properties.</li> </ul>

- 24. Click **Save** button. This displays a screen confirming that the Advance Database Schema activity has been created successfully. If the *Comments* property is enabled, then clicking **Save** will display a screen where you need to enter comments related to creating the Advance Database schema (refer to Figure 3.6).
- 25. Enter the comments in the Add Comments field.



The comment should be at least 1 character in length.

26. Click **OK** to save the comments. This displays a screen confirming that the Advance Database Schema activity has been created successfully.



By default, the *Comments* property is disabled. To enable it, refer to the *Updating System Properties* section in *Administrator* Guide.

## Special Usage Scenario Delete Records from target table

In Advance Database schema, you can set action attribute to delete the records from the target database table, if they are matching with the records of source database table. Source and target records are matched based on primary key. This attribute is enabled in Data Mapper, while mapping source and target schemas.

#### Steps to set action attribute to delete matching records

Load required source and target schema in Data Mapper. In target schema, there will be an *Action* attribute.

1. Create a constant '*delete*' and map it to *Action* attribute of the target schema.



In order to delete records where the target end database is ORACLE, IBM DB2, MS SQL server or HSQLDB, the keyword "*delete*" should be used. However for MS SQL server DBMS, the "*cancel*" keyword can also be used. "*cance*" keyword cannot be used for other RDBMS except Ms SQL server.

2. Save the Mapping activity.






To learn how to use Data Mapper, refer to section Using Data Mapper.

### Enable RollBackOn Error Attribute

In Advance Database schema, you can set the *RollBackOnError* attribute. To roll back data updation or insertion, in case any error is encountered in the target database, you need to enable *RollBackOnError* attribute. This attribute is enabled in Data Mapper, while mapping source and target schemas.

#### Steps to Enable RollBackOnError attribute

- 1. Load required source and target schema in Data Mapper. In target schema, there will be a *RollBackOnError* attribute.
- 2. Create a constant 'true' and map it to RollBackOnError attribute of the target schema.
- 3. Save the Mapping activity.



# **CREATING ADVANCE POSITIONAL SCHEMA ACTIVITY**

The Advance Positional schema activity defines the procedure to read data from a multiple record format positional file and write data in a multiple record format. To do so, user needs to specify the names and positions of the required fields in order to enable identification of those fields.

In the Adeptia Suite this feature is available in:

BPM Suite	Integration Suite	ETL Suite
$\checkmark$	$\checkmark$	



#### Steps to create Advance Positional schema

- 1. In the Adeptia Suite homepage menu, click **[+]** Configure to expand the tree. All the items in the Configure category are displayed.
- 2. Click [+] Services to expand the tree. All the items in the Services category are displayed.
- 3. Click **[+]** Schema to expand the tree, and then click Adv. Positional. The Manage Adv. Positional Schema screen is displayed (see Figure 7.10).

[-] Configure [+] Forms	Configure > Services > Schema > Adv. Posit	tional		
[+] WorkFlow [-] Services	New   Edit   Delete   Revisions   Dependencies	Select	Field to Search 💌	Search
[+] Data Dictionary				
[+] Source	# Name	Description	Owner Perm.	Modified 🔻
[-] Schema		No records found		
🞒 Adv. Database				
R Adv. Positional				
👯 Adv. Text				

Figure 7.10: Manage Advance Positional Schema

4. Click the **New** link. The Create Advance Positional Schema screen is displayed (see Figure 7.11).

Configure > Services > Schema	a > Adv. Positional	
[-] Standard properties		
Name *		
Description *		
Create Schema Definiti	on* Using . Field Length . C Start & End Positions	
C Use Definition File	XSD Browse	
C Use Data Dictionary	SELECT	Select Record
Enter the Fields Sec	uentially	
[+] Record Definition [-] Hierarchy Definition		
Add Root Re	cord Refresh	Add Child
[+] Advanced properties		
* Mandatory fields.		
Save Cancel		

Figure 7.11: Create Advance Positional Schema

- 5. Enter the name and description for Advance Positional Schema in the *Name* and *Description* fields respectively.
- 6. You need to create the schema definition for the Advance Positional Schema. You can define the schema in three ways. These are outlined as:
  - Use Definition file

- Use Data Dictionary
- Enter the Fields Sequentially
- 7. To define the schema using definition file, select the *Use Definition File* radio button, select the type of file from the drop-down list and click **Browse** button to select the required file.
- 8. To define the schema using a data dictionary, click the *Use Data Definition* radio button, select the name of the data dictionary from the drop-down list and click **Select Record** button. This displays the Select Record screen (see Figure 7.12).

Data Dictionary Name :	customer	
Record	Description	Version
🗌 Select All		
John	name	1
	Ok Cancel	

Figure 7.12: Select Data Dictionary



To know, how to create Data Dictionary, refer to the Creating Data Dictionary section.

9. This screen displays the name of the selected data dictionary and a list of all the records defined in the dictionary. Check the checkbox against the record that you want to display in the Advance Positional schema.



To display all records, check the Select All checkbox.

10. Click **OK**. This closes the Select Record screen and displays the selected records under Record Definition on the Manage Advance Positional Schema screen (see Figure 7.13). You can view or delete a record from this screen by clicking the appropriate button for that record.



Schema >	Advance Posit	ional Schema								
Stand	dard properti	es								
	Name *		customer	customer						
	Description *			customer						
	Create Sche	ma Definition*								
	OUse Defin	ition File	XSD 🛩		Browse					
	⊙Use Data	Dictionary	custom	er (customer) 🗸 👘 Sele	ect Record					
		1		g ⊙Field Length ⊙Sta		ons				
[-]	Record Defi					20.0 Electronic				
	#	Record N	ame	Description	Version	Action				
	1	John		name	1	View Delete				
[-]	Hierarchy Do Ad	d Root Recor John	d required	Refresh Y N minoccur 1 m	axoccur 1	Remove Add (				
Advar	nced proper									
		ties								
landatory		lies								

Figure 7.13: Create Record Definition using Data Dictionary

11. To enter the fields manually, select the *Enter the Fields Sequentially Using* radio button and click **(+) Record Definition**. This expands to display the Record Definition fields (see Figure 7.14).



Schema > Advance Positional Schema	
[-] Standard properties	
Name *	
Description *	
Create Schema Definition <sup>*</sup> Using	
OUse Definition File XSD Browse	
OUse Data Dictionary SELECT	Select Record
[-] Record Definition	
UKG - Kenneral besiden vertik inv	
1) Field Definition for Record Identifier* Value*	
# FieldName Description Type DateFormat TimeFormat Start End L	ength Align Skip
1 string v mmddyyyy v hh:mm:ss v 1	
2 string v mmddyyyy v hh:mm:ss v	L 🖌 🗖
3 string v mmddyyyy v hh:mm:ss v	L 🖌 🗖
4 string rmddyyyy hh:mm:ss	L 🗹 🗖
Number of Rows 1 at Position 5 Add Row Remove Row Remove Record Add Record	
[-] Hierarchy Definition	
Add Root Record Refresh	
Y	
Record ID* required N minoccur 1 maxoccur 1 Remove A	Add Child
[+] Advanced properties	
* Mandatory fields.	
Save Cancel	

Figure 7.14: Create Record Definition

- 12. Enter name and description of the field in *FieldName* and *Description* fields respectively.
- 13. Select the type of data from *Type* drop-down list. For data type selection, refer to Table 7.2.
- 14. If data type is *Date*, select the format of date and time from the *DateFormat* and *TimeFormat* drop-down lists respectively.
- 15. To define field position select one of the following options:
  - Field Length
  - Start & End Positions
- 16. To define the field position using field length, select *Field Length* radio button and enter the length of the field in the *Length* field.
- 17. To define the field position using start and end position, select the *Start & End Positions* radio button.
- 18. Enter the start position of the field in the *Start* field.



19. Enter the end position of the field in the *End* field.

Ø	The starting position of a row in a positional file is 1. In a positional file, tab is counted as one position and not eight positions.
	By default, field positions are created in sequence. You can also create a schema with fields that are not in sequence. For details, refer to the Defining Field Positions Non-Sequentially section.

20. Select the alignment of the field from the Align drop-down list.



From **Align** select **L** if the field is left aligned. **R** if the field is right aligned.

To insert rows, specify the number and position of the rows to be added in the *Number of Rows* and at *Position* fields respectively and click **Add Row** button. Maximum 99 rows can be added at a time.

21. Check the *Skip* checkbox if you want to skip this field while generating the XML. This selection skips the fields that are not required for the schema. For example, the source file has over 1500 fields, but you just need to use 1000 fields. This selection skips the 500 unrequired fields, and does not read them, when the data is parsed to the XML. When the data file is created, the skipped fields are displayed in the file but are not read. If the schema is created using an existing XSD, the skipped fields will appear as a blank value. However, when the schema is used in other activities such as Mapping, all its fields are displayed.



The skipping of unrequired fields is useful in case of a standard XSD with a large number of fields, as it reduces the size of the generated XML which now contains only the required fields.

While editing the schema, when the data file is downloaded, the skipped fields are represented by 'T' and the unskipped fields by 'F' (see Figure 7.15). Similarly, while viewing the Print-Friendly Page, the skipped fields are represented by 'T' and the unskipped fields by 'F'.



sd	xml version="1.0" encoding="ISO-8859-1"? W3C Schema generated by Adeptia Editor <xs:schema xmlns:xs="http://www.w3.org/2001/XMLSchema"> <xs:element name="Root"> <xs:element name="Root"> <xs:annotation><xs:appinfo><xsdtype>Advanced</xsdtype></xs:appinfo></xs:annotation></xs:element></xs:element></xs:schema>						
<xs:annotation><xs:appinfo><xsdtype>Advanced</xsdtype> Field Name:John John,Name,Name,string,,,1,10,L,F John,Age,Age,string,,,11,14,L,1</xs:appinfo></xs:annotation>							

Figure 7.15: Skipped and Unskipped Fields in the Data File

- 22. Enter the name of any field in *Record Identifier* field and the value of the field in the *Value* field.
- 23. Click **Add Record** to define another set of data and repeat the steps from 6 to 20.
- 24. After defining records you need to define their hierarchy. This is mandatory for creating an Advance Positional schema.
- 25. Once you have added the records and defined the Record Identifiers and their values, click the **Refresh** button under **Hierarchy Definition**. This populates the Record Identifiers of the defined records, in the Record ID field under Hierarchy Definition (see Figure 7.16).



End Length Aligr
i0 50 L 🗠
i4 4 L 🗙
LY
e Record
End Length Aligr
00 50 L V
e Record
End Length Aligr
0 10 L 🗸
L
L

Figure 7.16: Create Record Hierarchy Definition

26. Select a record from the *Record ID* listbox.


- 27. Select *Y* or *N* from the required listbox, to indicate whether the selected record needs to present in the source file.
- 28. Enter the minimum number of occurrences of the selected record required in the source file, in the *minoccur* field. This value is based on the selection in the required field. If it has the value as 'Y', then the minoccur field should have a value as a minimum of 1. If the value is 'N', then the minoccur field can be 0.
- 29. Enter the maximum number of occurrences of the selected record required in the source file, in the *maxoccur* field. It should be a maximum of 2147483647.
- 30. You can now create a hierarchy either at the root level or at the child level.

#### Using Hierarchy at Root Level

#### To use a hierarchy at the Root Level

1. Click **Add Root Record** button. This creates a record at the same level as that of the displayed record (see Figure 7.17).

[-] Hiera	rchy Definitio	n									
	Add Root Record			Refresh							
	🗀 Record ID*	John Stationary	*	required	Y N	minoccur	1	maxoccur	1	Remove	Add Child
	🗀 Record ID*	John Stationary	~	required	Y N	minoccur	1	maxoccur	1	Remove	Add Child



- 2. Select a record from the Record ID field of the displayed record and enter all its related information.
- 3. Similarly, select a record from the *Record ID* listbox of the root record and repeat step 25-26 to create another root record.




Every record must have a unique Record ID. For example, if *John* is selected as the first root record, then you need to select *Stationary* in the next root record.


#### Using Record at Child Level

#### To use a record at the Child Level

1. Click **Add Child** button. This creates a record at a level below that of the displayed record (see Figure 7.18).







- 2. Select a record in the *Record ID* field of the displayed record and enter all its related information.
- 3. Select a record from the *Record ID* listbox of the root record and repeat step28-29 to create a child record.



A parent and child record must have a unique Record ID in one hierarchy. For example, if *John* is selected as the parent record, then you need to select *Stationary* as the child record. Similarly, if you create another child record under *Stationary*, then you need to select *North* as its Record ID (see Figure 7.19).





Figure 7.19: Create another Child Record



4. Click **[+]** to expand **Advanced Properties**. Advanced properties of advance positional schema are displayed (see Figure 7.20).



[-] Advanced properties		
Hierarchy XML	Рори	late
Handle CR/LF (Source Data)	<b>v</b>	
Target Record Separator		
Data Truncation		
Validate Target Record Identifier		
Allow Less Fields		
Allow More Fields		
Filter Invalid XML Characters		
Owner*	admin (Default Administrator)	
	Read Write Execute	
	Owner 🔽 🔽	
Permissions*	Group 🔽 🗖	
	Other	
* Mandatory fields.		
Save Cancel		

#### Figure 7.20: Change Advanced Properties

5. Click **Populate** to display the XML code for the defined hierarchy. This field is editable. In case there are numerous records, you can create a flat hierarchy and then edit this xml code to change to the desired hierarchy. If you edit or enter new XML code for the hierarchy, then it will override the existing hierarchy.



It is recommended that you edit this xml code in another editor by copying it to the editor and then making the changes. Once you are done with the changes, you can paste it into the *Hierarchy xml* field. Once you have pasted the xml code in this field, you should not click the **Populate** button again or make changes to the Hierarchy, as it will replace the edited xml with the original xml code.

- 6. Uncheck the *Handle CR/LF (Source Data)* checkbox, if the source file does not have any carriage return. By default, this option is checked, and schema expects file with carriage return. Handle CR/LF (Source Data) option is applicable only for the schema used at the source end.
- 7. Enter the record separator for target records, in the *Target Record Separator* field.
- 8. Check the *Data Truncation* checkbox, in case the data length is more than specified in the schema and you want to pass the specified length of data and ignore the rest of the data.
- 9. Check the *Validate Target Record Identifier* checkbox, if the value of the target record identifier in XML must match with the value specified in the schema. By default, this checkbox is unchecked. It means that if the Record Identifier Value is not exactly same, then it does not generate error records.



- 10. Check the *Allow Less Fields* checkbox, if you want to parse the data even if the number of fields in the data file is less than the number of field specified in the schema. If Allow Less Fields checkbox is checked and the schema is used at source end, schema will parse the input data and insert the empty tag of missing fields. If the schema is used at target end, it will write all the tags coming in input XML.
- 11. Incase number of fields in source data is more than the number of fields specified in the schema, only those fields are parsed, which are specified in schema. Other fields are ignored. If you want to generate error records, when number of fields in source data is more than the number of fields specified in schema, uncheck the *Allow More Fields* checkbox.
- 12. In case the input data contains some characters that are invalid in XML, then this may result in the mapping getting aborted. You can filter these invalid XML characters by checking the *Filter Invalid XML Characters* checkbox.



To learn about other Advanced Properties refer to **Changing Advanced Properties** section.

- 13. Click **Save** button. This displays a screen confirming that the Advance Positional schema activity has been created successfully. If the *Comments* property is enabled, then clicking Save will display a screen where you need to enter comments related to creating the Advance Positional schema (refer to Figure 3.6).
- 14. Enter the comments in the *Add Comments* field.



The comment should be at least 1 character in length.

15. Click **OK** to save the comments. This displays a screen confirming that the Advance Positional schema activity has been created successfully.



By default, the *Comments* property is disabled. To enable it, refer to the *Updating System Properties* section in *Administrator* Guide.

#### **Defining Field Positions Non-Sequentially**

By default, the fields of a schema are created in a sequence. At times, you may need to create a schema with field positions that are not in sequence. For example, there are 500 fields in the source file, but you need to create a schema with only 200 fields. But these 200 fields are not in sequence. In such a case, you can create a schema by defining the start and end position of the fields in a non-sequential manner.

#### Steps to define field positions non-sequentially

- 1. Click the Start & End Positions radio button.
- 2. Enter the end position of the field in the End field, after which you want to create a field position that is not in sequence.
- 3. The *Start* field of the next field is activated, where you can define a new start position for the field. For example, you can define a start position (other than

11) such as 15 and the end position such as 25 for the Address field (see Figure 7.21).

Sche	ma >	• Advan	ice I	Positiona	I Schem	18													
[-] \$	Stan	dard p	rop	perties															
		Name	•			customer													
		Desc	ripti	ion*		customer													
		Creat	te S	ichema D	Definitio	on* Usin	g Of	Field L	ength	💿 Sta	rt & End	Position	S						
		OUs	ie D	efinition	File	XSD 👻					Browse.								
		OUs	ie D	)ata Dicti	ionary	SELE	CT								~	Se	lect	Re	cord
		⊙Er	iter	the Field	ls Sequ	uentially													
	[-]	Reco	rd [	Definitio	n														
				Field De								Je* John	1982						
				# Field Name	dName Name	Descrip	Sector States	2.1	Date dww	Forma	at Tin hh:mm	neFormat	S	tart 1	End L	ength	Alig	1	kip
			-	Address	Addres			1	dww	4	hh:mm			15	25	11			
			3		1	string			dyyyy	~	hh:mm		V		1		Ē	~	_
			4		<u> </u>	string		1	ldww	¥	hh:mm		~	1		+	-	~	
			Nu	mber of F	Rows 1		- Positi			dd R				<u> </u>		-			
			1	Remov			Remo	ove Re	cord		Add	Record	ĵ						
	[-]	Hiera	rch	y Defini	0.0000000000				_										
				Add Ro	oot Re	1		Refres	h										
			🗀 F	Record IE	)* n	equired	Y N	minoc	cur 1	m	axoccur	1 F	tem	iove	4	dd C	hild		
					Are the	20 1.2													
[+]	Adva	anced	pro	perties															
* Man	dator	y fields																	
Sav	е	Cano	el																

Figure 7.21: Defining Field Positions Non-Sequentially

4. This implies that when the schema is created, the *Name* field is created with 10 positions. However, the *Address* field starts at the 15th position. The positions between 11 and 14 remain blank.



You can also change the field positions non-sequentially, while editing the schema. This feature is available in the case of Advance Positional and Positional

This feature is available in the case of Advance Positional and Positional Schemas only.

## **Viewing Print-Friendly Page**

You can view a summary of the schema and its record definition and hierarchies in edit mode.

#### Steps to view Print-friendly page

- 1. In the Adeptia Suite homepage menu, click **[+]** Configure to expand the tree. All the items in the Configure category are displayed.
- 2. Click [+] Services to expand the tree. All the items in the Services category are displayed.
- 3. Click **[+]** Schema to expand the tree, and then click Adv. Positional. The Manage Advance Positional Schema screen is displayed (refer to Figure 7.10).
- 4. Click the radio button against the schema activity whose summary you want to view. This selects the schema and activates the **Edit** link. Clicking this link displays the Edit Advance Positional Schema screen (see Figure 7.22).

Schema > Advance Positional Schema	> customer	
[-] Standard properties		
Name *	customer	
Description *	cust	
Download Schema Defin	ion File Download Print-friend	ly Page
Create Schema Definition	*	
OUse Definition File	XSD Browse	
Enter the Fields Seque	ntially Using ● Field Length ● Start & End I	Positions
[+] Record Definition [-] Hierarchy Definition		
Add Root Rec	ord Refresh	
<mark>John</mark> ⊐Record ID* Static	nary required N minoccur 1 maxoo	CCUI 1 Remove Add Child
□ ₽-Record ID*	n Y	xoccur 1 Remove Add Child
□ Record ID* Static	ary required N minoccur 1 maxo	ccur 1 Remove Add Child
[+] Advanced properties		
* Mandatory fields.		
Save Save As Cancel	Test	

Figure 7.22: Edit Advance Positional Schema

5. Click **Print-friendly Page** button. The summary screen is displayed (see Figure 7.23).



Advance Positional Schema Field Definition
Advance Positional Schema Name: Customer

### 1) Record Identifier Name = CustomerName, Record Identifier Value = John

1) Record Identifier Hame - Customeritane, Record Identifier Value - Solut											
FieldName	Description	Туре	DateFormat	TimeFormat	StartPos	EndPos	Length	Alignment			
CustomerName	Name	string			1	50	50	L			
Age	Age	number			51	54	4	L			

2) Record Id	entifier Nan	ie = C	ategory, Red	ord Identifie	r Value =	Station	ary	
FieldName	Description	Туре	DateFormat	TimeFormat	StartPos	EndPos	Length	Alignment
ProductName	Product	string			1	50	50	L
Category	Category	string			51	100	50	L

#### **Record Hierarchy Definition**

M

Record ID = John, required = N, minOccurs = 1, maxOccurs = 1

 $\Box$   $\Box$  Record ID = Stationary, required = N, minOccurs = 1, maxOccurs = 1

Figure 7.23: Print-Friendly Page

You can print a summary of the EDI segment definition and hierarchies too.

Similarly, you can view the Print-friendly page for the Positional Data Dictionary, by clicking the **Print-friendly Page** button on the Edit Positional Data Dictionary screen.

If the source file of the schema contains skipped fields, then the skipped fields are represented by 'T' and the unskipped fields by 'F'.

## Special Usage Scenario

### Enable IsRemoveHeader Attribute

In Advance Positional schema used as target schema, you can set the *IsRemoveHeader* attribute. To skip a record from the source file to be inserted/updated in the target database, you need to set *IsRemoveHeader* attribute to 'True'. This attribute is set in Data Mapper, while mapping source and target schemas.

#### Steps to set IsRemoveHeader attribute

Load required source and target schema in Data Mapper. In target schema, there will be an *IsRemoveHeader* attribute.

- 1. Create a constant 'true' and map it to IsRemoveHeader attribute of the target schema.
- 2. Save the Mapping activity.



Ø

To learn how to use Data Mapper, refer to section Using Data Mapper.

# **CREATING ADVANCE TEXT SCHEMA ACTIVITY**

The Advance Text Schema activity is used to define how to read data from advance text files and how to write data in advance text file. Advance text file refers to text file which can have multiple record formats and multiple field separators.

In the Adeptia Suite this feature is available in:

BPM Suite	Integration Suite	ETL Suite
$\checkmark$	$\checkmark$	$\checkmark$

Figure 7.24 displays a sample Advanced Text file.

```
12345678D 07/12/2007 XYZ SYSTEMS, INC. 443 NORTH CLARK AVE, SUITE 350 CHICAGO, IL
60610
Agent: JOHN SMITH 443 NORTH CLARK AVE, SUITE 350 CHICAGO, IL 60610
Officer: JOHN SMITH 443 NORTH CLARK AVE, SUITE 350 CHICAGO, IL 60610
56789101D 07/16/2007 XYZ INTERNATIONAL INC 443 NORTH CLARK AVE, SUITE 350
CHICAGO, IL 60610
Agent: NICK MASSA 443 NORTH CLARK AVE, SUITE 350 CHICAGO, IL 60610
Officer: NICK MASSA 443 NORTH CLARK AVE, SUITE 350 CHICAGO, IL 60610
```

Figure 7.24: Sample Advanced Text File

In the Text File shown in Figure 7.24 there are three types of records. The first field of all record is considered as the *Record Identifier*. In this example, the record identifier of the first record is an eight-digit number followed by character 'D' (e.g. *12345678D*). It could be any number followed by 'D'. The second and third record identifiers are *Agent* and *Officer* respectively. In this text file, two field separators ':' colon and space are used.

#### Steps to create Advance Text Schema

- 1. In the Adeptia Suite homepage menu, click **[+]** Configure to expand the tree. All the items in the Configure category are displayed.
- 2. Click [+] Services to expand the tree. All the items in the Services category are displayed.
- 3. Click **[+]** Schema to expand the tree, and then click Adv. Text. The Manage Adv. Text Schema screen is displayed (see Figure 7.25).



[-] Configure	Configure > Services > Schema > Adv. Po	sitional		
[+] WorkFlow [-] Services	New   Edit   Delete   Revisions   Dependencies	Select Fie	ld to Search 💙	Search
[+] Data Dictionary				
[+] Source	# Name	Description	Owner Perm.	Modified 🔻
[-] Schema		No records found		
📋 Adv. Database				
📲 Adv. Positional				
S Adv. Text				
🗊 Database				


Figure 7.25: Manage Advance Text Schema

4. Click the **New** link. The Create Advance Text Schema screen is displayed (see Figure 7.26).

Configure > Services > Schema > Adv.	Text	
[-] Standard properties		
Name *		
Description *		
Record Separator*		
Field Separator*		
Create Schema Definition*		
C Use Definition File	XSD 🔽	Browse
Enter the Fields Sequentially		
[+] Record Definition [-] Hierarchy Definition		
Add Root Record	Refresh Y Minoccur 1 maxoccur 1	Remove Add Child
[+] Advanced properties		
* Mandatory fields.		
Save Cancel		

Figure 7.26: Create Advance Text Schema

- 5. Enter the name and description of new Advance Text schema activity in *Name* and *Description* fields respectively.
- 6. Enter the record separator, for example \n for new line or \s for space, in the *Record Separator* field. The record separator is used to separate records.
- 7. Enter the Field Separator, for example \t for Tab or \s for space in the *Field Separator* field. Field Separator is used to separate fields.





'+', '*', or ' ' cannot be directly used as field separator. To use such character as field separator you need to use these characters within parentheses e.g. [+], [*] or [ ] in <i>field separator</i> field.
<ul> <li>But if same schema is used at target end, in target data file, field separator will be [+], [*] or [I]. To avoid it enter '+', '*', or ' ' etc in the <i>Target Field Separator</i> in the <i>Advanced Properties</i>.</li> </ul>
<ul> <li>You can also use hex values in record and field separator.</li> </ul>
<ul> <li>To define the hex values as field separator at target end, you need to use <b>Ox</b> before the value. For example if you want to use <b>space</b> as field separator, you need to define <b>Ox20</b>.</li> </ul>
<ul> <li>To use hex value in field separator at source end, you need to define the hex value as regular expression. For example for <b>space</b> as field separator at source end, you need to define \x20.</li> </ul>
<ul> <li>In Record Separator, hex values are supported at both source and target end. To define hex value in record separator at source end you need not enter the value as regular expression. For example for space as record separator, you need to define Ox20.</li> </ul>
<ul> <li>You can also specify two hex values together in record and field separator. For example for two spaces you need to define 0x200x20.</li> </ul>

- 8. To define schema definition, select one of the following options:
  - Use Definition File
  - Enter the Fields Sequentially
- 9. To define the schema using definition file, select the *Use Definition File* radio button; select the type of file from the drop-down list and click the Browse button to select the required file.
- 10. To enter the fields sequentially, select *Enter the Fields Sequentially* radio button and click **(+) Record Definition**. This expands to display the Record Definition fields (see Figure 7.27).



Configure > Services >	Schema > Adv. Tex	t				
[-] Standard properties						
Name *	Ţ	Advanced_Text_Sche	ma			
Description *	ע	Advanced Teext Schema				
Record Separa	tor*	\n				
Field Separator		s				
Create Schema	L	0				
C Use Definit	-	XSD 💌	Brov	wse		
Enter the Fi	elds Sequentially	,				
[-] Record Defini						
1) Field	Definition for Record	Identifier*				
#	FieldName	Match Pattern	Skip Pattern	Min Size	Max Size	Position
1						
2						
3						
4						
Numbe	of Rows 1 at Po	sition 5 Add R	ow Remove Rov	N		
		ld Record				
[-] Hierarchy Def	inition					
Add	Root Record Re	fresh				
C Poco	Record ID* required N minoccur 1 maxoccur 1 Remove Add Child					
		minoccur	maxoccur	itemove /		
[+] Advanced properties	5					
* Mandatory fields.						
Save Cancel						

Figure 7.27: Create Record Definition

- 11. Enter the record identifier in the *Record Identifier* field. You can use regular expression in Record Identifier.
- 12. Enter name the field in the *FieldName* field.
- 13. Enter the match pattern, against which you want the record to be matched, in the Match Pattern field.



You can use regular expression in the Match Pattern. For example, in the data file, there is field Company Name which can have value like **XYZ SYSTEMS, INC**. Since **\S** is used as Field Separator, **XYZ, SYSTEM**, and **INC** will be considered separate fields. But they need to be a part of the same field. To parse this type of data, you can use match pattern. For example **\S+**.\*

(INC\.|INC(ORPORATED)?) match pattern is used specify that the field can have spaces and end with INC. or INCORPORATED.

- 14. Enter the Skip Pattern in the *Skip Pattern* field. Skip Pattern is used to skip a particular pattern. You can use regular expression in Skip Pattern.
- 15. Enter the minimum and maximum size of the field in the *Min Size* and *Max Size* fields respectively.

- 16. Enter the position in the *Position* field.
- 17. Click **Add Record** to define another type of Record format, and follow the steps from 10 to 15.

Ø	For adding more fields in the same record format, click <b>Add Row</b> button. To insert rows, specify the number and position of the rows to be added in the <i>Number of Rows</i> and at <i>Position</i> fields respectively and click <b>Add Row</b> button. A maximum of 99 rows can be added at a time.
	Advance text schema supports only String data type.
	To learn about Advanced Properties refer to <u>Changing Advanced</u> <u>Properties</u> section.
	You can enable quotes handling, by marking the <i>Quotes Handling on</i> checkbox as checked, in Advanced Properties.
	If a character (say \$) is specified as Field Separator in a record, then any \$ character in the field data of that record (Chocolate\$20\$perpack) will be considered as a Field Separator, even though it is part of the field data. In the above example the \$ after 20 will also be considered as Field Separator, whereas it is the data. To avoid this situation put that field within the double quote i.e. (Chocolate\$"20\$perpack")
	When <i>Quotes Handling on</i> is checked regular expression doesn't work on any field.
	Header contains the information about the different record structure of the Text file. You may not want to send the header information to target. In this case you can mark the <i>Ignore Header</i> checkbox as checked in Advanced Properties. This ignores the header information. This property is applicable only when schema is used at source end. This property is not applicable when schema is used at target end.
	If there are multiple record separators in an input file, then to parse this input file, you need to mark the <i>Look Ahead</i> checkbox as checked in the Advanced Properties.
	At times the input data may contain some characters that are invalid in XML, thus resulting in the mapping getting aborted. You can filter these invalid XML characters by marking the <i>Filter Invalid XML Characters</i> checkbox as checked, in Advanced Properties.

- 18. After defining records you need to define their hierarchy. This is mandatory for creating an Advance Text schema.
- 19. Once you have added the records and defined the Record Identifiers, click the **Refresh** button under **Hierarchy Definition**. This populates the Record Identifiers of the defined records, in the *Record ID* field under **Hierarchy Definition** (see Figure 7.28).



Schema > Advance Text Sch	ema > Advance	TextSource				
[-] Standard properties						
Name *	Α	AdvanceTextSource				
Description *	A	AdvanceTextSource				
Download Schema D	Definition File	Download Print	-friendly Page	1		
Record Separator*	N	n		-		
		\s :)				
Create Schema Defi						
O Use Definition Fil	le 🛛	(SD 🔽	Bro	wse		
Enter the Fields 8	Sequentially					
[-] Record Definition						
1) Field Defi	nition for Record I	dentifier* [0-9]{8,8}+[D	ı]			
#	FieldName	Match Pattern	, Skip Pattern	Min Size	Max Size	Position
1 fild	2			0	97	1
2 fld3	3	\S+.* (INC\.  INC(OF		0	97	1
3 fld4	4			0	97	1
Number of Ro	ows 1 at Pos	sition 4 Add Roy	w Remove Roy	n Remo	ove Record	
2) Field Defi	nition for Record I	dentifier* Agent				
#	FieldName	Match Pattern	Skip Pattern	Min Size	Max Size	Position
1 fldE	6	(\D+\s)+		0	97	2
2 fld7				0	97	2
Number of Ro	ows 1 at Pos	sition 3 Add Roy	w Remove Roy	v Remo	ove Record	
3) Field Defi	nition for Record I	dentifier* Officer				
#	FieldName	Match Pattern	Skip Pattern	Min Size	Max Size	Position
1 fld9	9	(\w+\.?\s?)+(,\s?l+\{		0	97	3
2 fld1	10	(\D+\s)+		0	97	3
3 fld1				0	97	3
Number of Ro		sition 4 Add Roy	w Remove Roy	<i>n</i>		
Remove Record Add Record						
[·] Hierarchy Definition						
Add Root		fresh				
🖻 Record ID	[0-9]{8,8}+[D] ▲ * Agent	required N mino	ccur 1 maxo	ccur 1	Remove	Add Child
[+] Advanced properties						
* Mandatory fields.						
Save Save As Cancel	Test					

Figure 7.28: Create Record Hierarchy Definition

20. Select a record from the Record ID list box.

- 21. Select *Y* or *N* from the required list box, to indicate whether the selected record needs to present in the source file.
- 22. Enter the minimum number of occurrences of the selected record required in the source file, in the *minoccur* field. It should be a minimum of 1.
- 23. Enter the maximum number of occurrences of the selected record required in the source file, in the *maxoccur* field. It should be a maximum of 2147483647.
- 24. You can now create a record either at the root level or at the child level.


### Using Record at Root Level

### To use a Record at the Root Level

1. Click **Add Root Record** button. This creates a record at the same level as that of the displayed record (see Figure 7.29).

[-]	Hierarchy Definition
	Add Root Record Refresh
	CI-9](8,8)+[D] A required N minoccur 1 maxoccur Add Child
	Record ID* Agent required minoccur 1 maxoccur <b>1</b> Remove Add Child

- 2. Select a record in the *Record ID* field of the displayed record and enter all its related information.
- 3. Select a record from the *Record ID* listbox of the root record and repeat step 24-25 to create another root Record.



### Using Record at Child Level

### To create a record at the Child Level

1. Click **Add Child** button. This creates a record at a level below that of the displayed record (see Figure 7.30).

Figure 7.29: Create Root Record






Figure 7.30: Create Child Record

- 2. Select a record in the *Record ID* field of the displayed record and enter all its related information.
- 3. Select a record from the *Record ID* listbox of the root record and repeat step 28-29 to create a child record.



A parent and child record must have a unique Record ID in one hierarchy. For example, if [0-9][8,8]+[D] is selected as the parent record, then you need to select *Agent* as the child record. Similarly, if you create another child record under *Agent*, then you need to select *Officer* as its Record ID (see Figure 7.31).




Figure 7.31: Create another Child Record

 You can remove a record by selecting the record and clicking Remove. This will display a confirmation delete message, where on clicking OK, will delete the record.
 Alternately, if you delete the last fieldname of a record, and then save the schema, the entire field gets deleted. For example, a record has three fields – *Name, Description* and *Age*. If you delete *Age*, the entire field will get deleted.
 If a record has one or more child record, deleting the parent record will delete all its child record too.

4. Click **Save** button. This displays a screen confirming that the Advance Text Schema activity has been created successfully. If the *Comments* property is enabled, then clicking **Save** will display a screen where you need to enter comments related to creating the Advanced Text Schema. (refer to Figure 3.6).



5. Enter the comments in the Add Comments field.

The comment should be at least 1 character in length.

Ø

6. Click **OK** to save the comments. This displays a screen confirming that the Advanced Text Schema activity has been created successfully.



By default, the *Comments* property is disabled. To enable it, refer to the *Updating System Properties* section in *Administrator* Guide.

# **CREATING DATABASE SCHEMA ACTIVITY**

The Database schema activity defines the procedure to read data from a database table and to insert/update/delete data into a database table. Database schema uses the predefined Database Info activity to connect to the database.

In the Adeptia Suite this feature is available in:

BPM Suite	Integration Suite	ETL Suite
$\checkmark$	$\checkmark$	$\checkmark$

### Prerequisites:

• *Database Info* activity must be created before creating *Database Schema* Activity.

Steps to create Database Schema

- 1. In the Adeptia Suite homepage menu, click **[+]** Configure to expand the tree. All the items in the Configure category are displayed.
- 2. Click [+] Services to expand the tree. All the items in the Services category are displayed.
- 3. Click **[+]** Schema to expand the tree, and then click **Database**. The Manage Adv. Database Schema screen is displayed (see Figure 7.32).

[-] Configure						
[+] Forms	Confi	gure > Services > Schema > Databa	150			
[+] WorkFlow						
[-] Services	New	Edit   Delete   Revisions   Dependencies	Select Field to Se	arch 💌		Search
[+] Data Dictionary	Refres	sh				
[+] Source	#	Name	Description	Owner	Perm.	Modified 🔻
[-] Schema	1 ()	EvalJMSE_DBSchema	Database schema for Stock Quotes	demouser	RWX	04/20/06 17:21
🗊 Adv. Database	2 ()	EvalXform_DbSchema	Database Schema to parse Insurance data.	demouser	RWX	11/10/05 11:51
25 Adv. Positional	3 ()	EvalPF_DatabaseSchema_Database2	Database schema for database2	demouser	RWX	08/23/05 12:08
Database	4 ()	EvalPF_DatabaseSchema_Database1	Database schema for database1	demouser	RWX	08/23/05 12:04
Excel						
Positional						

Figure 7.32: Manage Database Schema

Configure > Services > Schema > Database				
[-] Standard properties				
Name *				
Description *				
Select Database Info*				
O Use Existing	SELECT			
O Create New	Create Database Info			
Create Schema Definition*				
O Use XSD File	Browse			
Table Name	Browse Tables			
SQL Query				
Primary Key				
[+] Advanced properties				
* Mandatory fields.				
Save Cancel				

4. Click the **New** link. The Create Database Schema screen is displayed (see Figure 7.33).

Figure 7.33: Create Database Schema

- 5. Enter the name and description for new database schema in the *Name* and *Description* fields respectively.
- 6. Select the database info activity.



To learn how to create Database Info activity, refer to the section *Creating Database Info* in *Administrator Guide*.

- 7. To select an existing database info activity, select the *Use Existing* radio button and select the database info activity from the drop-down list.
- 8. To create a new database info activity, select the *Create New* radio button and then click **Create Database Info** button. This displays the Crate Database Info screen (see Figure 7.34).



Configure > Services > Connector > I	Database Info	
[-] Standard properties		
Name *		
Description *		]
Select JDBC Driver*		
Ose Existing	SELECT	•
C Create New		Create Database Driver
Server URL *		Help
User*		]
Password		
Confirm Password		
Test Database Connec	tion	
[+] Advanced properties		
* Mandatory fields.		
Save Cancel		

Figure 7.34: Create Database Info

- 9. Enter the required parameters and click **Save** to save the database info activity and return to Create Database Schema page.
- 10. To define schema definition, select one of the following options:
  - Use XSD File
  - Table Name
- 11. To select the XSD file, which contains schema information, select the *Use XSD File* radio button and click **Browse**.
- 12. To define schema using a database table, select *Table Name* radio button and click Browse Tables button. The Select Schema screen is displayed with the list of RDBMS Schemas in case of *SQL Server* and *DBO* Database Info (see Figure 7.35).




Figure 7.35: Select Schema

 In the Select Schema screen, select the required RDBMS schema and click Get Tables. The Select Table screen is displayed with list of database tables (see Figure 7.36).




Figure 7.36: Select Tables



A Close button appears on the Select Table screen, in case of *SQL Server* or *DBO* Database Info. Clicking this button takes the control to the Select Schema screen.

ADEPTIA



If the schema and its tables are created on *DB2*, then you need to remember that the schema name in *DB2* is case-sensitive. Else, it will display the same table more than once.

14. Select the required table and click **Get Columns** button. The Select Table Column(s) screen is displayed with list of columns and their data types along with the data format whether encrypted or plaintext (see Figure 7.37).

Select Table Column(s	s):
Table name is : dbo.[sysfilegroups]Select All(Click on Select all to select all the Columnfrom specified table) or click on individucolumn name and write the simple Selequery with Comma (,) Separated Columnnames.)	al ct
groupid (smallint)	Plain Text 💌
allocpolicy (smallint)	Plain Text 💌
status (int)	Plain Text 💌
groupname (nvarchar)	Plain Text 💌
Ok Back Close	

Figure 7.37: Select Table Column(s)

15. Click **Select All** link to get select query for all columns or click on individual column names to get only those columns in select query in the provided text field. You can also specify the where clause in the generated select query.



There should not be any special character (except  $\$  and SID#) in column name.

A column name should not include any standard SQL keyword (for example, *Identity*), as it generates an error, when the database schema is used as a source or target database.

16. Select the mode of data in the column, whether *Encrypted* or *Plain Text* from the drop-down list. If the table column is used at source end and encrypted data is coming from the source, select *Encrypted* from the drop-down list. Similarly if



the table column is used at the target end and you want to send the encrypted data to the target, select *Encrypted* from the drop-down list.

Ø	<ul> <li>If Encrypted is selected in table column, you must select Encryption/Decryption secret key from Advanced Properties.</li> </ul>	
	• If <i>Encrypted</i> is selected, the encrypted data length can be more than the source data length. In this case you must define the target table column length more than the corresponding source table column length.	
	<ul> <li>If <i>Encrypted</i> is selected in table column, you must set the <i>Data</i> <i>Action</i> property in Process Designer, while creating the process flow. To know more about Process Designer, refer to the <u>Working with</u> <u>Process Flow</u> section.</li> </ul>	

17. Click **OK** to return to the Database Schema screen. The generated select query is displayed in the *SQL Query* field. You can edit this query, if required.

A	<ul> <li>This query is validated, once you click the Save button.</li> </ul>
Ŵ	<ul> <li>In case some SQL function is used or some calculation is done over the Column Name(s), use the alias name for that Column Name(s).</li> </ul>
	For example, for query like:
	SELECT SID, Name+Dept, Salary FROM dbo.Employee
	You can use:
	SELECT SID, (Name+Dept) as AliasName,Salary FROM dbo.Employee
	Reason:
	While getting the result set, you have to assign the output of
	(Name+Dept) to some new field.


- 18. Enter the Primary Key in the *Primary Key* field. Primary is the name of the field on the basis of which target database table is updated. Primary key is only used, when the database schema is used with database target.
- 19. Click [+] to expand **Advanced Properties**. Advanced properties of the Database Schema are displayed (see Figure 7.38).



[-] Advanced properties	
Query Batch Update	
Query Batch Size	
Use NoLock Option	
Update Empty Tag	
Filter Invalid XML Characters	
Encryption Secret Key	None 💌
Decryption Secret Key	None 💌
Owner*	admin (Default Administrator)
	Read Write Execute
Received	Owner 🔽 🔽
Permissions*	Group 🗹 🗌 🗹
	Other
* Mandatory fields.	
Save Cancel	

Figure 7.38: Advanced Properties of Database Schema

20. By default one record at a time is updated in Database Target. You can specify the number of records that can be updated at a time in database target. To enable batch update, check the *Query Batch Update* checkbox and enter the number of records in the *Query Batch Size* field.



- 21. To enable the No Lock option, check the *Use No Lock Option* checkbox. Whenever there are chances of locking the database table, you can enable Use No Lock Option. When this option is enabled, database schema can read the data from the database table even if the database table is locked.
- 22. When *Update Empty Tag* option is checked, empty tag (e.g. -<id/> ) in the input XML to the database target is handled as given below:

Number Type	:	updated to null value
Date Type	:	updated to null value
String type	:	updated to empty value



To learn about Advanced Properties refer to <u>Changing Advanced</u> <u>Properties</u> section.

- 23. In the Database Schema screen click **Save** button. This displays a screen confirming that the database schema activity has been created successfully. If the *Comments* property is enabled, then clicking Save will display a screen where you need to enter comments related to creating the database schema (refer to Figure 3.6).
- 24. Enter the comments in the Add Comments field.



The comment should be at least 1 character in length.

25. Click **OK** to save the comments. This displays a screen confirming that the database schema activity has been created successfully.

Ø

By default, the *Comments* property is disabled. To enable it, refer to the *Updating System Properties* section in *Administrator* Guide.

### Special Usage Scenario Delete Target Records

In Database schema, you can set *Action* attribute to delete the records from the target database table, if they are matching with the records of source database table. If Primary Key is defined in the source and target schemas, source and target records are matched based on primary key. If primary key is not defined, whole records are matched. This attribute is enabled in Data Mapper, while mapping source and target schemas.

### Steps to set action attribute to delete matching records

Load required source and target schema in Data Mapper. In target schema, there will be an *Action* attribute.

1. Create a constant 'delete' and map it to Action attribute of the target schema.



In order to delete records where the target end database is ORACLE, IBM DB2, MS SQL server or HSQLDB, the keyword "delete" should be used. However for MS SQL server DBMS, the "cancel" keyword can also be used. "cancel" keyword cannot be used for other RDBMS except Ms SQL server.

2. Save the Mapping activity.



To learn how to use Data Mapper, refer to section Using Data Mapper.

# **CREATING EDI SCHEMA ACTIVITY**



This feature is a paid service and is thus not available in any of the Adeptia products by default.

The EDI (Electronic Data Interchange) Schema activity is created to define how the data in predefined EDI format; an industry standard is managed.



This feature is a paid service and is thus not available in any of the Adeptia products by default.

### Steps to create EDI Schema

- 1. In the Adeptia Suite homepage menu, click **[+]** Configure to expand the tree. All the items in the Configure category are displayed.
- 2. Click [+] Services to expand the tree. All the items in the Services category are displayed.
- 3. Click **[+]** Schema to expand the tree, and then click **EDI**. The Manage EDI Schema screen is displayed (see Figure 7.39).

[-] Configure	Configure > Services > Scl	nema > EDI		
[+] Forms				
[+] WorkFlow				
[-] Services	New   Edit   Delete   Revisions	Dependencies	Select Field to Search 💙	Search
[+] Data Dictionary				
[+] Source	# Name	Description	Owner	Perm. Modified 🔻
[-] Schema		No records found	d	
Adv. Database				
👯 Adv. Positional				
📲 Adv. Text				
📋 Database				
Excel				
29 Positional				
Text				
HE XML				
KML Validator				
EDI				

Figure 7.39: Manage EDI Schema

4. Click the **New** link. The Create EDI Schema screen is displayed (see Figure 7.40).



Configure > Services > Schema > EDI				
[-] Standard properties				
Name *				
Description *				
Create Schema Definition*	SELE	CT 💌	Select Transaction	
[-] Segment Definition				
# EDI Specifi	cation	Description	Transaction Set	Action
[+] Advanced properties				
* Mandatory fields.				
Save Cancel				

Figure 7.40: Create EDI Schema

- 5. Enter the name and description of new EDI schema activity in the *Name* and *Description* fields respectively.
- 6. Enter the Segment Separator, e.g. '~' in the Segment Separator field.
- 7. Enter the Field Separator, e.g. '\*' in the Field Separator field.
- 8. Enter the Composite Separator, e.g. '+' in the *Composite Separator* field. A Composite Separator is used to separate composite fields (a field which contains more than one sub-fields) inan EDI file.
- 9. Check *Validate Incoming/Outgoing Data* checkbox if you want to validate the incoming and outgoing EDI Data. If this schema is used at source end, it validates the incoming EDI file and generates intermediate XML stream and an EDI acknowledgment stream. If this schema is used at target end, then it validates the input XML and generates error records if there is any error.
- 10. Select the required EDI Data Dictionary from the *Create Schema Definition* field and click **Select EDI Specification** button. This displays the Select EDI Specification screen (see Figure 7.41).

Select EDI Specification				
Data Dictionary Name : Sample_EDI_Dictionary				
EDI Specification	Description	Version		
C 832_4010.xsd	Sampel EDI Dictionary	4010		
	Ok Cancel			

Figure 7.41: Select EDI Specification



To know how to create EDI Data Dictionary, refer to the Creating EDI Data Dictionary section.



11. Select the required EDI Specification and click **Ok** button. This closes the Select EDI Specification screen. The selected EDI specification is populated under Segment Definition in Create EDI Schema screen (see Figure 7.42).

Schema >	EDI Se	chema				
[-] Stand	ard prop	erties				
	Name	*	EDI_Schema			
	Descri	ption *	Sample EDI Schema			
	Segme Separa		~			
	Field Separa	ator*	~			
	Create Definit	Schen	<sup>na</sup> Sample_EDI_Dictionary (Sar	nple EDI Data Dictiona) 💌	Select EDI Spe	cification
[-]	Segme	nt Defii	nition			
		#	EDI Specification	Description	Version	Action
		1	832_4010.xsd	Sampel EDI Dictionary	4010	View Delete
[+] Advan	iced proj	perties				
* Mandatory fi						
Save	Cancel					

Figure 7.42: Populated Create EDI Schema screen



- 12. Click **Save** button. This displays a screen confirming that the EDI schema activity has been created successfully. If the *Comments* property is enabled, then clicking **Save** will display a screen where you need to enter comments related to creating the EDI schema (refer to Figure 3.6).
- 13. Enter the comments in the Add Comments field.

1
Ø

The comment should be at least 1 character in length.

14. Click **OK** to save the comments. This displays a screen confirming that the EDI schema activity has been created successfully.

By default, the *Comments* property is disabled. To enable it, refer to the *Updating System Properties* section in *Administrator* Guide.



### Manipulating EDI Schema Hierarchy

At times you may not need all the elements of an EDI schema hierarchy. In such cases, you can remove the elements that you do not require, from the hierarchy. If you remove an element at the parent level, then all its sub-level elements are also removed.

### Steps to manipulate EDI Schema hierarchy

- 1. In the Adeptia Suite homepage menu, click **[+]** Configure to expand the tree. All the items in the Configure category are displayed.
- 2. Click [+] Services to expand the tree. All the items in the Services category are displayed.
- 3. Click **[+]** Schema to expand the tree, and then click **EDI**. The Manage EDI Schema screen is displayed (refer to Figure 7.39).
- 4. Click the EDI schema whose hierarchy you want to manipulate, and click the **Edit** link. This displays the EDI schema in the Edit mode (see Figure 7.43).

			Uter	some eroups some	nature Permissions1 (read, with
Manage	Schema > EDI Schema > El	01_837			
Automate [+] DataTransform [+] Extensions		-			
(+) HumanWorkFlow (+) Miscellaneous (+) BativeService	Name * Description *	EDI_83 Schem	a for X12 4010 837		
[+] Hotification [+] Polling	Download Schema Segment Separato	Definition File Download			
<ul> <li>Schema</li> <li>Adv. Database Schema</li> <li>Database Schema</li> </ul>	Field Separator	\n \n			
11 Excel Schema 11 HTML Schema	Composite Separa Create Schema De		Full (837Full) 💌 select ED1 specificatio	-	
11 Text Schema 11 XML Schema 11 XML Validator	[] Segment Definiti	•			0.01015
EDI Schema	1	EDI Specification full837,xsd	Description 837Feil	Version 837Full	Action View Data Manipulation Dele
12 Adv. Peollonal Schema					
12 Adv. Pestional Schema 13 Positienal Schema 19 Adv. Database Schema (*) Source					
12 Adv. Pesitional Schema 12 Positional Schema (3 Adv. Database Schema	[*] Advanced properties				

Figure 7.43: Edit EDI Schema

5. Click the **Data Manipulation** link against the EDI Segment whose hierarchy you want to manipulate. This displays the Schema XSD Tree at the root level (see Figure 7.44).



Tree Representation of Schema XSD
* Root
Save Cancel

Figure 7.44: Tree Representation of Schema XSD

6. Expand the **Root** node to view the segment hierarchy (see Figure 7.45).



e [	Root
Ŧ	ISA minOccurs :: 1 maxOccurs :: 1
+	
+	TS_837 minOccurs :: 1 maxOccurs :: unbounded
+	GE minOccurs :: 0 maxOccurs :: 1
±	IEA minOccurs ∷ 0 maxOccurs ∷ 1

Figure 7.45: Expand Root Node

7. Expand a parent node to view its child nodes (see Figure 7.46).



Tree Representation of Schema XSD
E Root
ISA minOccurs :: 1 maxOccurs :: 1
+ GS minOccurs :: 1 maxOccurs :: 1
E TS_837 minOccurs :: 1 maxOccurs :: unbounded
★ ST minOccurs :: 1 maxOccurs :: 1
■ BHT minOccurs :: 1 maxOccurs :: 1
+ SE minOccurs :: 1 maxOccurs :: 1
+ GE minOccurs :: 0 maxOccurs :: 1
+ IEA minOccurs :: [] maxOccurs :: ]
Save Cancel

Figure 7.46: Expand Parent Node

8. You can remove a child node by unchecking the checkbox (see Figure 7.47). If you uncheck a parent node, then all its child nodes will also be removed.



Tree Representation of Schema XSD
E Root
+ GS minOccurs :: 1 maxOccurs :: 1
□ IS_837 minOccurs :: 1 maxOccurs :: unbounded
▪ ST minOccurs :: 1
■ BHT minOccurs :: 1     ■ maxOccurs :: 1
+ REF minOccurs :: 0 maxOccurs :: 3
+ GE minOccurs :: 0 maxOccurs :: 1
Save Cancel

Figure 7.47: Remove Child Node

- 9. You can also change the occurrence of the elements in the hierarchy by changing the values in the *minOccurs* and *maxOccurs* fields.
- 10. Once all the changes are done, click **Save**. This saves the changes and displays the manipulated hierarchy (see Figure 7.48).



Tree Representation of Schema XSD
E Root
▪ GS minOccurs :: 1 maxOccurs :: 1
☐ TS_837 minOccurs :: 1 maxOccurs :: unbounded
+ ST minOccurs :: 1 maxOccurs :: 1
■ REF minOccurs :: 0 maxOccurs :: 3
▪ 🔽 winOccurs :: 1
▪ GE minOccurs :: 0 maxOccurs :: 1
Save Cancel

Figure 7.48: Saved Manipulation

# **CREATING EXCEL SCHEMA ACTIVITY**

The Excel Schema activity is used to define how to read data from an Excel file, and write data to an Excel file. To do so, user needs to specify the name of the Excel sheet and required fields, so as to enable identification of those fields.



While creating Excel Schema you can also define hierarchy (parent-child relationship) between the records. Parent-child relationship can be defined only when you create the schema using data file.

In the Adeptia Suite this feature is available in:

BPM Suite	Integration Suite	ETL Suite
$\checkmark$	$\checkmark$	$\checkmark$

#### Steps to create Excel Schema

- 1. In the homepage menu, click **[+]** Configure to expand the tree. All the items in the Configure category are displayed.
- 2. Click [+] Services to expand the tree. All the items in the Services category are displayed.
- 3. Click **[+]** Schema to expand the tree, and then click **Excel**. The Manage Excel Schema screen is displayed (see Figure 7.49).

[-] Configure [+] Forms	Configure > Services > Schema > Excel		
[+] WorkFlow [-] Services	New   Edit   Delete   Revisions   Dependencies	Select Field to Search M	Search
[+] Data Dictionary [+] Source [-] Schema	# Name	Description Owner	
Adv. Database     Schort A	1     OrderFulfillmentExcelSchema       2     EmployeeBenfitsExcelSchema	schema definition of order file demouser schema definition of benefit file demouser	
👷 Adv. Text	3 O EvalScript_ExcelSchema 4 O EvalXform_ExcelSchema	Excel Schema for employee record demouser Excel Schema demouser	
Excel	5 O EvalPF_ExcelSchema_Format2 6 O EvalPF_ExcelSchema_Format1	excel schema format 2 demouser excel schema format 1 demouser	
Text			

Figure 7.49: Manage Excel Schema

4. Click the **New** link. The Create Excel Schema screen is displayed (see Figure 7.50).



Configure	> Ser	vices > Schema	> Excel			
[-] Stand	ard pr	operties				
	Name	e *				
	Desc	ription *				
	Data	Header Present				
	Creat	te Schema Definitio	n*			
	ΟU	se Definition File		Data 💌		Upload File
	ΘE	nter the Fields Seq	uentially			
	Shee	t Name*				
	#	FieldName	Туре	Format	SubForma	t Data Mode
	1		string	<ul> <li>mmddyyyy</li> </ul>	▼ hh:mm:ss	▼ Plain Text ▼
	2		string	<ul> <li>mmddyyyy</li> </ul>	hh:mm:ss	Plain Text 💌
	3		string	<ul> <li>mmddyyyy</li> </ul>	hh:mm:ss	<ul> <li>Plain Text</li> </ul>
	4		string	<ul> <li>mmddyyyy</li> </ul>	hh:mm:ss	<ul> <li>Plain Text</li> </ul>
	Numb	er of Rows 1	at Positio	on 5 Add R	ow Remove Ro	N
	Define	e Hierarchy		Merge Criter	ria 💌Mer	ge Key 💌
[+] Advan	iced p	oroperties				
* Mandatory fie	lds.					
Save (	Cancel	Save & I	Launch Dat	ta Mapper		

Figure 7.50: Create Excel Schema

- 5. Enter the name and description of new excel schema in the *Name* and *Description* fields respectively.
- 6. Data Header usually contains the name of the fields in an excel file. If schema is used at source end, and data header is present in the file, check the *Data Header Present* checkbox. If the schema is used at the target end, and the Data Header Present checkbox is checked, the Header will be written in the target excel file.



Name of the Headers in the data file and the Field Names in schema must be same and in same order. If they are not same, then you need to use Dynamic Header Support option. To know how to use Dynamic Header Support, refer to the <u>Using Dynamic Header Support</u> section.

7. To define the schema using definition file, select the *Use Definition File* radio button; select the type of file from the drop-down list and click the **Upload File** button to select the required file. The Schema File upload screen is shown (see Figure 7.51).



🖉 Schema File Upload - Windows Internet Explorer	- O ×
	*
Choose File(s)	
Click on Browse button to choose the file.	
Browse File Browse	
<b>Oupload File</b> Click on the "Upload File" button. Please wait till your file appears under File Name.	
File Name	
Upload File	
Olick on Finish button to complete the process.	
Finish Unload File	

Figure 7.51: Upload file

- 8. Click **Browse** and select the file, you want to upload. Path of the selected file is shown in the *Browse File* Field.
- 9. Now click **Upload File** button. Name of the uploaded file is shown in the *File Name* list and list of sheets of the excel file is shown (see Figure 7.52).

🎒 Schem	a File Upload - Microso	oft Internet Explorer	
1 Choo	se File(s)		
Click on	Browse button to choose	the file.	
Browse F	ile		Browse
	<b>ad File</b> the "Upload File" button.	. Please wait till your file appears und	der File Name.
File Na	ame		
Emp_Re	cords.xls		
Uploa	d File		
Sheet Name	Start Row No.	Start Column No.	
Sheet3	1	A	
Sheet2	1	A	
Sheet1	1	A	
Pro	cess Sheet(s)		
3 Click	on Finish button to com	plete the process.	
Finish		Unload File	

Figure 7.52: Specify Start Row and Start Column No.

10. Specify the Start Row No. and Start Column No. of the sheets in respective fields and then click *Process Sheet(s)*. This will read the sheets and field names.



Start Row No. and Start Column No. specify that from which row and Column onwards data should be fetched. For example if you have an excel file in which first 4 rows of sheet1 are blank. So in that case you have to specify 5 in sheet1 *Start Row No.* Another scenario can be that the data is there in first 4 row, but you don't want to fetched those records.

- 11. Once the processing is done, click **Finish** to close the Schema File Upload screen and return to create schema page.
- 12. Select the sheet name of the excel file for which you are creating this schema activity, from the *Sheet Name* drop-down list. Fields of the selected sheet are populated.
- 13. If you want to create schema by entering the fields manually, select *Enter the Fields Sequentially* radio button and follow the steps given below:
- 14. Enter the sheet name of the excel file in the *Sheet Name* field.
- 15. Enter the name of each field in the *FieldName* field.
- 16. Select the type of data from the *Type* drop-down list. The datatypes supported by Excel schema are listed in the table below.


Data Type	Description
String	This data type is selected if the field will accept a string value.
Number	This data type is selected if the field will accept a numeric value.
Date	This data type is selected if the field will accept a Date or Date and Time value.
Currency	This data type is selected if the field will accept a currency value.

Table 7.2: Supported Datatypes



The Currency datatype is supported by Excel Schema only.

17. If data type is *Date*, select the format of date and time from the *Format* and *SubFormat* drop-down lists respectively.



ADEPTIA

18. If the datatype is selected as *Currency*, select the required currency from *Format* drop-down list. The currencies supported by excel schema are listed in the table below.

Currency	Description
Dollar(\$)	Dollar
USD	US Dollar
CAD	Canadian Dollar
CNY	Chinese Yen
EUR	Euro
GBP	British Pound
JPY	Japanese Yen

Table 7.3: Currencies Supported by Excel Schema

- 19. Select the mode of data, whether *Encrypted* or *Plain Text* from the *Data Mode* drop-down list. If the schema is used at source end and encrypted data is coming from the source, select *Encrypted* from the *Data Mode* drop-down list. Similarly if the schema is used at the target end and you want to send the encrypted data to the target, select *Encrypted* from the *Data Mode* drop-down list.
  - If Encrypted is selected in Data Mode, you must select Encryption/Decryption secret key from Advanced Properties.
    - If Encrypted is selected in Data Mode, you must set the Data Action property in Process Designer, while creating the process flow. To know more about Process Designer, refer to the <u>Working with</u> <u>Process Flow</u> section.
    - To insert rows, specify the number and position of the rows to be added in the *Number of Rows* and at *Position* fields respectively and click **Add Row** button. Maximum 99 rows can be added at a time.
    - To remove rows, specify the number and position of the rows to be deleted in the *Number of Rows* and at *Position* fields respectively and click **Remove Row** button.

If you delete the last fieldname of a record, and then save the schema, the entire field gets deleted. For example, a record has three fields – *Name*, *Description* and *Age*. If you delete *Age*, the entire field will get deleted.

20. Click [+] to expand the **Advanced Properties**. The following screen is displayed (see Figure 7.53).


đ



Target XML Schema	
Row Start Position	1
Column Start Position	A
Dynamic Header Support	
Allow Less Fields	
Filter Invalid XML Characters	
Handle Enclosing Character	
Encryption Secret Key	None 💌
Decryption Secret Key	None 💌
Owner*	admin (Default Administrator) 💌
	Read Write Execute
	Owner 🔽 🔽
Permissions	Group 🔽 🗖
	Other
landatory fields.	

Figure 7.53: View Advanced Properties of Excel Schema

- 21. Enter the Row Start Position in the *Row Start Position* field. Row Start Position specifies which row of the Excel Sheet is counted as first row. For example if you entered 5 in the Row Start Position field, 5th row of the Excel Sheet is counted as first row. If this schema is used at source end, the data form 5th row onwards is taken for processing. If this schema is used at target end, data is copied into the 5th row onwards. From 1st to 4th row of the target excel sheet will remain blank.
- 22. Similarly, enter the Column Start Position in the Column Start Position field.
- 23. If you want to enable Dynamic Header Support, check the Dynamic Header Support check box. For detailed information about Dynamic Header Support refer to the section **Using Dynamic Header Support**.
- 24. In case the number of fields in the data file is less than the number of fields defined in schema, you need to enable *Allow Less Fields* checkbox to process the data.



- When *Allow Less Field* option is enabled, empty tag is generated for fields that are not present in the data file.
- This option is applicable only when schema is used at source end.
- 25. In case the input data contains some characters that are invalid in XML, then this may result in the mapping getting aborted. You can filter these invalid XML characters by checking the *Filter Invalid XML Characters* checkbox.
- 26. If you want to remove enclosing characters (e.g. ', ", < , > ) from the data file while parsing, enter the enclosing character that you want to remove, in Handle En*closing Character* field. Currently following enclosing characters are supported:
  - Single Quote (')
  - Double Quote (")
  - Less than symbol (<)</li>
  - Greater than symbol (>)
- 27. If schema is used at target end and you want to convert the data from Plain Text to encrypted mode, select the secret key activity from the *Encryption Secret Key* drop-down list. The selected secret key activity is used to encrypt the data.
- 28. If schema is used at source end and you want to convert the data from Encrypted Mode to Plain Text, select the secret key activity from the *Decryption Secret Key* drop-down list. The selected secret activity is used to decrypt the data.



To know, how to create secret key activity, refer to the *Creating Secret Key Activity* section in the *Administrator Guide*.

To learn more about Advanced Properties refer to <u>Changing Advanced</u> <u>Properties</u> section

29. Click **Save** button. This displays a screen confirming that the excel schema activity has been created successfully. If the *Comments* property is enabled, then clicking **Save** will display a screen where you need to enter comments related to creating the excel schema (refer to Figure 3.6).

 You can directly open the Data Mapper applet from the *Create Excel Schema* page. You can use this feature if you want to use the same excel schema in mapping, which you are creating. In this case you can only use XML Schema at target end. To launch Data Mapper applet, enter the ID of the XML schema that you want to use at target end, in *Target XML Schema* and click *Save and Launch Data Mapper*.
 To view the ID of XML Schema, in *Manage XML Schema* page, click on the XML Schema that you want to use. A 30 digit entity ID is shown in the view page.

30. Enter the comments in the Add Comments field.





The comment should be at least 1 character in length.

31. Click **OK** to save the comments. This displays a screen confirming that the excel schema activity has been created successfully.



By default, the *Comments* property is disabled. To enable it, refer to the *Updating System Properties* section in *Administrator* Guide.

### Using Excel Schema to parse XLSX file

When you excel schema to parse and XLSX file, then you need to do some additional setting while creating process using this schema.

While creating the pocess flow, in Process Designer, double click the Excel schema that you are using in the prcess flow. Properties of the Excel Schema is displayed in the properties panel (see Figure 7.54)

200 225 250 Start Event 275 300 275	e rm_File orm_Na )
👿 Properties 🚫 OnException Scripts 🐼 Alerts 🛐 Process Flow V	/ariables 📴 Comments
Name	Value
Activity Maximum Retries on Failure	0 🕂 🔺
Activity Wait Time(in seconds) between Retries	60 🗮
Character Set Encoding	ISO-8859-1
dataAction	No Action
Error Records	File
File Type	Excel 97-2003 Workbook (*.xls)
ID	192168001166112200685798400006
Label	EvalXform_ExcelSchema
Name	EvalXform_ExcelSchema
source	EvalXform_Mapping
streamNames	EvalXform ExcelSchema

Figure 7.54: View Advanced Properties of Excel Schema

In value of File Type property, select Excel Workbook (\*.xlsx).

### **Defining Field Hierarchy**

You can define hierarchy (parent-child relationship) between the records of an excel file using *Define Hierarchy* option of excel schema. To understand how to define hierarchy lets assume that you have an excel file which contains records of insurance policies of families (see Figure 7.55).



ID	EMPFIRSTNAME	EMPLASTNAME	SSN	GENDER	DOB	ADDR1	ADDR2	CITY	STATE	COVERAGETYPE
7812	John	Smith	8989	M	4/11/1960	123 DummySt	Apt 12	Gowen	MI	1
	Mary	Smith	7871	F	1/1/1962	123 DummySt	Apt 12	Gowen	MI	1
	Kevin	Smith	1211	M	5/7/1989	89 Main St		Chicago	IL	4
2311	Larry	Johnson	8672	M	2/4/1967	123 DummySt	Apt 2A	Gowen	MI	1
	Samantha	Johnson	5430	F	11/8/1971	123 DummySt	Apt 2A	Gowen	MI	1
	Anna	Johnson	9231	F	9/10/1995	123 DummySt	Apt 2A	Gowen	MI	4
	Rea	Johnson	9231	F	3/15/1998	123 DummySt	Apt 2A	Gowen	MI	4

Figure 7.55:	Policy Details
--------------	----------------

As you can see in the above table for ID 7812 there are there policies and similarly for ID 2311 there are four policies. While defining schema you can specify the criteria based on that the hierarchy can be defined. For example you can select that if the ID field is blank, merge the record in the previous record which is having ID. Similarly you can define the criteria for the matching record. For example if value of the ID field is matching with that of the previous record, merge the record with the previous record.

Define Hierarchy option works only when you define the schema using data file.

### Steps to define hierarchy

- 1. While creating schema, select *Use Definition File* radio button and then select Data from the drop-down list.
- 2. Click **Upload File** button. The Schema File Upload screen is displayed (refer to Figure 7.51).
- 3. Click **Browse** and select the file, you want to upload. Path of the selected file is shown in the *Browse File* Field.
- 4. Now click **Upload File** button. Name of the uploaded file is shown in the *File Name* list and list of sheets of the excel file is shown (refer to Figure 7.52).
- 5. Specify the Start Row No. and Start Column No. of the sheets in respective fields and then click **Process Sheet(s)**. This will read the sheets and field names.



Start Row No. and Start Column No. specifies that from which row and Column onwards data should be fetched. For example if you have an excel file in which first 4 rows of sheet1 are blank. So in that case you have to specify 5 in sheet1 *Start Row No.* Another scenario can be that the data is there in first 4 row, but you don't want to fetched those records.

- 6. Once the processing is done, click **Finish** to close the Schema File Upload screen and return to create schema page.
- 7. Once the file is uploaded the *Sheet Name* field is converted into Drop-down list and all the sheet names of the selected excel file are populated in this drop-down list.
- 8. Select the sheet name from the *Sheet Name* drop-down list. All the fields of the selected sheet are populated.
- 9. To define the hierarchy, select *Define Hierarchy* checkbox and select the merge criteria from the *Merge Criteria* drop-down list.



Currently two merge criteria are supported:

**Matching Child Record**: Records are merged in case the value Key fields are matching.

**Blank Child Record:** In case the value of key field is blank, the records are merged with the previous record which is having some value in the key field.

- 10. Select the field name from the *Merge Key* drop-down list on basis of which record are merged.
- 11. Click Save to save the excel schema.

### Using Dynamic Header Support

Dynamic Header is an advanced feature of Excel Schema, which is used to parse an excel file, if:

- *FieldNames* defined in the Excel Schema and the Data Headers (Column Name) of the excel file are same but not in same order.
- *FieldNames* defined in the Excel Schema and the Headers of the excel file are not same. They may or may not be in same order.

### **Pre requisites**

Ø

- Data Header must be present in the Excel file
- Data Type must be same in the Excel Schema and the excel file

To parse an excel file, whose Headers are same but not in order with the FieldNames of the Excel Schema, check the Dynamic Header Support checkbox in the Advanced Properties. Now the Excel Schema will parse the data from the respective columns.

To parse an excel file, whose headers are different and not even in order with the fieldnames of the Excel Schema, check the *Dynamic Header Support* checkbox in the Advanced Properties. Apart from this an XML file is used by the schema, which contains the mapping between the headers of the excel file and the fieldnames of the Excel Schema. Following is the sample XML (see Figure 7.56).

<?xml version="1.0" encoding="ISO-8859-1"?> <HeaderMap type="Name"> <Map> <SchemaHeader>Name</SchemaHeader> <DataFileHeader>EMP\_Name</DataFileHeader> </Map>



<map></map>
<schemaheader>DOB</schemaheader>
<datafileheader>EMP_DOB</datafileheader>
<map></map>
<schemaheader>Age</schemaheader>
<datafileheader>EMP_Age</datafileheader>
<map></map>
<schemaheader>Address</schemaheader>
<datafileheader>EMP_Address</datafileheader>

Figure 7.56: XML to map Field Name with Data Header

### where:

SchemaHeader is the FieldName defined in the Excel Schema.

DataFileHeader is the name of the Header in excel file.

Excel Schema reads this XML file from process flow context. So you have to pass this XML file to the process flow context. The following figure shows a sample process flow to depict this scenario:




Figure 7.57: Sample Process Flow

In the process flow shown in Figure 7.57, a file source activity is used to read an excel file. An Excel Schema is used to parse the data from the excel file. FieldNames defined in the excel Schema and Headers in Excel file are different. To parse the data from the excel file, an XML file, which contains the mapping between FieldName and the Header is passed to the process flow context. To pass the XML file to process flow context, another File source activity (*File\_Src\_ExcelHeaderXML*) is used. This file source activity reads the XML file from a specified location and passes it to the context target activity. In context Target activity, you need to define the value of the *parameterName* property. Properties of the Context Target activity are shown in Figure 7.58:



🐷 Properties 🚳 OnException Scripts 🧭 Errors 🛐 Process Flow Variables 🗒 Comments		
Name	Value	
Document Repository	false 🔽	
ID		
Label	ContextTarget	
Name	ContextTarget	
parameterName	FieldName_Header_Mapping	
source	File_Src_ExcelHeaderXML	
streamNames		
Synch	true	
Туре	ContextTarget	

Figure 7.58: Context Target Properties

In this process flow, value of *parameterName* is given as *FieldName\_Header\_Mapping*.

After context target, *PutContextVa*r action is used. This action is used to set the value of a variable *Service.* <*ActivityName>.excelHeaderMappingXML* of XML Schema. The properties of *PutContextVar* action are shown in Figure 7.59:

👿 Properties 🚫 OnException Scripts 🧭 Errors 🔄 Process Flow Variables 🗐 Comments				
Name Value				
Context Variables Edit				
Label PutContextVarTag1				
Name PutContextVarTag1				
Type Put-Context-Var				

Figure 7.59: PutContextVar Properties

1. Click **Edit** to define the variable name and the value to be set. The Edit Context variable screen is displayed (see Figure 7.60).



Edit Context Variables		
Context Variable Information Table		
Activity Name	Variable Name	Variable Value
<u>l</u>		
		Done Cancel

Figure 7.60: Edit Context Variables

2. Click **New** ( ) icon. The Context Variable Information Dialog box is displayed (see Figure 7.61).



🙏 Context Variable Information	×
Activity Name :	<b>•</b>
Variable Name :	<b>•</b>
Variable Value :	
	Done

Figure 7.61: Context Variable Information

3. Enter *Service.* <*ActivityName*>.*excelHeaderMappingXML* in the *Variable Name* field. For Example *Service.Excel\_Schema.excelHeaderMappingXML* 

#### where

*Activity Name* is name of the Excel Schema Activity. For Example *FieldName\_Header\_Mapping*.

- 4. In the Variable Value field enter the value, which you defined in the parameterName in the ContextTarget activity.
- 5. Click *Done* twice to return to graph canvas area.
- 6. Make sure to create a stream from file source to Excel Schema activity.

To Know how to create a process flow, refer to the <u>Creating Process Flow</u> section.

# **CREATING POSITIONAL SCHEMA ACTIVITY**

The Positional Schema activity defines the procedure to read data from a Positional file, and write data in a Positional file. User needs to specify the names and the positions of required fields in order to enable identification of those fields.

In the Adeptia Suite this feature is available in:

BPM Suite	Integration Suite	ETL Suite
$\checkmark$	$\checkmark$	



#### Steps to create Positional schema

- 1. In the Adeptia Suite homepage menu, click **[+]** Configure to expand the tree. All the items in the Configure category are displayed.
- 2. Click [+] Services to expand the tree. All the items in the Services category are displayed.
- 3. Click **[+]** Schema to expand the tree, and then click **Positional**. The Manage Positional Schema screen is displayed (see Figure 7.62).

[-] Configure	Confie	jure > Services > Schema > Positio				
[+] Forms	Config	jure > Services > Schema > Posicio	ndi			
[+] WorkFlow						
[-] Services	New	Edit   Delete   Revisions   Dependencies		Select Field to Search 💙		Search
[+] Data Dictionary						
[+] Source	#	Name	Descript	on Owner	Perm.	Modified 🔻
[-] Schema	1 0	EvalRec_PositionalSchema	Positional Schema	demouser	RWX	08/16/05 15:23
📋 Adv. Database						
Adv. Positional						
Adv. Text						
📋 Database						
Excel						
Positional						

Figure 7.62: Manage Positional Schema

4. Click the **New** link. The Create Positional Schema screen is displayed (see Figure 7.63).

Configure > Servi	ces > Schema > Posit	tional				
[-] Standard pro	ortios					
	Jerties					
Name *						
Descrip	tion *					
Data He	ader Present					
Create	Schema Definition* Using	) 🖲 Field Le	ength O Start & End	Positions		
O Use	Definition File	XSD 💌		Upload File		
• Ente	er the Fields Sequentially				-	
#	FieldName Description	Туре	DateFormat	TimeFormat	Start End	Length Align Skip
1		string 💌	mmddyyyy 🔽	hh:mm:ss 💌	1	
2		string 💌	mmddyyyy	hh:mm:ss 💌		
3		string 💌	mmddyyyy 💌	hh:mm:ss 💌		
4		string 💌	mmddyyyy 💌	hh:mm:ss 💌		
Numbe	r of Rows 1 at Positi	ion 5	Add Row Ren	nove Row		
[+] Advanced pro	perties					
* Mandatory fields.						
manuatory fields.						
Save Cancel						

Figure 7.63: Create Positional Schema

5. Enter the name and description for new Positional Schema in the *Name* and *Description* fields respectively.



- 6. Data Header usually contains the titles of the fields in a text file. If data header is present in the text file, check the *Data Header Present* checkbox.
- 7. To define the schema using definition file, select the *Use Definition File* radio button; select the type of file from the drop-down list and click the **Upload File** button to select the required file. The Schema File upload screen is shown (refer to Figure 7.51).
- 8. Click **Browse** and select the file, you want to upload. Path of the selected file is shown in the *Browse File Field*.
- 9. Now click **Upload File** button. Name of the uploaded file is shown in the *File Name* list (see Figure 7.64).


🖉 Schema File Upload - Microsoft Internet Explore	er 📃 🗙
Choose File(s)	
Click on Browse button to choose the file.	
Browse File B	Irowse
<b>2</b> Upload File Click on the "Upload File" button. Please wait till your t	file appears under File Name.
File Name	
Emp_record.txt	
Upload File	
3 Click on Finish button to complete the process.	
Finish Unload File	
	<b>•</b>

Figure 7.64: Uploaded File

- 10. Click **Finish** to close the Schema File Upload screen and return to create schema page.
- 11. If you want to create schema by entering the fields manually, select *Enter the Fields Sequentially* radio button and follow the steps given below:
- 12. Enter name and description of the field in the *Name* and *Description* fields respectively.
- 13. Select the type of data from the *Type* drop-down list. For data type selection, refer to Table 7.2.
- 14. If data type is *Date*, select the format of date and time from the *DateFormat* and *TimeFormat* drop-down lists respectively.
- 15. To define field position select one of the following option:
  - Field Length

🛕 ADEPTIA

- Start & End Positions
- 16. To define the field position using field length, select *Field Length* radio button and enter the length of the field in the *Length* field.
- 17. To define the field position using start and end position, select the *Start and End Position* radio button.
- 18. Enter the start position of the field in the *StartPos* field.
- 19. Enter the end position of the field in the *EndPos* field.



In a positional file, tab is counted as one position and not eight positions.

By default, field positions are created in sequence. You can also create a schema with fields that are not in sequence. For details, refer to the Defining Field Positions Non-Sequentially section.

20. Select the alignment of the field from the Align drop-down list.

1	From Align select
Ø	L if the field is left aligned.
	<b>R</b> if the field is right aligned.
	To insert rows, specify the number and position of the rows to be added in the <i>Number of Rows</i> and at <i>Position</i> fields respectively and click <b>Add Row</b> button. Maximum 99 rows can be added at a time.
	To remove rows, specify the number and position of the rows to be deleted in the <i>Number of Rows</i> and at <i>Position</i> fields respectively and click <b>Remove Row</b> button.
	To learn about Advanced Properties refer to <u>Changing Advanced</u> <u>Properties</u> section
	Properties section



If you delete the last fieldname of a record, and then save the schema, the entire field gets deleted. For example, a record has three fields – *Name, Description* and *Age*. If you delete *Age*, the entire field will get deleted.

21. Check the *Skip* checkbox if you want to skip this field while generating the XML. This selection skips the fields that are not required for the schema. For example, the source file has over 1500 fields, but you just need to use 1000 fields. This selection skips the 500 unrequired fields, and does not read them, when the data is parsed to the XML. When the data file is created, the skipped fields are displayed in the file but are not read. If the schema is created using an existing XSD, the skipped fields will appear as a blank value. However, when the schema is used in other activities such as Mapping, all its fields are displayed.



Skipping of unrequired fields is useful in case of a standard XSD with a large number of fields, as it reduces the size of the generated XML which now contains only the required fields.


While editing the schema, when the data file is downloaded, the skipped fields are represented by 'T' and the unskipped fields by 'F' (refer to Figure 7.15). Similarly, while viewing the *Print-Friendly Page*, the skipped fields are represented by 'T' and the unskipped fields by 'F'.

22. Click **[+]** to expand **Advanced Properties**. Advanced properties of positional schema are displayed (see Figure 7.65).

[-] Advanced properties	
Handle CR/LF(Source Data)	
Target Record Separator	
Data Truncation	
Allow Less Fields	
Allow More Fields	
Filter Invalid XML Characters	
Owner*	admin (Default Administrator) 💌
	Read Write Execute
Descriptions	Owner 🔽 🔽
Permissions*	Group 🔽 🗖
	Other
* Mandatory fields.	
Save Cancel	

Figure 7.65: Advanced Properties of Positional Schema

- 23. Uncheck the *Handle CR/LF (Source Data)* checkbox, if the source file does not have any carriage return. By default, this option is checked, and schema expects file with carriage return. Handle CR/LF (Source Data) option is applicable only for the schema used at the source end.
- 24. Enter the target record separator in the *Target Record Separator* field, if you want to write each record in new line in target file. By default records are written in single line. This option is applicable only for the schema used at target end.
- 25. Check the *Data Truncation* checkbox, in case the data length is more than specified in the schema and you want to pass the specified length of data and ignore the rest of the data.



26. Check the *Allow Less Fields* checkbox, if you want to parse the data even if the number of fields in the data file is less than the number of field specified in the schema. If Allow Less Fields checkbox is checked and the schema is used at source end, schema will parse the input data and insert the empty tag of



missing fields. If the schema is used at target end, it will write all the tags coming in input XML.

- 27. Incase number of fields in source data is more than the number of fields specified in the schema, only those fields are parsed, which are specified in schema. Other fields are ignored. If you want to generate error records, when number of fields in source data is more than the number of fields specified in schema, uncheck the *Allow More Fields* checkbox.
- 28. In case the input data contains some characters that are invalid in XML, then this may result in the mapping getting aborted. You can filter these invalid XML characters by checking the *Filter Invalid XML Characters* checkbox.
- 29. Click **Save** button. This displays a screen confirming that the positional schema activity has been created successfully. If the *Comments* property is enabled, then clicking **Save** will display a screen where you need to enter comments related to creating the positional schema (refer to Figure 3.6).
- 30. Enter the comments in the Add Comments field.



The comment should be at least 1 character in length.

31. Click **OK** to save the comments. This displays a screen confirming that the positional schema activity has been created successfully.



By default, the *Comments* property is disabled. To enable it, refer to the *Updating System Properties* section in *Administrator* Guide.

### **CREATING TEXT SCHEMA ACTIVITY**

The Text Schema activity is used to define how a text file is to be read or written in a predefined format. To create a Text Schema activity, you need to specify the format of text file.

In the Adeptia Suite this feature is available in:

BPM Suite	Integration Suite	ETL Suite
$\checkmark$		$\checkmark$

#### Steps to create a text schema activity

- 1. In the Adeptia Suite homepage menu, click **[+] Configure** to expand the tree. All the items in the **Configure** category are displayed.
- 2. Click [+] Services to expand the tree. All the items in the Services category are displayed.

3. Click **[+]** Schema to expand the tree, and then click **Text**. The Manage Text Schema screen is displayed (see Figure 7.66).

[-] Configure [+] Forms [+] WorkFlow	Config	gure > Services > Schema > Text				
[+] Workhow [-] Services [+] Data Dictionary	New	Edit   Delete   Revisions   Dependencies	Se	lect Field to Search 💌		Search
[+] Source [-] Schema	#	Name InventoryItemsCSVSchema	Description text schema for CSV file	Owner	Perm.	Modified •
🗊 Adv. Database 😨 Adv. Positional	2 ()	EvalScript_TextSchema EvalJMSE_TextSchema	Text Schema for Employee data Text Schema for Stock Quotes	demouser demouser	RWX	08/22/05 22:03
탑양 Adv. Text (前) Database 물양 Excel	. 0	Evalumbe_rextschema	Text Schema for Stock Quotes	demodser	NWA	08/22/03 17:46
😨 Positional						
II XML						

Figure 7.66: Manage Text Schema

4. Click the **New** link. The Create Text Schema screen is displayed (see Figure 7.67).

Design > S	ervices	Schema > Text					
[-] Standa	ard prop	perties					
	Name *						
	Descrip	tion *					
	Data He	ader Present					
	Record	Separator*					
	Field Se	parator*					
	Create \$	Schema Definition*					
	C Use	Definition File		Data 💌		Upload Fi	ile
	Enter	r the Fields Sequentially					
	#	FieldName	Туре	DateFormat	TimeFormat		
	1		string	mmddyyyy	hh:mm:ss	Y	
	2		string	mmddyyyy	hh:mm:ss	V	
	3		string	mmddyyyy	hh:mm:ss	<b>V</b>	
	4		string	mmddyyyy	▼ hh:mm:ss	~	
	Number	of Rows 1 at Posit	tion 5	Add Row	Remove Row		
[+] Advan	ced pro	perties					
* Mandatory fiel	lds.						
Save C	ancel						

Figure 7.67: Create Text Schema

5. Enter the name and description of the new text schema in the *Name* and *Description* fields respectively.



- 6. Data Header usually contains the titles of the fields in a text file. If data header is present in the text file, check the *Data Header Present* checkbox.
- 7. Enter the record separator, for example \n for new line or " " for space, in the *Record Separator* field. The record separator is used to separate records.
- 8. Enter the Field Separator, for example \t for Tab or " " for space. In the *Field Separator* field. Field Separator is used to separate fields.

Ø

You can also specify record separator and field separator in Hex format. To specify record separator and field separator you need to use 0x before the hex value. For example to specify new line in hex format, you need to use 0x0A.

- 9. To define the schema using definition file, select the *Use Definition File* radio button; select the type of file from the drop-down list and click the **Upload File** button to select the required file. The Schema File upload screen is shown (refer to Figure 7.51).
- 10. Click **Browse** and select the file, you want to upload. Path of the selected file is shown in the *Browse File* Field.
- 11. Now click **Upload File** button. Name of the uploaded file is shown in the *File Name* list (see Figure 7.68).

🚈 Schema File Upload - Microsoft Internet E	kplorer	<u> </u>
		-
Choose File(s)		
Click on Browse button to choose the file.		
Browse File	Browse	
<b>Opload File</b> Click on the "Upload File" button. Please wait til	l your file appears under File Name.	
File Name		
Emp_record.txt		
Upload File		
3 Click on Finish button to complete the proce	255.	
Finish Unload File		
		<b>v</b>

#### Figure 7.68: Uploaded File

- 12. Click **Finish** to close the Schema File Upload screen and return to create schema page
- 13. If you want to create schema by entering the fields manually, select *Enter the Fields Sequentially* radio button and follow the steps given below:



- 14. Enter the name of each field in the Field Name field.
- 15. Select the type of data from the *Type* drop-down list. For data type selection, refer to Table 7.2.



The Currency data type is supported by Excel Schema only.

16. If data type is *Date*, select the format of date and time from the *DateFormat* and *TimeFormat* drop-down lists respectively.



To insert rows, specify the number and position of the rows to be added in the *Number of Rows* and at *Position* fields respectively and click **Add Row** button. Maximum 99 rows can be added at a time.

To remove rows, specify the number and position of the rows to be deleted in the *Number of Rows* and at *Position* fields respectively and click **Remove Row** button.



If you delete the last fieldname of a record, and then save the schema, the entire field gets deleted. For example, a record has three fields – *Name, Description* and *Age*. If you delete *Age*, the entire field will get deleted.

17. To enable quotes handling, click **[+]** to expand the **Advanced Properties** and check the *Quotes Handling On* checkbox.



- If a character (say \$) is specified as Field Delimiter in a record, then any \$ character in the field data of that record (Chocolate\$20\$perpack) will be considered as a Field Delimiter, even though it is part of the field data. In the above example the \$ after 20 will also be considered as Field Delimiter, whereas it is the data. To avoid this situation put that field within the double quote i.e. (Chocolate\$"20\$perpack")
- 18. In case the number of fields in the data file is less than the number of fields defined in schema, you need to enable *Allow Less Fields* checkbox to process the data.

- When number of fields in the data file is less than the number of fields defined in the schema, then data is not processed and gives error during execution.
  - If you still want to process the data, then you need to enable *Allow Less Field* checkbox.
- When *Allow Less Field* option is enabled, empty tag is generated for fields that are not present in the data file.
- This option is applicable only when schema is used at source end.
- 19. If you want to remove enclosing characters (e.g. ', ", & , < , > ) from the data file while parsing, enter the enclosing character that you want to remove, in *Handle Enclosing Character* field. Currently following enclosing characters are supported:
  - Single Quote (')

- Double Quote (")
- Less than symbol (<)</li>
- Greater than symbol (>)
- 20. In case the input data contains some characters that are invalid in XML, then this may result in the mapping getting aborted. You can filter these invalid XML characters by checking the *Filter Invalid XML Characters* checkbox in Advanced Properties.



To learn about Advanced Properties refer to <u>Changing Advanced</u> <u>Properties</u> section

- 21. Click **Save** button. This displays a screen confirming that the text schema activity has been created successfully. If the *Comments* property is enabled, then clicking **Save** will display a screen where you need to enter comments related to creating the text schema (refer to Figure 3.6).
- 22. Enter the comments in the Add Comments field.



The comment should be at least 1 character in length.

23. Click **OK** to save the comments. This displays a screen confirming that the text schema activity has been created successfully.



By default, the *Comments* property is disabled. To enable it, refer to the *Updating System Properties* section in *Administrator* Guide.

### **CREATING WORD SCHEMA ACTIVITY**

Word Schema is used to convert MS Word file into XML format, so that it can be further processed. Word Schema uses a pre-built template XSD XMSW.xsd, which defines the structure of the XML file. When a word schema is created, this XSD is stored into the backend database to define the structure of the schema. Word to XML conversion is done at execution time.




This feature is a paid service and is thus not available in any of the Adeptia products by default.

#### Steps to create Word Schema

- 1. In the Adeptia Suite homepage menu, click **[+]** Configure to expand the tree. All the items in the Configure category are displayed.
- 2. Click [+] Services to expand the tree. All the items in the Services category are displayed.
- 3. Click **[+]** Schema to expand the tree, and then click Word. The Manage Word Schema screen is displayed (see Figure 7.69).



sSelect Field to Search 🔽 Sear Description Owner Perm. Modified 🔻 No records found
No records found



4. Click the **New** link. The Create **Word** Schema screen is displayed (see Figure 7.70).

Schema > Word Schema		
[-] Standard properties		
Name *		
Description *		
Create Schema Definition using*	Pre-built Template XSD 💌	
Generate XML from Word(doc) file		Browse
[+] Advanced properties		
* Mandatory fields.		
Save Cancel		

Figure 7.70: Create Word Schema

- 5. Enter the name and description for Word Schema in the *Name* and *Description* fields respectively.
- 6. Leave the Create Schema Definition Using field as default.
- 7. If you want to view the XML of the word file, which you want to convert, click the **Browse** button and select the required word file.


Ø	This field is not mandatory because at execution time, Word file is taken from the File Source activity.
	This field is required only if you want to view the XML of the Word file. To view the XML of the Word file, first browse and select the required word file. Save the Word Schema activity and then edit the word schema activity that you have created. Click <b>Download</b> in the Edit Word Schema screen. The Download Word Schema Definition File screen is displayed (see Figure 7.71).

4



Wo	wnload WordSchema Definition File rdSchema Name: Purchase_Order ect Definition File XML 💌
xml	<pre><?xml version="1.0"?><xmsw system="file:/C:/DOCUME~1/ADMINI~1.ADE/LOCALS~1/Temp/MSPars er34094.ms" xmlns="http://www.davisor.com/offisor/3.1/xmsw"><head><property propertytype="comments"><value></value></property><property propertytype="created"><value>//property&gt;<property propertytype="created"><value>Mon Jul 02 11:02:00 GMT+05:30 2007</value><value>726502</value></property><property propertytype="title"><value>Hi Kuljeet, Shailendra,</value></property><property< property<="" th=""></property<></value></property></head></xmsw></pre>

Figure 7.71: Download Word Schema Definition File





To learn more about Advanced Properties refer to <u>Changing Advanced</u> <u>Properties</u> section

- 8. Click **Save** button. This displays a screen confirming that the word schema activity has been created successfully. If the *Comments* property is enabled, then clicking **Save** will display a screen where you need to enter comments related to creating the Word schema (refer to Figure 3.6).
- 9. Enter the comments in the Add Comments field.



The comment should be at least 1 character in length.

10. Click **OK** to save the comments. This displays a screen confirming that the Word schema activity has been created successfully.

 $\langle n \rangle$ 

By default, the *Comments* property is disabled. To enable it, refer to the *Updating System Properties* section in *Administrator* Guide.

### CREATING XML SCHEMA ACTIVITY

The XML Schema activity defines the procedure to read data from an XML file, and write data in an XML file. To do so, user needs to specify the schema definition location.

In the Adeptia Suite this feature is available in:

BPM Suite	Integration Suite	ETL Suite
$\checkmark$		$\checkmark$

#### Steps to create XML Schema

- 1. In the Adeptia Suite homepage menu, click **[+]** Configure to expand the tree. All the items in the Configure category are displayed.
- 2. Click [+] Services to expand the tree. All the items in the Services category are displayed.
- 3. Click **[+]** Schema to expand the tree, and then click XML. The Manage XML Schema screen is displayed (see Figure 7.72).

[-] Configure [+] Forms	Confi	gure > Services > Schema > XML				
<ul> <li>[+] WorkFlow</li> <li>[-] Services</li> <li>[+] Data Dictionary</li> </ul>	New	Edit   Delete   Revisions   Dependencies		Select Field to Search 💌		Search
[+] Source	#	Name	Descriptio	on Owner	Perm.	Modified 🔻
[-] Schema	1 ()	InventoryItemsXMLSchema	schema for inventory XML	demouser	RWX	08/31/09 15:59
Adv. Database	2 ()	EmployeeBenifitXMLSchema	XML schema definition	demouser	RWX	08/31/09 15:59
20 Adv. Positional	3 ()	FulfillmentSOAPXML_Response	response SOAP XML schema	demouser	RWX	08/31/09 15:59
Database	4 ()	FulfillmentSOAPXML_Request	request SOAP XML schema	demouser	RWX	08/31/09 15:58
Excel	5 ()	PurchaseOrderXMLSchema	PO XML schema definition	demouser	RWX	08/31/09 15:54
20 Positional						
Text						

Figure 7.72: Manage XML Schema

4. Click the **New** link. The Create XML Schema screen is displayed (see Figure 7.73).



Configure > Services > Schema > XMI	L
[-] Standard properties	
Name *	
Description *	
Validate XML	
Upload XSD/DTD/XML from*	
	Browse
C Web Service Consumer	
Consumer ID	V
XSD Type	V
[+] Advanced properties	
* Mandatory fields.	
Save Cancel Validate	XSD

Figure 7.73: Create XML Schema

- 5. Enter the name and description for XML Schema in the *Name* and *Description* fields respectively.
- 6. Select one of the following Schema Definition Location:
  - File Path
  - Web Service Consumer
- 7. Select the desired option in the *Upload XSD/DTD/XML from* field. The selection process of options is explained in the table below.

Table 7.4: Selection Process of Value for Upload XSD/DTD/XML from Field

Option	Process
File Path	Click the <b>Browse</b> button and select the DTD, XSD or XML file. If the DTD, XSD or XML file is located on an HTTP URL, enter the URL, where DTD/XSD/XML file is located in the <i>HTTP URL</i> field.



Web Service Consumer	In this case, XSD is picked up from pre-defined Web Service Consumer activity. Each WS Consumer activity has two XSD's associated with it (i.e. Input Data XSD and Output Data XSD).					
	Select the Web Service Consumer activity from the <i>Consumer ID</i> drop-down list.					
	Select the type of XSD as either Input or Output from the <i>XSD Type</i> drop-down list.					
	<ul> <li>Input: XSD for input data format.</li> </ul>					
	<ul> <li>Output: XSD for output data format.</li> </ul>					




Check the *Validate XML* checkbox if you want to validate the XML during execution. It validates the input XML file at runtime.

- 8. Click **Validate XSD** button to validate file entered in the Filepath field. You can validate all file types such as XML, XSD or DTD. If it is not an XSD file, then it will convert it to XSD format and then validate.
- 9. Click **[+]** to expand **Advanced Properties**. The Advanced Properties of XML Schema activity is displayed (see Figure 7.74).

[-] Advanced properties					
Convert to XSD/DTD *					
Owner*		admin (Default Administrator) 💌			
			Read	Write	Execute
Provide the state		Owner	•	•	•
Permissions*		Group	✓		<b>v</b>
		Other			
* Mandatory fields.					
Save Cancel	Validate XSD				

Figure 7.74: Advanced Properties of XML Schema

10. The *Convert to XSD/DTD* checkbox is marked as checked. This implies that all xml file will be converted to XSD or DTD. The XSD file remains as XSD file whereas, DTD file is converted to XSD file. If you don't want to convert the uploaded XML file into DTD, uncheck this checkbox.





displayed, while loading the schema in Mapper. This is because of the limitation is JDOM. In this case, check the *Convert to XSD/DTD* checkbox.

To learn more about Advanced Properties refer to <u>Changing Advanced</u> <u>Properties</u> section.

- 11. Click **Save** button. This displays a screen confirming that the XML schema activity has been created successfully. If the *Comments* property is enabled, then clicking **Save** will display a screen where you need to enter comments related to creating the XML schema (refer to Figure 3.6).
- 12. Enter the comments in the Add Comments field.

Ø

The comment should be at least 1 character in length.

13. Click **OK** to save the comments. This displays a screen confirming that the XML schema activity has been created successfully.



By default, the *Comments* property is disabled. To enable it, refer to the *Updating System Properties* section in *Administrator* Guide.

### **TESTING SCHEMA ACTIVITY**

Once a schema is created, you can verify the schema activity. Schema can be tested for both source and target end. In order to test a schema you have to supply the source file, and schema will show you the output file and the error file if any. When a schema is tested, it parses the supplied file as per the structure defined in the schema and generates the output and error files. The output file contains the record which are parsed successfully error file contains the record which are not parsed. The process of testing a text schema is explained below.

#### Steps to verify text schema activity

- 1. In the Adeptia Suite homepage menu, click **[+]** Configure to expand the tree. All the items in the Configure category are displayed.
- 2. Click [+] Services to expand the tree. All the items in the Services category are displayed.
- 3. Click **[+]** Schema to expand the tree, and then click **Text**. The Manage Text Schema screen is displayed (refer to Figure 7.66).
- 4. Select the radio button adjacent to required schema activity that you want to test and click **Edit** link. This displays the Edit Text Schema screen (see Figure 7.75).




	dard pro					
	Name *			EvalScript_1	extSchema	
	Descrip	tion *		Text Schem	Text Schema for Employee data	
	Data Header Present					
Record Separator*			\n			
	Field Se	eparator*		\t		
	Downlo	ad Schema Definition File	e Download			
	Create	Schema Definition*				
	O Use	Definition File		Data 💌		Upload File
		er the Fields Sequentially				
	#	FieldName	Туре	DateFormat	TimeFormat	
	1	NAME	string -	mmddyyyy	hh:mm:ss	
	2	ADDRESS	string 💌	mmddyyyy	hh:mm:ss	-
	3	EMAILID	string -	mmddyyyy	▼ hh:mm:ss	<b>v</b>
	4	PHONENO	number 💌	mmddyyyy	hh:mm:ss	
	Number	of Rows 1 at Pos	ition 11	Add Row Re	emove Row	
[+] Advs	anced pro	nortios				
	inceu pro	pernes				

Figure 7.75: Edit Text Schema

5. Click **Test** button. The Test Schema screen is displayed (see Figure 7.76).

TextSchema > Emp_Records	
Type Source 🔽 Source File Name	Browse
Submit Close	



- 6. Select the type of schema to test, from the *Type* drop-down list. By default, Source is selected.
- 7. Click **Browse** button and select the file which you want to test.



Ø

The file extension in this field will vary based on the schema being tested. If a text schema is being tested, then the file will have *.txt* extension. If an excel schema is being tested, then the extension will be *.xls*.

If you want to test this schema for the target end, select *Target* from the *Type* drop-down list. Now the source file will be an xml file that is generated by the mapping activity used in the process flow. In this case target file will be the file which will be generated by schema as output. For example if your are testing Text Schema which will be used at target end, the target file will a .txt file.

8. Click **Submit** button. This tests the specified source file according to the defined schema and gives you the link of out files generated (see Figure 7.77).

	a > Emp_Records	
Source File	Emp_record.txt	26 Records
Target File	targetFile.xml	24 Records
Error File	errorFile.xml	2 Records

Figure 7.77: Test Schema

Once you click the **Submit** button, there files are generated:

Source File: File which you have selected Target File: File which is generated by schema as output Error File: File which contains erroneous record if any.

9. To view the file click on the link of file you want to view.

Ø	

All schemas except Advance Database schema, Database schema and XML Schema can be tested.

### **CREATING XML VALIDATOR ACTIVITY**

XML Validator is used to validate the whole XML file or part of it. For validation user needs to supply the Xpath from which part of the XML starts and the path of the XSD against which that XML file is validated.

In the Adeptia Suite this feature is available in:

BPM Suite	Integration Suite	ETL Suite
$\checkmark$	$\checkmark$	$\checkmark$



#### Steps to create a XML Validator activity

- 1. In the Adeptia Suite homepage menu, click **[+]** Configure to expand the tree. All the items in the Configure category are displayed.
- 2. Click **[+] Services** to expand the tree. All the items in the **Services** category are displayed.
- 3. Click **[+]** Schema to expand the tree, and then click XML Validator. The XML Validator screen is displayed (see Figure 7.78).

[-] Configure	Configure > Services > Schema > XML V	alidatos		
[+] Forms	Configure > Services > Scheina > AME V	andator		
[+] WorkFlow				
[-] Services	New   Edit   Delete   Revisions   Dependencies	Select Fi	ald to Search 💙	Search
[+] Data Dictionary				
[+] Source	# Name	Description	Owner Perm.	Modified <b>*</b>
[-] Schema		No records found		
👘 Adv. Database				
👷 Adv. Positional				
S Adv. Text				
🗊 Database				
28 Excel				
Positional				
Text				
SE XML				
S XML Validator				

Figure 7.78: Manage XML Validator

4. Click the **New** link. The Create XML Validator screen is displayed (see Figure 7.79).

Configure > Services > Schema > XML Validator			
[-] Standard properties			
Name *			
Description *			
Validate Sub XML			
Enter XPath *			
XSD File Path *			
[4] Advanced groupstice			
[+] Advanced properties			
* Mandatory fields.			
Save Cancel			

Figure 7.79: Create XML Validator

- 5. Enter the name and description of new XML Validator activity in *Name* and *Description* fields respectively.
- 6. If you want to validate the Sub XML, check the *Validate Sub XML* checkbox.
- 7. Enter the XPath of the XML, which needs to be validated in the *Enter XPath* field.
- 8. Enter the path of the XSD file, against which the above defined XML is validated, in the *XSD File Path* field.



To learn about Advanced Properties refer to **Changing Advanced Properties** section.

- 9. Click **Save** button. This displays a screen confirming that the XML Validator activity has been created successfully. If the *Comments* property is enabled, then clicking **Save** will display a screen where you need to enter comments related to creating the XML Validator (refer to Figure 3.6).
- 10. Enter the comments in the Add Comments field.



The comment should be at least 1 character in length.

11. Click **OK** to save the comments. This displays a screen confirming that the XML Validator activity has been created successfully.



By default, the *Comments* property is disabled. To enable it, refer to the *Updating System Properties* section in *Administrator* Guide.



# 8 CREATING TARGET ACTIVITY

A Target Activity allows you to identify specific data to be created and the means to deliver it. The Target activity screen allows you to identify specific data set (i.e., flat file, XML or database record) to be created, its location, and the transport protocol to be used to send this data. The Adeptia Suite allows following types of Target activities:

- Advanced Database Target
- Database Target
- File Target
- FTP Target
- HTTP Target
- JMS Target
- LAN File Target
- Mail Target
- WebDAV Target
- Context Target

Context Target is used to put the data in process flow context. To know how to use Context Target refer to the section **Using Context Source and Context Target** activity.

### **CREATING ADVANCED DATABASE TARGET ACTIVITY**

The Advanced Database Target activity provides the ability to specify multiple tables of a database as Target.

In the Adeptia Suite this feature is available in:

BPM Suite	Integration Suite	ETL Suite
$\checkmark$		$\checkmark$

#### Prerequisites:

• *Database Info* activity and *Advanced Database Schema* must be created before creating Advanced Database Target activity.

#### Steps to create an Advanced Database Target Activity

1. In the Adeptia Suite homepage menu, click **[+]** Configure to expand the tree. All the items in the Configure category are displayed.



- 2. Click [+] Services to expand the tree. All the items in the Services category are displayed.
- 3. Click **[+] Target** to expand the tree, and then click **Adv.Database**. The Manage Advanced Database Target screen is displayed (see Figure 8.1).

[-] Configure [+] Forms [+] WorkFlow	Config	jure > Services > Target > Adv. Dat	abase			
[-] Services	New	Edit   Delete   Revisions   Dependencies	Select Field to S	earch 💙		Search
<ul> <li>[+] Data Dictionary</li> <li>[+] Source</li> </ul>	. #	Name	Description	Owner	Perm.	Modified <b>*</b>
[+] Schema [-] Target	1 ()	PointofSalesDatabaseTarget	insert output data records into backend db	demouser	RWX	08/06/09 14:42
ol Adv. Database						
<b>¢0</b> Database <b>₽</b> File						
PS FTP						

Figure 8.1: Manage Advanced Database Target

4. Click the **New** link. The Create Advanced Database Target screen is displayed (see Figure 8.2).

Configure > Services > Target > Adv. D	atabase
[-] Standard properties	
Name *	
Description *	
Database Info *	SELECT
Schema Name *	SELECT
Database Operation *	● Insert ○ Update ○ Insert/Update ○ Update/Insert
[+] Advanced properties	
* Mandatory fields.	
Save Cancel	

Figure 8.2: Create Advanced Database Target

- 5. Enter the name of the new Advanced Database Target in the *Name* field. Then, enter the description for the Advanced Database Target in the *Description* field.
- 6. Select the database info activity and database schema activity from the *Database Info* and *Schema Name* drop-down lists respectively.
- 7. Database Operation specifies how data records are inserted into database tables. Select one of the following database operations:
  - Insert
  - Update
  - Insert/Update
  - Update/Insert



If the specified database operation fails on any source data, error records are created. While creating a process using an Advance Database Source, you can specify what to do with error records.
 Error records can be saved into repository file.
 Error records can be ignored.
 It can be further processed (e.g. can be sent to file target).
 Process Flow can be aborted, if there is any error record.
 In process designer, right click on the advance database source activity and select view properties. Select the value of the "Error Record" properties.

To learn, how to use Process Designer, refer to the section Using Process Designer.

To learn how to create Database Info activity, refer to the *Creating Database Info* section in the *Administrator Guide*. To learn how to create the Advance Database Schema activity, refer to the Creating Advance Database Schema Activity section.



When an excel file is used as a database target, only *Insert* operation is supported. The *Update*, *Insert/Update* and *Update/Insert* operations are not supported.

When an excel file is used as a database target, the error records are not generated in case of data type mismatch.

When a database operation is selected, the database is affected. For details, refer to Table 8.2.

To learn about Advanced Properties refer to Changing Advanced Properties section.

- 8. Click **Save** button. This displays a screen confirming that the Advanced Database target activity has been created successfully. If the *Comments* property is enabled, then clicking **Save** will display a screen where you need to enter comments related to creating the advanced database target (refer to Figure 3.6).
- 9. Enter the comments in the Add Comments field.



The comment should be at least 1 character in length.

10. Click **OK** to save the comments. This displays a screen confirming that the Advanced Database target activity has been created successfully.



By default, the *Comments* property is disabled. To enable it, refer to the *Updating System Properties* section in *Administrator* Guide.



### Understanding Record Count in Process Flow Logs

The number of records processed by an Advanced Database Target activity during the execution of a process flow is displayed in the Process Flow Log. This record count differs based on its type. The various types of record counts are explained below.

#### Transaction Commit Count

This record count type includes the total number of records in the input at root level, which are successfully processed and committed by the Advanced Database Target activity. It includes inserted, deleted and updated records.

#### Insert Query: Submitted/Successful

This record count type includes the Insert Query which are submitted or successful. Submitted is the total number of Insert Query submitted/executed by the Advanced Database Target activity. Successful is the total number of records, which are inserted and committed in the table for the Insert Query and which are not rolled back.

Ø

The 'Successful' count can be equal or less than the 'Submitted' count in case of "Insert" operation.

#### Delete Query: Submitted /Successful

This record count type includes the Delete Query which are submitted or successful.

Submitted is the total number of Delete Query submitted/executed by the Advanced Database Target activity.


Successful is the total number of records, which are deleted and committed from the table for the Delete Query and which are not rolled back.

#### Update Query: Submitted /Successful

This record count type includes the Update Query which are submitted or successful.

Submitted is the total number of Update Query submitted/executed by the Advanced Database Target activity.

Successful is the total number of records, which are updated and committed in the table for the insert query and which are not rolled back.



#### Rollback Transaction Count



This record count type includes the total number of records in the input at root level, which are rolled back by the Advance Database Target activity.

#### Rollback Insert Count

This record count type includes the total number of records, which are supposed to be inserted but rolled back due to any error.

#### Rollback Delete Count

This record count type includes the total number of records, which are supposed to be deleted but rolled back due to any error.

#### Rollback Update Count

This record count type includes the total number of records, which are supposed to updated but rolled back due to any error.

To further understand the different counts, assume the following example.

R1 (10)	R1C1 (20)	R1C1C1 (100)
R2 (20)	R2C1 (40)	R2C1C1 (80)

Suppose there are two records *R1* and *R2* at root level of input. *R1* has a child *R1C1* and further *R1C1* has a child *R1C1C1*. Similarly *R2* has a child *R2C1* and further *R2C1* has a child *R2C1C1*.

Their number of records is displayed in the brackets. For these records, insert queries are issued by the Advanced Database Target activity. Records from R1, its child (R1C1) and sub-child (R1C1C1) are successfully inserted in the target table. At the same time, while inserting the records from R2C1C1 the Advance Database Target activity encountered an error in 8 records. Now, the record of R2 and its child (R2C1) corresponding to erroneous records will be rolled back. Thus, the number of records rolled back from R2C1C1, R2C1, R2 will be 8, 4 and 2 respectively.

Thus, in this scenario, the values of the record count types will differ as displayed below.

Table 8.1:	Record	Count	Туре	Values
------------	--------	-------	------	--------

Record Count Type	Value	Description
Transaction Commit Count	28	10 records from R1 and 18 records from R2



Insert Query: Submitted/Successful	270/256	Total number of records (270) – Total number of rolled back records (14)
Rollback Transaction Count	2	Number of records rolled back from root level
Rollback Insert Count	14	R2 (2) + R2C1 (4) + R2C1C1 (8)

All the other counts will be zero.

### **CREATING DATABASE TARGET ACTIVITY**

The Database Target activity provides the ability to specify a database as target.

In the Adeptia Suite this feature is available in:

BPM Suite	Integration Suite	ETL Suite
$\checkmark$		$\checkmark$

#### Prerequisites:

• *Database Info* activity and *Database Schema* must be created before creating Database Target activity.

#### Steps to create a Database Target Activity

- 1. In the Adeptia Suite homepage menu, click **[+]** Configure to expand the tree. All the items in the Configure category are displayed.
- 2. Click [+] Services to expand the tree. All the items in the Services category are displayed.
- 3. Click [+] Target to expand the tree, and then click **Database**. The Manage Database Target screen is displayed (see Figure 8.3).

[-] Configure [+] Forms	Config	gure > Services > Target > Databas	e			
[+] WorkFlow [-] Services [+] Data Dictionary	New	Edit   Delete   Revisions   Dependencies	Select Field to Se	arch 💙		Search
[+] Source [+] Schema	#	Name EvalPF_DatabaseTarget_Database2	Description database target database2	Owner demouser	Perm. RWX	Modified •
[-] Target \$0 Adv. Database	2 ()	EvalPF_DatabaseTarget_Database1 EvalJMSE_DBTarget	database target database1 Database Target for Stock Quotes	demouser demouser	RWX RWX	08/22/05 18:57 08/22/05 18:33
이 Database 된 File 얍 FTP						
HTTP						

Figure 8.3: Manage Database Target


4. Click the **New** link. The Create Database Target screen is displayed (see Figure 8.4).



Configure > Services > Target > Data	base
[-] Standard properties	
Name *	
Description *	
Database Info *	SELECT
Schema Name *	SELECT
Database Operation *	☉ Insert C Update C Insert/Update C Update/Insert
[+] Advanced properties	
* Mandatory fields.	
Save Cancel	

Figure 8.4: Create Database Target

- 5. Enter the name and description of the new Database Target in the Name and Description fields respectively.
- 6. Select the database info activity and database schema activity from the *Database Info* and *Schema Name* drop-down lists respectively.



Database target can insert/update current date in the database. This current date is added in the input XML in two ways:

- Source XML
- Mapping

It can be added through the source XML which has the current date already defined in its code.

It can be added through mapping, if current date is defined as a constant in the Date field, or as a variable which has the value "Current Date". In this case, when mapping is done, then database target accesses the current date and inserts/updates it accordingly.

- 7. Database Operation specifies how data records are inserted into database tables. Select one of the following database operations:
  - Insert
  - Update
  - Insert/Update
  - Update/Insert

The effect that the selection has on the database is listed in the table below.



Database Operation	Effect on Database
Insert	This option is selected when you want to insert records into the database tables. If records already exist in the database table, new records are added in the database table along with existing records. When a column e.g. CompanyName of database table is marked as Primary Key, more than one record cannot exist in the database table for the same Company Name. In this case if data of a company i.e. Microsoft Corporation already exist, insert operation fails and data is not inserted into the database.
Update	This option is selected when you want to update the existing record. To use updated option a column of database must be marked as Primary Key. When Update option is selected, database target first checks which column of the database table is marked as Primary Key. Suppose CompanyName column is marked as Primary Key. Now database target check whether data of a company e.g. Microsoft Corporation already exists, database target updates the existing records. If none of the column is marked as Primary key, Update operation fails.
Insert/Update	This option is selected when the database target first tries to insert the data into database table. If insert operation fails, database target tries to update the data.
Update/Insert	This option is selected when the database target first tries to update the database table. If update operation fails, database target tries to insert the data.

Table 8 2. Effect on	Database based	on the selected	Database Operation
		on the selected	Database operation

If the specified database operation fails on any source data, error records are created. While creating a process using Database Target, you can specify what to do with error records.

- Error records can be saved into repository file.
- Error records can be ignored.
- It can be further processed (e.g. can be sent to file target).
- Process Flow can be aborted, if there is any error record.

In process designer, right click on the database target activity and select view properties. Select the value of the "Error Record" properties.

To learn, how to use Process Designer, refer to the section Using Process Designer.

To learn about Advanced Properties refer to <u>Changing Advanced</u> <u>Properties</u> section.

Ø



When an excel file is used as a database target, only *Insert* operation is supported. The *Update, Insert/Update* and *Update/Insert* operations are not supported.

When an excel file is used as a database target, the error records are not generated in case of data type mismatch.

- 8. Click **Save** button. This displays a screen confirming that the database target activity has been created successfully. If the *Comments* property is enabled, then clicking **Save** will display a screen where you need to enter comments related to creating the database target (refer to Figure 3.6).
- 9. Enter the comments in the *Add Comments* field.



The comment should be at least 1 character in length.

10. Click **OK** to save the comments. This displays a screen confirming that the database target activity has been created successfully.



By default, the *Comments* property is disabled. To enable it, refer to the *Updating System Properties* section in *Administrator* Guide.

### **CREATING FILE TARGET ACTIVITY**

The File Target activity provides the ability to specify the name and path of the target file to be created.

In the Adeptia Suite this feature is available in:

BPM Suite	Integration Suite	ETL Suite
$\checkmark$	$\checkmark$	$\checkmark$

#### Steps to create a File Target Activity

- 1. In the Adeptia Suite homepage menu, click **[+]** Configure to expand the tree. All the items in the Configure category are displayed.
- 2. Click [+] Services to expand the tree. All the items in the Services category are displayed.
- 3. Click [+] Target to expand the tree, and then click File. The Manage File Target screen is displayed (see Figure 8.5).



] Configure [+] Forms	Configure > Services > Target > File				
<ul> <li>[+] WorkFlow</li> <li>[-] Services</li> <li>[+] Data Dictionary</li> </ul>	New   Edit   Delete   Revisions   Dependencies	Select Field to S	earch 💌		Search
[+] Source	# Name	Description	Owner	Perm.	Modified 🔻
[+] Schema	1 O InventoryItemsTarget	output XML location	demouser	RWX	11/24/09 14:24
[-] Target ♦0 Adv. Database	2 🔘 EmployeeBenefitTarget	output XML file location	demouser	RWX	11/24/09 14:24
<ul> <li>Adv. Database</li> <li>Database</li> </ul>	3 O EvalScript_FileTarget	File Target for Appended Employee Records	demouser	RWX	11/24/09 14:24
File File	4 O EvalPF_FileTarget_ErrorRecord	Erroneous records in input excel	demouser	RWX	11/24/09 14:23
안 FTP	5 O EvalPF_FileTarget_UpdateError	Erroneous records found while updating records in database2	demouser	RWX	11/24/09 14:23
HTTP I JMS	6 O EvalPF_FileTarget_InsertError	Erroneous records found while inserting records in database1	demouser	RWX	11/24/09 14:23
LAN File	7 O EvalXform_FileTarget	excel file target	demouser	RWX	11/24/09 14:23
🖾 Mail	8 O EvalPD_FileTarget	file target with purchase order	demouser	RWX	11/24/09 14:23
WebDAV					
[+] Web Services					

#### Figure 8.5: Manage File Target

4. Click the New link. The Create File Target screen is displayed (see Figure 8.6).

Configure > Services > Target > File	
[-] Standard properties	
Name *	
Description *	
File Path *	
File Name *	
[+] Advanced properties	
* Mandatory fields.	
Save Cancel Test	

Figure 8.6: Create File Target

- 5. Enter the name and description of the new File Target in the *Name* and *Description* fields respectively.
- 6. To specify the target location, enter the full path of the target file in the *File Path* field.
- 7. Enter the name of the target file in the *File Name* field.



8. Click **Save** button. This displays a screen confirming that the file target activity has been created successfully. If the *Comments* property is enabled, then clicking **Save** will display a screen is displayed where you need to enter comments related to creating file target (refer to Figure 3.6).



9. Enter the comments in the *Add Comments* field.


11
×//

The comment should be at least 1 character in length.

10. Click **OK** to save the comments. This displays a screen confirming that the file target activity has been created successfully.



By default, the *Comments* property is disabled. To enable it, refer to the *Updating System Properties* section in *Administrator* Guide.



## CREATING FTP TARGET ACTIVITY

feature for multiple sheet is not supported.

FTP Target provides the ability to specify a target location that is accessible via FTP.

In the Adeptia Suite this feature is available in:

BPM Suite	Integration Suite	ETL Suite
$\checkmark$		

Steps to create a FTP Target Activity

- 1. In the Adeptia Suite homepage menu, click **[+]** Configure to expand the tree. All the items in the Configure category are displayed.
- 2. Click [+] Services to expand the tree. All the items in the Services category are displayed.
- 3. Click **[+]** Target to expand the tree, and then click **FTP**. The Manage FTP Target screen is displayed (see Figure 8.7).



[-] Configure [+] Forms	Confi	gure > Services > Target > FTP				
<ul> <li>[+] WorkFlow</li> <li>[-] Services</li> <li>[+] Data Dictionary</li> </ul>	New	Edit   Delete   Revisions   Dependencies	Select Field to S	earch 💙		Search
<ul> <li>[+] Data Dictionary</li> <li>[+] Source</li> <li>[+] Schema</li> </ul>	#	Name	Description	Owner	Perm.	
[-] Target	1 ()	PlaceCorrectedInventoryFile	place CS∨ file in ftp	demouser	RWX	09/01/09 12:25
<b>∳]</b> Database						
E File						

Figure 8.7: Manage FTP Target

4. Click the **New** link. The Create FTP Target screen is displayed (see Figure 8.8).



Configure > Services > Target > FTP			
[-] Standard properties			
Name *			
Description *			
Host Name *			
Port *	21		
User Id *			
Password			
Confirm Password			
Remote File Path			
File Name *			
Transfer Mode *	BINARY -		
Transfer Type *	PASSIVE -		
SSH FTP (SFTP) *			
FTP Over TLS/SSL (FTPS) *			
FTPS Mode	Explicit 💌		
Protection Level	Clear		
Validate Server			
Keystore Name	SELECT		
[+] Advanced properties			
* Mandatory fields.			
Save Cancel Test			

Figure 8.8: Create FTP Target

- 5. Enter the name and description of the new FTP Target in the *Name* and *Description* fields respectively.
- 6. Enter the host name/IP address and port number of the FTP Server in the *Host Name* and *Port* field respectively.



- 7. Enter the username and password of FTP Server in the *User ID* and *Password* fields respectively. Then, re-enter the password in the *Confirm Password* field.
- 8. Enter the full path of the target file in the *Remote File Path* field.
- 9. Enter the name of the target file in the *File Name* field.
- 10. Select the transfer mode as either BINARY or ASCII from *Transfer Mode* drop-down list. In BINARY mode a file is copied bit for bit from one machine to the other. Both files (the original and the transferred file) will contain exactly the same sequence of bytes. In ASCII mode a file may be changed slightly to maintain the meaning of EOL (End Of Line) characters.
- 11. Select the transfer type as either Active or Passive from the *Transfer Type* drop-down list. Active transfer is more secure since the client only initiates communication to the Server on one port whereas in case of Passive transfer the client initiates communication to the Server over two ports. Passive mode is useful when you are behind a firewall or a proxy.
- 12. Check the *SSH FTP (SFTP)* checkbox if the FTP Server specified in the *Host Name* field is an FTP Server over SSH.
- 13. Check the *FTP Over TLS/SSL (FTPS)* checkbox, if the FTP Server, specified in the *Host Name* field is an FTP Server over TLS/SSL.
- 14. Incase you have selected *FTP Over TLS/SSL (FTPS)*, checkbox, then select the FTPS mode from *FTPS Mode* drop-down list. It can be *Explicit* or *Implicit* depending on FTP Server that you are accessing.
- 15. Select the protection level supported by the FTP Server, from the *Protection Level* dropdown list. It can be *Clear* or *Private*.
- 16. If you want to validate the certificate sent by the FTPS Server, check the *Validate Server* check box.
- 17. Select keystore activity from the *Keystore Name* drop-down list. This option is applicable only when you have checked the *Validate Server* checkbox.

When *Validate* option is unchecked, it always accepts the certificate sent by FTPS Server.

When this option is checked, it validates the certificate sent by FTPS server against the certificate imported in Keystore.

Keystore is repository of security certificates.

To know how to create Keystore and import certificates, refer to *Creating Keystore* secton of *Administrator Guide*.



0

To learn about Advanced Properties refer to **<u>Changing Advanced</u>** <u>Properties</u> section.

- 18. Click **Save** button. This displays a screen confirming that the FTP target activity has been created successfully. If the *Comments* property is enabled, then clicking **Save** will display a screen where you need to enter comments for creating the FTP target (refer to Figure 3.6).
- 19. Enter the comments in the *Add Comments* field.



The comment should be at least 1 character in length.



20. Click **OK** to save the comments. This displays a screen confirming that the FTP target activity has been created successfully.



By default, the *Comments* property is disabled. To enable it, refer to the *Updating System Properties* section in *Administrator* Guide.



You can verify the FTP target activity at design time. For this, click **Test**. This verifies the values given in the *Host Name, Port, User ID, Password,* and *Secured* fields.

## CREATING HTTP TARGET ACTIVITY

HTTP Target provides the ability to specify file location that is accessible via HTTP.


In the Adeptia Suite this feature is available in:

BPM Suite	Integration Suite	ETL Suite
$\checkmark$	$\checkmark$	

Steps to create a HTTP Target Activity

- 1. In the Adeptia Suite homepage menu, click **[+]** Configure to expand the tree. All the items in the Configure category are displayed.
- 2. Click [+] Services to expand the tree. All the items in the Services category are displayed.
- 3. Click [+] Target to expand the tree, and then click HTTP. The Manage HTTP Target screen is displayed (see Figure 8.9).


[-] Config [+] Fo	gure orms	Configure > Servi	ices > Target > HTTP			
[+] We	orkFlow ervices	New   Edit   Delete	Revisions   Dependencies	Select Fi	eld to Search 💙	Search
[+]	Data Dictionary					
[+]	Source	#	Name	Description	Owner	Perm. Modified •
[+]	Schema			No records found		
[-]	Target					
	<b>⇒</b> ] Adv. Database					
	<b>⇔</b> 0 Database					
	🛃 File					
	연출 FTP					
	E HTTP					




4. Click the **New** link. The Create HTTP Target screen is displayed (see Figure 8.10).



Configure > Services > Target > HTTP				
[-] Standard properties				
Name *				
Description *				
HTTP URL *				
Post Type *	HTTP 💌			
RFC Format *	RFC1867 💌			
[+] Advanced properties				
* Mandatory fields.				
Save Cancel Test				



- 5. Enter the name and description of the new HTTP Target in the *Name* and *Description* fields respectively.
- 6. Enter the URL of the target application to which you want to post the data, in the *HTTP URL* field. For example, *http://www.adeptia.com/Employee/sales.jsp*.



- 7. Select the post type whether HTTP or HTTPS from the *Post Type* drop-down list.
- 8. Select RFC format from the *RFC Format* drop-down list.



To learn about Advanced Properties refer to **Changing Advanced Properties** section.

- Click Save button. A screen is displayed confirming that the HTTP Target activity has been created successfully. If the *Comments* property is enabled, then clicking Save will display a screen where you need to enter comments related to creating the HTTP target (refer to Figure 3.6).
- 10. Enter the comments in *Add Comments* field.



The comment should be at least 1 character in length.

11. Click **OK** to save the comments. A screen is displayed confirming that the HTTP Target activity has been created successfully.



Ø	

By default, the *Comments* property is disabled. To enable it, refer to the *Updating System Properties* section in *Administrator* Guide.



You can verify the HTTP target activity at design time. For this, click **Test**. This verifies the values given in the *HTTP URL* and *Port Type* fields.

### **CREATING JMS TARGET ACTIVITY**

The JMS Target activity provides the ability to specify a queue or topic of a JMS Server as a Target. JMS target is used to publish the target data in a topic or to post the data in the queue of a JMS Server.

In the Adeptia Suite this feature is available in:

BPM Suite	Integration Suite	ETL Suite
$\checkmark$	$\checkmark$	

#### Prerequisites:

• JMS Provider activity must be created before creating JMS Target activity.

#### Steps to create a JMS Target Activity

- 1. In the Adeptia Suite homepage menu, click **[+]** Configure to expand the tree. All the items in the Configure category are displayed.
- 2. Click [+] Services to expand the tree. All the items in the Services category are displayed.
- 3. Click [+] Target to expand the tree, and then click JMS. The Manage JMS Target screen is displayed (see Figure 8.11).

[-] Configure [+] Forms [+] WorkFlow	Confi	gure > Services > Target > JMS				
[-] Services	New	Edit   Delete   Revisions   Dependencies	Select Field to S	earch 💌		Search
[+] Data Dictionary						
[+] Source	#	Name	Description	Owner	Perm.	Modified <b>*</b>
[+] Schema	1 🔾	EvalRec_JMSTarget	JMS Queue target	demouser	RWX	08/12/05 17:22
[-] Target ⇒0 Adv. Database	2 ()	EvalJMSE_JMSTarget	JMS Target to post the message to the queue1	demouser	RWX	07/20/05 17:27
+0 Database						
🛃 File						
₽ <u>\$</u> FTP						
🖹 НТТР						
🖂 JMS						
🛃 LAN File						

Figure 8.11: Manage JMS Target

4. Click the **New** link. The Create JMS Target screen is displayed (see Figure 8.12).




Configure > Services > Target > JMS				
[-] Standard properties				
Name *				
Description *				
JMS Provider*	EvalRec_JMSProvider (JMS Provider to connect)			
Connection Type*				
Queue Or Topic Name *				
CreateDynamically				
UserName				
Password				
Confirm Password				
[+] Advanced properties				
* Mandatory fields.				
Save Cancel Test				

Figure 8.12: Create JMS Target

- 5. Enter the name and description of the new JMS Target in the *Name* and *Description* fields respectively.
- 6. Select the JMS Provider activity from the *JMS Provider* drop-down list.

3	To learn how to create JMS Provider activity, refer to Creating JMS
Ø	Provider Activity section in Administrator Guide.

- 7. Select the connection type as either queue or topic from the *Connection Type* drop-down list.
- 8. Enter the name of queue or topic as configured in the JMS Server in the *Queue Or Topic Name* field.
- 9. Check the *Create Dynamically* checkbox, if queue or topic specified above, doesn't already exist on the JMS Server. If you enable create dynamically check box, it will create the queue or topic specified above on the JMS Server.
- 10. Enter the username and password required to connect to JMS Server in the *UserName* and *Password* fields respectively. Then, re-enter the password in the *Confirm Password* field.



11. Click **Save** button. This displays a screen confirming that the JMS target activity has been created successfully. If the *Comments* property is enabled, then clicking **Save** will display a screen where you need to enter comments related to creating the JMS target (refer to Figure 3.6).

ADEPTIA

12. Enter the comments in the *Add Comments* field.



The comment should be at least 1 character in length.

13. Click **OK** to save the comments. This displays a screen confirming that the JMS target activity has been created successfully.



By default, the *Comments* property is disabled. To enable it, refer to the *Updating System Properties* section in *Administrator* Guide.



You can verify the JMS target activity at design time. For this, click **Test**. This verifies the values given in the *JMS Provider* and *Connection Type* fields.

### CREATING LAN FILE TARGET ACTIVITY

LAN File Target provides the ability to specify a target file location that is accessible on the network.

In the Adeptia Suite this feature is available in:


BPM Suite	Integration Suite	ETL Suite
$\checkmark$	$\checkmark$	$\checkmark$

### Steps to create a LAN File Target Activity

- 1. In the Adeptia Suite homepage menu, click **[+]** Configure to expand the tree. All the items in the Configure category are displayed.
- 2. Click [+] Services to expand the tree. All the items in the Services category are displayed.
- 3. Click [+] Target to expand the tree, and then click LAN File. The Manage LAN File Target screen is displayed (see Figure 8.13).




[-] Configure [+] Forms	Configure > Services > Target > LAN File			
[+] WorkFlow [-] Services	New   Edit   Delete   Revisions   Dependencies	Select Fiel	d to Search 💙	Search
[+] Data Dictionary				
[+] Source	# Name	Description	Owner Perm.	Modified 🔻
[+] Schema		No records found		
[-] Target				
Adv. Database				
Database				
🛃 File				
😤 FTP				
🗄 HTTP				
🖂 JMS				
🛃 LAN File				



4. Click the **New** link. The Create LAN File Target screen is displayed (see Figure 8.14).

Configure > Services > Target > LAN File				
[-] Standard properties				
Name *				
Description *				
File Path *				
File Name *				
File System *	UNIX			
Use VFS *				
Secure				
User Id *				
Password				
Confirm Password				
[+] Advanced properties				
* Mandatory fields.				
Save Cancel Test				



- 5. Enter the name and description for the new LAN File Target in the *Name* and *Description* fields respectively.
- 6. Enter the network path of the folder where you want the target file to be created in the *File Path* field in the following format:



#### \\hostname\folder name

- 7. Enter the name of target file in the *File Name* field.
- 8. Select the target file system, whether Windows or Unix from the *File System* drop-down list.
- 9. When Adeptia Suite is installed on Windows Operating System, LAN File Target uses windows service to connect to remote machine. It just connects once and uses the same connection with the same User ID and Password (which is stored in the cache) every time. If you want to enforce the validation of User ID and Password every time while accessing the remote machine, check the *Use VFS* checkbox.
- 10. If username and password is required to access the target location, check the Secure checkbox.
- 11. Enter the username and password in the *User ID* and *Password* fields respectively. Then reenter the password in the *Confirm Password* field.



To learn about Advanced Properties refer to Changing Advanced Properties section.

- 12. Click **Save** button. This displays a screen confirming that the LAN file target activity has been created successfully. If the *Comments* property is enabled, then clicking **Save** will display a screen where you need to enter comments related to creating the LAN file target (refer to Figure 3.6).
- 13. Enter the comments in the *Add Comments* field.



The comment should be at least 1 character in length.

14. Click **OK** to save the comments. This displays a screen confirming that the LAN file target activity has been created successfully.



By default, the *Comments* property is disabled. To enable it, refer to the *Updating System Properties* section in *Administrator* Guide.

You can verify the LAN file target activity at design time. For this, click **Test**. This verifies the values given in the *File Path, User ID* and *Password* fields.

When using a LAN file target activity in a process flow, the *append* property is set to *False* by default. This implies that an existing target activity is overwritten by the new target activity. If you want to append the new target activity to the existing target activity, you need to set this property to *True*. However, this feature is supported for Excel and Text files only.

## CREATING MAIL TARGET ACTIVITY

Mail Target provides the ability to specify target location that is accessible via Mail.

In the Adeptia Suite this feature is available in:



BPM Suite	Integration Suite	ETL Suite
$\checkmark$	$\checkmark$	

### Steps to create a Mail Target Activity

- 1. In the Adeptia Suite homepage menu, click **[+]** Configure to expand the tree. All the items in the Configure category are displayed.
- 2. Click [+] Services to expand the tree. All the items in the Services category are displayed.
- 3. Click [+] Target to expand the tree, and then click Mail. The Manage Mail Target screen is displayed (see Figure 8.15).

[+] Forms [+] WorkFlow	Confi	gure > Services > Target > Mail				
[-] Services	New	Edit   Delete   Revisions   Dependencies	Select Field to 3	Search 💙		Sear
[+] Data Dictionary						
[+] Source	#	Name	Description	Owner	Perm.	Modified 🔻
[+] Schema [-] Target	1 ()	SendCustomerOrders	this email sends updated file with shipping and invoice info	demouser	RWX	09/01/09 12:27
<ul> <li>Adv. Database</li> </ul>	2 🔿	NotifySales	notify sales if quantity exceeds 100	demouser	RWX	09/01/09 12:26
<b>⇒</b> ] Database	3 ()	EvalPD_MailTargetLessThan50k	mail target for purchase order less than \$50,000	demouser	RWX	08/23/05 15:02
🛃 File	4 ()	EvalPD_MailTargetGreaterThan50k	mail target for approved purchase order	demouser	RWX	08/12/05 15:21
Cố FTP						
🕒 НТТР						
🖾 JMS						
🛃 LAN File						
🖾 Mail						

Figure 8.15: Manage Mail Target

4. Click the **New** link. The Create Mail Target screen is displayed (see Figure 8.16).



Design > Services > Target > Mail				
[-] Standard properties				
Name *				
Description *				
Protocol *	SMTP -			
Outgoing Mail Server *				
Domain				
CDO host machine				
Enable SSL				
Port	25			
From(Email-Id) *				
To Email-Id(s) (comma separated) *				
Subject *				
User Id				
Password				
Confirm Password				
Message Content Type	Plain 💌			
Data Location*	Attachment 💌			
File Name				
[+] Advanced properties				
* Mandatory fields.				
Save Cancel Test				

Figure 8.16: Create Mail Target

- 5. Enter the name and description of the new Mail Target in the *Name* and *Description* fields respectively.
- 6. Select the Internet standard protocol to be used for sending outgoing mails, from the *Protocol* drop-down list. You can select either the SMTP or the MAPI protocol. Based on the selected protocol, the default port number for that protocol is displayed in the *Port* field.
- 7. Enter the outgoing mail (SMTP) Server address in the *Outgoing Mail (SMTP) Server* field.



To access mails from Microsoft Exchange Server use *MAPI* in *Protocol* dropdown list. To connect Adeptia Suite with Microsoft Exchange Server, you need to buy a third party tool called J-Integra for Exchange. J-Integra for Exchange is a high performance middleware bridge that enables Java Exchange interoperability. If you want to retrieve mails from an Exchange Server using J-Integra, Select MAPI in the *Protocol* drop-down list.

If MAPI is selected in Protocol drop-down list:

- Enter name of the exchange server in Outgoing Mail Server field
- Enter the domain name in the *Domain* field
- Enter the name of the CDO host machine in CDO host machine field. CDOConfig.exe is a tool that comes with the J-Integra for Exchange SDK and is used for configuring CDO. Host where CDO is configured is called CDO host machine.

For detailed information about Jintegra for Exchange, refer to <a href="http://j-integra.intrinsyc.com/products/exchange/">http://j-integra.intrinsyc.com/products/exchange/</a>.

- 8. Check the *Enable SSL* checkbox, if the specified outgoing mail server requires a secure connection.
- 9. Enter the port of Outgoing Mail Server in the *Port* field.
- 10. Enter the sender's Email-Id in the *From (Email-Id)* field.
- 11. Enter the Email-Id(s) of the email recipients separated by commas in the *To Email-Id(s) (comma separated)* field.
- 12. Enter the subject of Target email in the *Subject* field.
- 13. Enter the username and password of Mail Server in the *User ID* and *Password* fields respectively. Then, re-enter the password in the *Confirm Password* field.
- 14. Select the content type of the outgoing message (as Plain or HTML) from *Message Content Type* drop-down list.

This field is enabled only when SMTP is selected in the Protocol field.

- 15. Select the location of data in the mail whether it is to be sent as an attachment or in email body from the *Data Location* drop-down list.
- 16. If the data is to be sent as attachment, enter the name of the file in the *File Name* field.

A	То	learn	about	Advanced	Properties	refer	to	Changing	Advanced
	Pro	<u>pertie</u>	sectio	n.					

- 17. Click **Save** button. This displays a screen confirming that the mail target activity has been created successfully. If the *Comments* property is enabled, then clicking **Save** will display a screen where you need to enter comments related to creating the mail target (refer to Figure 3.6).
- 18. Enter the comments in the *Add Comments* field.



Ø

The comment should be at least 1 character in length.



19. Click **OK** to save the comments. This displays a screen confirming that the mail target activity has been created successfully.



By default, the *Comments* property is disabled. To enable it, refer to the *Updating System Properties* section in *Administrator* Guide.



You can verify the mail target activity at design time. For this, click **Test**. This verifies the values given in the *Outgoing Mail (SMTP) Server, Port, User ID* and *Password* fields.

## CREATING WEBDAV TARGET ACTIVITY

The WebDAV Target activity provides the ability to specify a WebDAV Server as a target.

In the Adeptia Suite this feature is available in:

BPM Suite	Integration Suite	ETL Suite
$\checkmark$	$\checkmark$	$\checkmark$

### Steps to create WebDAV Target Activity

- 1. In the Adeptia Suite homepage menu, click **[+]** Configure to expand the tree. All the items in the Configure category are displayed.
- 2. Click [+] Services to expand the tree. All the items in the Services category are displayed.
- 3. Click [+] Target to expand the tree, and then click **WebDAV**. The Manage WebDAV Target screen is displayed (see Figure 8.17).

[-] Configure [+] Forms	Configure > Services > Target > WebDAV			
[+] WorkFlow [-] Services	New   Edit   Delete   Revisions   Dependencies	Select Fi	eld to Search 💌	Search
<ul> <li>[+] Data Dictionary</li> <li>[+] Source</li> <li>[+] Schema</li> </ul>	# Name	Description No records found	Owner Perm.	Modified <b>•</b>
[-] Target +0 Adv. Database				
¢0 Database ∯ File የਨੂੰ FTP				
HTTP I JMS				
紀 LAN File 외 Mail				
WebDAV				

Figure 8.17: Manage WebDAV Target

4. Click the **New** link. The Create WebDAV Target screen is displayed (see Figure 8.18).



Configure > Services > Target > WebDAV				
[-] Standard properties				
Name *				
Description *				
Server Name *				
Server Port *	8080			
Secure				
User Id				
Password				
Confirm Password				
File Location *				
File Name *				
[+] Advanced properties				
* Mandatory fields.				
Save Cancel Test				

Figure 8.18: Create WebDAV Target Activity

- 5. Enter the name and description of the new WebDAV target in the *Name* and *Description* fields respectively.
- 6. Enter the name of WebDAV Server and port on which WebDAV Server is running in the *Server Name* and *Server Port* fields respectively.
- 7. If the WebDAV is secured i.e. username and password is required to access it, then check the *Secure* checkbox and enter the username and password of the WebDAV Server in the *User ID* and *Password* fields respectively.

Ø

If you are using WebDAV Server, which is built in with Adeptia Suite, the default Username is "Administrator" and the password is "indigo".

- 8. Re-enter the password in the *Confirm Password* field.
- 9. Enter the path of the target file in the *File location* field.
- 10. Enter the name of the target file in the *File Name* field.





Directory specified in the File location field, must be available in the WebDAV repository. To learn about Advanced Properties refer to <u>Changing Advanced</u> <u>Properties</u> section.

- 11. Click **Save** button. This displays a screen confirming that the WebDAV target activity has been created successfully. If the *Comments* property is enabled, then clicking **Save** will display a screen where you need to enter comments related to creating the WebDAV target (refer to Figure 3.6).
- 12. Enter the comments in the *Add Comments* field.



The comment should be at least 1 character in length.

13. Click **OK** to save the comments. This displays a screen confirming that the WebDAV target activity has been created successfully.



By default, the *Comments* property is disabled. To enable it, refer to the *Updating System Properties* section in *Administrator* Guide.



You can verify the WebDAV target activity at design time. For this, click **Test**. This verifies the values in the *Server Name* and *Server Port* fields and checks whether the file actually exists in the specified location.



# **9** CREATING WEB SERVICES

The Web Services module has two components:

- <u>Consumer</u>
- Provider

The *Consumer* component allows users to access any Web Services on the Web unless the service to be accessed has restricted access. Using the *Provider* component users can publish their Web Services for access to others. Access to Web Services to be published can also be restricted to selected users

This section also describes the creation process of:

- <u>Security Policy activity for Web Services</u>
- <u>Consumer Web Services using UDDI</u>
- <u>Consumer Web Services using URI</u>
- Provider or Publisher Web Services

### **CREATING SECURITY POLICY ACTIVITY FOR WEB SERVICES**

Since Web Services expose crucial business information, Web services security is critically important. A Web service can be secured using Security Policy activity. It is recommended that users create an appropriate security policy before they publish Web services using the Web service provider.

In the Adeptia Suite this feature is available in:


BPM Suite	Integration Suite	ETL Suite
$\checkmark$	$\checkmark$	

#### Steps to create a Security Policy Activity

- 1. In the Adeptia Suite homepage menu, click **[+]** Configure to expand the tree. All the items in the Configure category are displayed.
- 2. Click [+] Services to expand the tree. All the items in the Services category are displayed.
- 3. Click **[+] Web Services** to expand the tree, and then click **Security Policy**. The Manage Security Policy screen is displayed (see Figure 9.1).



[+] My Tasks	Configure > Serv	vices > Web Services >	curity Policy			
[+] My Documents						
[+] My Solutions	New   Edit   Delete	Revisions   Dependencies	Soloct Eig	ld to Search 🔻		Search
[+] My Monitor	New   cold   Delete	Revisions   Dependencies	Select Pie	to search	1	Search
[+] History						
	#	Name	Description	Owner	Perm.	Modified <b>T</b>
[+] Design			No records found			
[-] Configure						
[+] Forms						
[+] WorkFlow						
[-] Services						
[+] Data Dictionary						
[+] Source						
[+] Schema						
[+] Target						
[-] Web Services						
Security Policy						
Consumer						
🛃 Provider						



4. Click the **New** link. The Create Security Policy screen is displayed (see Figure 9.2).

Design > Services > Web Services > Security Policy				
[-] Standard properties				
Name *				
Description *				
Basic Authentication				
User ID				
Password				
Confirm Password *				
SSL				
Key Store Name	None 💌			
<ul> <li>[+] Outgoing Message properties</li> <li>[+] Incoming Message properties</li> <li>[+] Advanced properties</li> </ul>				
* Mandatory fields.				
Save Cancel				

Figure 9.2: Create Security Policy

5. Enter the name and description of the new Security Policy in the *Name* and *Description* fields respectively.



- 6. To use basic authentication, check the *Basic Authentication* checkbox and enter the user id and password in the *User Id* and *Password* field respectively. Enter the password in the *Confirm Password* field also.
- 7. To use basic authentication with SSL, check the *SSL* checkbox and select the keystore from the *Keystore* drop-down list.
- 8. To define message level security (WS-Security) for outgoing message, expand the *Outgoing Message Properties* (see Figure 9.5).



[-] Outgo	oing Message properties			
	Signature			
	Key Store	None	Ŧ	
	Alias			
	Key Identifier Type	None	~	
	Signature Algorithm	Default		
	Signature Canonicalization	Default		v
	Use Single Certificate	🔲 Use single certificate for si	gning	
		# Name	Namespace	Encode
		1		Content 💌
		2		Content 💌
	Parts	3		Content 💌
		4		Content 💌
				Content
	Encryption	Add Row Remove Row		
	Key Store	None	*	
	Alias			
	Key Identifier Type	None	-	
	Embedded Key Name	Tione		
	Emboddod Roy Hamo	I		
	Symmetric Encoding Algorithm	Default	-	
	Symmetric Encoding Algorithm	Default	<b>•</b>	1
	Key Encryption Algorithm	Default	V	
	Key Encryption Algorithm Encryption Canonicalization	Default Default	Y	- -
	Key Encryption Algorithm	Default Default Indicate whether to encrypt	the symmetric key into an e	encrypted key or not
	Key Encryption Algorithm Encryption Canonicalization	Default Default Indicate whether to encrypt # Name	Y	encrypted key or not
	Key Encryption Algorithm Encryption Canonicalization	Default Default Indicate whether to encrypt # Name 1	the symmetric key into an e	encrypted key or not Encode
	Key Encryption Algorithm Encryption Canonicalization	Default           Default           Indicate whether to encrypt           # Name           1           2	the symmetric key into an e	Content
	Key Encryption Algorithm Encryption Canonicalization Create Encrypted Key	Default Default Indicate whether to encrypt # Name 1	the symmetric key into an e	encrypted key or not Encode
	Key Encryption Algorithm Encryption Canonicalization Create Encrypted Key	Default           Default           Indicate whether to encrypt           # Name           1           2	the symmetric key into an e	Content
	Key Encryption Algorithm Encryption Canonicalization Create Encrypted Key	Default           Default           Indicate whether to encrypt           # Name           1           2           3	the symmetric key into an e Namespace	Content
	Key Encryption Algorithm Encryption Canonicalization Create Encrypted Key Parts User Name Token	Default           Default           Indicate whether to encrypt           # Name           1           2           3           4	the symmetric key into an e Namespace	Content
	Key Encryption Algorithm Encryption Canonicalization Create Encrypted Key Parts	Default           Default           Indicate whether to encrypt           # Name           1           2           3           4           Add Row           Remove Row	the symmetric key into an e Namespace	Content
	Key Encryption Algorithm Encryption Canonicalization Create Encrypted Key Parts User Name Token	Default           Default           Indicate whether to encrypt           # Name           1           2           3           4           Add Row           Remove Row	the symmetric key into an e Namespace	Content
	Key Encryption Algorithm Encryption Canonicalization Create Encrypted Key Parts User Name Token UserName	Default           Default           Indicate whether to encrypt           # Name           1           2           3           4           Add Row           Remove Row	the symmetric key into an e Namespace	Content
	Key Encryption Algorithm Encryption Canonicalization Create Encrypted Key Parts Varts User Name Token UserName Password Confirm Password *	Default           Default           Indicate whether to encrypt           # Name           1           2           3           4           Add Row           Remove Row	the symmetric key into an e Namespace	Content
	Key Encryption Algorithm Encryption Canonicalization Create Encrypted Key Parts Ver Name Ver Name Password Confirm Password * Token Nonce Add Created	Default Default Indicate whether to encrypt  Name I I Z I Add Row Remove Row I Adds a nonce Adds a created	the symmetric key into an e Namespace	Content
	Key Encryption Algorithm Encryption Canonicalization Create Encrypted Key Parts User Name Token UserName Password Confirm Password * Token Nonce Add Created Password Type	Default Default Default Indicate whether to encrypt # Name 1 2 3 4 Add Row Remove Row Adds a nonce Adds a created None	the symmetric key into an e Namespace	Content
	Key Encryption Algorithm Encryption Canonicalization Create Encrypted Key Parts Ver Name Ver Name Password Confirm Password * Token Nonce Add Created	Default Default Indicate whether to encrypt  Name I I Z I Add Row Remove Row I Adds a nonce Adds a created	the symmetric key into an e Namespace	Content

Figure 9.3: Define Message Level Security for Outgoing Message

9. You can use one or more following options:

### Signature

Signs outgoing message content. Specify which Keystore to use and the desired alias/password. The parts table allows you to selectively sign only subsets of the message content (if left empty the entire message will be encrypted). To sign the



parts of the message you need to specify the name or namespace of the element to be signed.

#### Encryption

Encrypts outgoing message content. Specify which Keystore to use and the desired alias/password. The parts table allows you to selectively sign only subsets of the message content (if left empty the entire message will be encrypted). To encrypt the parts of the message you need to specify the name or namespace of the element to be encrypted

#### User Name Toke

Adds a Username Password token to the outgoing message, specify the username and password to use and if nonce/created should be added. The Password Type drop-down selects how the password should be serialized in the message.

### **Time Stamp**

Adds a Timestamp token to the outgoing message with the specified Time To Live value.

### Configure Signature

- a. To configure signature, select the *Signature* checkbox.
- b. Select the Key store from the Key Store drop-down list and define the following property in the respective fields.
  - Alias (This should be same as defined in *Alias* field in the Keystore)
  - Key Identifier Type (You can use *Binary Security Token* or X509 Certificate).
  - Signature Algorithm (This should be same as defined in the Key Algorithm field in the Keystore)
  - Signature Canonicalization
  - Use Single Certificate (Adeptia Suite always uses Single Certificate.)
- c. To define the parts to be signed, enter the name and its namespace in the *Name* and *Namespace* field respectively.
- d. Select whether you want to sign the *Content* or *Element* from the *Encode* drop-down list.

In case you do not define any part, whole message is signed.

### **Configure Encryption**

- a. To encrypt the message, select the Encryption checkbox.
- b. Select the Keystore from the Key Store drop-down list.



While using encryption, select the keystore with *RSA* key algorithm only.

- c. Enter the following property in the respective fields.
  - Alias (This should be same as defined in Alias field in the Keystore)
  - Key Identifier Type (You can use *Binary Security Token* or X509 Certificate).
  - Embedded Key Name (Keep it empty.)



- Symmetric Encoding Algorithm
- Key Encryption Algorithm
- Create Encrypted Key
- Encryption Canonicalization
- d. To define the parts to be encrypt, enter the name and its name space in the Name and Namespace field.
- e. Select whether you want to encrypt the Content or Element from the Encode dropdown list.

### Configure Username Token

- a. To add user name token, check the User Name Token checkbox and define the following properties in the respective fields.
  - User Name
  - Password
  - Confirm Password
  - Token Nonce
  - Add Created
  - Password Type

#### Configure Time Stamp

- a. To add Time Stamp with the message check the Time Stamp checkbox and enter the time (in seconds) in Time To Live field.
- 10. To define message level security (WS-Security) for incoming message expand *Incoming Message Properties* and check the *Incoming Message* checkbox (see Figure 9.4).

[-]	Incoming Message properties		
	Incoming Message		
	Decryption Key Store	None	T
	Signature Key Store	None	<b>•</b>

Figure 9.4: Define Message Level Security for Incoming Message

- 11. Select the keystore to decrypt the incoming message from the *Decryption Key store*.
- 12. To receive the singed message, select the keystore from the *Signature Keystore* field.

\$	То	learn	about	Advanced	Properties	refer	to	<u>Changing</u>	Advanced
Ø	Pro	pertie	<mark>s</mark> sectio	n.				<u>Changing</u>	

- 13. Click **Save** button. This displays a screen confirming that the security policy has been created successfully. If the *Comments* property is enabled, then clicking **Save** will display a screen where you need to enter comments for creating the security policy (refer to Figure 3.6).
- 14. Enter the comments in the *Add Comments* field.



The comment should be at least 1 character in length.



15. Click **OK** to save the comments. This displays a screen confirming that the security policy has been created successfully.



By default, the *Comments* property is disabled. To enable it, refer to the *Updating System Properties* section in *Administrator* Guide.

## **CREATING WEB SERVICE CONSUMER ACTIVITY**

A Web Service Consumer locates a Web service and invokes the operations it provides. A Web Service consumer activity is created to access any Web Service.

In the Adeptia Suite this feature is available in:

BPM Suite	Integration Suite	ETL Suite
$\checkmark$		

A Web Service can be located in two ways, explained in the table below.

	Table	9.1:	Web Services	5
--	-------	------	--------------	---

Method	Description
UDDI	UDDI (Universal Description, Discovery, and Integration) provides a mechanism for clients to dynamically find other Web Services. Using the UDDI interface, businesses can dynamically connect to services provided by external business partners. UDDI is a public registry, where one can publish and inquire about Web Services. A UDDI registry has two kinds of clients: businesses that want to publish a service (and its usage interfaces), and clients who want to obtain services of a certain kind and bind programmatically to them.
URI	URI (Uniform Resource Identifiers) provides a way for clients to define the location of Web Services by giving an HTML URL or Local LAN path for a WSDL file.

### **Creating Web Services Consumer Activity using UDDI**

### Steps to create a Web Service Consumer Activity using UDDI

- 1. In the Adeptia Suite homepage menu, click **[+]** Configure to expand the tree. All the items in the Configure category are displayed.
- 2. Click [+] Services to expand the tree. All the items in the Services category are displayed.



3. Click **[+] Web Services** to expand the tree, and then click **Consumer**. The Manage Consumer screen is displayed (see Figure 9.5).

Hen	ne  About   Help  Change Password  My Profile  Logo	at	User: ad	min Group: administrators P	ermissions: (read,	write, execute) User Type: sysadm
[+] [+]	My Tasks My Documents	Design > Services > Web Services > Consumer				
[+]	My Solutions	New   Edit   Delete   Revisions   Dependencies	-	-Select Field to Search	-	Search
[+] [+]	History	SaveAs				
		ø Name	Description	Style	Owner P	erm. Modified •
[+]	Model		No records found			
0	Design					
	[+] Forms					
	[+] WorkFlow					
	[-] Services					
	[+] Data Dictionary					
	[+] Source					
	[+] Schema					
	[+] Target					
	[-] Web Services					
	Security Policy					
	Consumer					


Figure 9.5: Manage Web Service Consumer Activity

4. Click the **New** link. The Create Web Service Consumer screen is displayed (see Figure 9.6).

Design > Services > Web Services > Consumer	
[-] Standard properties	
Specify web service definition location.	
Name *	
Description *	
Web Service Definition Location*	© UDDI O URI
Next Cancel	

Figure 9.6: Create Web Service Consumer Activity

- 5. Enter the name and description of the new Web Service Consumer activity in the *Name* and *Description* fields respectively.
- 6. Select UDDI in Web Service Definition Location.





Click Next button. The Web Service Consumer screen is displayed (see Figure 9.7).

Search allows you to search for a Business, Se	ervice, or Technical Model by NAME. You	I may use the '%' symbol as a wildcard that matches any character.
Name *	WS_Customer	
Description *	webservice_Customer	
Enquiry URL *		
Search For a *	Business	
Starting with *		
	Match Case	
	Find Whole Words Only	
Back Next Cancel		

Figure 9.7: Search a Web Service

8. Enter the URL of UDDI search site in *Enquiry URL* field.

For example, http://uddi.microsoft.com/inquire

- 9. Select the required category from the *Search For a* drop-down list.
- 10. Enter the relevant letter or word in the *Starting with* field.
- 11. You can check the *Match Case* and the *Find Whole Words* only checkbox to filter the search result.
- 12. Click **Next** button. A screen is displayed with the search result (see Figure 9.8).

100	echnical model results	tching model(s). Press the Back button to search a	niene
nul t	lacif relatives a total of 2 mai	wining insulation. These are black ballon to search a	a Alam P
	Technical Models Technical Model Name	Description	Overview URL
n.	Country Details	Get Currency, Currency code, International Dialing code, ISO Country code for all countries	http://www.webservices.net/country.asmx?WSDL
c	Country State	Country State	http://9.162.151.177AVSCountryState/?wsdl

Figure 9.8: Web Service search result

13. Select the required search result and click **Next** button. The Web Service screen is displayed with list of operations (see Figure 9.9).



Name *	WS_Consumer
escription *	Web Service Consumer
Service Name *	country -
Port Type*	Soap
Port *	countrySoap -
Style Name *	document
Operation(s) *	GetCountryByCountryCode GetISD GetCountries GetCurrencyCodeByCurrencyName GetISOCountryCodeByCountyName GetCurrencyCode

Figure 9.9: Select Web Service Operation

- 14. Select the name of Service from the Service Name drop-down list.
- 15. Select the port type from the *Port Type* drop-down list. A port type can support multiple ports. This selection populates the options in the *Ports* drop-down list.
- 16. Select the port for the selected port type from the *Ports* drop-down list.

Currently, the Soap12 port is not supported by Adeptia.

17. Select the required operation from the *Operation(s)* field. This selection automatically displays the style name in the *Style Name* field.

<b>Document</b> : When a WS Consumer invokes a <i>document</i> style Web service, the consumer typically sends it an entire document, such as a purchase order, rather than a discrete set of parameters. The Web service accepts the entire document, processes it, and may or may not return a result document. In a <i>document</i> style, the input can be read from context or a stream coming from another activity. Similarly, output can be set to context	Ø	The <i>Style Name</i> field is automatically populated according to the specified operation. There are two types of Style: <b>document</b> and <b>rpc</b> .
or can be generated as stream to other activities. In case the output is set to context, a variable is created in the context with name as specified in the		the consumer typically sends it an entire document, such as a purchase order, rather than a discrete set of parameters. The Web service accepts the entire document, processes it, and may or may not return a result document. In a <i>document</i> style, the input can be read from context or a stream coming from another activity. Similarly, output can be set to context or can be generated as stream to other activities. In case the output is set



Output Parameter Name field and then output is set into that variable.

**rpc**: In *rpc* style when WS Consumer invokes the Web service, the consumer sends parameter values to the Web service, which executes the required methods, and then sends back the return values. In *rpc* style, input can be read from the context only and the output parameter is set in the context only. This style does not generate a stream. A variable is created in the context with name as specified in the Output Parameter Name field and then output is set into that variable.

In the current example, the specified Web Service is of *document* style.

18. Click **Next** button. The Web Service Consumer Screen is displayed (see Figure 9.10).

ing input a gramater Valueta	Cound as the state of the second state of the	an and send out is not interaction of
ameters).	) and output parameter name (in ca	e operation has input/output
Name *	WS_Consumer	
Description *	Web Service Consumer	
Service Name *	country	
Port Type*	Soap	
Port*	countrySoap	
Operation*	GetCurrencyByCountry	
Style*	document	
Input Document*		
	1	Show input Schema
	\$inputHeader	-
nput Header document*		
nput Header document		Show Input Header Schema

### Figure 9.10: Enter Input XML

19. Enter the Input XML in the *Input Document* field. Input document is used to define the input data for WS Consumer activity. The actual value could be given in three ways, explained in the table below.



Method	Description
Definition Time	Here the complete XML document, which is compliant with the Input XSD, has to be copied in the <i>Input</i> <i>Document</i> field. To view sample XSD, click <b>Show Input</b> <b>Schema</b> link. The sample input schema is displayed. Do not paste this schema in the <i>Input Document</i> field.
Run Time	Here a variable prefixed with \$ is defined in the <i>Input</i> <i>Document</i> field. For example \$variable1. The value of variable1 will be searched in process flow context during process flow execution as the control reaches web service consumer activity. The value must be an XML string.
Streaming	WS Consumer activity can also consume stream as input data from another activity. This behavior is controlled at the time of the process flow creation not at the time of WS Consumer activity creation. At creation time user must give either an XML document or variable as defined above.

- 20. At execution time WS consumer activity will search for its input in following order:
- 1. Take input from Stream
- 2. Search variable in process flow context
- 3. Get XML document

The way input is passed to the WS Consumer activity depends upon the style *document* or *rpc* not on WSDL locator UDDI or URI.

21. Enter Header XML in the "*Input Header Document*" field to define this at design time. You can also enter a variable with \$ prefix if you want read this value dynamically from context. This value cannot be read from stream.

	-	The WS Header element supports multiple headers.
17	_	The WS frequer element supports multiple frequers.
Ø	•	Header is optional it may be there in some operations or may not be there in other.
	•	If there is any fault as an output of web service call, it sets as "Output Parameter Name" + "Fault" in the process context.
	-	Web service response may also have header. The header is set into context with variable "output Parameter Name" + "Header".


- 22. Enter relevant context variable in the *Output Parameter Name* field. Web Service stores the output in this context variable.
- 23. Click **Next** button. The Select Security Policy screen is displayed (see Figure 9.11).



Operation *	GetCurrencyByCountry	
	xml version=*1.0" encoding=*utf-8*?  <getcurrencybycountry xmlns="http://www.webserviceX.NET*&gt;<countryna CountryName&gt;</countryna </getcurrencybycountry 	ame>india </td
Input Document		
Output Parameter	Currency	Web serv
Style *	document	
Security Policy		
Maintain Session	$\checkmark$	

Figure 9.11: Select Security Policy

- 24. Select the Security Policy activity from the Security Policy drop-down list.
- 25. Enable *Maintain Session* checkbox if the web service, which you are accessing, maintains session through cookie. This field is applicable for only *Document* style web services.



- 26. Click **Save** button. This displays a screen confirming that the web service consumer has been created successfully. If the Comments property is enabled, then clicking **Save** will display a screen where you need to enter comments for creating the web service consumer (refer to Figure 3.6).
- 27. Enter the comments in the *Add Comments* field.



The comment should be at least 1 character in length.

28. Click **OK** to save the comments. This displays a screen confirming that the web service consumer has been created successfully.



```
Ø
```

By default, the *Comments* property is disabled. To enable it, refer to the *Updating System Properties* section in *Administrator* Guide.

### **Creating Web Services Consumer Activity using URI**

Steps to create a Web Service Consumer Activity using URI

- 1. In the Adeptia Suite homepage menu, click **[+]** Configure to expand the tree. All the items in the Configure category are displayed.
- 2. Click [+] Services to expand the tree. All the items in the Services category are displayed.
- 3. Click **[+] Web Services** to expand the tree, and then click **Consumer**. The Manage Consumer screen is displayed (refer to Figure 9.5).
- 4. Click the **New** link. The Create Web Service Consumer screen is displayed (refer to Figure 9.6).
- 5. Enter the name of the new Web Service Consumer activity in the *Name* field. Then, enter the description for the Web Service Consumer activity in the *Description* field.
- 6. Select URI in *Web Service Definition Location*. The Web Service Consumer screen is displayed (see Figure 9.12).




WSDL (Web Service Definition Language) is a document written in XML. The document describes a Web service. It specifies the location of the service and the operations (or methods) the service exposes.



Design > Services > Web Services > Consumer		
[-] Standard properties		
Specify web service definition location.		
Name *	WS_Consumer	
Description *	WS_Consumer	
Web Service Definition Location*	O UDDI O URI	
URI Location	C HTTP C Local/LAN	
WSDL URL (HTTP URL)*		
WSDL File Path(Local/Lan)*		Browse Wsdl
Secure		
Userld		
Password		
Next Cancel		

Figure 9.12: Locate WSDL

7. Select the location of URI.



8. Click **Browse Wsdl** button. This displays the Upload Wsdl file screen (see Figure 9.13).

Choose File
Click on Browse button to choose the wsdl file.
Browse File Browse
<b>2</b> Upload File Click on the "Upload File" button. Please wait till your file appears in list.
Upload File

### Figure 9.13: Upload WSDL File

9. Click Browse to select the wsdl file. Then click Upload File button. This uploads the file and displays it in the *WSDL File Path* field in the Web Consumer screen (see Figure 9.14).



Design > Services > Web Services > Consumer [-] Standard properties		
Specify web service definition location.		
Name *	WS_Consumer	]
Description *	WS_Consumer	]
Web Service Definition Location*	O UDDI O URI	
URI Location	C HTTP 💿 Local/LAN	
WSDL URL (HTTP URL)*		]
WSDL File Path(Local/Lan)*	TemperatureConversions[1].wsdl	Browse Wsdl
	TemperatureConversions[1].wsdl	
Secure		
Userld		]
Password		]
Next Cancel		

Figure 9.14: Uploaded WSDL File

- 10. Check the *Secure* checkbox if the path specified in *WSDL URL* field is secured. Then enter User ID in the *User ID* field and password in the *Password* field.
- 11. Click **Next** button. The Web Consumer screen is displayed (see Figure 9.15).



Web Service Consumer				
Select operation name for web service consumer activity WS_Consumer.				
Name *	WS_Consumer			
Description *	WS_Consumer			
Service Name *	TemperatureConversions 💌			
Ports *	TemperatureConversionsSoap 💌			
Port Type *	TemperatureConversionsSoapType -			
Operation(s) *	CelciusToFahrenheit FahrenheitToCelcius WindChillInCelcius WindChillInFahrenheit			
Style Name *	document			
Input Document	\$in Show Input Schema out			
Output Parameter Name	Show Output Schema			
Back Next Cancel				

Figure 9.15: Select Web Service Operation

- 12. Select the name of Service from the *Service Name* drop-down list.
- 13. Select the port type from the *Port Type* drop-down list. A port type can support multiple ports. This selection populates the options in the *Ports* drop-down list.
- 14. Select the port for the selected port type from the *Ports* drop-down list.

(A)	Currently, Soap12 port is not supported by Adeptia Suite.
Ø	

15. Select the required operation from the *Operation(s)* field. This selection automatically displays the style name in the *Style Name* field.

Ø	The <i>Style Name</i> field is automatically populated according to the specified operation. There are two types of Style: <b>document</b> and <b>rpc</b> .
	<b>Document</b> : When a WS Consumer invokes a <i>document</i> style Web service, the consumer typically sends it an entire document, such as a purchase order, rather than a discrete set of parameters. The Web service accepts the entire document, processes it, and may or may not return a result document. In a <i>document</i> style, the input can be read from context or a



stream coming from another activity. Similarly, output can be set to context or can be generated as stream to other activities. In case the output is set to context, a variable is created in the context with name as specified in the *Output Parameter Name* field and then output is set into that variable. Additionally, the XSD of the Web Service Consumer can be used to create XML schema.

**rpc**: In *rpc* style when WS Consumer invokes the Web service, the consumer sends parameter values to the Web service, which executes the required methods, and then sends back the return values. In *rpc* style, input can be read from the context only and the output parameter is set in the context only. This style does not generate a stream. A variable is created in the context with name as specified in the Output Parameter Name field and then output is set into that variable.

In the current example, the specified Web Service is of rpc style.

- 16. Select required operation in the *Operation* field.
- 17. Click **Next** button. The Web Service Consumer screen is displayed (see Figure 9.16).

WebServices > Consumer	
[-] Standard properties	
Name *	WS_Consumer
Description *	WS_Consumer
Service Name *	TemperatureConversions
Ports *	TemperatureConversionsSoap
Port Type *	TemperatureConversionsSoapType
Operation *	CelciusToFahrenheit
Input Document	\$in
Output Parameter	out
Style *	document
Security Policy	None 💌
Maintain Session	
[+] Advanced properties	
* Mandatory fields.	
Back Save Cancel	

Figure 9.16: Enter Input and Output Parameters



18. Enter the input value in the *Input Parameter Value* field. Input Parameter is used to define the input data for WS Consumer activity. The actual value could be given in two ways, as shown in the table below.

Input Value	Description		
Definition Time	Here the actual value is given based on the data type of the parameter.		
Run Time	Here a variable prefixed with \$ is defined in the input document field. For example \$variable1. The value of variable1 will be searched in process flow context during process flow execution as the control reaches web service consumer activity. The value will be of Java primitive type.		

Table 9.3: Input Parameter Value for WS Consumer Activity

- 19. At execution time Ws consumer activity will search for its input in following order:
  - 1. Search variable in process flow context
  - 2. Get XML document

The way input is passed to the WS Consumer activity depends upon the style *document* and *rpc* not on WSDL locator UDDI or URI.

20. Enter relevant variable in the Output Parameter Name field.



Do not prefix \$ with the variable name defined in *Output Parameter Name* field.

21. Select the required Security Policy activity from the Security Policy drop-down list.



To learn about Advanced Properties refer to <u>Changing Advanced</u> <u>Properties</u> section.

- 22. Click **Save** button. This displays a screen confirming that the web service consumer has been created successfully. If the *Comments* property is enabled, then clicking **Save** will display a screen where you need to enter comments for creating the web service consumer (refer to Figure 3.6).
- 23. Enter the comments in the *Add Comments* field.



The comment should be at least 1 character in length.

24. Click **OK** to save the comments. This displays a screen confirming that the web service consumer has been created successfully.



By default, the *Comments* property is disabled. To enable it, refer to the *Updating System Properties* section in *Administrator* Guide.



### Using Web Service Addressing

Steps to Use Web Service Addressing (WS-Addressing)

1. To use WS Addressing, while creating Web Service Consumer activity, expand WS-A addressing properties (see Figure 9.17).

[-] WS-A addressing properties	
Enable WS-A addressing	
Must understand	None
WS-A version	200508
Action	
То	
Reply To	
Reply To Reference Parameters	
MessageID	
From	
Fault to	
Fault To Reference Parameters	
Relates To	
Relationship Type	
[+] Advanced properties * Mandatory fields.	
Back Save Save As Cancel	

Figure 9.17: Define WS-Addressing Parameter

2. Check the *Enable WS-A addressing* check box and define all the parameters



## CREATING WEB SERVICE PROVIDER ACTIVITY

Web Service Provider is used to publish process flows that are accessed by Web Service consumers. Once a Web Service is published, it creates a WSDL and makes it available to the Adeptia Suite users. The user can use this WSDL to invoke the Web Service. The Web Service can be published in two modes:

- **Synchronous:** In case the Web Service is published in synchronous mode the consumer waits for the completion of the process flow and hence for the output of the process flow.
- **Asynchronous:** In case the Web Service is published in asynchronous mode the consumer does not wait for the process flow to be completed. Thus consumer gets only a Co-relation ID not the output of the process flow. Later on, using this Co-relation ID, consumer can get the output.

### Prerequisites:

• To use Adeptia Suite as Web Service Provider, you must change the value of following property:

abpm.webservice.host

Replace its value from localhost to machine name, where Adeptia Suite is running. For more details refer to the section *Adeptia Suite Properties* in *Administrator Guide*.

In the Adeptia Suite this feature is available in:

BPM Suite	Integration Suite	ETL Suite
$\checkmark$		

#### Steps to create a Web Service Provider Activity

- 1. In the Adeptia Suite homepage menu, click **[+]** Configure to expand the tree. All the items in the Configure category are displayed.
- 2. Click [+] Services to expand the tree. All the items in the Services category are displayed.
- 3. Click **[+] Web Services** to expand the tree, and then click **Provider**. The Manage Provider screen is displayed (see Figure 9.18).



Home  About   Help  Change Password  My Profile  Logo	ut	User: adm	in Group: administrators Permissio	ns: (read, write, exec	.te) User Type: sysadmin
[+] My Tasks	Design > Services > Web Services > Provider				
[+] My Documents [+] My Solutions	New   Edit   Delete   Revisions   Dependencies	-	Select Field to Search 💌	_	Search
[+] My Monitor [+] History	New Lond Longer Liversions Logenoences				search
	# Name	Description	WSDL Owne	r Perm.	Modified <b>*</b>
[*] Model		No records found			
[-] Design					
[+] Forms					
[+] WorkFlow					
[-] Services					
[+] Data Dictionary					
[+] Source					
[+] Schema					
[+] Target					
[-] Web Services					
Security Policy					
Consumer					
Provider					


Figure 9.18: Manage Web Service Provider Activity

4. Click the **New** link. The Create Web Service Provider screen is displayed (see Figure 9.19).

Design > Services > Web Services > Provide	er
[-] Standard properties	
Name *	
Description *	
Asynchronous	
Request Service Name *	
Response Service Name	
Process Flow Name *	Select Process Flow
Input XML Schema *	Select Root
Output XML Schema	None Select Root
Input Variable Name *	
Output Variable Name	
Security Policy	None 💌
[+] Advanced properties	
* Mandatory fields.	
Save Cancel	

Figure 9.19: Create Web Service Provider Activity

- 5. Enter the name and description of the new Web Service Provider activity in the *Name* and *Description* fields respectively.
- 6. Uncheck the *Asynchronous* checkbox if you want to publish Web Service in *Synchronous* mode or else the Web Service will be published in asynchronous mode.





In case the Web Service is published in *asynchronous* mode, two WSDL's are available. First WSDL provides a web service to post the data and other to retrieve the data. First the WS Consumer posts the data (XML Document) to the Web Service and gets the correlation Id in form of an XML document. The actual data is not returned as the Web Service may take hours or days to process the input data. The second WSDL provides a web service to retrieve the data processed by the first web service. The consumer passes input as the correlation Id XML document obtained from output of first web service and get the processed data

In *asynchronous* case the same data exchange took two steps where as in *synchronous* only one. The main advantage of the first one is loose coupling.

7. Enter the request service name and response service name in the *Request Service Name* and *Response Service Name* respectively. The Web Service will be published with the respective service name given in *Request/Response Service Name* field.




In case the *Asynchronous* checkbox is unchecked, the *Response Service Name* field will be disabled.

- 8. Select the process flow, which you want to publish as Web Service from the *Process Flow Name* drop-down list.
- 9. Select Input XML Schema from the *Input XML Schema* drop-down list. This XML Schema corresponds to the XML Input provided by Web Service consumer activity.
- 10. Select the Output XML Schema from the Output XML Schema drop-down list.

Ø

If case, selected XML Schema is having multiple roots, click the **Select Root** button and select the required root.

- 11. Enter the Input and Output Variables in the Input Variable and Output Variable fields respectively.
- 12. Select the Security Policy activity from the Security Policy drop-down list.



- 13. Click **Save** button. This displays a screen confirming that the Web Service Provider activity has been created successfully. If the *Comments* property is enabled, then clicking **Save** will display a screen where you need to enter comments related to creating the web service provider activity (refer to Figure 3.6).
- 14. Enter the comments in the Add Comments field.

M
Ŵ

The comment should be at least 1 character in length.

15. Click **OK** to save the comments. This displays a screen confirming that the Web Service Provider activity has been created successfully.



Ŵ		Ø
---	--	---

Ø

By default, the *Comments* property is disabled. To enable it, refer to the *Updating System Properties* section in *Administrator* Guide.

In case the process flow is published as *asynchronous* web service, the Manage Web Services Provider screen looks like as displayed in Figure 9.20.

Des	Design > Services > Web Services > Provider				
New	Edit   Delete   Revisions   Dependencies	Select #	ield to Search 💌	Sear	:h
#	Name	Description	WSDL	Owner Per	m. Modified 🔻
1 0	Webservice_Provider	Webservice_Provider	Service to post data: View/Download Service to receive data: View/Download	admin RW	08/25/09 16:32

Figure 9.20: Manage Web Service Provider (asynchronous web service)



# **10** TRANSFORMING DATA

Adeptia Suite can transform any type of data into another type i.e. it facilitates any-to-any transformation. For example, the Adeptia Suite can transform a text file into an XML file. Data transformation can be done in two ways. These are outlined as:

- Using Data Mapper
- Using Record to Record Service

## USING DATA MAPPER

Data Mapper is a visual data-mapping tool used for mapping elements in advanced data integration projects. This tool allows you to specify source and target schemas and to map data fields from source schema to target schema.

The Data Mapper tool is used to map source schema elements to target schema elements. You can map one source schema element to a target schema element directly using the drag and drop approach. Additionally, this tool also offers certain mapping functions using which you can map source and target schema elements.

Furthermore, the Data Mapper supports multiple source and target schemas. This implies that you can select more than one schema at a time, both at the source and the target end. This facilitates mapping of multiple source and target schema elements.

In the Adeptia Suite, this feature is available in:

BPM Suite	Integration Suite	ETL Suite
$\checkmark$	$\checkmark$	$\checkmark$

### Accessing Data Mapper

### Pre- Requisites

- JRE 1.6 needs to be installed on your system to open the Data Mapper applet.
- *Pop-up Blocker* needs to be disabled in the web browser, to open the Data Mapper applet. By default, the *Pop-up Blocker* is enabled.

### Steps to access Data Mapper

1. In the Adeptia Suite homepage menu, click **[+]** Configure to expand the tree. All the items in the Configure category are displayed.

2. Click [+] Services to expand the tree. All the items in the Services category are displayed.

ADEPTIA

3. Click **[+] Data Transform** to expand the tree, and then click **Data Mapping**. The Manage Data Mapping screen is displayed (see Figure 10.1).

[+]	My Tasks	Co	Configure > Services > Data Transform > Data Mapping						
[+]	My Documents								
[+]	My Solutions	Nev	w I Ed	it   Delete   Revisions   Dependencies		Select Field to Search 💌			
[+]	My Monitor								
[+]	History	PDFView							
		#		Name	Descript	tion	Owner	Perm.	Modified 🔻
· · · · ·	[+] WorkFlow	1	0	EvalJMSE_Mapping	Text to Database Mapping		demouser	RWX	11/20/09 16:11
		2	$\circ$	EvalScript_Mapping	Mapping between Text And E	excel Schema	demouser	RWX	11/20/09 16:11
		з	0	EvalXform_Mapping	Mapping between DB Schema	a and Excel.	demouser	RWX	11/20/09 16:11
		4	$\bigcirc$	$EvalPF_MappingTransformation_Format1$	Mapping transformation for fo	ormat1	demouser	RWX	11/20/09 16:10
		5	0	$EvalPF_MappingTransformation_Format2$	Mapping transformation for fo	ormat2	demouser	RWX	11/20/09 16:10
		6	$\circ$	InventoryItemsMapping_part2	convert CS∨ to XML. Include conditions.	es data validation	demouser	RWX	08/09/09 10:29
		7	0	InventoryItemsMapping_part1	convert CSV to XML		demouser	RWX	08/08/09 10:48
		8	$\circ$	Fulfillment_ExcelToRequestXML	This mapping is used to conv XML request message.	vert excel data file to	demouser	RWX	08/07/09 16:45
	[-] Data Transform	9	0	Fulfillment_ResponseXMLtoExcel	This mapping is used to conv response to excel.	vert web service	demouser	RWX	08/07/09 13:20
	<ul> <li>Data Mapping</li> <li>Record to Record</li> </ul>	10	0	Fulfillment_WSMapping	This mapping is used in publi process flow. Generates Ship information.		demouser	RWX	08/07/09 13:05

Figure 10.1: Manage Data Mapping

4. Click New link. The Create Data Mapping screen is displayed (see Figure 10.2).

Configure > Services > Data Transform > Data Mapping						
[-] Standard properties						
Name *						
Description *						
	Data Mapper					
[+] Advanced properties						
* Mandatory fields.						
Save Cancel						

Figure 10.2: Create Data Mapping

- 5. Enter the name and description of the new mapping activity in the *Name* and *Description* fields respectively.
- 6. Click **Data Mapper** button. This displays the Data Mapper screen (refer to Figure 10.3).

If you are starting the Data Mapper on your system for the first time, then a warning message is displayed that prevents you from starting this application. Ignore this message and click **Start** to continue.



If you have *read-only* permissions, you can view a mapping activity in read-only mode. You can view the applied mapping, create new mapping rules, edit existing mapping rules and even run the simulation. For details, refer to the <u>View Mapping in Read-Only Mode</u> section.

7. Click **Advanced Properties** if you want to set options for splitting data. You can split the source data into different chunks. You can specify the size of chunks in terms of the number of records. In the output however, only one file is generated at the location specified in the target activity. To know more about splitting data, refer to the **Splitting Source Data** section.



You can set the **Advanced Properties** at any time of the mapping activity.

- 8. Once you have set the Advanced Properties, click **Save** to save the splitting options. If the *comments* property is enabled, then clicking **Save** will display a screen where you need to enter comments related to creating the mapping transformation. (refer to Figure 10.39).
- 9. Enter the comments in the *Add Comments* field.



The comment should be at least 1 character in length.

10. Click **OK** to save the comments.



By default, the *Comments* property is disabled. To enable it, refer to the *Updating System Properties* section in *Administrator* Guide.

# Understanding Data Mapper Applet

The Data Mapper screen is displayed below






Figure 10.3: Data Mapper Applet

The Data Mapper screen is divided into eight sections. These are outlined as:

- Menu Bar
- Tabs Panel
- Tool Bar
- Source Panel
- Target Panel
- Mapping Functions Panel
- Mapping Graph Area
- Parameters Panel

## Menu Bar

Options of the Menu Bar are explained in the table below.

Menu Option	Sub-Option	Function
File	Save	Save mapping activity
	Exit	Exit Data Mapper

Table	10.1:	Options	of	Menu	Bar
TUDIC	10.1.	options	01	inci ia	Dui



	Enable Tool Tips For Source/Target Tree	Activate or deactivate Tool Tips to be displayed at source or target leaf elements. Tool Tips are always displayed as active for root
View	Move Connection Ends	elements. Set the width of connecting lines. By default, it is set to 50px.
	View Mapping XML	Display generated XML file with line numbers. It is displayed in read- only mode.
	Validate XSL	Validate the generated XSL file.
	Global Custom XSL Before	Add custom XSL code at the top of the mapping XSL.
	Global Custom XSL After	Add custom XSL code at the bottom of the mapping XSL.
Actions	On Demand (optimized) loading of XML Schema tree	If the XSD is complex, then this option allows you to process only the root level element and not the complete XSD. Only when you expand the tree elements, it processes the child elements and loads them into the memory. The tree elements expansion is now displayed in the applet. This option is applicable only on XML schemas. It optimizes the processing of XML schemas and loads the XSD elements only up to 2 levels in the source and target panels. You need to click a tree element to load its further child elements.
	Namespace	Manage Namespace
	Enable DBQuery caching	Enable DBQuery cache. This implies that if the same DBquery is fired on another element, it will generate the result from the existing query, instead of creating a new connection. By default, the DBQuery cache is disabled.
	Search Element	Search an element in the Source or Target schema tree.
	Set Data Viewer Record Count	Set maximum number of records that can be shown in data viewer
	Add Custom Auto Map Options	Add custom options for Auto Mapper
	Add Value Map Options	Add options for value map
	Enable Quick Splitting	Splits data at source end and merges at target end automatically



	Help	Data Mapper Help	Display online help for the Data Mapper section.
		Mapping Functions Help	Display online help for mapping functions.
		About Data Mapper	Display the About box for the Data Mapper tool.

## Tabs Panel

Options of the Tabs Panel are explained in the table below.

Table 10.2: Optic	ons of Tabs Panel
-------------------	-------------------

Button	Name	Function
1	Data Mapper	Display the Data Mapper screen for mapping source and target elements.
	XSL	Display the generated XSL code with line numbers for the mapping activity.
<b>@</b>	Debugger	Validate and view output of the mapping activity.

## Tool Bar

Options of the Tool Bar are explained in the table below.

Table 10.3: Options of Tool Bar

Button	Name	Function
8	Save Mapping	Save mapping activity
	Remove All Mappings	Remove all the mapping between the source and the target elements
0	Validate XSL	Validate generated XSL
ð	Auto Mapper	Map the source and the target elements if the structure of the source and the target schemas and the names of the source and the target elements are similar
0	One to One Mapping	Map all the source and the target elements under a parent element if the number of elements in the source and the target schemas are same
	Toggle Element Property	Displays the property of the source or target element, if it is defined in the schema.
		To view the property, click this button and then click the element whose property
		you want to view.



<u> </u>	Open Source Schema	Open source schema
<u></u> 2	Open Target Schema	Open target schema

#### Source Panel

The Source Panel is used to display a source schema. All the elements of the source schema are listed in the Source Panel. When multiple source schemas are loaded, then all elements of each schema are listed under their respective source nodes.

### Target Panel

The Target Panel is used to display a target schema. All the elements of the target schema are listed in the Target Panel. When multiple target schemas are loaded, then all elements of each schema are listed under their respective target nodes.

#### Mapping Functions Panel

The Mapping Functions Panel displays all mapping functions that can be used to map source and target schema elements. Mapping functions are supported by XSLT. However, the Data Mapper also includes some customized functions, which are not standard of XSLT. Refer to <u>Using</u> <u>Mapping Functions</u> for details on mapping elements using these functions.

In addition to the mapping functions, an option of XSL Template is also displayed on the Mapping Functions Panel. This option enables you to <u>Add XSL Template</u> and further manage XSL templates from the Manage XSL Template screen.

### Mapping Graph Area

The Mapping Graph Area is used to map the source and the target elements. You can apply the mapping function between source and target elements in this section. Mapping of the selected target element is displayed in the Mapping Graph Area. This mapping is displayed in the form of Mapping Rules (graphical representation) or as Textual Rules (code representation). Additionally, you can view and <u>set target element properties</u> such as <u>adding comments</u> for target elements and also repeat occurrences of a target element based on the occurrences of a source element, by applying the <u>For Each property</u>. Further, you can <u>apply sorting rules</u> for elements and also set the Disable-Output-Escaping property.

Additionally, you can create <u>Local</u>, <u>Global</u> and <u>Context Variables</u> in Mapping Graph Area. You can also define <u>Custom Methods</u> and <u>Key Functions</u> in this section.

The Mapping Graph Area comprises of two tabs. These tabs further list sub tabs using which you can perform various functions. These are outlined in the table below.

Tab	Sub Tabs	Function
Node	Mapping Rules	Display graphical representation of the mapping of source and target elements.

Table 10.4: Tabs of Mapping Graph Area



	Textual Rule	Display the textual code representation of the mapping of source and target elements.
	Local Variables	Create and define local variables for mapping source and target elements.
	Properties	Display and set properties for source and target elements. Enables you to add comments for elements and applies sorting rules for target elements. It allows you to set the <i>Disable-Output-</i> <i>Escaping</i> property.
	Global Variables	Create and define global variables for mapping source and target elements.
	Custom Methods	Create global methods for mapping source and target elements.
Global	Key Functions	Create and define keys for mapping source and target elements.
	Context Variables	Create and define context variables for mapping source and target elements.
	Connection Info	Create and define connection info variables for mapping source and target elements.
Data	Source	Preview Data of the uploaded file at the source end.
Viewer	Target	Preview Data at the target end according the uploaded source file and mapping rule applied.

The Mapping Graph Area also comprises of buttons. These buttons are displayed based on the selected tabs. All buttons of the Mapping Graph Area are explained in the table below.

Button	Name	Function
~	Apply Mapping	Map the selected source elements to the selected target elements.
×	Remove Mapping	Remove the mapping between the selected source and the target elements
2	Pop Out Parameters Panel	Pop out the Parameters Panel and display it as maximized.
	Add Global/Local/Context Variable/Key	Add a new global, local, context variable or a key.
5	Save Global / Local /Context Variable/Key	Save a new local, global, context variable or a key.
Ì	Remove Selected Global/Local /Context Variable/Key	Remove the selected global variable, local variable, context variable or key.
	Remove all Global/Local/Context Variables/Keys	Remove all existing global variables, local variables, context variables or keys.

<b>T</b>	<b>B</b>	~		<u> </u>	
Table 10.5:	Buttons	OŤ	Mapping	Graph	Area



	Clears Global / Local variable name and value text fields	Clear all data entry fields while adding a local or global variable.
*	Add New Method	Add a new custom method.
ß	Remove Selected Method	Remove the selected custom method.

You can expand the Mapping Graph Area by clicking **Maximize** ( $\triangleq$ ) button displayed on the Split Bar below the Source and Target Panels. Similarly, by clicking **Minimize** ( $\equiv$ ) button, you can restore the Mapping Graph Area to its original size. Alternately, you can drag the Split Bar to resize the Mapping Graph Area and Source and Target Panels.

#### Parameters Panel

The parameters listed in the Parameters Panel are explained in the table below.

Parameters	Description
Global Variables	Display a list of all the global variables defined for the mapping of source and target elements in the current mapping object.
Local Variables	Display a list of all the local variables defined for the mapping of source and target elements in the current mapping object.
Custom Methods	Display a list of all the methods defined for the mapping of source and target elements in the current mapping object.
Keys	Display a list of all the keys defined for the mapping of source and target elements in the current mapping object.
Context Variables	Display a list of all the context variables defined for the mapping of source and target elements in the current mapping object. All context variables created in the Data Mapper are transferred to the Process Flow Designer.
Templates	Display a list of all the XSL templates created for the mapping of source and target elements in the current mapping object.
Connection Info	Display a list of all connection info variables.
Global Methods	Display a list of all class files present in the Custom Classes folder.
Value Map	Display a list of value maps created for the elements

Table 10.6: Parameters Listed in the Parameters Panel



All parameters are displayed in this section as and when they are created in the mapping process.You can remove a parameter by right-clicking the parameter and selecting

You can remove a parameter by right-clicking the parameter and selecting the Remove option.

You can expand the Parameters Panel horizontally by clicking **Maximize** (4) button displayed on the Split Bar left to the Parameters Panel. Similarly, by clicking **Minimize** (1) button, you can restore the Parameters Panel to its original size. Alternately, you can drag the Split Bar to resize the Mapping Graph Area and Parameters Panel.

# **Mapping Elements**

The process of mapping elements comprises of various steps. These are outlined as:

- Load Source and Target Schemas
- Map Source and Target Elements
- Save Mapping and Exit Data Mapper

# Load Source and Target Schemas

Steps to load Source and Target Schemas

1. Click **Open Source Schema** (<sup>()</sup>) button displayed on the Tool Bar. The Select Schema screen with a list of existing source schemas is displayed (see Figure 10.4).

Select Schen	na			×
-Load Schema				
		Schema Name	Schema Type	<b>_</b>
		EvalScript_TextSchema	TextSchema	
		EvalJMSE_TextSchema	TextSchema	
		EvalRec_PositionalSchema	PositionalSchema	
		EvalPF_DatabaseSchema_Database1	DbSchema	
		EvalPF_DatabaseSchema_Database2	DbSchema	
		EvalJMSE_DBSchema	DbSchema	
		EvalXform_DbSchema	DbSchema	
		EvalScript_ExcelSchema	ExcelSchema	_
	-	Search Criteria 💌 Search String Search	ch Synchronize Load Cancel	

Figure 10.4: Select Schema



If you have created a new schema, then it will not be displayed in this list. To refresh the list of schemas and add the new schema to this list, click **Synchronize** button.



2. Select the checkbox of the source schema that you want to load. This will enable the **Load** button.

You can select more than one schema at a time to load multiple schemas. At times, the list of schemas is very long. In such a case, you can search for schemas to be loaded, on the basis of the *schema name* or *type* by selecting the appropriate search criteria from the drop-down list and entering the search criteria in the text box. Clicking **Search** button will display only those schemas that conform to the entered criteria. You can also enter Wild Card characters like '\*', '?' and '[]' in the search criteria. You need to click the **Synchronize** button to synchronize the schema list before using the *Search* feature.

- 3. Click **Load** button. This loads the selected source schemas with all their elements in the Source Panel.
- 4. Click **Open Target Schema** (<sup>III</sup>) button displayed on the Tool Bar. This displays the Select Schema screen with a list of existing target schemas (refer to Figure 10.4).
- 5. Select the checkbox(s) of the target schema(s) that you want to load.
- 6. Click **Load** button. This loads the selected target schemas with all their elements in the Target Panel.



The schema name is displayed against the root node of the source and target trees. This is useful in case of loading multiple source and target schemas.

7. Click the **Expand** (+) button to expand and display all elements of the selected schemas in their respective panels (see Figure 10.5).



ADEPTIA - Data Happer - customer  No. View Actions Heb	
File View Actions Hep Tota Mapper (1) XSL (1) Debugger	
H 8 0 2 0	No Element Selected
Carl Open Source Schema	Carl Open Target Schema
S Structure, of source, 250 A Root (EvaScrot, TextSchema) A Record → RAALD (string) → RMALD (string) → RMALD (string) → RMALD (string) → RMALD (string) → RMALD (string) → RMALD (string) → RAALRY (nteger) → RAALRY (nteger) → AGE (integer) → AGE (integer)	Structure, of, destration, XSD (c) A Boot (MasGrout, Tratischema) (c) A Boot (MasGrout, Tratischema) (c) A DORESS (strung) 
Math String Date Aggregation Conditional Axis Boolean Context XSL Template DB	
gg Textual Rules Cocal Variables Cocal Variabl	Parameters     Giobal Variables     Goola Variables     Custom Methods     Custom Methods     Context Variables     Templates     Ical     Gobal Methods     Value Map

Figure 10.5: Source and Target Schema Elements



The Data Mapper tool allows you remove a loaded schema. For details, refer to the section **Removing a Schema**.

Elements in the Source and Target Panels are identified by the legends displayed before the name of the element. These legends are explained in the table below.

Table 10.7: Legends of Elements
---------------------------------

Legend	Description
<b>A</b>	Root Element
<b>A</b>	Parent/Complex Element
٥	Leaf Element
	Attribute Element



If no schema is loaded, then all tabs of the Data Mapper appear as disabled.

# Search Element in Source or Target Schema Tree



At times, when the source or target schemas are quite large, then searching an element can be very cumbersome. The Data Mapper applet eases this task by allowing you to search for an element in a source or target schema.

#### Steps to search an element in a source or target schema tree

- 1. Ensure that the <u>source and target schemas are loaded</u> and all their elements are listed under their respective nodes.
- 2. Click the **Actions** menu and select **Search Element** option (see Figure 10.6). Alternately you can press **<Ctrl> + <F>** on the keyboard.

	- Data Happer - customer		212	×
	Actions Help			
👔 Data M		Ctrl+V		
8	Global Custom XSL Before	Ctrl+B	No Element Selected	
	Slobal Custom XSL After	Ctrl+A	Q Open Target Schema	
Structa	On demand (optimized) loading of XML Schema t	ree Ctrl+E	Structure_of_destination_XSD	-
⊟-▲F	Namespace	•	E ▲ Root (EvalScrpt_TextSchema)	-
÷-	Enable DBQuery caching	Ctrl+D	i∃-▲ Record	
	🖉 Search Element	Ctrl+F	IAME (string)     ADDRESS (string)	
	Set Data Viewer Record Count		O EMAILID (string)     O PHONENO (integer)	
	© Add Custom Auto Map Options		OATEOFBIRTH (date)	
	(v)- Add Value Map Options		DEPARTMENT (string)     SALARY (ntoger)	
	Enable Quick Splitting	Ctrl+Q	OATEOFJOINING (date)     OESIGNATION (string)	
	Import Mapping	Ctrl+I	AGE (nteper)	
-				+
Math Strin	g Date Aggregation Conditional Axis Boolean	Context XSL T	Template D0	
a Elma	cono Rules 100 Textual Rules 100 Local Variables 110	Properties	Parameters	-
Data Nener   Global   Nod	Oprono Rules [ 🕐 Textual Rules   🕐 Local Yanabes   🥻			
4				

Figure 10.6: Select Search Element from Actions Menu

3. The Element Search dialog box is displayed (see Figure 10.7).

Element Search Dialog		
Search Value		
Element Path		
Scope	Direction	
C Source Tree	C Up	
Target Tree	🖸 Down	
Find	d Next Close	

Figure 10.7: Element Search Dialog Box



- 4. Enter the name of the element that you want to search for, in the *Search Value* field. You can also use Wild Card character(s) to search for an element. The Xpath of the element is automatically displayed in the *Element Path* field.
- 5. Select the appropriate option in the *Scope Pane*l, to search the element in the Source or Target schema tree. For example, if you want to search in the Source schema tree, then select *Source Tree* option. Only one option can be selected at a time. By default, *Target Tree* is selected (see Figure 10.8).

Element Search Dialog		X		
Search Value name				
Element Path /Root/Record/NAME				
Scope	Direction			
C Source Tree	C Up			
Target Tree     O     Down				
Find Find Next Close				

Figure 10.8: Enter Parameters in Element Search Dialog Box

6. Click **Find**. This searches for the first occurrence of the element in the selected tree. If the element match is found, then that element is selected and highlighted. The Xpath of that node is displayed in the *Element Path* field (see Figure 10.9).

ADEPTIA - Data Happer - customer		X
File View Actions Help		
👔 Data Mapper 🔄 XSL 🍓 Debugger		
💾 🖸 🥝 🤁 🛛	Current Element : NAME	
Carl Open Source Schema		⊇ Q Open Target Schema
Studure, of, source, XSD A Root (BaSorb, TextSchema) A Root (BaSorb, TextSchema) A Root (String) A RAUD (String) A RECOMMENT (Integer) A RECOMMENT (Integer) A RECOMMENT (Integer) A AGE (Integer) A GE (Integer)	Structure, of, destruction_XSD  Structure, of, destruction_XSD  A Boot (FoilSorger, Transcherma)  A Boot (FoilSorger, Transcherma)  A DPRESS (string)  A DROESS (st	2
Math String Date Aggregation Conditional Axis Boolean Context XSLTemplate DB		
gg Vacong Rules () Textual Rules () Local Vanables () R Properties ()	-	Parameters     Post Varables     Cost Varables     Cost Varables     Cost Varables     Cost Varables     Octav Varables

Figure 10.9: Element Match Found



7. If multiple matches are found for the search criteria, then the *Direction Panel* and the **Find Next** button is activated (see Figure 10.10). You can select the direction in which you want to search in the selected tree. For example, if you want to search upwards in the tree, select *Up* option. Only one option can be selected at a time. By default, *Down* is selected.

Element Search Dialog		×		
Search Value *e				
Element Path /Roo	t/Record/NAME			
Scope	Direction			
C Source Tree C Up				
<ul> <li>Target Tree</li> <li>Down</li> </ul>				
Find Find Next Close				

Figure 10.10: Multiple Matches Found

8. Click **Find Next** to search for the next element in the tree, based on the selected direction. Once the element match is found, click **Close** to close the Search Element dialog box. In case no element match is found, then a warning message is displayed (see Figure 10.11).

Adeptia Mapper Warning!		
•	Element not found.Do you want to search again?	
	Yes No	

Figure 10.11: Warning Message

9. Click **Yes** to search again, else click **No** to close this screen.

# Map Source and Target Elements

You can map source and target elements using any of the listed methods:

- Drag and Drop Approach
- Buttons on the Tool Bar
- <u>Copy/Paste Mapping</u>
- <u>Mapping Functions</u>

# Map Elements Using Drag and Drop Approach

This is the default and most commonly used method for mapping source and target elements.

### Steps to map elements using Drag and Drop approach



- 1. Ensure that the **source and target schemas are loaded** and all their elements are listed under their respective nodes.
- 2. Click a source element and drag it to the desired target element. A line is displayed, indicating the mapping between the selected source and target element. The graphical representation of the above mapping is displayed in the Mapping Graph Area (see Figure 10.12).





Figure 10.12: Map Source and Target Element using Drag and Drop Approach



3. Similarly, drag and drop each source and target element that you want to map. The mapping between all source and target elements will be displayed (see Figure 10.13).



k, ADEPTIA - Data Happer - customer File: View: Actions: Help	
20 Data Mapper ( 3 XSL ) Debugger	
H 8 0 2 0	Current Element : AGE
Copen Source Schema	🔄 🖓 Open Target Schema
Structure_of_source_XSD     Accord     Accord	Structure, of, destration, XSD         (c) A Noot (Existicnet, TextSchema)         (c) A TEOFERINE (date) (M)         (c) A Noot (Existicnet, TextSchema) (M)         (c) A SLARY (Resper) (M)         (c) A GE (Integer) (M)
Agr String Date Aggregation Conditional Axis Boolean Context XSL Template DB	
	Parameters
Image: Strate	Global Variables Bio Local Variables Custom Methods Context Variables Context Variab

Figure 10.13: Map Source and Target Elements


4. If you have loaded multiple source and target schemas, then drag and drop the source and target elements you want to map. The mapping between these elements will be displayed (see Figure 10.14).



4. ADEPTIA - Data Happer - customer File Vew Actors Help	
👔 Data Mapper 🔄 XSL 🥝 Debugger	
H 8 0 2 0	Current Element : CompanyName
Open Source Schema	Carl Q Open Target Schema
Structure_of_source_xS50	Structure_of_destination_XSD         ▲           Structure_of_destination_XSD         ▲           B         A Record           B         A Record           B         A Record           B         A Rock (subscript_TextSchema)           B         A Rock           B         A Rock           B         A Rock (subscript_TextSchema)           B         B Rock (strupt) (H)           B         B Rock (strupt_Hext) (H)           B         D DEFARTHERING (strupt)           B         D DEFARTHERING (strupt)           B         D Station (strupt) (H)           B         D A Rock (strupt) (H)           B         A Rock (strupt) (H)
Mam Strig Date Appression Conditional Avis Boolean Context XX Template D0       Image: Strig Date Appression Conditional Avis Boolean Context XX Template D0       Image: Strig Date Appression Conditional Avis Boolean Context XX Template D0       Image: Strig Date Appression Conditional Avis Boolean Context XX Template D0       Image: Strig Date Appression Conditional Avis Boolean Context XX Template D0       Image: Strig Date Appression Conditional Avis Boolean Context XX Template D0       Image: Strig Date Appression Conditional Avis Boolean Context XX Template D0       Image: Strig Date Appression Conditional Avis Boolean Context XX Template D0       Image: Strig Date Appression Conditional Avis Boolean Context XX Template D0       Image: Strig Date Appression Context XX Templat	Parameters     Global Varables     Bio Local Varables     Bio Local Varables     Context Varables     Good     Fermbase     Good     Good     Good     Good     Good     Good     Value Map

Figure 10.14: Map Multiple Source and Target Schema Elements

5. <u>Save</u> the mapping activity and exit the Data Mapper.



Once you have mapped source and target elements, you can <u>view and</u> <u>validate the generated mapping XSL</u>, from the Data Mapper screen. You can also <u>view the target XML</u> and <u>view and validate mapping</u> <u>output</u> from this screen.

# Map Elements using Buttons on the Tool Bar

You can map source and target elements using certain buttons on the Tool Bar. These buttons are explicated as:

- One To One Mapping (
  )
- <u>Auto Mapper</u> ( 2)
- <u>Remove All Mappings</u> (<sup>11</sup>)



#### One to One Mapping

If the number of leaf elements of the parent element in the source and target schema is same, then you can use the One to One mapping button to map all the source elements to the corresponding target elements.

#### Steps to use One to One mapping

- 1. Ensure that the **source and target schemas are loaded** and all their elements are listed under their respective nodes.
- 2. Click and drag the parent element of the source schema to the parent element of the target schema. This will apply template of the source parent element on the target parent element, and activate the **One to One Mapping** button.
- 3. Click **One to One Mapping** ( ) button. All the leaf elements of the parent element in the source schema will be mapped to their respective leaf elements of the parent element in the target schema.



Only leaf elements are mapped using this button. It does not map complex elements. To map complex elements, you need to use the <u>drag</u> and drop method.



If multiple schemas are loaded, then dragging a source parent element will map all leaf elements of schemas displayed previous to the current schema. Moreover, in multiple schemas, mapping can be performed between parents at any level, if the number of their leaf elements is the same.

#### Auto Mapper

If the hierarchy and the names of the complex elements are similar, then you can use the **Auto Mapper** option to map the source elements to the corresponding target elements. In case of complex elements, the hierarchy and the name of all elements must be the same.

#### Steps to use the Auto Mapper

1. Ensure that the **source and target schemas are loaded** and all their elements are listed under their respective nodes. Additionally, the hierarchy and name of the all elements is the same (see Figure 10.15).



ADEPTIA - Data Happer - customer	X
20 gev gev gebors geb	
	No Element Selected
ුටු Open Source Schema	Carl Open Target Schema
Sturdure_of_source_XSD     According (surger)     According (s	Structure of destruction XSD         G ▲ Alcoid         G → Alcoid
	Va Parameters
La Magorg Rules Textus Rules Ru	

Figure 10.15: Same Hierarchy and Element Names

2. Click **Auto Mapper** (*R*) button. The Auto Mapper Options dialog box is displayed (see Figure 10.16).

AutoMapper Options	×
Choose The Criteria :	
Ignore Case	-
OK Cancel	



- 3. Select the mapping criteria from the *Choose the Criteria* drop-down list. Its options are listed as:
  - **Ignore Case:** The source and the target elements are mapped even if they are of different case. Their attributes are not mapped.
  - **Case Sensitive:** The source and target elements are mapped only if they are of the same case. Their attributes are not mapped.
  - **Ignore Case and Include Attributes:** The source and target elements and their attributes are mapped even if they are of different case.
  - **Case Sensitive and Include Attributes:** The source and target elements and their attributes are mapped, only if they are of the same case.
  - **Consider Only Leaf Element Count:** The source and target elements are mapped only if the number of leaf elements in the source schema and target schema are the same. It



is not necessary that names of source and target elements are similar. Their attributes are not mapped.

- Consider Only Leaf Element Count and Include Attributes: The source and target elements and their attributes are mapped only if the number of leaf elements in the source schema and target schema are the same. It is not necessary that names of source and target elements are similar.
- 4. Click **OK** button. All elements of the source and target schema will automatically be mapped based on the selected criteria (see Figure 10.17).




Figure 10.17: Mapped Elements using Auto Mapper

### Remove All Mappings

You can use the Remove All Mappings option to remove all mappings from the Data Mapper.

### Steps to remove all mappings between source and target elements


1. Click **Remove all Mapping** (<sup>11</sup>) button. A Remove Options screen is displayed (see Figure 10.18).



🛝 Remove Options	×
-Remove Mapping Options	_
Remove Comments	
Remove For Each	
C Remove Local Variables	
Remove Sorting Rules	
🗖 Remove Global Variables	
Remove Custom Methods	
🗖 Remove Keys	
Remove Context Variables	
Remove Templates	-
OK Cancel	

Figure 10.18: Remove Options

2. This screen displays a list of the properties, variables, custom methods, keys and templates associated with a mapped element, which can be removed with the mapping.



3. Select the checkbox(s) of the options that you want to remove and click **OK** button. All the selected options and all mappings between source and target elements will be removed.



You can remove mapping associated with each element individually. For details, refer to the section **<u>Remove Mapping of an Element</u>**.

# Using Custom Auto Map Options

You can use Auto Mapper feature only when the elements of source and target schema are in same hierarchy and have the same names. Now, if you want to automatically map elements of source and target schemas where hierarchy and elements are different, you can use *Custom Auto Map Options*. This option allows you to define custom options for Auto Mapper. For example you can define, if the source element is *EmPName*, it should map to *Name*.

All the Custom Auto Map Options that you create are saved globally and can be used in any mapping activity.



#### Steps to use Custom Auto Map Options

1. Ensure that the <u>source and target schemas are loaded</u> and all their elements are listed under their respective nodes (see Figure 10.19).




Figure 10.19: Same Hierarchy and Element Names

2. Click Actions menu and select Add Custom Map Options (see Figure 10.20).






Figure 10.20: Select Add Custom Map Options

3. The Custom Auto Map Options dialog box is displayed (see Figure 10.21).



1	Custom Auto Map Options Dialog		×
	Custom Auto Map Source Data	Custom Auto Map Target Data	Add Delete Edit
	syn	chronize Close	

Figure 10.21: Custom Auto Map Options Dialog box

4. Click Add button. The Add Data Dialog box is displayed (see Figure 10.22).

Add Data Dialog			×
Custom Source Data		Custom Target Data	
	Ok	Cancel	

Figure 10.22: Add Data Dialog box

- 5. Enter the name of the source element for which you want to define custom auto map option in the *Custom Source Data* field.
- 6. Enter the name of the target element to which you want to map the source element specified in previous step, in the *Custom Target Data* field.
- 7. Click **OK** to close the Add Data Dialog box. The added entry is shown in Custom Auto Map options dialog box (see Figure 10.23).



🙈 Custom Auto Map Options Dialog		×
Custom Auto Map Source Data	Custom Auto Map Target Data	
EmpName	Name	Add
		Delete
		Edit
synch	Close	

Figure 10.23: Added Entry for Custom Auto Map

- 8. Similarly you can add other entries.
- 9. Click **Close** to close this dialog box.
- 10. Map the parent record of Source and Target Schema.
- 11. Right-click the parent record of the target schema and select **Connect Matching Record** options (see Figure 10.24).



& ADEPTIA - Data Mapper - ExcelSchemaForEmployees_Map		B ×
File View Actions Help		
Data Mapper St. Or Debugger		
	Current Element : Employee	
Core Schema	Copen Target Schema	
Structure_of_source_XSD	Structure_of_destination_XSD	-
A Root (ExcelSchemaForEmployees)		
ecordNumber	Remove Mappings	
<ul> <li>OrganisationID (string)</li> </ul>		
	Duplicate Node (50)	
SSN (string)	Assign Stream	
→ DOB (string) → Address1 (string)	💘 Select Root	
Address2 (string)	Remove Schema	
Octy (string)	N Remove Clone	
Employer (string)	Copy Mapping	
Designation (string)     DOJ (string)	Paste Mapping	
Salary (string)	😨 Set As Merger XPath	
	in Remove Merger XPath	
v	Custom XSL Before	-
Math String Date Aggregation Conditional Axis Boolean Context XSL Template DB		-
	Kers	_
Be Mapping Rules Textual Rules Cocal Variables	Apply Filter phal Variables	
T C C C C C C C C C C C C C C C C C C C	cal Variables	
8	Connect Matching Children stom Methods	
Image: Second.     Image: Second.	Context Variables	
View		
ata	- O local	
	global	
	Connection Info	
	Er-● Global Methods → Value Map	

Figure 10.24: Select Connect Matching Children

12. The Connect Matching Children Dialog box is displayed (see Figure 10.25).



Figure 10.25: Connect Matching Children Options

- 13. Select the mapping criteria from the *Automap options* list. Its options are listed as:
  - **Ignore Case:** The source and the target elements are mapped even if they are of different case. Their attributes are not mapped.

ADEPTIA

- **Ignore Namespace:** The source and target elements are mapped, when their names are same but source schema has any namespace prefix.
- **Recursive:** Elements of parent level as well as all child level with the corresponding target elements.
- Mix Attributes: Attributes of source and target schemas are mapped.
- 14. Select the mapping criteria from the *Existing Options* list. These options are :
  - **Retain:** If any source and target elements are already mapped, those mapping will not be overwritten.
  - **Overrite:** Overrites all the existing mappings.
- 15. Click **OK**. This will map source and target schema as per the criteria selected (see Figure 10.26).




Figure 10.26: Source and Target elements are mapped

# Using Add Value Map Options



You can set the Map for a particular value of an element using the Add Value Map feature. For example, if the value of an element, (for example, *EmpGender*) from source schema is coming as F and M, then you can set the map for these values as Female and Male respectively and pass it to the target element.

All the Value Map Options that you create are saved globally and can be used in any mapping activity.

#### Steps to use Value Map Options

1. Ensure that the **source and target schemas are loaded** and all their elements are listed under their respective nodes (see Figure 10.27).




Figure 10.27: Elements of Source and Target Schema

2. Click Actions menu and select Add Value Map Options (see Figure 10.28).



🙏 AD	EPTIA - Data	a Mapper - EmployeeMapping					_	. 8 ×
File	View Actions	Help						
10	Data M 🛛 🥑 '	Validate XSL	Ctrl+V					
8 🖡	4 🧯 🏝 י	Global Custom XSL Before	Ctrl+B	Current	Element : Employees			
- SS		Global Custom XSL After	Ctrl+A		Cope	n Target	Schema	
1.5	tructi	On demand (optimized) loading of XML Schema tree	Ctrl+E		Structure of destination XSI		Science	
		Namespace	•		⊨ A Root (ExcelSchemaofEr		:)	
	ė	Enable DBQuery caching	Ctrl+D		E-A Record			
	:	Search Element	Ctrl+F		- 🥹 OrganisationID	(string)		
	:	Set Data Viewer Record Count						
	C	Add Custom Auto Map Options						
	(v)=	Add Value Map Options			→ DOB (string) → Address1 (string	J)		
		ddress2 (string)				g)		
		ity (string)						
		tate (string)						
		mployer (string)						
		esignation (string)			> Designation (str	ing)		
		OJ (string)			> DOJ (string)			
	i Sa	alary (string)			Salary (string)			
-								-
Math	String Date	e Aggregation Conditional Axis Boolean Co	ontext XSL Tem	nplate DB				
Node	📒 Mapping Ru	ules 🔞 Textual Rules 🧶 Local Variables 🔣 F	roperties				Parameters Global Variables	
		1 5D	ployees			×	E S Local Variables	
8								
Data Viewer   Global						2	<ul> <li>Keys</li> <li>Context Variables</li> </ul>	
/iew							E - Templates	
sta /							local	
ă							o dobal	
							Connection Info	
							Global Methods	
							Value Map	
	4							

Figure 10.28: Select Add Value Map Option

3. The Value Map Options dialog box is displayed (see Figure 10.29).

Value Map Options Dialog			×
	Name:		
Value Map	Value	Мар	Add Delete Scope: © Global © Group
Sy	Default Value:	Value Map Delete Value Map Close	]

Figure 10.29: Value Map Options Dialog box



- 4. Click **New Value Map** button and enter the name of value map (for example, *GenderMap*) in the *Name* field.
- 5. Click **Add** button and enter the value (for example, *F*) in *Value* field and enter its map value(for example, *Female*) in *Map* field.
- 6. Similarly you can add more Value and Map fields.
- 7. You can provide the default Map value in the *Default Value* field (for example, *Not Provided*). Incase at source side the value is neither *F* nor *M* then *Not Provided* value is mapped set to the target element (see Figure 10.30).

Value Map Options Dialog					×
	Na	ame: GenderMap			
▲ Value Map		lue		Чар	
	F		Female		Add
	M		Male		Delete
					Scope:
					Global
					C Group
	Default	Value: Not Provided			
S	ynchronize New Value M	lap Save Value Map	Delete Value Map	Close	

Figure 10.30: Add Value Map

- 8. Click the **Save Value Map** button to save the value map. This will add the newly saved value map in *Value Map* tree of *Add Value Map Options* dialog box and *Parameter Panel*. Similarly you can add more Value Map.
- 9. To synchronize the list of value map, click **Synchronize** button. This will list value maps created by other users.
- 10. Click **Close** to close the Value Map Options Dialog box.
- 11. Now to map it, select a target element, for example *Gender*. The selected target element is shown in Mapping Graph Area.
- 12. Double click on a value map you want to use, from the *Value Map* tree of Parameter Panel. For example, *GenderMap*.
- 13. Now double click the source element. For example, EmpGender.
- 14. Connect the output of the source element to input of value map and then connect the output of value map to the input of the target element.
- 15. Once you have performed the mapping activity, click **Apply Mapping** (**\***) button to save the mapping.



# Copy/Paste Mapping

This is an additional feature of mapping elements. You can copy the mapping associated with a target element and paste it on other target elements.

### Steps to copy the mapping of a target element

- 1. Ensure that the <u>source and target schemas are loaded</u> and all their elements are listed under their respective nodes. Additionally, a source and target element should be mapped.
- 2. Right-click the target element whose mapping you want to copy and select the **Copy Mapping** option. This copies the mapping of the selected target element.

#### Steps to paste the mapping on a target element

- 1. Ensure that the <u>source and target schemas are loaded</u> and all their elements are listed under their respective nodes. Additionally, the mapping of a target element should be copied.
- 2. Right-click the target element on which you want to paste the mapping and select the **Paste Mapping** option. The Paste Mapping Options screen is displayed with a list of Paste options (see Figure 10.31).




Figure 10.31: Paste Mapping Options

3. This screen displays a list of options that can be pasted with the mapping. It includes the *For Each* and *Comments* properties and local variables.

0	The Paste Mapping opt				options	are
Ø	enabled only if they have b	been defined for	the copied eler	ment.		

4. Select the checkbox(s) of options you want to paste with the mapping, and click **OK** button. The mapping with the selected options is pasted on the target element.



M	If local variables are pasted for a target element, they are not overwritten, but are added to the existing local variables of that target element.
Ŵ	but are added to the existing local variables of that target element.

m	
V	

You can also copy a mapping instance and paste it onto another instance. This is possible only if the schemas are same in both the mapping instances.

# Import Mapping

If you want to map elements in a pattern that is similar to an existing mapping, you can import the existing mapping.

## Steps to import an existing mapping to a new mapping

1. Ensure that the <u>source and target schemas are loaded</u> and all their elements are listed under their respective nodes. (see Figure 10.32).




Figure 10.32: Elements of Source and Target Schema

2. Click **Actions** menu and select **Import Mapping** (see Figure 10.33).



	O teldan IS.	CREW .				
	Links Cotter VL forfare	014				
81	Cate Constants, after	China	Ho Demonst Lawscard			
	Ovtenand (potential) leading of UNL Schema tee				Quen Target Schene	
# 50y(C)	Televergenie			destruction_XID		
	Even 000-eventing	040	A Rest (B)	(dScrat_TextSchem)) eff		
		Catel		LAME (string)		
	Ser Data verse Record Court			ODRESS (Johng) MASJD (Johng)		
			- 31	<ul> <li>PhiONERO (integer)</li> </ul>		
	D Add Curton Auto Hay Options			A TEOPERTH (date) RPARTHENT (drive)		
	No. Add Value Map Optime			ALARY (miniper)		
		cared.		DATEORIORMIG (mm)     DESIMATION (mm)		
	Depart Meeting	CREAT		dE (ntepe)		
2						
v] Halt Door	See Agricole Centred Ava Bolies Ce	tert 15.7equile (8			-	
Adaptic - Station	Som Appropriate Contributed Avia Baskeen Co ang Avias (Chartan Kines ) 😄 (avia ranatase) 🍙 m	Sett 15. Sevelete (18 an for)			Promises	
1 200	i Sen Agriptor Centeral Aus Indeer Ce orgitues (Shotal Rules ) @ Local Leader ( ) Th	Dert 15. Service (18) Dertre		,	Gotar Vandes	
1 100	i Sen Agrigator Castland Aus Italian Ce orgitus (Chasanthan ) is local revealer (Cam	cent (5. Terulate (2)			34 - Octor Hambles 34 - Octor Hambles - Octor Nemole	
1 100	s Sens Augrepter: Carolined Aux Insider: Co org Rules (Schoold Rules ) @ Inside toxologie ) @ Im	tert (5. Terulate (8 ant Ter)			Gotar Vandes	
1 100	. Sons Augmenter: Constituted Aux Boolaam Co ang Fules (Constant Rules ) @ Locar Locarees ) @ Pr	sert 18. Sevelate 18 sec. for			Cobar Vanables     Tempadoes     S Tempadoes	
1 200	. Som Approprier Control Aus Busies Co org Lues (Chanad Lues ) @ Local to else ) 🔐 In	tert 15. Service (8 uerter)			Optic formation	
1 200	i Sere Agrigator Carditani Aux Ibuikan Ge ang Kuas (@Robuitikula ( @ Lacat Konstein ( @ H	tert (6. Service (8)				
Adaptic - Station	i See Auguster Centred Ava Italies Cr orgitues (@Robalture ) @ lace tenders (@ M	tert (5. Terulate (8. Letting)				
1 200	: Sons Augregator: Carolined Ann Insien: Co orginues (Constantifiums ) @ Insertances ) (a m	sent 18. Service 18 an fait				
1 200	. Sons Augmenter: Constituted Aux Boolean: Co orgifices (© Northal Rules ) @ Local Incodes ) @ He	Sett 18. Sevelate (18 an for )				

Figure 10.33: Select Import Mapping Option

3. The Import Mapping Dialog screen is displayed (see Figure 10.34).

	Mapping Name	Mapping ID
C	PA_CashSalesSearchMore_Resp_V2008	12700000001121300731315600005
CL	PA_InvolcesSearchMore_Resp_V2008	12700000001121300748550000006
C	PA_CreditMemosSearchMore_Resp_V2008	12700000001121300772675000007
CF	PA_InventoryItemSearch_Resp_V2008	12700000001121308254568700001
c	EmployeeBenifitDataMapping	192168001002124950163011400018
cF	PurchaseOrderDataMapping	192168001002124958745789500056
cr	Fulfilment_WSMapping	192168001002124966823914900022
сГ	Fulfilment_ExcelToRequestVML	192168001002124966853066500026
- F	P. Miller and Research Million Print	10011000100010001000000000000000

Figure 10.34: Import Mapping Dialog

4. Select the mapping you want to import, and click **Load**. This imports the mapping of the selected schemas to the new schemas (see Figure 10.35).



Fill Vern Active resp	
Deta Trace The Information of the Information	
H 🖸 O 2 0	Ho Demont Longitud
🔂 Öper Source Scheme	Copen Target Scheme
2 Structure, JP, Severet, 2007 A Rectord (90) A Rectord (90)	Stouture, of perioretary, 200 III A Real Descript, TextScheme) PA Realed (K, F) III A Real Descript, TextScheme) III A Real Descript IIII A Real Descript IIIII A Real Descript IIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIII
8	
Net long Sets Agregator Cardianal Ave Booler Centert 15 Terulate 18	
Comparent Role (Sherica Guar Sanaking California)	Sector Vanides     Sector

Figure 10.35: Mapping Imported

# Mapping Functions

You can use the mapping functions built-in the Data Mapper to map source schema elements to the target schema elements. These mapping functions are listed as:

- Math
- <u>String</u>
- Date
- <u>Aggregation</u>
- <u>Conditional</u>
- <u>Axis</u>
- Boolean
- <u>Context</u>
- <u>DB</u>

All these mapping functions comprise of sub-functions using which you can map elements.

### Steps to map elements using Mapping Function

- 1. Ensure that the **source and target schemas are loaded** and all their elements are listed under their respective nodes.
- 2. Click a target element. The target element node is displayed in the Mapping Graph Area (see Figure 10.36).



& ADEPTIA - Data Happer - customer	_6×
Ele Yew Actions Help	
👔 Data Mapper 📷 XSL 🎯 Debugger	
💾 🛛 🗢 🤁 🛛	Current Element : NAME
Copen Source Schema	Carl Open Target Schema
Studture_of_source_XSO A Southers_of_source_XSO A Record A Record A Record A RABLO (string) A RABLO (string) A RABLO (string) A RABLO (string) A DATEOFBRITH (date) A DATEOFBRITH (string) A SALAY (nteger) A DESIGNATION (string) A AGE (nteger) A AGE (nteger)	Structure_of_destruition_XSD ⊖ A Record → R
×	
Math String Date Aggregation Conditional Axis Boolean Context XSL Template DB	
Image: Second Rules     Image: Second Rules       Image: Second Rules     Image: Second Rules       Image: Second Rules     Image: Second Rules	A constant set of the

Figure 10.36: Select Target Element

3. Double-click a source element. The source element is displayed in the Mapping Graph Area (see Figure 10.37).




Figure 10.37: Select Source Element



Ø

You can double-click more source elements if required. This will display the selected source elements in the Mapping Graph Area (see Figure 10.38).




Figure 10.38: Select Second Source Element

- 4. Click the desired mapping function. This displays a list of sub-functions associated with the selected mapping function.
- 5. Select the desired sub-function and use it to map the displayed source and target elements.
- 6. Once you have performed the mapping activity, click **Apply Mapping** (**\***) button to save the mapping.



Once you have mapped source and target elements, you can <u>view and</u> <u>validate the generated mapping XSL</u>, from the Data Mapper screen. You can also <u>view the target XML</u> and <u>view and validate</u> <u>mapping output</u> from this screen.

For details on using these mapping functions, refer to the section Using Mapping Functions.

While mapping elements, certain suffixes are displayed next to source and target elements in the Source and Target Panels. These suffixes are explained in the table below.

Table 10.8: Suffixes of Source and Target Elements



(C)	Target element can be cloned to create another target element.
(CM)	Comments have been added for the target element.
(F)	For Each property has been applied for the target element.
(LV)	A local variable has been declared to the target element.
(M)	Element has been mapped.
(SR)	Target Element has been sorted.
(S)	Source Element has been set as Splitter XPath. Target element has been set as Merger XPath.
(FL)	Filter has been applied on the target element.



More than one suffix can be displayed next to a source and target element.

# Save Mapping and Exit Data Mapper

Once you have mapped source and target elements, you can save the mapping and exit the Data Mapper.

## Steps to save the mapping and exit the Data Mapper

1. Click File menu and select Save to save the mapping. Alternately, you can click the Save

(b) button on the toolbar. The server first validates the mapping activity. If successful, it displays a dialog box confirming that the mapping has been saved successfully. If the *Comments* property is enabled, then clicking **Save** will display a screen where you need to enter comments related to the mapping. (see Figure 10.39).

Enter Co	mments
i	Specify comments for mapping object EvalXform_Mapping
	OK Cancel

Figure 10.39: Add Comments (Mapping)

2. Enter the comments in the *Specify comments for mapping object (object name)* field.





The comment should be at least 1 character in length.

If you enable/disable the *Comments* property in the middle of a mapping activity, you need to restart the mapping applet.

3. Click **OK** to save the comments. This displays a dialog box confirming that the mapping has been saved successfully.



By default, the *Comments* property is disabled. To enable it, refer to the *Updating System Properties* section in *Administrator* Guide.

4. Click **File** menu and select **Exit** to close the Data Mapper applet. A confirmation dialog box is displayed (see Figure 10.40).



Figure 10.40: Exit from Data Mapper

5. Click **Yes** button to exit the Data Mapper screen and return to the Manage Data Mapping screen. If the mapping object has not been saved, then the Save Mapping Object dialog box is displayed (see Figure 10.41).

Save Mapping Object			×
	ent Mapping Object I • To Save Current Ma		
Save To Server	Do Not Save	Cancel	

Figure 10.41: Save Mapping Object

- 6. Click **Save To Server** button to save the mapping object to the Adeptia Suite. A screen is displayed where you need to enter comments related to the mapping. (refer to Figure 10.39).
- 7. Enter the comments in *Specify comments for mapping object (object name)* field.
- 8. Click **OK** to save the comments. This displays a confirmation dialog box stating that the mapping has been saved successfully. The control returns to the Manage Data Mapping screen, where a list of mapping activities is displayed.
- 9. Refresh the Internet browser to view the saved mapping activity.



You can <u>view and validate the generated mapping XSL</u>, <u>view</u> <u>the mapping XML</u> and <u>view and validate mapping output</u>, before saving the mapping activity.

At times, on saving a mapping activity, the memory usage may exceed its actual capacity depending on the JVM and the operating system.

## View and Validate Generated Mapping XSL

This is a very useful feature of the Data Mapper. It enables you to validate and test the generated XSL before saving the mapping activity.

#### Steps to view and validate the generated mapping XSL

1. Click **XSL** tab on the Tabs Panel to view the generated mapping XSL. The generated XSL code with line numbers is displayed (see Figure 10.42).




Figure 10.42: Mapping XSL

2. Click the **Action** menu and select **Validate XSL** option to validate the generated XSL. A dialog box is displayed confirming that the XSL is valid.




Ø

If generated XSL is invalid, then an error is displayed as a selected line. Error details are displayed in the XSL Errors Pane. It displays one error at a time.



3. Click **OK** button to close the above dialog box.



## View Mapping XML

The Data Mapper allows you to view the generated XML code, before saving the mapping activity.

#### Steps to view Mapping XML

1. Click the **View** menu and select **View Mapping XML** option. This displays the generated XML code with line numbers, in read-only mode (see Figure 10.43).




Figure 10.43: View Mapping XML

## View and Validate Mapping Output

Once you have mapped source and target schema elements, you can view and validate the output of the mapping activity. This feature enables you to test the data and make modifications to the mapping activity, before saving it.

#### Steps to view and validate mapping output



1. Click **Debugger** tab on the tabs panel to view and validate the output of the mapping activity. The Debugger is displayed on the Data Mapper screen (see Figure 10.44).

& ADEPTIA - Data Happer - customer		×
Pile View Actions Help		
Data Mapper 😁 XSL 🌼 Debupper		
Input	×9.	Output
EvalScript_TextSchema	1 Cixal version='1.0'>>	EvalScript_TextSchema
1 x x x x x x x x x x x x x x x x x x x	<pre>christyleshet xulosisl="http://www.sl.org/1999/GL/Tansform" version christma mass"_watHars"/&gt; christma mass"_uatHars"/&gt; christma mass"_idssT'/&gt; christma mass"_idssT'//&gt; christma massT'///////////////////////////////////</pre>	
	Run on desktop C Run on server Run Stop	
Variables [Parans] Name V Name	alor 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	د ح اد

Figure 10.44: Debugger screen

This screen is divided into five sections as listed in the table below.

Section	Description
Input	Displays data for all input schemas in XML format. This data can be mockup data or a selected XML file.
XSL	Displays the generated XSL. You can generate sample output data based on the input data.
Output	Displays the generated output data for all schemas.
Variables/	This section comprises of two tabs:
Params	Variables
	Params
	The Variables tab displays the local variables that are encountered in the generated XSL.
	The Params tab displays all parameters that are defined for a XSL template. These parameters are displayed only if that XSL template is used in the mapping activity.
Errors	Displays all errors encountered during debugging.



Click Generate Input Mock up Data button displayed in the Input section, to generate the 2. sample input data in XML format. The sample input data contains name of the element as XML Tags and some randomly generated values as their data. The sample input XML file is displayed in the Input section (see Figure 10.45).





Figure 10.45: Generate Mockup Data



- Alternately, you can attach a source file to the root element of the source schema. Right-3. click the root element of the source schema and select Attach Source from the drop-down list. Select the source file to attach it. This automatically converts the actual data of the source file into XML input data, which can be validated.
- Alternately, you can display input data from an existing XML file. Click Load Input XML 4. button (😕) displayed in the Input section to select and upload the existing XML file.

Ø	Another way of uploading the XML file is right-clicking the <i>Input</i> section and clicking the <b>Load</b> option.
	If you load an XML file, then the existing XML code is overwritten. It is not appended.



Click **Save** button ()) displayed in the Input section to save the generated input data. 5.

Ø

You can simulate the mapping either on the desktop or on the server. By default, simulation is done on the desktop. Simulating on the server supports global functions, custom methods, Context Variable, Set Context, Get Context



and the DBlookup () functions. However, it can be used only in case of mapping of single source and target elements.

While simulating on the server using context variables, if you assign a value to the context variable using the Set Context function and retrieve its value using the Get Context function, it will return the default value of the context variable, instead of the new value assigned. For example, a context variable 'Var1' has the default value as 10 and is later assigned the value of 20 by Set Context function. When the Get Context function is used to retrieve the value of the value of the value of the value of 20.

- 6. Click the *Run on Server* radio button if you want to simulate the mapping activity on the server.
- Click **Run** button displayed in the XSL section to generate sample output data based on input data. The generated sample output data is displayed in the Output section (see Figure 10.46).




Figure 10.46: Output XSL

You can stop the generation of output data at any time by clicking the<br/>Stop button displayed in the XSL section.In case XML Schema is used at target end, then unmapped elements are<br/>filtered out automatically.



- 8. Click **Save** button () displayed in the Output section to save the generated mapping output.
- 9. A dialog box is displayed using which you can save the XML file at the desired location.

# Using Data Viewer

Data Viewer is an advanced feature of Data Mapper which is used to view actual input and output data after applying mapping rules. In data viewer, you can upload actual input file and view the actual output. It also displays error records (if any). Additionally, it also validates the enumerated values and displays the list of enumerated literals for the target element incase XML Schema is used at target.

Data Viewer is helpful if you want to know what will be the output of the mapper. In this case you need not to execute the process flow. You can simply upload the source file and view input and output record.

In data viewer, records are displayed in Grid View as well as Tree View. Table 10.10 lists the schemas, whose records can be displayed in data viewer.

Schema	Tree View	Grid View
Adv. Text Schema	$\checkmark$	Х
Excel Schema	$\checkmark$	$\checkmark$
Hierarchical Excel Schema	$\checkmark$	Х
Text Schema	$\checkmark$	$\checkmark$
XML Schema	$\checkmark$	x
Adv. Positional Schema	V	Х
Positional Schema	V	V

Table 10.10: List of schema whose records can be shown in Data Viewer

#### Steps to use Data Viewer

1. Ensure that the <u>source and target schemas are loaded</u> and all their elements are listed under their respective nodes.



- 2. Map source and target elements and apply the mapping rule as per your need.
- 3. To use Data Viewer, click **Data Viewer** tab. The **Data Viewer** panel is displayed (see Figure 10.47).




Figure 10.47: Data Viewer

4. To attach the source file, right click the **Root** element in the Source Panel and select **Attach Source** option and select the source file (see Figure 10.48).



& ADEPTIA - Data Happer - customer	
File View Actions Help	
👔 Data Mapper 🕤 XSL 🏟 Debugger	
💾 🛚 🗢 🤁 🛛	No Element Selected
Copen Source Schema	Copen Target Schema
Image: Status       Statu	Studture_cf_detarbato_VSD (=) & Bot (Gastrong Leadscherne)) (=) & Bot (Gastrong Leadscherne)) (=) & ApoRESS (strong) (H) (=) & ApoRESS (strong) (H) (=) & ApoRESS (strong) (H) (=) & ApoRESS (strong) (H) (=) & DATEOFERTH (state) (H) (=) & DATEOFERTH (strong) (H) (=) & DATEOFERTH (strong) (H) (=) & DAEGE (strong) (H) (=) & DAEGE (strong) (H) (=) & AGE (integer) (H) (=) & AGE (integer) (H) (=) & AGE (integer) (H)
Barrow           Ba	Teropt

Figure 10.48: Attach Source

5. After selecting the source file, again right click the **Root** element in source panel and select **Preview**. Source Data is displayed in the *Grid View* panel (see Figure 10.49).




Figure 10.49: Source records in Grid View





By default maximum 50 records are displayed in the Data Viewer. To view more records, click **Action** menu and select **Set Data Viewer Record Count** and enter the desired value. When you change this value, you need re-attach the source.

6. If there is any error record in the source file, a pop-up message is displayed that *"Error Records found in the source data."* (see Figure 10.50).



Figure 10.50: Pop-up message

- 7. Click **OK** to close this pop-up message.
- 8. To view the source data in *Tree View*, click the **Tree View** tab. The source data is selected in the tree view (see Figure 10.51).

#### Figure 10.51: Tree View

9. To view the values of the record, click [+] to expand the *Record*. Values of the expanded record are shown (see Figure 10.52).



Source		
Grid View T Tree View O Errors		
Name	Value	-
a Root		<u> </u>
🖨 🗁 Record		
····   NAME	John Smith	
ADDRESS	10-street	
	john.smith@snet.net	
PHONENO	657828	
ATEOFBIRTH	1977-04-04 05:30:00	
	sales	
SALARY	10000	
ATEOFJOINING	1998-04-04 05:30:00	
	1998-04-04 05:30:00 manager	-

Figure 10.52: Records in Tree View

- 10. Similarly to view values of other records, expand other records.
- 11. If there is any error encountered in the source data, those error records are shown in the *Errors* tab. To view the error records, click **Errors** tab (see Figure 10.53).

Global Node	Preview	
ž	Source	
bal	Grid View T Tree View 🔮 Errors	
ဗီ	Name	<u>î</u> ,
	C Root	
÷.	🗈 💼 ErrorRecord	
Data Viewer	🗄 💼 ErrorRecord	
ta V	🗄 🗁 ErrorRecord	
Da		

Figure 10.53: Error Record

12. To view the output record, right click the **Root** element of the target panel and select **Preview** option. The generated output records are displayed in the *Target* panel of *Preview* pane (see Figure 10.54).



y 🖸 🗿 🤗 (	•				Current Element : Root				
	Cope Cope	1 Source Schema					Carl Open Target Schema		
DATEOFBJ     DEPARTME     SALARY ()     DATEOFJO	(string) (M) (string) (M) (RTH (date) (M) ENT (date) (M) ENT (string) (M) (integer) (M) DINING (date) (M) TON (string) (M)					ecord (M) IAAME (string) (M) ADDRESS (string) (M) EMAILID (string) (M) DHOHEND (megae) (M) DATEOFERTH (date) (M) DEPARTMENT (string) (M) SALARY (mtegae) (M) DATEOFENTING (date) DESIGNATION (string) (M) DESIGNATION (string) (M)	M) M) (M)		
AGE (inte	ger) (H)					AGE (hteger) (M)			
AGE (inte	gaton Conditional Axis Booles	in Context XSL Template (	NB		Torget				
AGE (inte String Date Appres Preview	gaton Conditional Axis Booles	n Context XSL Template (	NB				PHALD	E PHONENO	
String Date Appres	pation Canditional Asia Bookel e View [☉ Briers]	EMA1.1D John.smith@snet.net		1977	Target inii Ord Ven   T. Tree John Smith	View O Brors	john.smith@snet.net	657828	1977
String Date Aggreg Preview Source Source NAME NAME NAME	etien Canditonal Avis Booles etien (◯) Errors ACCEESS 1049-teet> <1249-teet>	EMABLID John.smith@snet.net jdcoffin01@snet.net	PHONENO 657828 689567	1976	Terget en Grd Vew T Tree NAME John Smith Devid Coffin	View V Errors AORESS 10494eet <12494eet>	john.smith@snet.net dcoffin01@snet.net	657828 689567	1976
String Date Apprep Prevew Source Cond View   T Tree NAME John Smith David Coffin Gold Man	pation Conditional Avia Bodela te View ♥ Errors ACCESS 10-59-et 13-59-et 13-59-et	EMA3LID john.smith@snet.net dcoffn01@snet.net goldman@snet.net	PHONENO 657828 659567 657398	1976 1965	Target iiii Grd Ven T Tree John Smith David Ceffin Gold Man	View O Errors ACCR55 20-5rest -13-5rest -3-5rest	john.smith@snet.net dcoffin01@snet.net goldman@snet.net	657828 689567 657898	1976 1965
AGE (inter String Date Aggreg Preview Source Hill Of Vew [1] The NMMC Offin David Coffin Gold Man Kary Seahdman	etien Canditonal Avis Booles etien (♥) Errors ACCEESS 1049eet 1349eet 1349eet	EMAILID john.smith@snet.net dooffn01gsnet.net goldman@snet.net k.seahoin@snet.net	PHONENO 657828 689567 657898 579076	1976 1965 1974	Target and Vew TT Tree and Vew TT Tree and Vew Coffin Gold Yean Xery Sealchan	Wew V Errors           AORESS           10499et           13499et>           13499et           1449et	john.smith@snet.net dcoffin01@snet.net goldman@snet.net k.seaholm@snet.net	657828 689567 657898 579076	1976 1965 1974
AGE (inter String Date Aggreg III Preve Source III of View TT Tree Source III of View TT Tree NAME Joint Source Joint Seaton Karry Beatonan Karry Seatonan Karry Seatonan	e View P Ennrs Avis Eooles e View P Ennrs ACCRESS 10-51eet -13-51eet 14-51eet 14-51eet	EMADLID john.smith@snet.net dooffn01gsnet.net k.seaholm@snet.net k.fitl@wnet.net	PHONENO 657828 689567 657898 579076 456735	1976 1965 1974 1959	Target iiii od Viei T Tree 24h Smith David Coffin God Kan Karry Seahdman Start Utle	New         O Errors           ACORESS         20-treet           13-street         13-street           14-street         17-street	john.smith@snet.net dcoffn01@snet.net goldman@snet.net k.seaholm@snet.net s.fittle@snet.net	657828 689567 657898 579076 456735	1976 1965 1974 1959
AGE (inter AGE (i	e View Official Avia Booles e View Officers ADDRESS 10-9-beet 12-9-beet 12-9-beet 12-9-beet 12-9-beet 12-9-beet	EMABLED John.smith.@snet.net goldman@snet.net s.Ration@snet.net s.Ritie@snet.net "#idokano@snet.net"	PHONENO 657828 689567 657898 579076 456735 236788	1976 1965 1974 1959 1949	Target in Grid View T Tree in Grid View T Tree David Coffin Gold Nan Kary Sealchian Shart Little Anar Little Shart Little	View         O         Errors           AORESS         20-94-9841	john.smith@snet.net dcoffin01@snet.net goldman@snet.net k.seaholm@snet.net s.fitte@snet.net ""sdickinson@snet.net"	657828 689567 657898 579076 456735 236788	1976 1965 1974 1959 1949
String Date Appres Prevew Source Grot View TT Tree	e View P Ennrs Avis Eooles e View P Ennrs ACCRESS 10-51eet -13-51eet 14-51eet 14-51eet	EMADLID john.smith@snet.net dooffn01gsnet.net k.seaholm@snet.net k.fitl@wnet.net	PHONENO 657828 689567 657898 579076 456735	1976 1965 1974 1959	Target iiii od Viei T Tree 24h Smith David Coffin God Kan Karry Seahdman Start Utle	New         O Errors           ACORESS         20-treet           13-street         34-street           14-street         17-street	john.smith@snet.net dcoffin01@snet.net goldman@snet.net k.seaholm@snet.net s.fittle@snet.net	657828 689567 657898 579076 456735	1976 1965 1974 1959

Figure 10.54: Target Records in Grid View

In case XML Schema is used at target end, then unmapped elements are filtered out automatically.

- 13. To view the error records at the target end, click **Errors** tab of target panel of Data Viewer. It displays:
  - The number of errors occurred during transformation
  - The list of errors occurred during transformation
  - List of enumerated literals for the target element if invalid data is mapped to the target element which is restricted to the enumerated values
- 14. In case you perform any changes in mapping rules, you need to click to refresh the target data according to mapping rules applied.
- 15. You can also view the output data in tree view, by clicking the *Tree View* tab.
- 16. To expand the **Source** or **Target** panel, click



📻 Grid View 🕇 Tree Vi								
		1						-
NAME	ADDRESS	EMAILID	PHONENO	DATEOFBIRTH	DEPARTMENT	SALARY	DATEOFJOINING	D
hn Smith	10-street	john.smith@snet.net	657828	1977-04-04 05:30:00	sales	10000	1998-04-04 05:30:00	manager
vid Coffin	<12-street>	dcoffin01@snet.net	689567	1976-04-04 05:30:00	production	5894	1996-04-04 05:30:00	executive
d Man	13-street	goldman@snet.net	657898	1965-04-09 05:30:00	<accounts></accounts>	3477	1985-09-04 05:30:00	manager
ry Seaholman	14!-street	k.seaholm@snet.net	579076	1974-04-04 05:30:00	-human resource	2467	2000-04-04 05:30:00	consulta
art Little	17-street	s.l'ittle@snet.net	456735	1959-04-06 05:30:00	<sales -?=""></sales>	8934	1999-06-04 05:30:00	sr. exect
n Dickinson	47-street	""sdickinson@snet.net"	236788	1949-04-03 05:30:00	development	3469	1979-03-04 05:30:00	develop
illen Smith	25-street?	seawatch@snet.net	758995	1968-04-07 05:30:00	testing	2490	1988-07-04 05:30:00	Trainee
a Vista	26-street	alta.ct@snet.net	567893	1962-04-08 05:30:00	accounts	3578	1991-08-04 05:30:00	sr. execu

Figure 10.55: Target Panel in expanded mode

17. To close the expanded **Source** or **Target** panel, click

# Viewing Mapping in PDF format

#### Steps to view mapping activity in PDF format

- 1. In the Adeptia Suite homepage menu, click **[+]** Configure to expand the tree. All the items in the Configure category are displayed.
- 2. Click [+] Services to expand the tree. All the items in the Services category are displayed.
- 3. Click **[+] Data Transform** to expand the tree, and then click **Data Mapping**. The Manage Data Mapping screen is displayed (refer to Figure 10.1).
- 4. Click the radio button against the mapping activity whose PDF details you want to view. This selects the mapping activity and activates the *PDF View* link. Clicking this link displays a PDF file with all information associated with the mapping activity.
- 5. This file displays divides the mapping information into various pages. The first page contains mapping information such as mapping name, description; creation details and the group owner (see Figure 10.56).



# Adeptia Mapping Information Document

Mapping Name	EvalScript_Mapping
Mapping Description	Mapping between Text And Excel Schema
Creation Date	08/12/2006 15:43:42
Last Modified On	09/21/2005 10:25:50
Created By	admin
Last Modified By	admin
Group Owner	administrators

Figure 10.56: Mapping Information Document

6. The next page displays all source and target schema information (see Figure 10.57).

		Source S	Schemas		
Schema Name Schema ID				Schem	a Root
[.		TextSchema:1921680010061 15537684214000004		Root	
		Target S	chemas		
Schema Name	Schem	a ID	Schema Root		Stream Name
EvalScript_TextSchem a	TextSchema:1921680 010061155376842140 00004		Root		output_1

Figure 10.57: Schema Information



7. The next page displays all other mapping information such as XSL templates used, variables defined, properties, keys, and sorting rules (see Figure 10.58).

		(	Global Va	ariable	S				
Variable Nar	ne			Value					
var2				50					
		C	Custom N	Nethod	ls				
Alias Name Class Name				Method Name Paramaters				ters	
java class		class1	ss1 a		add		02		
		Ma	ipping In	forma	tion				
TARGET NAME	TARGET FIELD	MAPPING FIELD	FOR EACH		SORTING RULES Source Data Order Elemei Type		IMENTS	LOCAL V Variable Name	Value
EvalScript_TextSche ma	/Root/Record/NA	ME Sinput_EvalScript_Te xtSchema/Root/Reco d/NAME							
EvalScript_TextSche ma	/Root/Record/AD 88	DRE \$input_EvalScript_Te xtSchema/Root/Reco d/ADDRESS							
EvalScript_TextSche ma	/Root/Record/EM D	AILI \$Input_EvalScript_T( xtSchema/Root/Reco d/EMAILID							
EvalScript_TextSche ma	/Root/Record/PH NO	IONE \$Input_EvalScript_T( xtSchema/Root/Reco d/PHONENO							
EvalScript_TextSche ma	/Root/Record/DA FBIRTH	TEO \$input_EvalScript_To xtSchema/Root/Reco d/DATEOFBIRTH							
EvalScript_TextSche ma	/Root/Record/DE TMENT	PAR \$input_EvalScript_T( xtSchema/Root/Reco d/DEPARTMENT							
EvalScript_TextSche ma	/Root/Record/SA Y	LAR \$Input_EvalScript_TextSchema/Root/Reco d/SALARY							
EvalScript_TextSche ma	/Root/Record/DA FJOINING	TEO \$Input_EvalScript_To xtSchema/Root/Reco d/DATEOFJOINING							
EvalScript_TextSche ma	/Root/Record/DE NATION	SIG Sinput_EvalScript_Te xtSchema/Root/Reco d/DESIGNATION							
EvalScript_TextSche ma	/Root/Record/AG	E \$Input_EvalBcript_T( xtSchema/Root/Reco d/AGE							
EvalScript_TextSche ma	/Roof/Record	Sinput_EvalScript_Te xtSchema/Root/Reco d							

Figure 10.58:	Detailed	Mapping	Information
---------------	----------	---------	-------------

# View Mapping in Read-Only Mode

If you have read-only rights, you can still view a mapping activity. You can view the applied mapping, create new mapping rules, edit existing mapping rules and run simulation. However, you cannot save the mapping activity.

#### Steps to view mapping in read-only mode

- 1. In the Adeptia Suite homepage menu, click **[+]** Configure to expand the tree. All the items in the Configure category are displayed.
- 2. Click [+] Services to expand the tree. All the items in the Services category are displayed.
- 3. Click **[+] Data Transform** to expand the tree, and then click **Data Mapping**. The Manage Data Mapping screen is displayed (refer to Figure 10.1).



4. Click the mapping activity that you want to view in read-only mode. The View Data Mapping screen is displayed (see Figure 10.59).

Properties	Value	
Description	Mapping between Text And Excel Schema	
Source Schema	192168001006115537684214000004	
Target Schema	192168001006113537717745300006	
Splitting Data	No	
Optimized Loading	Ne	
PDF File Name	Adp_Map_Rules52143.pdf	
Character Set Encoding	150-8839-1	
Mapping XSL	xmi version=1.0" encoding="UTF-0" <cxi: <="" extension-elementy="" hybeheet="" p="" referses"redirect"="" version="1.1"> xmfs: giva="http://xmi apache org/xmi/jixa"  xmfs: redirect="crag pache xalar, xala: toesnoins. Redirect"  xmfs: sci="http://www.di.org/1990/SL/Transform"&gt;  <ushtp: smission="1.0" top:=""></ushtp:> <ushtp: smissi<="" smission="top://smission=" td="" top:=""><td></td></ushtp:></cxi:>	
Mapping XML	xml version="1.0" encoding="UTF-8"? <maps> <sourceroots>Root</sourceroots> <targetroots> <targetroots> <targetroot> <targetroot></targetroot></targetroot></targetroots></targetroots></maps>	
Entity Id	192168001006115537762268700008	
Ounar	evalUser	
Owner's Group	evalGroup	
Creation Date	08/12/2006 15:43:42	
Last Modified Date	09/21/2003 10:25:50	
Last Modified By	admin	
Permissions	Owner(R.W.X) Group(R.X)	
Maximum Concurrent Processors	1	
Parallel processing	No	
Data Action	No Action	
Transformer Type	Xalan	

#### Figure 10.59: View Data Mapping

5. Click **Data Mapper** button. This displays the selected mapping activity in the Data Mapper applet in read-only mode (see Figure 10.60).




Figure 10.60: Data Mapper in Read-Only Mode



In the read-only mode all save options in the Data Mapper are disabled.



- 6. You can edit this mapping activity, by adding new mapping rules, or modifying existing ones. Additionally, you can also run simulation on this mapping.
- 7. Once you have made all changes, if you try and save the modified mapping, you will not be

able to save it, as all save options are disabled in read-only mode. The **Save** (**b**) icon and the **Save** option in the **File** menu are disabled. Additionally, after making the changes, if you close the Data Mapper applet, then the pop-up to save the mapping activity before exiting, will not appear.

# Splitting Source Data

Splitting feature enables you to process large files. You must use splitting if your source file is huge. If you do not use splitting in this case, then Data Mapper may not be able to map it. If the data in the source file is huge, you can split the source data into different chunks. You can specify the size of the chunks in terms of the number of records or data streams. In the output, however, only one file is generated at the location specified in the target activity.

#### Steps to split the source data

1. Click **[+]** Advanced Properties on the Create Data Mapping screen to expand the advanced properties of the new Mapping activity (see Figure 10.61).



Standard properties	
Name *	
Description *	
	Data Mapper
Advanced properties	
Splitting Data	
Split Number of Records	500
Parallel processing	
Maximum Concurrent Processors	1
Owner*	admin (Default Administrator)
	Read Write Execute
Permissions*	Owner 🗹 🗹
	Group 🔽 🗖
	Other 🗆 🗖
Mapping XSL*	
Mapping XML*	



Figure 10.61: Advanced Properties

2. Select the *Splitting Data* checkbox to enable the splitting of data.

If you select this checkbox, then you have to split the data. You can do this by <u>setting the Splitter XPath</u> in the Data Mapper applet. Alternately, you can split the data by *Enabling Quick Splitting* feature.

- 3. Enter the number of records into which you want to split the data, in the *Split Number of Records* field. For example, if you have a source file of 100,000 records and you want split this file into records of 10,000 each, then you need to enter 10,000 in this field.
- 4. Select the *Parallel Processing* checkbox to parallel process these records. By default, records are processed sequentially.
- 5. Enter the number of chunks you want to process concurrently, in the *Maximum Concurrent Processes* field. By default, value of 1 is entered.

It is advised to change this value, if *Parallel Processing* is selected. Else, only one chunk is processed at a time and hence sequentially.

- 6. Select the owner from the *Owner* drop-down list. By default, Administrator is selected.
- 7. Select the *Read, Write* and *Execute* checkboxes to set permissions for the Owner, Group or Other entities. By default, permissions are selected for the Owner and Group entities.
- 8. If mapping has been saved in the Data Mapper applet, then the XSL code is displayed in *Mapping XSL* field. This is a very useful feature. You can enter new XSL code or edit existing code to test or debug the mapping. If you save these changes, then they are reflected in the applet. For example, if you need to change the value of a constant, you can change it from this screen itself, instead of the applet. Additionally, any modifications made in the Mapping XSL code in the Data Mapper applet, will overwrite the XSL code in this field.



If the Advanced Properties and the Data Mapper screens are open simultaneously, then the changes made in the Mapping XSL field in the Advanced Properties screen will not be reflected in the Data Mapper screen.

- 9. The mapping XML code is displayed in *Mapping XML* field. You can enter new code or edit existing code. If you save these changes, they will be reflected in the applet.
- 10. Click **Save** to save the splitting details. A screen is displayed where you need to enter comments related to the splitting done. (refer to Figure 10.39).
- 11. Enter the comments in the Add Comments field.
- 12. Click **OK** to save the comments. This displays a screen confirming that the mapping transformation activity has been updated successfully.

# Set Splitter XPath

To split data you need to set the Splitter XPath on the source tree. The data is split and sent to the transformer which executes the split data. You can set the Splitter XPath in case of a single source schema only. You can also set multiple Splitter XPaths in a source schema.



The following example explains the use of multiple Xpath splitting:

Root | |- R1 | |-R1C1 | |-R1C2 |- R2 | |-R2C1 | |-R2C2


In this scenario we have **Root** element as the Root for schema. It has two child elements **R1** and **R2** at the first level. R1 element has two children **R1C1** and **R1C2**. **R2** element has two children **R2C1** and **R2C2**.

If in the source xml, there are multiple occurrences for **R1** and **R2** elements, then we need to set split XPath on both **R1** and **R2** elements. If we set split XPath on **R1** element only then the Data Mapper will assume that **R2** has only one occurrence and vice versa. Similarly, if child elements **R1C1**, **R1C2**, **R2C1** and **R2C2** have multiple occurrences, then also **R1** and **R2** should be set as split XPath. Thus the thumb rule is that the top most node which is repeating, should be set as splitter XPath.

Once splitter XPath is defined, during execution, mapping will split the source tree using each splitter Xpath and each chunk will have records specified by *Split Number of Records*.

In this scenario, when we set **R1** and **R2** as split XPath then *Split Number of Records* property is applied for both **R1** and **R2**. For example if the value of *Split Number of Records* property is 500 then 500 records of **R1** and 500 records of **R2** are selected.

Splitting data and setting Splitter XPath is very effective when the source data is very large. You can set the Splitter XPath in case of a single source and target schema. You can also set multiple Splitter XPaths in a source and target schema.



#### Steps to set Splitter XPath

1. Ensure that all the **source and target schemas are loaded** and all their elements are listed under their respective nodes.



2. Right-click the source schema element that you want to split and select the **Set as Splitter XPath** option. A screen showing the Splitter XPath details is displayed (see Figure 10.62).




Figure 10.62: Splitter XPath Details



Splitting can be set only on root or record levels. You cannot split on an element level.

3. Click **OK**. This splits and sets the Splitter XPath on the selected source element.



Once a Splitter XPath is set for a source element, the letter **(S)** is displayed next to that source element. This signifies that the source element has been split and the Splitter XPath has been set. Refer to **Table of Suffixes** for details on suffixes displayed next to an element.

Once you have set a Splitter XPath, you can view it in the Output XML.

# Enabling Quick Splitting

Another way of splitting source data is to enable the quick splitting feature. This splits the source and sets the Splitter Xpath.

#### Steps to split data by enabling quick splitting

- 1. Ensure that all the **source and target schemas are loaded** and all their elements are listed under their respective nodes.
- Select Actions menu and select Enable Quick Splitting option. Alternately, you can press ctrl> + <Q>. This splits the data and displays the splitter Xpath details (see Figure 10.63).





Figure 10.63: Splitter Xpath Details(Enable Quick Splitting)




3. Click **OK**. This splits and sets the Splitter XPath on the selected source element.

However, quick splitting splits the records in default numbers. To split into a specific number, you need to set the Splitter Xpath explicitly.



#### Steps to view Splitter XPath

1. Click **View** menu and select **View Mapping XML**. The Mapping XML window is displayed. The Splitter XPath details are displayed with a \$Input tag prefixed to Source XPath code (see Figure 10.64).



#### Figure 10.64: Splitter XPath in Mapping XML

You can remove a Splitter XPath that has been set for a source element.

#### Steps to remove Splitter XPath

1. Right-click the source schema element whose Splitter XPath you want to remove and select the **Remove Splitter XPath** option. A screen showing the Splitter XPath details is displayed (see Figure 10.65).






Figure 10.65: Remove Splitter XPath Details

2. Click **OK**. This removes the Splitter XPath set on the selected source element.

# Set Merger XPath

Once you have split the source data by setting the Splitter XPath on a source element, you need to merge the split data at the target end. For this, you need to set the Merger XPath on a target element.

Setting the Merger XPath is largely dependent upon the Splitter XPath. You need to ensure that the number of Splitter XPaths and the Merger XPaths at the source and target schemas respectively are the same.

#### Steps to set Merger XPath

- 1. Ensure that all the **source and target schemas are loaded** and all their elements are listed under their respective nodes.
- 2. Ensure that a Splitter XPath has been set for a source schema element.
- 3. Right-click the target schema element on which you want to merge the split data and select the **Set as Merger XPath** option. A screen showing the Merger XPath details is displayed (see Figure 10.66).




Figure 10.66: Merger XPath Details

-	
17	
UN	

Merging can be set only on root or record levels. You cannot merge on an element level.

4. Click **OK**. This merges the split data and sets the Merger XPath on the selected target element.



Once a Merger XPath is set for a target element, the letter **(S)** is displayed next to that target element. This signifies that the split data has been merged on the target element and the Merger XPath has been set.



Refer to **Table of Suffixes** for details on suffixes displayed next to an element.

You can view Merger XPath details in the output XML. A \$ input tag is prefixed to the line containing the Splitter XPath details.

Ø

When using Enable Quick Splitting feature, the Merger Xpath is also automatically set when this feature is selected.

Once you have set a Merger XPath, you can view it in the Output XML.

#### Steps to view Merger XPath

1. Click **View** menu and select **View Mapping XML**. The Mapping XML window is displayed. The Merger XPath details are displayed with *Target* XPath code (refer to Figure 10.64).

You can remove a Merger XPath that has been set for a target element.

#### Steps to remove Merger XPath

1. Right-click the target schema element whose Merger XPath you want to remove and select the **Remove Merger XPath** option. A screen showing the Merger XPath details is displayed (see Figure 10.67).



Figure 10.67: Remove Merger XPath Details

2. Click **OK**. This removes the Merger XPath set on the selected target element.

# Assign Data Streams

When mapping multiple source and target schema elements, you need to assign streams to the root element of the target schema structures.

#### Steps to assign data streams

1. Ensure that all the **source and target schemas are loaded** and all their elements are listed under their respective nodes.



2. Right-click the root element of a target schema structure and select the **Assign Stream** option. The Assign Streams dialog box is displayed (see Figure 10.68).

🙏 Assign Streams					x
Assign Streams					
	Orde	er Schema Name	Root Element	Stream Name	
	1	EvalScript_TextSchema	Root	output_1	
	2	EvalJMSE_TextSchema	Root	output_2	
			OK Cancel		

Figure 10.68: Assign Streams

3. This dialog box contains the fields listed in the table below. All fields are populated with values.

Field	Description
Order	Represents the order of occurrence of target schema in the Data Mapper. This field is a read-only field and is automatically populated with value.
Schema Name	Represents the name of the schema which includes the root to which the stream is to be assigned. This field is a read-only field and is automatically populated with value.
Root Element	Represents the root element to which the stream is to be assigned. This field is a read-only field and is automatically populated with value.
Stream Name	Represents the name of the stream to be assigned. This field is automatically populated with value, but is an editable field.

#### Table 10.11: Fields of Assign Streams Screen

The root elements, occurrence order and default stream names of all the loaded target schemas are listed in the Assign Streams dialog box. You can edit the stream name.

It is important to note that the order of streams and the stream names, listed in the Assign Streams dialog box (Mapping) and the Multiple Streams defined in Process Designer should be the same. If you edit a stream name of a mapping activity or add or delete a stream or schema after the activity has already been used in the Process Designer, then you need to update it manually in the Process Designer (Create Multiple Streams section). To know how to use multiple stream in Process Designer, refer to the section Creating Multiple Stream.

4. Enter the name of the data stream(s) that you want to edit, for the target element(s), in the *Stream Name* field.



6	1
1	

The name of the data stream does not accept special characters and white spaces.

5. Click **OK** to assign the stream(s), else click **Cancel**.

# **Remove Mapping of an Element**

You can remove mapping associated with a particular element.

#### Steps to remove mapping of a particular element

- 1. Ensure that all the <u>source and target schemas are loaded</u> and all their elements are listed under their respective nodes.
- 2. Right-click the target element whose mapping you want to remove and select the **Remove Mappings** option. The Remove Options screen is displayed (see Figure 10.69).

🙏 R	emove Options						
Ren	nove Mapping Options						
	Remove Mapping						
∥⊏	Remove ForEach						
∥⊏	Remove Comments						
∥⊏	Remove Local Variables						
∥⊏	Remove Sorting Rules						
	OK Cancel						

Figure 10.69: Remove Options (Particular Element)

This screen displays a list of properties and variables associated with the selected element that can be removed with the mapping.

(A)	Only the Remove Mapping is displayed as always enabled. The other options	
	are enabled only if they have been defined for the particular element.	

3. Select the checkbox(s) of the options that you want to remove and click **OK** button. All the selected options and mapping associated with the particular element will be removed.



# Using Context Schema

Context schema allows you to map Context Variable with any element of schema.

This section explains you how to use context schema to map context variable.

High level steps to use context schema are as follows:

- <u>Create Context Schema Definition</u>
- Load Context variables
- Map schema elements
- Modify streaming properties of Mapping Activity

#### **Create Context Schema Definition**

First of all you need to create context schema definition. Context schema definition contains name of the context variable that you want to map to other element. While creating context schema definition, you can create context variables or you can import it from the process flow within which you want to use this mapping activity.

#### Steps to create Context Schema Definition

1. In Data Mapper applet, click *Action* menu and select *Create Context Schema Definition*. *Create Context Schema Definition* dialog box is displayed (see Figure 10.70).



Context Schema Definition Dialog			
Context Variable Name	T		
	Add		
	Delete		
	Delete All		
Import From Process Flow Save			

Figure 10.70: Create Context Schema

- 2. To add a context variable click *Add* button and enter the name of the variable.
- 3. Repeat the same steps to create other variables (see Figure 10.71).



Context Schema Definition Dialog	×
Context Variable Name	[
var1	Add
var2	Delete
var3	Delete All
Import From Process Flow Save	

Figure 10.71: Add Variables

4. You can also import the context variables of the process flow in which you want to use this mapping activity. To import context variables from process flow, click *Import From Process Flow* button. *Import Context Variable* dialog box is diaplayed (see Figure 10.72)

	Process Flow Name	Process Flow ID
	EmployeeBenefitsConversion	192168001002124949379495800007
	PurchaseOrderProcessing	192168001002124950793861400029
° 🗌	PurchaseOrderProcessing_extended	192168001002124959023689300070
° 🕅	OrderFulfillment	192168001002124965911479900001
o 🕅	FulfillmentWebService_subprocess	192168001002124966303071300005
° 🕅	InventoryItemsProcessing_part1	192168001002124973613007800075
o 🕅	InventoryItemsProcessing_part2	192168001002124974311548800097
C PurchaseRequisition		192168001002124976246457600127

Figure 10.72: Import Context Variables

- 5. Select the process flow, from which you want to import context variables and click Load.
- 6. Click Save.



## Load Context Variable

Once you have created the context schema, you need to load it at source or target end depending on your need.

#### Steps to Load Context Schema Definition

1. To load the Context Schema at source end, click *Open Source Schema* button in the source panel. *Select Schema* dialog box is displayed (see Figure 10.73).

9	Select Schema					
Γ	Load Schema					
		O Schemas 🤇	Context Variables			
		Schema Name	Schema Type 🔶			
		EmployeeBenifitXMLSchema	XMLSchema			
	Г	PurchaseOrderXMLSchema XMLSchema				
		FulfillmentSOAPXML_Request XMLSchema				
		FulfillmentSOAPXML_Response XMLSchema				
		InventoryItemsXMLSchema XMLSchema				
		InventoryItemsCSVSchema	TextSchema			
		EvalScript_TextSchema TextSchema				
		EvalJMSE_TextSchema TextSchema				
		EvalRec_PositionalSchema	PositionalSchema			
	Search Criteria Search String Search Synchronize Load Cancel					

Figure 10.73: Load Context Variable

- 2. Select *Context Variable* radio button and click *Load* button. The variables on Context schema are loaded in source panel.
- 3. Similarly you can load context schema in the target panel.

## Map Schema Elements

Once you load the context schema, you can map its variables to elements of other schema (see Figure 10.74).






Figure 10.74: Map elements

## Modify Streaming Properties of Mapping Activity

Once you created the mapping activity using context schema you need to changes its streaming properties while creating process flow using this mapping activity.

If Context Schema is loaded at source side then there is no need to provide the source (dummy source) stream to the Mapping activity. Similarly if Context schema is loaded at target side then Mapping activity will not generate any output stream, so there is no need to attach dummy target. To achieve this **Generate Stream** and **Consume Stream** property has been added to Data Mapper activity in the Process Designer. User can disable these properties based on whether Context schema is loaded at source or target side.

#### Steps to disable input and output stream of mapping activity

 While designing the process flow, double click the mapping activity that you have created using context schema definition. Properties of the mapping activity are displayed (see Figure 10.75)

🐷 Properties 🚫 OnException Scripts 🚫 Alerts 🔄 Process Flow Variables 🗒 Comments			
Name	Value		
Activity Maximum Retries on Failure	0 🗮 🔺		
Activity Wait Time(in seconds) between Retries	60 🚔		
Character Set Encoding	ISO-8859-1		
Consume Stream	false		
Error Records	File		
Generate Stream	false		
Ъ	192168001006115537762268700008		
Label	EvalScript_Mapping		
Name	EvalScript_Mapping		



2. Change the value of *Consume Stream* or *Generate Stream* property to *false*.



If Context Schema is used at source side, then at run time the actual value of these context variables will be used in the Data mapping. Similarly if Context Schema is used at target side then the output of the data mapping will be parsed and corresponding new value of these context variables will be set.

# **Using Mapping Functions**

You can map source and target schema elements using the various mapping functions built-in the Data Mapper. All these mapping functions comprise of sub-functions, which are used to map elements.

Some mapping functions require use of constant values for mapping elements. For this, you need to add the constant node to the Mapping Graph Area.

## Adding a Constant

#### Steps to add a Constant

- 1. Ensure that the <u>source and target schemas are loaded</u> and all their elements are listed under their respective nodes.
- 2. Ensure that the **source and target elements to be mapped are selected and displayed** in the Mapping Graph Area.
- 3. Right-click the blank space in the Mapping Graph Area and select the **Constants** option. A *Constant* node is displayed in the Mapping Graph Area (see Figure 10.76).



& ADEPTIA - Data Happer - customer	_6×
Ele Yew Actions Help	
👔 Data Mapper 📷 XSL 🤬 Debugger	
	Current Element : NAME
Copen Source Schema	🔄 🖓 Open Target Schema
▲ Structure_of_source_XSD         ● A Roc (EvaScrot_Frashchera)         ● A Roc (S)         ● A Roc (nteger)         ● A A GE (nteger)	Structure_of_detration.XSD  G A Record F A Record O HAME (sring) O
Math String Date Apprepation Conditional Axis Boolean Context XSL Template DB	
Macong Rules () Textual Rules () Local Variables () In Properties	Parameters     Parameters     Point Variables     Docal Variables     Context Variables     Context Variables     Temperature     Societat Variables     Temperature     Societat Variables     Temperature     Societat Variables     Temperature     Societat Variables     Temperature     Value Map     Value Map


Figure 10.76: Add a Constant Node

4. Double-click the **Constant** node. The Input dialog box is displayed (see Figure 10.77).

Constant Value Dial	og			×
Constant Value			Add Quotes	
	ОК	Cancel		

Figure 10.77: Enter Constant Value

- 5. Enter the desired constant value in the *Constant Value* field.
- 6. Mark the *Add Quotes* checkbox as checked, if you want to define the constant as a string. Else, the constant is defined as numeric data. By default, this checkbox is unchecked, implying that a constant is defined as a number. However, you can change the constant to string datatype by checking this checkbox anytime.



7. Click **OK** button. This displays the entered value in the *Constant* node in the Mapping Graph Area.

## Using Math Function



The Math mapping function enables you to map elements by performing simple mathematic operations. It comprises of various sub-functions, which are listed in the table below.

Mapping Function	Sub Functions	Description	Example
Math	Add	Adds two numeric elements.	(10) + (5) returns 15
	Ceiling	Rounds a passed number to the smallest integer that is greater than or equal to the passed number.	Ceiling <i>(33.9)</i> returns 34
	Division	Divides two numeric elements.	(100) div (5) returns 20
	Floor	Rounds a passed number to the largest integer that is not larger than the passed number.	floor <i>(33.9)</i> returns 33
	Mod	Returns the remainder of a division between two numeric values.	(50) mod (3) returns 2
	Multiply	Multiplies two numeric elements.	<i>(10) * (5)</i> returns 50
	Round	Rounds a passed number to the nearest integer.	round (4.6) returns 5
	Subtract	Subtracts one numeric value from other.	<i>(10) – (5)</i> returns 5
	Number	Converts parameter to a number.	number ("- <i>17.3")</i> returns - 17.3
	Format- number	Transforms input data into a specific format. The specific formats allowed are decimals (upto 2 places) and %. This function can be used only if the target node is of string data type.	format-number (12.5, '\$#.00") returns \$12.50

Table 10.12: Sub-Functions of Math Mapping Function

You can use the required sub-function of Math mapping function to map elements. The process of using the Math function is the same for all its sub-functions. Thus, the mapping process using one sub- function is outlined below.

#### Steps to map elements using the 'Division' Math Mapping Function



- 1. Ensure that the <u>source and target schemas are loaded</u> and all their elements are listed under their respective nodes.
- 2. Ensure that the <u>source and target elements to be mapped are selected and</u> <u>displayed</u> in the Mapping Graph Area.
- 3. You need to <u>add a constant value</u> for using this function. Once it is added, a *Constant* node with its value is displayed in Mapping Graph Area.
- 4. Click **Math** function menu and select the **Division** sub-function. A div node is displayed in the Mapping Graph Area (see Figure 10.78).

4. ADEPTIA - Data Mapper - customer	
File View Actions Help	
👔 Data Mapper 🕋 XSL 🧑 Debugger	
💾 🖸 🗢 🤁 🛛	Current Element : SALARY
ြူပို Open Source Schema	😭 🖓 Open Target Schema
Surdure, of source, XSD	Structure, of, destruction, SSD         (a) & Accord         (a) & Accord         (a) & Accord         (a) & Accord         (b) & Accord         (c) & Accord <tr< th=""></tr<>
Math String Date Apprepation Conditional Axis Boolean Context XS, Template DB	2
	Jo Parameters
g Li Magong Rules () Terstall Rules () Local Variables () A Properties	Context Variables     Value Map

Figure 10.78: Add Div Sub-Function Node

- 5. Create a link from the output of the *Source* element to the first input of the *div* node.
- 6. Create a link from the output of *Constant* node to the second input of the *div* node.
- 7. Create a link from the output of the *div* function node to the *Target* element (see Figure 10.79).



ADEPTIA - Data Happer - customer	
20 gen guoss geo	
₩ 2 2 2 0	Current Element : SALARY
Carl Open Source Schema	Copen Target Schema
Succure of source XSD     Accord (S)     Acco	Stucture of destration_XSD A Root (ENS/ortp_TextSchema) B A Root A Root (HAME (strap) (N) A ADDRESS (strap) (N) A ADDRESS (strap) (N) ADDRESS (strap) (
Math String Date Aggregation Conditional Axis Boolean Context XSL Template DB	
	Parameters     Global Vanibles     Global Vanibles     Global Vanibles     Custom Methods     Contom Vanibles     Contom Vanibles     Contom Vanibles     Contom Vanibles     Global Methods     Global Methods     Value Map

Figure 10.79: Create Links between Nodes for Mapping Elements using Div Function

8. Click **Apply Mapping** () button. This maps elements using the *div* sub-function. A line is displayed between the source and target panels showing the mapping of the source element to the target element.

# **Using String Function**

The String mapping function enables you to map elements by manipulating strings. It comprises of various sub-functions, which are listed in the table below.

Mapping Function	Sub Functions	Description	Example
String	Concat	Concatenates the second string after the first string. This function accepts only two parameters in graphical mode. However, there is no limitation to the number of parameters in text mode.	concat <i>('Jane', 'Brown')</i> returns the string JaneBrown

Table 10.13 : Sub-Functions of String Mapping Function



	Substring	Returns the sub string from the string starting from the specified position and of the specified length. When using this function, you always start counting its position from 1. This implies that the second argument (position) is always greater than or equal to 1.	substring ('abcdef' ,3,4) returns cdef
	String	Returns the string value of the argument.	string ('1000') returns the string 1000
	Translate	Translates each occurrence of the first argument in the specified string to the second argument. Both the arguments must consist of one or equal number of characters.	translate <i>('alphabet', 'a','t')</i> returns tlphtbet
	Substring-after	Returns the string after the specified argument from the string.	substring-after ('print=yes', '=') returns yes
	Substring-before	Returns the string before the specified argument from the string.	substring-before ('print=yes', '=') returns print
	Starts-with	Returns true if the string starts with the specified argument or false otherwise.	starts-with <i>('Sales', 'S')</i> returns True
	String-length	Returns the length of the specified string.	string-length <i>('adeptia')</i> returns 7
	Contains	Returns true if the string contains the specified argument or false otherwise.	contains <i>('adeptia', 'tia')</i> returns True



Normalize-space	Removes leading and trailing white space (space, tab and new line) from a string, and replaces internal sequences of white space with a single space character.	normalize-space (' <i>Adeptia Inc '</i> ) returns Adeptia Inc
Name	Returns the name of the source node and field name on which mapping is currently done.	If the context node is an element named < <i>ms: schema</i> >, then name () will return ms: schema
Local-name	Returns name with the name prefix. If no prefix was specified, then name and local name are same.	If context node is an element named < <i>ms: schema</i> >, then local-name () will return schema

You can use the required sub-function of String mapping function to map elements. The process of using the String function is the same for all its sub-functions. Thus, the mapping process using one sub- function is outlined below.

## Steps to map elements using the 'Concat' String Mapping Function

- 1. Ensure that the <u>source and target schemas are loaded</u> and all their elements are listed under their respective nodes.
- 2. Ensure that the source and target elements to be mapped are selected and displayed in the Mapping Graph Area.



You need to load two source elements for using this mapping function.

3. Click **String** mapping function and select **Concat** sub-function. A *Concat* node is displayed in the Mapping Graph Area (see Figure 10.80).



Image: Construent Processing Construct Schema       Current Dement : NAME         Image: Construct of source, XS0       Image: Construct Schema         Image: Construct of source, XS0       Image: Construct of source, XS0         Image: Construct of source, XS0       Image: Construct of source, XS0         Image: Construct of source, XS0       Image: Construct of source, XS0         Image: Construct of source, XS0       Image: Construct of source, XS0         Image: Construct of source, XS0       Image: Construct of source, XS0         Image: Construct of source, XS0       Image: Construct of source, XS0         Image: Construct of source, XS0       Image: Construct of source, XS0         Image: Construct of source, XS0       Image: Construct XS0         Image: Construct of source, XS0       Image: Construct XS0         Image: Construct XS0       Image: Construct XS0         Image: Construct XS0       Image: Construct XS0      <	& ADEPTIA - Data Mapper - customer	X
Image: Contract Scheme       Image: Contract Scheme         Image: Structure, of, source, XSD       Image: Contract Scheme         Image: Structure, of, destructure, Structure, of, destructure, Structure, St	Ele Yew Actions Help	
Control (Source, SSD     Context Schema)     Structure, of Jource, SSD     Assot (ExaScropt, TractsChema)     Action (SaScropt, TractsChema)     ADDRESS (Sching)     O ADDRESS (		
Image: Structure, of Security TextSchema)         Image: Assoc (EvaScret_TextSchema)         Image: Assoc (EvaScret_EvaSchema)         Image:	💾 🛚 🗢 🤁 🔘	Current Element : NAME
Image: A Boot (Balacropt_TextSchema)         Image: Boot		
Math String Date Aggregation Conditional Axis Boolean Context XSLTemplate DB		ii → Root (EvaSkrote_TextSchema) iii → Record → 0.14ME (string) → 0.400ESS (string)
Math String Date Aggregation Conditional Axis Boolean Context XSLTemplate DB	×	
Context Vanables	Math String Date Aggregation Conditional Axis Boolean Context XSL Template DB	
		Color Varables     Color Varables     Color Varables     Color Varables     Color Varables     Color Varables     Context Varables     Order     Varables     Order     Ord

Figure 10.80: Add Concat Sub-Function Node

- 4. Create a link from the output of the first *Source* element to the first input of the *concat* node.
- 5. Create a link from the output of the second *Source* element to the second input of the *concat* node.
- 6. Create a link from the output of the *concat* node to input of the *target* element node (see Figure 10.81).




5. ADEPTIA - Data Happer - customer File: View: Actions: Help	
The view Actions hep	
H 8 0 2 0	Current Element : NAME
Carl Q Open Source Schema	Copen Target Schema
Structure, of, source, XSD     Source, X	Stucture_of_destron_XSO G ▲ Roc (Gastron_LessChema) M ▲ Rocod ● NAME (etmg) ● ADDEESS (strmg) ● PHONENO (resper) ● DATEOFBUTH (strmg) ● SALAY (resper) ● DATEOFDUTH (strmg) ● SALAY (resper) ● DESIGNATION (strmg) ● AGE (resper) ■ AGE (resper)
	Parameters
gg ↓ Magong Rules (③ Textual Rules ) @ Local Vanables ) @ Properties ] ↓ Manue. ↓	Parameters → Gibbal Varables B ← Cucil Varables B ← Cucil Varables B ← Cucil Varables B ← Cucil Varables D ← Consector Varables B ← Connector Info B ← Connector Info B ← Connector Info B ← Connector Info B ← Connector Info

Figure 10.81: Create Links between Nodes for Mapping Elements using Concat Function

7. Click **Apply Mapping** () button. This maps elements using the *concat* sub-function. A line is displayed between the source and target panels showing the mapping of the source element to the target element.

# **Using Date Function**

The Date mapping function enables you to map elements by generating dates in specific formats. It also returns the current date and the difference between two dates. It comprises of various sub-functions, which are listed in the table below.



Mapping Function	Sub Functions	Description	Example
Date	Date-Format	This is a customized mapping function. Changes the date from the input date format to specified output date format.	date-format ( <i>employee/ 1998-</i> <i>03-31, 'yyyy-mm-</i> <i>dd', 'dd-mm-yyyy'</i> ) returns 31-03- 1998



Date -Difference	Generates the difference between two dates in milliseconds. Supports all java date formats.	date- difference ('12-08- 2006', 'dd-mm- yyyy', '12-08- 2005', 'dd-mm- yyyy') returns 31536000000
Current Date	Returns the current system date in Month- day-year format. It accepts the argument according to standard Java arguments as defined for SimpleDateFormat class.	current date <i>('MM- dd-yyyy')</i> returns the current date in month- day-year format.

You can use the required sub-function of Date mapping function to map elements. The process of using the Date function is the same for all its sub-functions. Thus, the mapping process using one sub- function is outlined below.

## Steps to map elements using the 'Date-Difference' Date Mapping Function

- 1. Ensure that the <u>source and target schemas are loaded</u> and all their elements are listed under their respective nodes.
- Ensure that the source and target elements to be mapped are selected and displayed in the Mapping Graph Area.
- 3. You need to <u>add a constant value</u> for using this function. Once it is added, a *Constant* node with its value is displayed in Mapping Graph Area.

This function requires four inputs. The first input represents the value of *Date1*. The second input represents the value as the format of *Date1*. The third input represents the value as *Date2*. The fourth input represents the value as format of *Date2*. The *Date1* and *Date2* values can either be in the form of constants or XPath values. The formats of *Date1* and *Date2* are however always in the form of constants.

4. Click **Date** mapping function and select **Date-Difference** sub-function. A date-difference node is displayed in the Mapping Graph Area (see Figure 10.82).



& ADEPTIA - Data Happer - customer		×
Rie View Actions Help		
	at Element : DATEOFBIRTH	
QÎ Qpen Source Schema	Gil Qpen Target Schema	
Structure, of source, XSD     A Roar (BaSroct, Tustscheme)     A Roar (Integer)	Structure, of Jestimation, XSD Structure, of Jestimation, XSD A Record A Record A ADRESS (string) (M) A ADRES	×
😵 🔛 Mapping Rules 🔞 Textual Rules 🙋 Local Variables 👔 Properties	Parameters	
Image: State of the state o	Gobal Varables     Gustom Methods     Gobal     Gob	

Figure 10.82: Add Date-Difference Sub-Function Node

- 5. Create a link from the output of the first *constant* value to the first input of the *date-difference* node.
- 6. Create a link from the output of the second *constant* value to the second input of the *date-difference* node.
- 7. Create a link from the output of the third *constant* value to the third input of the *date-difference* node.
- 8. Create a link from the output of the fourth *constant* value to the fourth input of the *date-difference* node.
- 9. Create a link from the output of the *date-difference* node to input of the *target* element node (see Figure 10.83).



∑ Data Macoor	Element: DATEOFBIRTH   Structure_of_destination_XSD   A Root (EvaScryc_TextSchema)   A Record  A			
Copen Source Schema      Structure_of_source_XSD      A Root (E-NSCOPL_TextSchema)      ▲ Record (S)      AnANE (string) (M)      ADDEES5 (str	Great Control (Control (Contro) (Control (Contro) (Control (Contro) (Contro) (Contro) (Contro) (			
Structure_of_source_XSO	Structure_of_destination_XSD B ▲ Root (ExaStoreTextSchema) B ▲ Record ● 0444E (string) (4) ● 0400ESS (string) (M)			
	A Root (EvalScrpt_TextSchema)     B→ A Record     A Record     A Model     A A Model     A A A Model     A A A Model     A A Model     A A A Model     A A A Model     A A A Model     A A Model     A A A Model     A			
PRALID (String) (H)     POLIERIO (checke) (H)     OESPATINEIT (date)     OESPATINEIT (string)     OSSARA TIGOTI (string)     OESIGNATION (str	OHTEGHO (crteger) (M)     OATEGFBIRTH (date)     OEPARTMENT (strng)     OSLAAY (nteger)     OATEGFBIRTH (date)     OATEGFBIRTH (date)     OATEGFBIRTH (date)     OATEGFBIRTH (date)     OATEGFBIRTH (date)     OATEGFBIRTH (date)			
Math String Date Aggregation Conditional Axis Boolean Context XSLTemplate DB				
Image: Second Variables     Image: Second Variables				

Figure 10.83: Create Links between Nodes for Mapping Elements using Date-Difference Function

10. Click **Apply Mapping** ( ) button. This maps elements by generating the difference between *Date1* and *Date2* using the date-difference sub-function.

# **Using Aggregation Functions**

The Aggregation function enables you to map elements by aggregating or counting the values of all nodes in an element. It comprises of various sub-functions, which are listed in the table below.

Mapping Function	Sub Functions	Description	Example
Aggregation	Sum	Returns total of all values under all nodes of the specified element.	Sum <i>(Age)</i> returns the sum of all Age elements under the specified node.
	Count	Returns the total number of nodes for the specified element.	Count (Age) returns the total number of records under the Age element.

Table 10.15: Sub-Functions of Aggregation Mapping Function



Position	Returns the position of the current context node in the specified element.	<i>position()</i> returns 1 for the first node, 2 for second node and so on.
Кеу	Returns matched records using two parameters: Name of key to be used Fields to be matched	Refer to the section <u>Using</u> <u>Key Function</u> .

You can use the required sub-function of Aggregation mapping function to map elements. The process of using the Aggregation function is the same for all its sub-functions. Thus, the mapping process using one sub- function is outlined below.

## Steps to map elements using the 'Sum' Aggregation Mapping Function

- 1. Ensure that the <u>source and target schemas are loaded</u> and all their elements are listed under their respective nodes.
- 2. Ensure that the **source and target elements to be mapped are selected and displayed** in the Mapping Graph Area.
- 3. Click **Aggregation** function and select the **Sum** sub-function. A Sum node is displayed in the Mapping Graph Area (see Figure 10.84).



& ADEPTIA - Data Happer - customer	
Be yew Actors Hep	
H Q Q 2 0	Current Element : SALARY
Carl Open Source Schema	Gen Target Schema
Structure_of_source_XSD	Structure of destruction_XSD A Root (ExiStryC_TextSchema) B A Record O LANE (string) (M) O ARCESS (string) (M) O BEALLED (string) (M) O DATEOFERTH (date) O DATEOFERTH (string) O DATEOFERTH (string) O DATEOFICIES (string) O DESIGNATION (string) O AGE (nteger) O AGE (nteger)
Math String Date Aggregation Conditional Axis Boolean Context XSLTemplate DB	
g	Parateris     Goby Varbles     B - Context Varables     Context Var

Figure 10.84: Add Sum Sub-Function Node

- 4. Create a link from the output of the *Source* element to the input of the *Sum* node.
- 5. Create a link from the output of the *Sum* function node to the *Target* element (see Figure 10.85).



S. ADEPTIA - Data Happer - customer File View Actions Help	<u>_</u>
👔 Dota Mapper 🍵 XSL 🏟 Debugger	
H 🖸 🛛 🕀 🔍	Current Element : SALARY
Carl Qpen Source Schema	🔄 🖓 Open Target Schema
	Structure_of_destructon_XSD G & & Roote (F & A Second
Math String Date Aggregation Conditional Axis Boolean Context XSL Template DB	
gg ↓ Macoro Rules () Textual Rules () Local transities () Properties 1 SALARY	Source of the second seco

Figure 10.85: Create Links between Nodes for Mapping Elements using Sum Function

6. Click **Apply Mapping** (**S**) button. This maps elements using the Sum sub-function. A line is displayed between the source and target panels showing the mapping of the source element to the target element.

# **Using Conditional Function**

The Conditional mapping function enables you to map elements by building conditional expressions. It comprises of various sub-functions, which are listed in the table below.

Mapping Function	Sub Functions	Description	Example
Conditional	IF Conditions	This function comprises of two sub functions:	
	For Filtering Records	Filters the records/eleme nts on basis of the specified condition.	IFF CONDITION {#Age=25} Value= [100] Returns the filtered target node-set/node if the Age is 25 in the source record.

Table 10.16: Sub-Functions of Conditional Mapping Function



For Mapping To	Returns a	IF CONDITION {#Age=25}
Elements	value if the specified condition is true.	Returns 100 if the Age has the value of 25 in the source record.
When Condition	Returns a particular value if the specified condition is true, else it returns another value.	WHEN Condition {contains (Email_ID, '@')} Value= [100] Otherwise Value= [200] Returns 100 if the Email_ID contains @, else it returns 200.
Select Query	This is a customized mapping function. Returns the output based on the applied select query on a table in the any of the three databases (Oracle, Sql, IBM DB2). Select Query supports single field selection and returns first matching record.	SELECT FIELD = [Value1] FROM DB.TAB = [Value2].[Value3] WHERE {Condition} Here: Value1 = Field name in the table, whose value is to be retrieved Value 2 = Name of the Database Info object where the table exists. It contains database location and the user ID and password to connect to that database. Value 3 = Name of the table for which the select query is implemented Condition = Condition, based on which value is returned For example: SELECT FIELD = [EMPNO] FROM DB.TAB = [oracle_databaseserver].[EM P] WHERE {ENAME= 'Smith'} Returns Employee number of employee from the table EMP with the name Smith.



Sequence	This is a customized mapping function. Returns integer values starting from the first argument and incrementing it by the second argument for each record. Both the arguments must be integer constants.	Sequence {10, 20} Returns 10, 30, 50and so on. You can also use multiple where condition. Incase of multiple where condition each condition must be within square braces as shown in the example below: SELECT FIELD = [EMPNO] FROM DB. TAB = [oracle_databaseserver]. [EM P] WHERE {[ENAME= 'Smith'] AND [AGE = 28]}
Append	This is a customized mapping function.	Append ('IF CONDITION {condition} Value [Value1]', ('IF CONDITION {condition} Value [Value2]'
	Appends the second string after the first string. Used to append only IF Condition.	Returns IF CONDITION {condition} Value [Value1] Value [Value2]

Some conditional sub-functions are not included in the Data Mapper screen, but are implemented by extending the 'IF' and 'When' conditions declared in Table 13.14 These sub-functions are listed in Table 13.15.

Table 10.17:	Conditional	Functions	('lf'	and	'When')
--------------	-------------	-----------	-------	-----	---------

Sub Function	Custom Function	Description	Example
IF Condition	Nested IF	Contains IF condition inside the value of previous IF condition. Returns output when all IF conditions are satisfied. For example: IF CONDITION {condition1} VALUE=[IF CONDITION {condition2} VALUE=[IF	IF CONDITION {#Age=25} Value= [IF CONDITION {#Designation= 'Manager'} Value = IF CONDITION {#Salary= 20000} Value = [100]]] Returns 100 if all conditions are satisfied such that a manager of age 25 has a salary of



		CONDITION	20000
		CONDITION {condition3} VALUE=[Value1]]] Returns Value1 when all IF conditions are satisfied.	20000.
When Condition	Nested When	Contains When condition inside the value of previous When condition. Returns varied output based on the When conditions being satisfied. For example: WHEN CONDITION {condition1} VALUE=[WHEN CONDITION {condition2} {VALUE=[value1'] OTHERWISE VALUE=['value2']] OTHERWISE VALUE=['value2']] OTHERWISE VALUE=['value3'] Returns Value1 when both When conditions are satisfied. Returns Value3 when the first When condition fails. Returns Value2 when the first When condition is satisfied, but the second one fails.	WHEN CONDITION {/employees/employee/ Age=25} Value= [WHEN CONDITION {/employees/employee/ Designation= 'Manager'} Value = ['100'] OTHERWISE Value = ['200'] OTHERWISE Value = ['300']] Returns 100 if both conditions are satisfied such that the employee is a manager of age 25. It returns 300 if the employee is a manager but not of 25 years of age. It returns 200 if the employee is 25 years of age, but is not a manager.
IF and When Condition		Returns value based on the function used as whether the condition returns True or False. If a string or source element contains a character or group of characters, then True is returned, else False is returned. Based on the return value of the condition, the output value is generated. For example:	WHEN CONDITION {contains (var1, str)} Value= ['100'] OTHERWISE Value = ['200'] Returns true if Var1 contains Str, else it returns False. If the condition returns true, then this function returns 100, else it returns 200.



		WHEN CONDITION {contains (var1, str)} VALUE=[var2] OTHERWISE VALUE=[var3] If var1 contains str, then True is returned, else False is returned. If the condition returns True, then var2 is generated as output, else var1 is the output value.	
IF and When Condition	Mixed condition	Contains IF condition inside the value part of When condition or vice versa. Returns varied output based on the conditions being satisfied. For example: WHEN CONDITION {condition1} VALUE=[IF CONDITION {condition2} VALUE=['value1']] OTHERWISE VALUE=['value2'] Returns Value1 when both conditions are satisfied. Returns Value2 when the first condition fails. Returns no output when the first condition is satisfied but second condition fails or when both conditions fail.	WHEN CONDITION {/employees/employee/ Salary=50000} Value= IF CONDITION {/employees/employee/ Designation= Project Manager} Value = ['100'] OTHERWISE Value = ['200'] Returns 100 if the employee is a Project Manager and has a salary of 50000. It returns 200 if the employee is a Project Manager but does not have a salary of 50000.
IF Condition	Multiple IF	Contains IF conditions placed sequentially, with each IF having its value part. Two IF conditions are appended using Append sub-function of the String Function. Returns varied output	IF CONDITION {#Age=25} Value= ['500'] IF CONDITION {#Designation= 'Manager'} Value = [1000] Returns 500 if employee is of age 25. It returns



		based on the condition being satisfied. For Example: IFCONDITION {condition1} VALUE=['value1'] IF CONDITION {condition2} VALUE=['value2'] Returns Value1 if condition1 is satisfied. Returns Value2 if condition2 is satisfied.	1000 if employee is a Manager.
When Condition		Contains When condition containing logical operators like and/not to make multiple conditions inside the When condition. There are many permutations/combina tions for this sub- function. Example 1: WHEN CONDITION (cond1 and cond2) Value = ['value1'] otherwise value = ['value2'] Returns Value1 if both conditions are satisfied, else returns Value2. Example 2: WHEN CONDITION (cond1 or cond2) Value = ['value1'] otherwise value = ['value2'] Returns Value1 when either one or both conditions are satisfied, else returns Value2.	WHEN CONDITION {/employees/employee/ Age=25 and /employees/employee/D esignation=Manager} Value= ['100'] OTHERWISE Value = ['200'] Returns 100 if both conditions are satisfied such that the employee is a manager of age 25. Else it returns 200.
IF Condition	IF condition with more than one conditions in it.		IF CONDITION {/employees/employee/ Age=25 and /employees/employee/D esignation=Manager} Value= ['100']



There are many permutations/combina tions for this sub- function. Example 1: IF CONDITION (cond1	Returns 100 if both conditions are satisfied such that the employee is a manager of age 25. Else it returns 200.
and cond2) Value = [] Returns Value1 when both conditions are satisfied, else no output is returned. Example 2:	
IF CONDITION (cond1 or cond2) Value = []	
Returns Value1 when either one or both conditions are satisfied, else no output is returned.	

You can use the required sub-function of Conditional mapping function to map elements. The process of using the Conditional function is the same for all its sub-functions. Thus, the mapping process using one sub- function is outlined below.

# Steps to map elements using the 'IF' Condition (IF CONDITION {} VALUE=[]) Conditional Mapping Function

- 1. Ensure that the <u>source and target schemas are loaded</u> and all their elements are listed under their respective nodes.
- 2. Ensure that the **source and target elements to be mapped are selected and displayed** in the Mapping Graph Area.
- 3. Click **Boolean** function menu and then select the **>=Greater than Equal** operator. A **>=** node is displayed in the Mapping Graph Area (see Figure 10.86).



ADEPTIA - Data Happer - customer	
Be yew Actors Hep	
	Current Element : SALARY
City Open Source Schema	Open Target Schema
Structure_of_source_XSD Shalloot (Eradionet_TextSchema) Shalloot (Eradionet_TextSchema) Shalloot (String) (H) → BHALBJ (String) (H) → BHALBJ (String) (H) → BHALBJ (String) (H) → DATEOFBIRH (date) → DATEOFBIRH (date) → DATEOFBIRH (date) → DATEOFBIRH (date) → AGE (Integer) → AGE (Integer)	Structure_of_destination_XSD is A Root (Residence_TestSchema) is A Root A Root (Residence_TestSchema) A Root (Residence_TestSchema) A Root (Residence) A Root (R
Image: Second Prufer     Image: Second Prufer       Image: Second Prufer     Ima	Pananetes

Figure 10.86: Add Greater Than or Equal To Boolean Function Node

8	То	learn	more	about	Boolean	Functions,	refer	to	the	section	<u>Using</u>
Ø	<u>Bo</u>	olean	Func	<u>tions.</u>							

- 4. Add a constant value in the Mapping Graph Area.
- 5. Create a link from the output of the *source* element to the first input of the >= operator node.
- 6. Create a link from the output of the *Constant* node to the second input of the >= operator node (see Figure 10.87).



s. ADEPTIA - Data Happer - customer File View Actions Help	<u></u>
👔 Data Mapper 🔄 XSL 🚱 Debugger	
💾 🖸 🗢 🤁 🛛	Current Element : SALARY
Copen Source Schema	Ca 🖓 Open Target Schema
▲ Structure, of source, XSD	Structure_of_destruton_XSD i a_ Root (FeakStoret_TextSchema) ii a_ Rootd
Math String Date Aggregation Conditional Axis Boolean Context XSL Template DB	
Image: Specific and Specifi	A farmetes     Gola Variables     Gola Variabl

Figure 10.87: Create Links between Nodes for Mapping Elements using Greater Than Equal To Function

7. Click **Conditional** mapping function and select **IF CONDITION** sub-function. Further select For Mapping to Elements option. An *IF CONDITION* node is displayed in the Mapping Graph Area (see Figure 10.88).



& ADEPTIA - Data Happer - customer	
Pile View Actions Help Tota Mapper ( XX) ( Debugger	
H 8 0 2 0	Current Element : SALARY
Carl Open Source Schema	🔄 û Open Target Schema
Sourcura of source, XSD     Assot (EvaScrot, TextSchema)     Ansot (EvaScrot, TextSchema)     Ansot (EvaScrot, TextSchema)     Ansot (EvaScrot, 1)     Ansot (EvaScrot,	Structure_of_destnation_XSD B & Root (EvaScret_TextSchema) B & Record
	Jo Parameters
Norma Rules     (1) Textual Rules     (2) Cool Vanidies       1     SãA ANV	Gibal Variables     Gibal Variables     Gustom Herbods     Concerton Info     Gibal Methods     Gobal     Gobal     Gobal Methods     Gobal     Gobal Methods     Value Map

Figure 10.88: Add IF Conditional Function Node

- 8. Create a link from the output of the >= operator element to the first input of the *IF CONDITION* node.
- 9. Add a constant value of integer type (for example, 25) in the Mapping Graph Area.
- 10. Create a link from the output of the *Constant* element to the second input of the *IF CONDITION* node.
- 11. Create a link from the output of the *IF CONDITION* node to the input of the *target* element node (see Figure 10.89).




k, ADEPTIA - Data Happer - customer Fle Vew Actions Hep		<u>_8</u> >
	Current Element : SALARY	
N2 Open Source Schema	Copen Target Schema	
Structure_of_source_XSO ⇒ Aloo: (EvaScrot_TextSchema) ⇒ Aloo: (EvaScrot_TextSchema) ⇒ Aloo: (Strong) (M) → PARLED (Strong) (M) → PARLED (Strong) (M) → PARTHEIT (Strong) → DATEOFBRITH (Strong) → SALARY (Integer) → DATEOFDINIES (dtreng) → AGE (Integer)	Structure_of_destination_XSD G ▲ Root (EvaScrop_TextSchema) B ▲ Record → 040AE(strop) (M) → 040AE(strop) (M) → 040AE(strop) (M) → 040AE(strop) (M) → 040AE(strop) (M) → 040AE(strop) → 040AE(strop)	
Math String Date Aggregation Conditional Axis Boolean Context XSL Template DB		
Image: product ()     Image: product ()     Image: product ()       Image: product ()     Image: product ()     Image: product ()       Image: product ()     Image: product ()     Image: product ()       Image: product ()     Image: product ()     Image: product ()       Image: product ()     Image: product ()     Image: product ()       Image: product ()     Image: product ()     Image: product ()       Image: product ()     Image: product ()     Image: product ()       Image: product ()     Image: product ()     Image: product ()       Image: product ()     Image: product ()     Image: product ()       Image: product ()     Image: product ()     Image: product ()       Image: product ()     Image: product ()     Image: product ()       Image: product ()     Image: product ()     Image: product ()       Image: product ()     Image: product ()     Image: product ()       Image: product ()     Image: product ()     Image: product ()       Image: product ()     Image: product ()     Image: product ()       Image: product ()     Image: product ()     Image: product ()       Image: product ()     Image: product ()     Image: product ()       Image: product ()     Image: product ()     Image: product ()       Image: product ()     Image: product ()     Image: product ()	Aligned as a second secon	

Figure 10.89: Creating Links between Nodes for Mapping Elements using IF Conditional Function

If the value of *SALARY* element in the source data is greater than or equal to 5000, output will be 3000. If the value of *TESTCASENO* element in the source data is less than 100, output will be an empty tag.

12. Click **Apply Mapping** (**S**) button. This maps elements using IF CONDITION function. A line is displayed between source and target panels showing the mapping of the source element to the target element.



# **Using Axis Function**

The Axis function contains a list of advance XSL functions that are used to map elements only when the For Each function is applied on the Target node. It comprises of various sub-functions, which are listed in the table below.

Table 10.18:	Sub-Functions	of Axis	Mapping	Function
--------------	---------------	---------	---------	----------

Mapping Sub Function Functions	Description	Example
-----------------------------------	-------------	---------



Axis	File Path – XPath	This is a customized mapping function. This is an XML Lookup which returns the value of the element/attribute within the XML file whose path is specified. The File path and XPath must be specified in single quotes.	FilePath ['C:/correct_file.xml'] XPath {'/employees/employee/Na me'} Returns value of Name element from the file correct_file.xml.
	Self	Returns the element which is the context node itself.	Self::Employee Returns Employee which is the context node itself.
	Child	Returns the element which is the child of the context node.	Self::Name Returns Name which is a child of the context node.
	Parent	Returns the element, which is the parent (if any) of the context node.	Parent::Name Returns Name which is a parent of the context node.
	Following- sibling	This axis contains all the following siblings of the context node. It returns the first occurrence of the element/attribute in the next sibling of the context node. If the context node is an attribute node or namespace node, then this axis is empty.	following-sibling: employee/Name Returns the first occurrence of Name in the next employee node.
	Ancestor	Returns the element which is the ancestor of the context node. This axis always includes the root node, unless the context node is the root node.	Parent::Name Returns Name which is an ancestor of the context node.



	Ancestor-or- self	This axis contains the context node and the ancestors of the context node. It always includes the root node. It returns the context node or ancestors of the context node.	ancestor-or- self::employees/@val Returns context node or ancestors of context node.
	Preceding- sibling	This axis contains all the preceding siblings of the context node. It returns the first occurrence of the element/attribute in the preceding sibling of the context node. If the context node is an attribute node or namespace node, then this axis is empty.	preceding-sibling: employee/Name Returns the first occurrence of Name in the previous employee node.
	Descendant	Returns the element which is the descendant of the context node. This axis does not contain attribute nodes.	descendant::Name Returns Name, which is a descendant of the context node.
	Descendant- or-self	This axis contains the context node and the descendants of the context node. It returns the context node or descendants of the context node.	descendant-or- self::employees/salary Returns context node or descendants of context node.
	Generate-id	Generates a unique id for the element/attribute specified by the XPath argument.	<i>generate-id (employees/employee/Name )</i> Returns unique ID for Name element
	Current	Removes all tags from the specified xml file and returns the data.	<i>current()</i> Returns data of the xml file without tags.

You can use the required sub-function of Axis mapping function to map elements. The process of using the Axis function is the same for all its sub-functions.



# Using Boolean Function

The Boolean mapping function enables you to map elements by applying various logical operators in building Boolean expressions. It comprises of various sub-functions, which are listed in the table below.

Mapping Function		Description	Example
Boolean	Equal	Returns TRUE the first variable argument is equal to the second variable argument.	<i>(5) = (5)</i> returns true
	Not Equal	Returns TRUE the first variable argument is not equal to the second variable argument.	<i>(5) != (50)</i> returns true
	Greater Than	Returns TRUE the first variable argument is greater than the second variable argument.	<i>(5)&gt; (3)</i> returns true
	Less Than	Returns TRUE the first variable argument is less than the second variable argument.	<i>(5) &lt; (8)</i> returns true
	Greater than Equal	Returns TRUE the first variable argument is greater than or equal to the second variable argument.	(5)>= (5) returns true (5)>= (3) returns true
	Less than Equal	Returns TRUE the first variable argument is less than or equal to the second variable argument.	(5) <= (8) returns true (5) <= (5) returns true

Table 10.19: Sub-Functions of Boolean Mapping Function



Or	Returns TRUE if either of the two variable arguments evaluate to TRUE otherwise FALSE. These variable arguments can only be of Boolean data type. Hence, their value can either be TRUE or FALSE only.	<i>(True) Or (True)</i> returns true <i>(True) Or (False)</i> returns true
And	Returns TRUE if both of the two variable arguments evaluate to TRUE otherwise FALSE. These variable arguments can only be of Boolean data type. Hence, their value can either be TRUE or FALSE only.	<i>(True) And (True)</i> returns true <i>(True) And (False)</i> returns false

A Boolean sub-function is always used in conjunction with a Conditional function. Thus for the process of using the Boolean function, refer to <u>Steps to map elements using the IF</u> <u>Conditional Mapping Function.</u>

# Using Context Functions

The Context mapping function enables you to map elements by setting or getting value of process flow context variables. It comprises of various sub-functions, which are listed in the table below.

Table 10 20.	Sub Eunstians	of Contout	Mapping Function
	SUD-FULCTIONS		

Mapping Function	Sub Functions	Description	Example
---------------------	------------------	-------------	---------



Context	Set-Context	This is a customized mapping function. Sets the value of the specified variable argument in the process flow context. This value can be string constant, numeric constant, XPath or output of limited set of mapping function, which can be used before set-context function. This function does not return a value. If mapped to a target element, it creates an empty tag of that target	set-context ('index', '123') sets the value of index variable as 123 in the process flow.
	Get-Context	element in output XML. This is a customized mapping function. Returns the value of the specified variable argument from process flow Context. This value can be string constant, numeric constant, XPath or output of limited set of mapping function. If no value has been set, then the value specified in the second argument is returned.	get-context ('index', '100') Returns the value of index variable from the process flow. If no value has been set for index, then 100 is returned. In get-context function you can also use any variable, which is not declared. In such case get-context creates a variable with the specified name and value, which can be further used with the selected target element. This can be done only in Textual Rule panel.

You can use the Set-Context sub-function of Context mapping function to set value of the process flow variable and send it to the Process Designer. The Get-Context sub-function is used to return the value of the process flow variable.

# Using Set-Context Function

You can use the Set-Context Function in various ways. These are outlined as:

- Mapping Set-Context function using local variable
- Global declaration of Set-Context function



Mapping Set-Context function to any target element

#### Mapping Set-Context function using local variable

#### Concept

You can map the Set-Context function to a local variable, when you want to set the value of process flow context variable based on output of a mapping function or condition. You can pass the output of mapping function or condition to a local variable and use that local variable as value of set-context function.

For example, if you want to set the value of process flow context variable based on the output of WHEN condition. The WHEN condition is used to return "True" when value of a source element "SALARY" is greater than 8000, else it will return "False". The output of WHEN condition is mapped to a local variable "*BolSalary8K*". To set the value of "BolSalary8K" to the process flow context variable, you can use Set-Context function. You have to create another local variable "*Var1*", where value of process flow context variable "*ContextVar*" is set using Set-Context function. This is done by mapping Set-Context to the value part of the local variable "*Var1*". The first argument of the Set-Context function is the name of the process flow context variable "*ContextVar*" and second argument is the local variable "*BolSalary8K*", which contains the output of WHEN condition.

#### Advantages

- Need not be mapped to a target element
- Local variable can be used as second argument of Set-Context function
- XPath of a source element can be used as second argument of Set-Context function
- Set-Context function is executed for each record of the source data

#### Disadvantages

• Local Variable used to map set-context function will have an empty value.

#### Map Set-Context Function using Local Variable

#### Steps to pass output of mapping function or condition to a local variable

- 1. Ensure that the **source and target schemas are loaded** and all their elements are listed under their respective nodes.
- 2. Click **Node** tab displayed in the Mapping Graph Area. All tabs of the Node tab are displayed.
- 3. Click Local Variables tab. The Local Variable pane is displayed. (refer to Figure 10.115).
- 4. Click any *target* element to declare the local variable in the Local Variable pane.
- Click Local Variable Name text field and enter the name of the local variable you want to create (e.g. BolSalary8K). Press the Tab or Enter key. This takes the control to the Local Variable Value field.



6. Enter the value of the local variable in the *Local Variable* Value field. In this example, you have to specify the WHEN condition as displayed in Figure 10.90.

🕽 Data Mapper 🔄 XSL 🤷 Debugge						
💾 🖸 🥥 🤁 🕘 📃		Current	Element : SALARY			
	데국 Open Source Schema			🖁 🖓 Open 1	Target Schema	
Structure_of_source_XSD i= A Root_Readsrow_Textschem ()= A Root_Readsrow_Textschem ()= A Root_Readsrow_Textschem ()= A ROOTESS (strup) - B RATELD (strup) - B DATEOFBIRH (date - D DEATRIEHT (strup) - B DATEOFBIRH (date - D DEATRIEHT (strup) - D DATEOFBIRH (date - D DEATRIEHT (strup) - D DATEOFBIRH (date - D DEATRIEHT (strup) - D DATEOFDIATEN (date - D DEATRIEHT (strup) - D AGE (nteger)	, ) x)		Structure_of_destruction_XSD G= & Roce = & Roce = & Roce = & ADRESS_(screg) = & ADRESS_(screg) = & FANILID_(screg) = & FANILID_(screg) = & DATEOFORITH_(screg) = & SALARY (retoper) = & SALARY (retoper) = & SALARY (retoper) = & ACE (nteger)			
	tional Axis Boolean Context XSLTemplate DB					
Mapping Rules 🕥 Textual Rules	🕐 Local Variables 🚺 Properties			1	Parameters     Global Variables	
Image: A state of the state	Local Variable Value		Add Comment	32	🕀 🍛 Local Variables	
O Loo I Variable Name Bol Salary BK	VAED CONDITION(SInput_EvalScript_TextSchema/Root/Record/S ALARY+6000) VALUE-("INCE") OINERWISE VALUE-("FALSE")			×		

Figure 10.90: Create Local Variable

7. Click **Save Local Variable** (<sup>111</sup>) button to save the declared local variable.

## Steps to map Set-Context function using local variable

- 1. Ensure that the **source and target schemas are loaded** and all their elements are listed under their respective nodes.
- 2. Click **Node** tab displayed in the Mapping Graph Area. All tabs of the Node tab are displayed.
- 3. Click Local Variables tab. The Local Variable pane is displayed. (refer to Figure 10.115).
- 4. Click any *target* element to declare the local variable in the Local Variable pane.
- 5. Click *Local Variable Name* text field and enter the name of the local variable you want to create (e.g. Var1). Press the **Tab** or **Enter** key. This takes the control to the *Local Variable Value* field.
- 6. Click **Context** mapping function menu and select **Set-Context** sub-function. Syntax for Set-Context function is displayed in *Local Variable Value* field.
- 7. Enter the process flow variable name you want to create (e.g. *ContextVar*) in the first argument of the *Set-Context* function.
- 8. Enter the value of the variable in the second argument of the *Set-Context* function (see Figure 10.91).



Second argument can be string constant, integer constant, XPath, local variable or output of limited set of mapping function, which can be used before Set-Context function. In this example, *BolSalary8K* variable is used as second argument of set-context function.




Figure 10.91: Mapping Set-Context to Local Variable

9. Click **Save Local Variable** (<sup>111</sup>) button to save the declared local variable.

## **Global Declaration of Set-Context Function**

## Concept

Another way of using the Set-Context function is to declare it globally. When doing this, you need not map it to a target element or local variable.

## Advantages

- Easy to use
- Need not be mapped to a target element
- Need not create any local variable

## Disadvantages

Local variable cannot be used in value part of Set-Context function



 If XPath of a source path is used, Set-Context function is executed for the first record only.

#### Declare Set-Context Function Globally

#### Steps to declare Set-Context function globally

- 1. Ensure that the **source and target schemas are loaded** and all their elements are listed under their respective nodes.
- 2. Click **Global** tab displayed in the Mapping Graph Area. All tabs of the Global tab are displayed.
- 3. Click **Context Variables** tab. The Context Variables pane is displayed (see Figure 10.92).




Figure 10.92: Context Variables Pane

- 4. Click *Context Variable Name* text field and enter the name of process flow context variable you want to create (e.g. *Var1*) Press the **Tab** or **Enter** key. This takes the control to the *Context Variable Value* field.
- 5. Enter the value of process flow context variable in *Context Variable Value* field (see Figure 10.93).



ADEPTIA - Data Happer - customer  File View Actions Help	X
👔 Data Mapper 🔄 XSL 🥝 Debugger	
H 🛛 🗢 😌 🛛	Current Element : NAME
Carl Open Source Schema	🔄 🖓 Open Target Schema
Structure of source XSD A Root (Eascing, TextSchema) A Root (S) INAME (simp) INAME (simp) B RABLD (simp) B RABLD (simp) D ATEOFERTH (date) D ATEOFERTH (simp) SALARY (resper) D ATEOFERTH (simp) B ALAD (resper) D AED CESSIOLATION (simp) AGE (nteger) Marm String Date Appropriate Conditional Avis Boolean Context XSL Template DB	Structure of, destruction, XSD G ▲ Asoc (FenSorop, TextSchema) B ▲ Record → HAHE (etrop) → AORESS (schma) → BHAILID (schma) → BHAILID (schma) → DEFARTHERIT (schma) → DEFARTHERIT (schma) → DEFARTHERIT (schma) → DESIGNATION (schma) → AGE (integer)
Image: Second Verside:     Context Versides     Context Versides       Image: Second Verside:     Context Versides     Context Versides       Image: Second Verside:     Variant     100	Separates       Sobie Value       Sobie Value

Figure 10.93: Enter Context Variable Value

- 6. Click the **Save Context Variable** () button to save the declared process flow context variable. This context variable is added to the list of existing context variables in the Context Variables tab. It is also displayed under Context Variables in the Parameters Panel. If you shift focus to another node, or click any of the Mapping Rules, Textual Rules, Node, Properties, *XSL* or *Debugger* tabs, without saving the context variable, an alert message is displayed (refer to Figure 10.110).
- 7. Click **No** to save the context variable and shift focus to the other object. If you click **Yes**, then the defined context variable is cleared and the focus is shifted to the other object.

Ø	You can also set the value of a context variable that is used in a particular condition. For example, if the context variable <i>Var1</i> is used in an IFF condition in such a way the value of Var1 depends on the condition being True or False. If it is True then <i>Var1</i> will have a different value. You can set this value of Var1 if the condition is True, using the Set Context function. Similarly, you can retrieve the value of a context variable used in a
	particular condition, if the condition is True.



## Mapping Set-Context function to any target element



# Concept

You can map the Set-Context function to a target element. Since this function does not return a value, it will create an empty tag of that target element in output XML. Thus, it is recommended that you should map the Set-Context function to a target element, whose value is not required at the target end.

#### Advantages

- Need not to create any local variable
- Executed for each record

#### Disadvantages

• Need an additional target element, whose value is not required at the target end

#### Map Set-Context Function to a Target Element

#### Steps to map Set-Context function to a target element

- 1. Ensure that the <u>source and target schemas are loaded</u> and all their elements are listed under their respective nodes.
- 2. Select the target element that you want to map with Set-Context function.
- 3. Click **Context** mapping function menu and select **Set-Context** sub-function. A set-context node is displayed in the Mapping Graph Area (see Figure 10.94).



4. ADEPTIA - Data Happer - customer			
File View Actions Help			
👔 Data Mapper y XSL 🤬 Debugger			
💾 😫 🗢 🧬 🔲 Current Element : SALARY			
Surce Schema	Copen Target Schema		
Structure_of_source_XSD ⊖ Ansor(EvaScore_TextSchema) ⇒ Alsec(viring) → ALANE (viring) → EVALED (viring) → EVALED (viring) → EVALED (viring) → DATEOFERTHI (date) → DATEOFERTHI (viring) → SALARY (viringer) → DATEOFERTHI → OESIGNATION (scring) → AGE (nteger)	Structure_of_destructor_XSD         Image: Consistent_TextSchema)         Image: Consistent_TextSchema)         Image: Constant_TextSchema)		
Math String Date Aggregation Conditional Axis Boolean Context XSL Template DB			
Image: Second Rules     Image: Textual Rules     Image: Textual Rules     Image: Textual Rules       Image: Textual Rules     Image: Textual Rules     Image: Textual Rules     Image: Textual Rules       Image: Textual Rules     Image: Textual Rules     Image: Textual Rules     Image: Textual Rules       Image: Textual Rules     Image: Textual Rules     Image: Textual Rules     Image: Textual Rules       Image: Textual Rules     Image: Textual Rules     Image: Textual Rules     Image: Textual Rules       Image: Textual Rules     Image: Textual Rules     Image: Textual Rules     Image: Textual Rules       Image: Textual Rules     Image: Textual Rules     Image: Textual Rules     Image: Textual Rules       Image: Textual Rules     Image: Textual Rules     Image: Textual Rules     Image: Textual Rules       Image: Textual Rules     Image: Textual Rules     Image: Textual Rules     Image: Textual Rules       Image: Textual Rules     Image: Textual Rules     Image: Textual Rules     Image: Textual Rules       Image: Textual Rules     Image: Textual Rules     Image: Textual Rules     Image: Textual Rules       Image: Textual Rules     Image: Textual Rules     Image: Textual Rules     Image: Textual Rules       Image: Textual Rules     Image: Textual Rules     Image: Textual Rules     Image: Textual Rules       Image: Textual Rules     Image: Textual Rules <td< td=""><td>Parameters     Parameters     Post set     Post set</td></td<>	Parameters     Parameters     Post set     Post set		

Figure 10.94: Set-Context Node

- 4. <u>Add a constant node</u> with the name of variable (e.g. *index*), whose value is to be set in the process flow context.
- 5. Create a link from the output of the *constant* node (*index*) to the first input of the *set*-*context* node.
- 6. <u>Add another constant node</u> for the second argument (e.g. 100) of the *set-context* function.



Second argument can be string constant, integer constant, XPath, local variable or output of limited set of mapping function, which can be used before Set-Context function.


- 7. Create a link from the output of second *constant* node (*100*) to the second input of the *set*-*context* node.
- 8. Create a link from the output of the *set-context* node to the *target* element (see Figure 10.95).



ADEPTIA - Data Happer - customer  File View Actions Help	_[6] ×
File View Actions Help	
H 8 0 2 0	Current Element : SALARY
Copen Source Schema	Carl Q Open Target Schema
Interface         Status         Sta	Structure_of_destructor_XSD G* Root (celastore_TextScherma) B* & Record • 0.400Et55 (struc) • 0.400Et55 (struc) • 0.90HAED((retager) • 0.90HAED((retager)) • 0.90HAED((retager) • 0.90HAED((retager)) • 0.90HAED((retager) • 0.90HAED((retager)) • 0.90HAED((reta
Math String Date Aggregation Conditional Axis Boolean Context XSL Template DB	Parameters
gg ↓ Magong Rules () Textual Rules () Local Vanables () Is. Properties ) 1 Since + 1 Since +	A cast virables      Context Virables      Context Virables      A seasoriarities      A context virables      O contextv

Figure 10.95: Create Links between Nodes for Mapping Set-Context Function to Target Element

- 9. Click **Apply Mapping** (**V**) button. This maps the Set-Context function to the target element. The defined variable (*index*) is passed to the process flow with the value 100. If you shift focus to another node, or click any of the *Mapping Rules, Textual Rules, Node, Properties, XSL* or *Debugger* tabs, without applying the mapping, an alert message is displayed (refer to Figure 10.110).
- 10. Click **No** to apply the mapping and shift focus to the other object. If you click **Yes**, then the mapping activity is cleared and is replaced by the previous mapping in the Mapping Graph Area and the focus is shifted to the other object.



# Using DB Function

The DB function enables you to get data from the database, based on a condition. It comprises of a sub-function, which is listed in the table below.



Mapping Function	Sub Functions	Description	Example
DB	DBQuery	Returns data from the database, based on a query.	DBQuery( 'select EmpID from EMP where EMPID=1035', var1, 'true') returns all the records from the EMP table, where EMPID is 1035. Here, 'var1' is the Connection Info variable. If you change the last boolean argument from true to false, only the first record is returned.

Table 10.21: 5	Sub-Function of I	DB Mapping	Function
----------------	-------------------	------------	----------

You can use this sub-function of DB mapping function to get data from the database. The process of using this sub-function is outlined below.

## Steps to get data from the database using the 'DBQuery' DB Mapping Function

- 1. Ensure that the <u>source and target schemas are loaded</u> and all their elements are listed under their respective nodes.
- 2. Ensure that a *Connection Info* variable is created for the DBQuery and is listed in the Parameters Panel.



For details on creating a Connection Info variable, refer to the **Declaring Connection Info Variable** section.

- 3. Double-click the target element that you want to map with the DBQuery. It is displayed in the Mapping Graph Area.
- 4. Click **DB** function and select the **DBQuery** sub-function. A DBQuery node is displayed in the Mapping Graph Area (see Figure 10.96).



Figure 10.96: Add DBQuery Sub-Function Node

- 5. <u>Add a constant node</u> with the query for searching data from the database based on the specified condition (e.g. *select Name from EMP where designation= 'Manager'*).
- 6. Create a link from the output of the *constant* node to the first input of the *DBQuery* node.
- 7. Double-click the required *Connection Info* variable under Connection Info in the Parameters Panel. The selected Connection Info variable node is displayed in the Mapping Graph Area (see Figure 10.97).



4. ADEPTIA - Data Mapper - customer	
Ple Vew Actions Help	
Tota Mapper 🔄 XSL 🚱 Debugger	
💾 😫 🗢 🤁 🕒	Current Element : NAME
Qpen Source Schema	Copen Target Schema
Structure_of_source_XSD     Asot (EvaScherma)     Asot (EvaS	Structure_of_destruction_XSD ⇒ A coord = A RAORE =
Math String Date Aggregation Conditional Axis Boolean Context XSL Template DB	
Records Rules () Textual Rules () Local Variables () In Properties )	

Figure 10.97: Connection Info Variable in Mapping Graph Area


- 8. Create a link from the output of the *Connection Info* variable to the second input of the *DBQuery* node.
- 9. <u>Add another constant node</u> for the third argument of the *DBQuery* function. This is a Boolean value as True or False.
- 10. Create a link from the output of this *constant* node to the third input of the *DBQuery* node.
- 11. Create a link from the output of the *DBQuery* node to the input of the *target* element (see Figure 10.98).



S. ADEPTIA - Data Happer - customer	
👔 Data Mapper 🔄 XSL 🍓 Debugger	
💾 🖸 🥥 🤤 🛛	Current Element : NAME
Copen Source Schema	🔄 🗘 Open Target Schema
Studene, of, source, XSO I studene, of, source, XSO I A Record (5) I ARE (Instructure) I ARABLE (string) I	Structure of estimation_XSD → Record → NAME (string) → ADORES (string) → BADORES (string) → BANAILD (string) → BANAILD (string) → DATEOFORINT (string) → DATEOFORINT (string) → DATEOFORINT (string) → DATEOFORINT (string) → DATEOFORINT (string) → AGE (integer)
Math String Date Aggregation Conditional Axis Bioolean Context XSL Template DB	
gg W Mapping Rules () Textual Rules () Local Vanables () A Properties 1 Statest	Carlos Vanables Se Local Vanables

Figure 10.98: Create Links between Nodes for Mapping DBQuery Function to Target Element

- 12. Click **Apply Mapping** (**S**) button. This maps the DBQuery function to the target element. The defined query is passed to the database where a connection is created using the Connection Info variable. If the Boolean value is set as 'True' then the database fetches all the values that match the query. If the value is 'False', then the database fetches only the first matching value. If you shift focus to another node, or click any of the *Mapping Rules*, *Textual Rules*, *Node*, *Properties*, *XSL* or *Debugger* tabs, without applying the mapping, an alert message is displayed (refer to Figure 10.110).
- 13. Click **No** to apply the mapping and shift focus to the other object. If you click **Yes**, then the mapping activity is cleared and is replaced by the previous mapping in the Mapping Graph Area and the focus is shifted to the other object.



# Using Textual Rules

Textual Rules are used for mapping source elements, mapping functions or constants to target elements, by defining the elements in syntax form.



### Steps to map elements using the Concat function using Textual Rules

- 1. Ensure that the <u>source and target schemas are loaded</u> and all their elements are listed under their respective nodes.
- 2. Select the *target* element that you want to map. It is displayed in the Mapping Graph Area.
- 3. Click **Textual Rules** tab in the Mapping Graph Area.
- 4. Click String mapping function and select **Concat** sub-function. The syntax for the Concat sub-function is displayed in the Mapping Graph Area (see Figure 10.99).

& ADEPTIA - Data Happer - customer		X
Ble Yew Actions Help		
👔 Data Mapper 🚍 XSL 🧑 Debugger		
💾 😫 🕗 😌 💿	Current Element : NAME	
Copen Source Schema	Copen Target Schema	
<ul> <li>Structure_of_source_XSD</li> <li>▲ Root (EvalScropt_TextSchema)</li> <li>▲ Root (S)</li> <li>● NANE (string)</li> <li>● ADRESS (string)</li> <li>● ADRESD (string)</li> <li>● ADATEOFERTH (date)</li> <li>● DATEOFERTH (string)</li> <li>● SALAFY (nteger)</li> <li>● DESIGNATION (string)</li> <li>● AGE (nteger)</li> </ul>	Structure_of_destruction_XSD (c) ▲ Accord B ▲ Accord → AADRES (string) → AADRESS (string) → HONAILD (string) → HONAILD (string) → HONAIND (string) → OFARTHENT (string) → OFARTHENT (string) → AALARY (nteger) → ACE (integer)	
×		-
Math String Date Apprepation Conditional Axis Boolean Context XSL Template DB		
Imageng Rules (*) Textus Rules (*) Roperties       Concet ( , )	Parameters     P	1112194194416000012)

Figure 10.99: Syntax for Concat Sub-Function

- 5. This syntax has two parameters. Double-click a *source* element that you want to set as the first parameter. This displays the selected source element in the syntax.
- 6. Similarly, double-click another *source* element as the second parameter. This is displayed in the syntax (see Figure 10.100).



S. ADEPTIA - Data Happer - customer				×
20 gev gev gebors geb				
H 8 0 2 0	Curre	int Element : NAME		
Carl Q Open Source Schema		<u></u>	2 Open 1	Farget Schema
Studture_of_source_XSO		Structure_of_destination_XSD ⊖ A Record → A Record → A MANE (string) → ADDRESS (string) → BMALID (string) → DATEOFRATH(date) → DATEOFRATH(		_ 
				Parameters
Imagency Rules         Textual Rules         Imagency			* × 1	Parameters     Gobal Variables     Gobal Variables     Custom Methods     Cal Variables     Custom Methods     Cal     Context Variables     Context

Figure 10.100: Parameters of the Concat Syntax



7. Click **Apply Mapping** () button. This maps elements using the concat sub-function. A line is displayed between the source and target panels showing the mapping of the source element to the target element.

# Using Namespace

Namespace allows you to add, view, edit, and remove the namespace in the XSL. All the Namespaces present in the source and target XSD's are automatically placed in the XSL generated. These Namespaces can be viewed using **View Namespace** option in the **Namespace** submenu.

# Adding Namespace

## Steps to add a Namespace in the XSL

- 1. Click Actions menu and select Namespace.
- 2. Click the **Namespace** submenu and select **Add Namespace**. The Namespace dialog box is displayed (see Figure 10.101).



Namespace Dialog	×
Namespace	
Ok Cancel	

Figure 10.101: Adding Namespace

Enter the Namespace and click **OK** button. The Namespace is added to the XSL.
 For Example, *xmlns: oa= "http://www.openapplications.org/oagis"*

Ø	The namespace added is shown in the XSL stylesheet tag.
---	---

# **Editing Namespace**

### Steps to edit a Namespace in the XSL

- 1. Click Actions menu and select Namespace.
- 2. Click the **Namespace** submenu and select **Edit Namespace**. The Select Namespace screen is displayed (see Figure 10.102).

ſ	🛝 Select Namespace	×
	Edit Namespace	
	Namespace	
	C xmlns:oa="http://www.openapplications.org/oagis"	
	Ok Cancel	

Figure 10.102: Select Namespace

- 3. Select the namespace you want to edit. This activates the **OK** button. This displays the *Namespace* dialog box in edit mode.
- 4. Make the necessary changes.
- 5. Click **OK** to save the modifications.



Similarly, you can view or remove an existing namespace.



# Using XSL Template

An XSL template is a customized template. If you need to repeatedly perform a set of functions, you can create an XSL template defining those functions, and then later call that XSL template whenever required. For example, if you need to perform addition of two numbers at regular intervals, you can define the addition function in an XSL template. You can then call this XSL template whenever required.

The XSL Template option enables you to manage XSL templates. You can add, update or delete an XSL template using this option.

Once you have added an XSL template, you can use it to map elements.

There are two type of XSL Templates:

- Local: Local templates are available within the mapping activity, in which you have created the template.
- **Global:** Global templates are available within all the mapping activities. Once you create a global template in a mapping activity, you can use it in all the mapping activities.

# Add XSL Template

### Steps to add an XSL template

1. Click **XSL Template** option displayed next to mapping functions on the Mapping Functions Panel. Then select **Manage XSL Template** option. The Manage XSL Template screen is displayed (see Figure 10.103).



🙏 Manage XSL Template		×
Templates		
local	Name :	
global	Parameter List	
	Name	٦
		Add
		Delete
		Edit
		Scope: Global
		C Group
	Mapping Rules XSL Rules	
	XSL Template	
	Click 'New Template' to add a new XSL Template.	
	Click Template Nodes on left to edit XSL Templates.	
	Click 'Save Template' to save XSL Template.	
	Click 'Delete Template' to delete created XSL Templates.	
		<b>•</b>
		•
	Synchronize         New Template         Save Local         Save Global         Delete Template         Close	

Figure 10.103: Manage XSL Template

- 2. Click **New Template** button. This activates the *Name* and *Parameter List* fields.
- 3. Enter the name of the new XSL template that you want to create, in the *Name* field.
- 4. Click **Add** button to add parameters for the new XSL template. This displays the Parameter Dialog box (see Figure 10.104).

Parameter Dialog				×
Paramete	er Name			
	Ok	Cancel	]	

Figure 10.104: Parameter Dialog Box

5. Enter the name of the parameter you want to add, in the *Parameter Name* field and click **OK**. This closes this screen and adds the new parameter in the Parameter List field. It also generates the corresponding XSL in the XSL Template editor on the Manage XSL Template screen (see Figure 10.105).



👗 Manage XSL Templat	ite	×
Templates		
local	Name : Template1	
global		
giobai	Parameter List	
	Name	[]
	Param1	Add
		Delete
		Edit
		Scope:
		Global
		C Group
	Mapping Rules XSL Rules	
	XSL Template	
	<xsl:template name="Templatel"></xsl:template>	<b>_</b>
	<xsl:param name="Paraml"></xsl:param>	
	<pre><!-- template code starts--></pre>	
	template code ends	
	Synchronize New Template Save Local Save Global Delete Template Close	

Figure 10.105: Parameters Added in XSL Template

6. Similarly, add additional parameters to the XSL template.

19	You can also define variables as the parameters of the XSL Template. To
Ø	add a global variable, refer to the section Using Global Variable.

7. Enter the code for the function that you want to perform, for example, addition of two numbers, in the 'add here' line, in the *XSL Template* field. The syntax of the addition function would be:

<xsl: value-of select = "\$param1 + \$param2"/>

where:

*value-of* is the syntax for the value to be returned *param1* and *param2* are the defined parameters

8. Once you have entered the code, click **Save Local** button to save the Local XSL template. This displays the saved template under the Templates list on the XSL Template screen. It is also displayed under Templates in the Parameters Panel.



9. If you want to save the template as Global Template, click **Save Global** button. This will save the XSL template as Global XSL template and can be used in any mapping activity.



On saving the template, XSL validation is performed. If XSL is invalid, then an alert message is displayed specifying the line number and reason for error.



The name and parameters of the new XSL template also get displayed under the Templates list in the Parameters Panel. You can edit or delete an XSL template from the Parameters Panel itself. For details, refer to the <u>Managing a Global Variable from Parameter Panel</u> section.



Once you have created a XSL template, you can use it to map elements.

# Map Elements using XSL Template

## Steps to map elements using an XSL Template

- 1. Ensure that the <u>source and target schemas are loaded</u> and all their elements are listed under their respective nodes.
- 2. Ensure that the **source and target elements to be mapped are selected and displayed** in the Mapping Graph Area.
- 3. Click the XSL template that you want to use for performing the required function, from the *Templates* list in the Parameters Panel. A Call XSL Template node is displayed in the Mapping Graph Area (see Figure 10.106).



A, ADEPTIA - Data Happer - customer	_8×
Ele Yew Actions Help	
👔 Data Mapper 💼 XSL 🎯 Debugger	
💾 😫 🕗 🤁 🔘	Current Element : NAME
Copen Source Schema	Copen Target Schema
Structure_d_fource_XSD     Acat (EvaScret_TextSchema)     Acat (EvaScret_TextSchema)     Acat (EvaScret_TextSchema)     Acat (EvaScret_Schema)     Acat (EvaSchema)     Acat (EvaScret_Schema)     Acat (EvaSchema)     Acat (EvaSchema	Structure_of_destrutor_XSD B A Root (EvaScrot_TextSchema) B A Root ● NIAME (drung) ● ADDRESS (drung) ● OPARTIMET (drue) ● OPARTIMET (drue) ● OPARTIMET (drue) ● OPARTIMET (drue) ● OPARTIMET (drue) ● DATEOFORNIK (drue) ● DESIGNATION (etring) ● AGE (integer)
1	
Math String Date Aggregation Conditional Axis Boolean Context XSLTemplate DB	
Image: Solution of the state Rules     Image: Solution of the soluti	Prameters     Prameters     Pointers     Pointers

Figure 10.106: Call XSL Template Node

- 4. Create a link from the output of the first *Source* element to the first input of the *Call XSL Template* node.
- 5. Create a link from the output of the second *Source* element to the second input of the *Call XSL Template* node.
- 6. Create a link from the output of the *Call XSL Template* function node to input of the *Target* element node (see Figure 10.107).



ADEPTIA - Data Happer - customer  File View Actions Help		_ <u>8 ×</u>
The vew Accors hep		
H 8 0 2 0	Current Element : NAME	
Copen Source Schema	Copen Target Schema	
▲ Structure, of source, XSD ♦ Another (S) • A Record (S) • A RE	Structure, of, destruction_XSD G ▲ Root (EndStrop(_TextSchema)) G ▲ Rootd → HAME (strop) → HOMESS (strop) → PHONEDIC (strop) → DATEOFORMITH (date) → DATEOFORMITH (date) → DESIGNATION (strop) → DATEOFORMIT(strop) → AGE (mteger)	X
Math String Date Appregation Conditional Axis Boolean Context XSL Template DB		_
gg ↓ Macong Rules (@ Local Variables ( In Properties ) 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1		0012)


Figure 10.107: Create Links between Nodes for Mapping Elements using XSL Template

7. Click **Apply Mapping** () button. This maps elements using the Call XSL Template function node.

# Using Global Variable

Global variables are used for mapping source elements, mapping functions or constants to target elements. They are declared and used globally for all target elements.

To use a global variable in a mapping activity, you need to map it to a target element. This will successfully execute the global variable when you execute the mapping activity in the process flow.



### Declare Global Variable

#### Steps to declare a Global Variable

1. Ensure that the **source and target schemas are loaded** and all their elements are listed under their respective nodes.



- 2. Click **Global** tab in the Mapping Graph Area. All tabs of the Global tab are displayed.
- 3. Click **Global Variables** tab. The Global Variable pane is displayed in the Mapping Graph Area (see Figure 10.108).

💾 🖸 🥥 👻 🔲 🗌		Current El	ement : NAME	
,	데 Q Open Source Schema			Open Target Schema
Structure, of Source, XSO ⇔ Acac (SoStork, TextSchen ⇒ Acac (SoStork, TextSchen ⇒ HAME (strung) → PADRESS (strung) → PAD	) )) 76)		Structure, of, destruction, XSD E→ & Root (RNASCrut_TextSchema) E→ & Root (RNASCrut_TextSchema) E→ & ADDRESS (string) -→ EHALLD (string) -→ EHALLD (string) -→ DATEO/BEKIN (date) -→ DATEO/BEKIN (date) -→ SLARY (integer) (LV) -→ DATEO/BIKIN (date) -→ DALARY (integer) -→ AGE (integer)	
	itional Axis Boolean Context XSLTemplate DB			
Global Variables Custom Methods 1	iey Functions Context Variables Connection Info			<ul> <li>Parameters</li> <li>Global Variables</li> </ul>
G Global Variable Name	Giobal Variable Value	1	Add Comment	Decal Variables
Click here to declare variable				Custom Methods     Context Variables     Context Variables

Figure 10.108: Global Variable Pane

- 4. Click *Global Variable Name* text field and enter the name of the global variable you want to create (e.g. *emp\_age*). Press the **Tab** or **Enter** key. This takes the control to the *Global Variable Value* field.
- 5. *Enter* the value of the global variable in the *Global Variable Value* field. You can enter the value of the global variable using one of the listed methods:
  - Click required source element
  - Select the required Mapping function
  - Type the required value manually
  - Select a Custom Method

Ø	To select a Custom Method as the value of a global variable, double click the desired <b>Custom Method</b> under <i>Custom Methods</i> in the Parameters Panel. The selected Custom Method is displayed in the Variable Definition field.			
	To learn how to declare a Custom Method, refer to section Using Custom Method.			

6. Enter comments for the global variable in the *Add Comment* field (see Figure 10.109). For example, if the global variable value contains complex XSLT logic, you can enter its description in this field.



The <i>Comments</i> field is resizable.			
ADEPITA - Data Happer - customer Die jien distons beb     Deta Maccor (1995) (2000)     Detauger			_ 8 _×
	Current	t Element : NAME	
Structure_of_source_XSD     Source_XSD     Accord (S)     Ac		Structure_of_destructor_XSD B- A floot (EvaScrot_TextSchema) B- A Record - NUME (string) - ADDRESS (String) - PHONEIO (crtager) - DATEOFBIRTH (date) - DEFARTNEIT (string) - DATEOFDIDING (date) - DESIGNATION (string) - AGE (nteger)	joen Target Schema 🗶
Math String Date Apprepation Conditional Asia Boolean Context XSL Template DB			
Global Variables [Custom Methods   Key Functions   Context Variables   Connection Info			Parameters     Global Variables
😤 💾 🛗 📰 📷 💮 Global Variable Name 🕞 Global Variable Value		0.000	Global Variables     B      O Local Variables
O Global Variable Value	variable to store a	Q AddComment age of employee	Custom Methods     Context Variables     Vari' (100)     Tempates     Context Variables     Context Variables     Context Variables     Context Variables     Context Variables     Context Variables     Social     Context Variables     Social     So

Figure 10.109: Enter Name, Value and Comments of Global Variable

7. Click **Save Global Variable** () button to save the global variable. This global variable is added to the list of existing variables in the *Global Variable Name* field. It is also displayed under *Global Variables* in the Parameters Panel. If you shift the focus to another node, or click any of the *Mapping Rules, Textual Rules, Local Variables, Properties, XSL* or *Debugger* tabs, without saving the global variable, an alert message is displayed. (see Figure 10.110). The comments added for the global variable are saved and displayed above the global variable declaration in the Mapping XSL (refer to Figure 10.111).

Adeptia Mapper Warning!				
•	Are you sure you want to proceed without saving global variable?			
	Yes No			

Figure 10.110: Alert Message

For example, you have defined a global variable Var1, and you click the Name target element, without saving Var1, then the alert message is displayed.
 The alert message is also displayed when shifting focus between Global and Node tabs.



8. Click **No** to save the global variable and shift the focus to the other object. If you click **Yes**, then the defined global variable is cleared and the focus is shifted to the other object.

& ADEP	TIA - Data Happer - customer
File Vier	w Actions Help
🞁 Data	a Mapper 📑 151, 🙀 Debugger
1 <	jonal version="1.0"/>
2 0	xsl:stylesheet xmlns:xsl="http://www.w3.org/1999/XSL/Transform" version="1.1" xmlns:java="http://xml.apache.org/xslt/java" xmlns:xalan="http://xml.apache.org/xalan" xmlns:oa="http://www.openapplic
3	<pre><xs1:output encoding="ISO-8859-1" indent="yes" method="xml" version="1.0"></xs1:output></pre>
4	<pre>(xs):param name="_userName"/&gt;</pre>
5	<pre><xs1:paraa name="_password"></xs1:paraa></pre>
6	cksl:param name="_olass"/>
7	<pre>(xsl:param name="_identifier"/&gt;</pre>
0	<pre><xs1:param name="_subject"></xs1:param></pre>
9	<pre>cksl:param name="_repositoryPath"/&gt;</pre>
10	<pre><xs1:param name="_Input1"></xs1:param></pre>
11	<pre><xs1:variable name="Input_EvalScript_TextSchema" select="document(s_Input]"></xs1:variable></pre>
12	🗱 ivariable name="varConn" select="java:com.adeptia.indigo.services.mapping.support.dbquery.MapperQueryExecutor.getInstance({_identifier,'false')"/>
13	<pre><xs1:variable name="apos">'</xs1:variable></pre>
14	<pre><xs1:variable name="civar1" select="'192168001011112194194416000012'"></xs1:variable></pre>
15 <	(variable to store age of employee>
16	<pre><xsl:variable name="emp_age" select="25"></xsl:variable></pre>
17	<pre><xs1:variable name="contextYarl" select="java:com.adeptia.indigo.services.mappingTransformation.setYariable(%_class,'Yarl',100)"></xs1:variable></pre>
18	<pre>(xsl:template name*"CallTemplate"&gt;</pre>
19	<pre><pre><pre><pre>cysl:param name="Paraml"/&gt;</pre></pre></pre></pre>

Figure 10.111: Comment in Mapping XSL



button.

You can rearrange the global variables by dragging it up or down in the list.

To remove a global variable, select the global variable and click **Remove** selected global variable (<sup>10</sup>) button. To remove all global variables, click **Remove all global variables** (<sup>10</sup>)

### Managing a Global Variable from the Parameters Panel

Once the global variable is added to the Parameters Panel, you can edit it or delete it anytime from this Panel itself.

### Steps to manage a Global Variable from the Parameters Panel

1. Right-click the **global variable** that you want to edit or delete. This displays the right dropdown menu (see Figure 10.112).






Figure 10.112: Right-Click Menu of Elements in Parameter Panel

- 2. Select **Edit** to edit the variable. This displays the selected global variable in Edit mode. You can edit the value of the global variable in the *Global Variable Value* field.
- 3. Alternately, select **Remove** to delete the selected variable. This displays a confirmation screen for the delete operation (see Figure 10.113).

Remove	Global Variable	×
٩	Are you sure you want to remove selected Global V	/ariable?
	Yes No	



4. Click **Yes** to delete the selected variable.

### Map Global Variable to Target Element

Once you have created a global variable, you can map it to a target element.

#### Steps to map Global Variable to target element

- 1. Ensure that the **source and target schemas are loaded** and all their elements are listed under their respective nodes.
- 2. Click **Node** tab displayed in the Mapping Graph Area. All tabs of the Node tab are displayed. Click **Mapping Rules** tab.



- 3. Select a *target* element. This displays the selected target element node in the Mapping Graph Area.
- 4. Double-click the required **global variable** under *Global Variables* in the Parameters Panel. The selected global variable node is displayed in the Mapping Graph Area (see Figure 10.114).




Figure 10.114: Add Global Variable Node

- 5. Create a link from the output of the global variable to the input of the target element.
- 6. Click **Apply Mapping** (**V**) button. This maps the global variable to the target element. If you shift the focus to another target element, or click any of the *Node, XSL* or *Debugger* tabs, without applying the mapping, then an alert message is displayed. (refer to Figure 10.110).
- 7. Click **No** to apply the mapping and then shift the focus to the other object. If you click **Yes**, then the mapping activity is cleared and is replaced by the previous mapping in the Mapping Graph Area and the focus is shifted to the other object.

Ø	Once a global variable is mapped to a target element, the letter (M) is displayed next to the mapped target element. This signifies that a target		
	element has been mapped. Refer to <u>Table of Suffixes</u> for details on suffixes displayed next to a target element.		

8. <u>Save</u> the mapping activity and exit the Data Mapper.



You can view and validate the generated mapping XSL, view the target XML and view and validate mapping output, before



saving the mapping activity.

# Using Local Variable

Local variables are used for mapping source elements, mapping functions or constants to a specific target element. They are declared and used only for the specific target element or attribute for which they are declared.

To use a local variable in a mapping activity, you need to map it to the specific target element or attribute. This will successfully execute the local variable when you execute the specific mapping activity in the process flow.

#### Declare Local Variable

#### Steps to declare a Local Variable

- 1. Ensure that the **source and target schemas are loaded** and all their elements are listed under their respective nodes.
- 2. Click **Node** tab displayed in the Mapping Graph Area. All tabs of the Node tab are displayed.
- 3. Click **Local Variables** tab. The Local Variable pane is displayed in the Mapping Graph Area (see Figure 10.115).



4. ADEPTIA - Data Happer - customer		
File View Actions Help		
Tata Mapper 🕤 XSL 🤬 Debugger		
💾 🛛 🗢 🤁 🛛	Current Element : AGE	
Copen Source Schema		n Target Schema
Structure, of, source, XSD                ● ▲ Record (S)                 ● ▲ Record (S)                 ● ▲ Record (S)                 ● ▲ Record (S)                 ● ● ADDRESS (strup)                 ● ● PAOREID (creager)                 ● ● PAOREID (creager)                 ● ● DOREID (creager)                 ● AGE (ntager)	Structure_of_destination_XSD ⊖: A Record → A Record → 0 HAME (terring) → 0 HAME (terring) → 0 HAME (terring) → 0 HAMEHO (strang) → 0 HAMEHO (strang) → 0 HAMEHOIT (strang) → 0 AFEC#IRTH (strang) → 0 AFEC#IRTH(strang) → 0 AFEC#IRTH(strang) → 0 AFEC#IRTH(strang) → 0 AFEC#IRTH(strang) → 0 AFEC#IRTH(strang) → 0 AFEC#IRTH(strang)	2
Math String Date Aggregation Conditional Axis Boolean Context XSL Template DB		Parameters
R Local Variables Rules Cocal Variables Reportes	×	Parameters
O Local Vanable Value     O Local Vanable Value     O Local Vanable Value     O Local Vanable Value	G Add Comment	A Serro_sge (25)     B

Figure 10.115: Local Variable Pane

- 4. Click *Local Variable Name* text field and enter the name of the local variable you want to create (e.g. *varQuery*). Press the **Tab** or **Enter** key. This takes the control to the *Local Variable Value* field.
- 5. Enter the value of the local variable in the *Local Variable Value* field. You can enter the value of the local variable using one of the listed methods:
  - Click required source element
  - Select the required Mapping function
  - Type the required value manually
  - Select a Custom Method
- 6. Enter comments for the local variable in the *Add Comment* field (see Figure 10.116). For example, if the local variable value contains complex XSLT logic, you can enter its description in this field.







Figure 10.116: Enter Name, Value and Comment for Local Variable



7. Click **Save Local Variable** ( ) button to save the local variable for the selected target element. This local variable is added to the list of existing variables in the *Local Variable Name* field. It is also displayed under *Local Variables* in the Parameters Panel. If you shift the focus to another node, or click any of the *Mapping Rules, Textual Rules, Global Variables, Properties, XSL* or *Debugger* tabs, without saving the local variable, an alert message is displayed (refer to Figure 10.110). The comments added for the local variable are saved and displayed above the local variable declaration in the Mapping XSL (refer to Figure 10.111).



The alert message is also displayed when shifting focus between Global and Node tabs.

8. Click **No** to save the local variable and shift the focus to the other object. If you click **Yes**, then the defined local variable is cleared and the focus is shifted to the other object.



Ø	Once the local variable is saved, it is categorized as <i>Current Variable</i> or <i>Ancestor Variable</i> in the Parameters Panel. If it is created for a child node,
	then it is saved as a <i>Current Variable</i> . If it is created for a parent's parent node, then it is saved as an <i>Ancestor Variable</i> .

Yo

You can rearrange the local variables by dragging it up or down in the list.



## Map Local Variable to Target Element

Once you have created a local variable, you can map it to the specific target element or attribute.

### Steps to map Local Variable to specific target element


- 1. Ensure that the **source and target schemas are loaded** and all their elements are listed under their respective nodes.
- 2. Click **Node** tab displayed in the Mapping Graph Area. All tabs of the Node tab are displayed. Click **Mapping Rules** tab.
- 3. Select a *target* element. This displays the selected target element node in the Mapping Graph Area.
- 4. Double-click the required **local variable** under *Local Variables* in the Parameters Panel. The selected local variable node is displayed in the Mapping Graph Area (see Figure 10.117).



ADEPTIA - Data Mapper - EMP_Record	
The volve record ring Contraction of the second ring of the second rin	
💾 🛛 📀 🤕 🔘	Current Element : SALARY
Copen Source Schema	Carl Open Target Schema
Structure_of_source_XSD  A Root (Evalscript_TextSchema)  A Root (Evalscript_TextSchema)  A Root (Evalscript_TextSchema)  A Root (String)  A ROOK (Integer)  D DATEOFBIRTH (date)  DEPARTMENT (string)  ARLARY (Integer)  AGE (Integer)  AGE (Integer)  AGE (Integer)	Structure_of_destination_XSD  A Root (EvalScript_TextSchema)  A Root (String)  ADDRESS (string)  PHONENO (integer)  DATEOFBIRTH (date)  DATEOFDINTHS (date)  DATEOFDINTNG (date)  AGE (integer)  AGE (integer)
Math String Date Aggregation Conditional Axis Boolean Context XSL Template DB	
Bigg       Image: Strain	Parameters     Gobal Variables     Corrent Variables     Corrent Variables     Corrent Variables     Corrent Variables     Context Variables     Context Variables     Templates     Connection Info     Global Methods     Value Map

Figure 10.117: Add Local Variable Node

- 5. Create a link from the output of the *local variable* to the input of the *target* element.
- 6. Click **Apply Mapping** (**S**) button. This maps the local variable to the selected target element. If you shift the focus to another target element, or click any of the *Global, XSL* or *Debugger* tabs, without applying the mapping, then an alert message is displayed (refer to Figure 10.110).
- 7. Click **No** to apply the mapping and then shift focus to the other object. If you click **Yes**, then the mapping activity is cleared and is replaced by the previous mapping in the Mapping Graph Area and the focus is shifted to the other object.



Local variables do not allow duplicate names at the same level. You need to right-click to edit the local variable, where you can select the source.

8. <u>Save</u> the mapping activity and exit the Data Mapper.



You can view and validate the generated mapping XSL, view the target XML and view and validate mapping output, before saving the mapping activity.



# **Using Custom Methods**

A custom method is used to call a function from a custom Java class in a package. It is declared and used globally for all target elements.

To use a custom method in a mapping activity, you need to map it to a target element. This will successfully execute the custom method when you execute the mapping activity in the process flow.

### Prerequisites:

The package containing the custom java class must be copied in the folder ../../AdeptiaServer-5.1/ServerKernel/customClasses.

#### Declare a Custom Method

#### Steps to declare a Custom Method

- 1. Ensure that the <u>source and target schemas are loaded</u> and all their elements are listed under their respective nodes.
- 2. Click **Global** tab displayed in the Mapping Graph Area. All tabs of the Global tab are displayed.
- 3. Click **Custom Methods** tab. The Custom Methods pane is displayed (see Figure 10.118).



A. ADEPTIA - Data Happer - customer			
File View Actions Help			
👔 Data Mapper 🔄 XSL 🍓 Debugger			
💾 🛛 🗢 🤁 🕕	No Element Se	lected	
Copen Source Schema			Target Schema
Structure_of_source_XSO     Accord (Saurce_XSO     Accord (Sau		bucture.d_destnation_XSD A boot (Evidence TextSchema) B Ascord → Ascord	۲ ۲
			Parameters
	thod	# Parameters	B Global Variables
003 Terrer 002			Ocal Vanables     Ocal V

Figure 10.118: Custom Methods Pane

- 4. Click Add New Method ()) button to add a Custom Method. A row is inserted with the listed columns as displayed in Figure 10.119:
  - Alias
  - Class (PKG)
  - Method
  - # Parameters



& ADEPTIA - Data Happer - customer					X
File View Actions Help					
👔 Data Mapper 😁 XSL 🧿 Debugger					
💾 😫 🥥 💐 🔘		N	o Element Selected		
	🚽 Open Source Schema			😭 🖓 Open Target Schema	
Structure_of_source_XSD     Accord (S)     Ac			Stucture_of_destination_XSD		٦ ٦
				Parameters	
Alas	Class (PKG)	Method	# Parameters	Global Variables	
				Local Variables	
hand (bac)				Custom Wethods How Kins How Context Vanables How Context Vanabl	

Figure 10.119: Add Custom Method

The value 'java' is automatically displayed in the *Alias* column. This is a read-only field.

- 5. Click *Alias* field and then press **Enter** or **Tab** key to activate the *Class (PKG)* field.
- 6. Enter the fully qualified name of the Java class in the *Class (PKG)* field and press **Enter** or **Tab** key to activate the *Method* field.
- 7. Enter the name of the custom method in the *Method* column and press **Enter** or **Tab** key to activate the *#Parameter* field.
- 8. Enter the number of arguments taken by Method in the *# Parameter* column. A custom method can take any number of arguments. However, if you enter a value greater than 4, then a warning message appears (see Figure 10.120).




Figure 10.120: Warning for Adding more than 4 Parameters

9. Click **OK** to close the message. This saves the custom method and displays it under *Custom Methods* in the Parameters Panel (see Figure 10.121).



A. ADEPTIA - Data Happer - customer	
File View Actions Help	
👔 Data Mapper 📷 XSL 🍓 Debugger	
💾 😫 🕹 🤤 🔲	No Element Selected
Carl Open Source Schema	Carl Open Target Schema
Studture_of_source_XSO	Structure, of_destruction, XSD ⊖ A Note (FWASCOPC_INSTSCHerma) ⊖ NAME (strong) → RADRESS (string) → BHAILED (strong) → DATOERENT (scing) → DATOERENT (scing) → DATOERENT (scing) → SALAYY (resper) (LV) → DATEOFJOBUNG (scing) → AGE (nteger) → AGE (nteger)
Math String Date Apprepation Conditional Axis Biodean Context XSL Template DB  (g) (Global Variables) "Custom Methods   Ykey Punctions   Context Variables   Connection Info	Parameters
	ethod # Parameters Local Variables Local Variables ■ Local Variables ■ Local Variables ■ Context Variables ■ O Context Variables ■

Figure 10.121: Custom Method added to Parameters Panel

Ø	To remove a custom method, select the custom method and click <b>Remove</b> selected method ( <sup>1</sup> ) button.
	Alternately, you can edit or delete a custom method from the Parameters Panel itself. For details, refer to the Managing a Global Variable from Parameter Panel section.

### Map Custom Method to Target Element

Once you have created a custom method, you can map it to a target element.

### Steps to map Custom Method to target element


- 1. Ensure that the **source and target schemas are loaded** and all their elements are listed under their respective nodes.
- 2. Click **Node** tab displayed in the Mapping Graph Area. All tabs of the Node tab are displayed. Click **Mapping Rules** tab.
- 3. Select a *target* element. This displays the selected target element node in the Mapping Graph Area.



4. Double-click the required **custom method** under *Custom Methods* in the Parameters Panel. The selected method node is displayed in the Mapping Graph Area (see Figure 10.122).

A, ADEPTIA - Data Happer - customer	
File View Actions Help	
👔 Data Mapper 🔄 XSL 🧑 Debugger	
💾 🖸 🕹 🤤 🕘	Current Element : SALARY
Copen Source Schema	Cal Q Open Target Schema
Sturture_of_source_XSD     Acct (BaSrott, TrextSchema)     Action (BaSrott, Basrott,	Structure_of_destruction_XSD         (a) A Societ (readscruct_TextSchema)         (a) A Record         - 0 HAME (readscruct_TextSchema)         (a) A Rocciet         - 0 HAME (readscruct_TextSchema)         - 0 HAME (readscruct_TextSchema)     <
With String Date Appreciation Conditional Axis Boolean Context XSL Template DB	<u> </u>
	Jo Parameters
Kapong Rules Testual Rules ( Rule	Social Variables     Social Variables     Coccil Variables     Coc

Figure 10.122: Add Custom Method Node



- 5. Click two *source* elements. The selected source nodes are displayed in the Mapping Graph Area.
- 6. Create a link from the output of the first *source* element to the first input of the *custom method* node.
- 7. Create a link from the output of the second *source* element to the second input of the *custom method* node.
- 8. Create a link from the output of the *custom method* node to the input of the *target* element (see Figure 10.123).



& ADEPTIA - Data Happer - customer			X
Pie View Actors Help			
	Current Element : SALARY		
Cal Qopen Source Schema		Call Open 1	arget Schema
Stucture of source XSD Active Action of Source XSD Action of Source	Structure, of, destruction, XS G & box (Fin3Struct, Text) B & Accord D AltHC (arroy) D ADDRESS (pro- D ALDDISS) (pr	chema) ) ger) (date) string) rr) (LV) i (date)	1
Math String Date Aggregation Conditional Axis Boolean Context XSL Template DB			Parameters
Image: Solution Pulses     (1) Execution Pulses     (1) Execution       Image: Solution Pulses     (1) Execution     (1) Execution       Image: Solution Pulses <td></td> <td></td> <td>Valanteess # Global Variables © Current Variables © Current Variables = A \$805JaivyKK (VHHE CONDTION(\$Input_Eval - A \$805JaivyKK (VHHE CONDTION(\$Input_Eval - A \$805JaivyKK (VHHE CONDTION(\$Input_Eval - A \$805JaivyKK (VHHE CONDTION(\$Input_Eval - A \$805JaivyKK (VHHE) © Curson Methods © Connect Variables © Connection Info © Soloal Methods - Value Map</td>			Valanteess # Global Variables © Current Variables © Current Variables = A \$805JaivyKK (VHHE CONDTION(\$Input_Eval - A \$805JaivyKK (VHHE CONDTION(\$Input_Eval - A \$805JaivyKK (VHHE CONDTION(\$Input_Eval - A \$805JaivyKK (VHHE CONDTION(\$Input_Eval - A \$805JaivyKK (VHHE) © Curson Methods © Connect Variables © Connection Info © Soloal Methods - Value Map

Figure 10.123: Create Links between Nodes

- 9. Click **Apply Mapping** ( ) button. This maps the custom method to the target element.
- 10. <u>Save</u> the mapping activity and exit the Data Mapper.

You can <u>view and validate the generated mapping XSL</u>, <u>view</u> <u>the target XML</u> and <u>view and validate mapping output</u>, before saving the mapping activity.

# Dynamically Loading Custom Methods

Adeptia supports dynamic loading of custom methods in the Data Mapper. It loads the custom methods available in the Custom Classes folder, under the Global Methods node in the Parameters Panel. This enables you to access any custom method from the Data Mapper itself, without any need to specify method parameters, such as class name, method name and the number of arguments in the Data Mapper applet.

### Steps to dynamically load Custom Methods

1. Copy all the class files in the Custom Classes folder and then restart the kernel.



The current implementation of Global Methods does not support package hierarchy. So all class files that are directly placed in the Custom Classes folder, will be visible through the Global Methods node in the Parameters



Panel.

2. Ensure that the **source and target schemas are loaded** and all their elements are listed under their respective nodes. The *Global Methods* node is already displayed in the Parameters Panel, each time Data Mapper is opened (see Figure 10.124)




Figure 10.124: Global Methods Node

3. Expand the **Global Methods** node to display all the class files present in the Custom Classes folder (see Figure 10.125).



ADEPTIA - Data Happer - customer  File View Actions Heb		X
File View Actions Hep Data Mapper (1) XSL (1) Debugger		
	Current Element : PHONENO	
Copen Source Schema	Carl Q Open T	arget Schema
Stockers, of, source, 250     A Root (EvalScrot, TextSchema)     & A Root (Sing) (H)     → ORCESS (string) (H)     → ORCESS (string) (H)     → ORAINE (string) (H)     → ORAINE (string) (H)     → OATEOFORNIH (date)     → OATEOFORNIH (date)     → OASE (integer)     → AGE (integer)	Structure of, destruction, XSD G: A bost (invision: Tustichems) G: A bost (invision: Tustichems) G: A bost (invision: Tustichems) G: A bost (invision: Tustichems) ADDESS (strup) (M) O ATEOFERTH (strup) O ATEOFERT	ية بر
Math String Date Apprepation Conditional Axis Boolean Context XSL Template DB		Parameters
Image: Solution Science Scien		B • Global Variables E • Local Variables E • Custom Hethods H • Keys B • Context Variables B • Context Variabl

Figure 10.125: List of Class Files in Custom Classes Folder

4. Expand a class node to display all custom methods available for that class (see Figure 10.126).




Figure 10.126: Custom Methods in a Custom Class



You can view more information (such as return type and parameter types) about a custom method as a tooltip, by placing the cursor over the custom method node.

You can then map the custom method to a target element by doubleclicking the custom method and then mapping by providing the input parameters.

# Using Key Function

The *Key* function is used to extract information from two or more related input data sources. For example, if there are two input data sources: *source1* and *source2*, then the *Key* function will extract information from *source2* based on the matching field from *source1*.

*Key* function is always created in context of *source2* (the data source from where data needs to be fetched based on matching field ). All the parameters of the *Key* function correspond to *source2* only. It has the following 3 parameters:

- Key Name : It is a name that you want to give to the Key function (for example, Key1))
- *Key Match* : It is the XPath of *source2* that will be returned as output by the *Key* function . This XPath is assumed to be present in the *source2* . A valid Xpath needs to be specified as this path will be returned as output. A schema name cannot be used here in the Xpath.
- Key Use: It is the name of the field from source2 which will be used to find the matching record from source2 based on the value passed to Key function. For example, if the Key Match is /Root/Record and Key Use is EmpID, and if we pass value 25 to the Key function, then it will start scanning EmpID of the source2 inside each record of source2. Whenever EmpID=25, the Key function will pass that record (Root/Record) as output.

Once the *Key* function is created, you need to pass the value to the *Key* function that will be used to match the *Key Use* defined for *source2* and map the output to the target element. For this, you need to use the *Key* mapping function. The syntax of the Key Mapping is :

key( , )

This function accepts 2 parameters. The first parameter is the name of the *Key* function (*Key1*) to be used and the second parameter is the actual value that will be passed to the *Key* function to perform the match on *source2*. The parameters will be:

## key( 'key1', 25 )

Once XSLT transformer finds this mapping it will call the *Key* function *Key1* and pass the value 25 to that function. The *Key* function *Key1* on recieving the mapping will pick this value 25 and start scanning *EmpID* of the *source2* inside each record of *source2*. When ever EmpID= 25, the *Key* function will pass that record (*Root/Record*) as output.

The *Key* function always executes inside current context or nearest *For Each* that is applied to the target element where *Key* function is mapped. So if the *For Each* is applied is for *source2* on the target element, then the *Key* function will use *source2* as the data source on which EmpID



scanning will be performed. So the *For Each* applied, helps the *Key* function to decide which data source to use, to perform the scanning and fetch the output.

## Usage Scenario

For example, there are two source schemas: *Schema\_EmpDetails* and *Schema\_Emp\_incrementalDetails*. There is one target schema: *Schema\_EmpCompleteDetails*. The objective is to map the fields *EmpName*, *EmpID*, *Age*, *Salary*, *City* and *Email* from *Schema\_EmpDetails* and map the field *Address* from *Schema\_Emp\_incrementalDetails* to the target schema. The *Address* from the *Schema\_Emp\_incrementalDetails* is fetched using *Key* function and using *EmpID* as *Key* Use.

The parameters are defined as:

- Key Name : Key1
- Key Match : /Root/Record
- Key Use : EmpID

The first *For Each* is applied from record of first Schema on target Record node. This will insure that target data will contain as many records as there are in *Schema\_EmpDetails*. Now *Key* mapping is used on the target *Address* element. So the deciding *For Each* (*\$Input\_Schema\_Emp\_incrementalDetails/Root*) for *Key* function is applied on this element. The *For Each* applied here is upto *Root* element only not *Record* so that only single *Address* target element is created per record. The Key mapping is defined as:

key( 'key1',\$\_varEmpID )/Address

Local variable \_*varEmpID* is used as second parameter which is dynamically picking value from the EmpID of the first schema (due to *For Each* applied on target *Record* node). . Once the *Key* function finds the match, it will return the matching record *Root/Record* from the second schema. Since the *Address* element is inside the *Record* element, */Address* is appended to the *Key* mapping, which becomes *Root/Record/Address*.

Using key function involves:

- Creating a key
- <u>Mapping the Key with target element</u>

# Creating a Key

### Steps to create a key

- 1. Ensure that the **source and target schemas are loaded** and all their elements are listed under their respective nodes.
- 2. Click **Global** tab displayed in the Mapping Graph Area. All tabs of the Global tab are displayed.



3. Click **Key Functions** tab. A list of existing keys is displayed in the Key Functions pane (see Figure 10.127).

& ADEPTIA - Data Mapper - EMP_Record	_6_×
File View Actions Help	
🞁 Data Mapper 📑 XSL 🍪 Debugger	
🗄 💾 🛛 🥥 🤁 🕕	Current Element : Record
्रि Open Source Schema	Carl Open Target Schema
Structure_of_source_XSD     Accord     Accord     PercondNumber     PercondNumber     PercondNumber     PercondNumber     Accord     Accor	Structure_of_destination_XSD  A Roord  A Record  Structure_of_destination_XSD  A Record  For recordNumber  Several (string)  NAME (string)  SALARY (integer)  AGE (integer)  ADDRESS (string)
Math String Date Aggregation Conditional Axis Boolean Context XSL Template DB	
Global Variables (Custom Methods) Key Functions (Context Variables (Connection Info	Parameters     Goldbal Variables     Goldbal Variables     Goldbal Variables     Goldbal Variables     Goldbal Variables     Goldbal Variables     Goldbal     Goldbal
Key Name = Key Match =	Key Use =

Figure 10.127: Key Functions Tab

- 4. Click Add Key () button to activate the Key Name field.
- 5. Enter the name of the new key in the *Key Name* field.
- 6. Enter the path of the source element (at the root node) to be matched, in the *Key Match* field. The path always starts with a '/'.



Here in the field, you need not to enter the complete Xpath. In path you need to enter only the *Root* and *Record*. For example */Root/Record*.

7. Enter the name of the field to be matched in the Key Use field For Example EMPID.



The Key Match and the Key Use fields are case-sensitive.

8. Click **Save Key** (<sup>111</sup>) button to save the key. This key is added to the list of existing keys in the **Key Function** tab. It is also displayed under Keys in the Parameters Panel. (see Figure 10.128).



A.ADEPTIA - Data Mapper - EMP_Record File View Actions Help		_ B ×
The view Actions Help		
	Current Element : Root	
Copen Source Schema	Current Lientent . Noot	Scheme
		Scrienia
Structure_of_source_XSD     Acot (Source1)     Acot (Source1)     Acot (Source1)     Acot (Source1)     Acot (String)    > EMAILID (string)    > SALARY (integer)    > ACE (integer)     Acot (Source2)     Acot (String)    > AADE (string)    > AADE (string)    > ADDRESS (string)    > EMAILID (string)    > ACOT (string)	Structure_of_destination_XSD A Root (Employee_Data) Faceord FrecordNumber PMPID (string) PHONENO (integer) ANDE (string) PHONENO (integer) ADDRESS (string)	2
		<b></b>
Math String Date Aggregation Conditional Axis Boolean Context XSL Template I		(a
Global Variables   Custom Methods   Key Functions   Context Variables   Connection Info		Parameters     Global Variables     Global Variables     Local Variables     Custom Methods     Keys     A'Address_Key' ("/Root     Context Variables     Templates     Global     Global     Global Methods     Global Methods     Value Map
Key Name = Key Match =	Key Use =	

Figure 10.128: Key Added to Parameters Panel

9. If you shift focus to another node, or click any of the *Mapping Rules, Textual Rules, Properties, XSL* or *Debugger* tabs, without saving the key, an alert message is displayed (refer to Figure 10.110).

10. Click **No** to save the key and shift the focus to the other object. If you click **Yes**, then the defined key is cleared and focus is shifted to the other object.



You can rearrange the keys by dragging it up or down in the list.



You can edit or delete a key from the Parameters Panel itself. For details, refer to the Managing a Global Variable from Parameter Panel section.

The alert message is also displayed when shifting focus between the *Global* and *Node* tabs.



# Mapping the Key with Target Element

#### Steps to use the Key Function

- 1. Ensure that the <u>source and target schemas are loaded</u> and all their elements are listed under their respective nodes.
- 2. Map source and target elements as displayed in figure below (see Figure 10.129).

🗛 ADEPTIA - Data Mapper - EMP_Record	
File View Actions Help	
👔 Data Mapper 🔄 XSL 🥥 Debugger	
💾 🛛 🥥 🎘 🕕	Current Element : AGE
ି Open Source Schema	Carl Popen Target Schema
A Structure_of_source_XSD ⇒ A Root (Source) ⇒ A Roord ⇒ Record ⇒ EMPID (string) (M) ⇒ EMAILID (string) (M) ⇒ SALARY (nteger) (M) ⇒ SALARY (nteger) (M) ⇒ AGE (nteger) (M) ⇒ ARecord ⇒ Record ⇒ Rec	Structure_of_destination_XSD
Math String Date Aggregation Conditional Axis Boolean Context XSL Template DB	
Mapping Rules Textual Rules     Decial Variables	Parameters     Global Variables     Global Var

Figure 10.129: Map Source and Target Elements

- 3. Click the parent node (e.g. *Record*) of the target element and apply the *For Each* for parent node (e.g. *Record*) of schema *Source1*
- 4. Create a local variable at Record level of the target schema. Select *EMPID* element of Source1 schema as the value of the variable.
- 5. Click *target* element (e.g. Address) on which you want to apply the key.
- 6. Click **Node** tab displayed in the Mapping Graph Area. All tabs of the Node tab are displayed.
- 7. Click **Textual Rules** tab. The Textual Rules pane is displayed in the Mapping Graph Area.
- 8. Click **Aggregation** mapping function and select **Key** sub-function. The Key function is displayed in the Textual Rules pane (see Figure 10.130).



& ADEPTIA - Data Mapper - EMP_Record	
File View Actions Help	
🗊 Data Mapper 📑 XSL 🧔 Debugger	
💾 🛛 🥥 🎘 🕕 Curre	nt Element : ADDRESS
Carl Open Source Schema	Carl Open Target Schema
Structure_of_source_XSD     A Root (Source1)     B ▲ Record     B recordNumber     B ← Record(Number)     B	Structure_of_destination_XSD A Root (Employee_Data) C A Record TecordNumber MANE (string) (M) C BMAILD (string) (M) C BMAILD (string) (M) C BMAILD (string) (M) C ADDRESS (nteger) (M) C ADDRESS (string) C ADDRESS (string)
EMAILID (string)     EMAILID (string)	
8 Local Variables 🔀 Properties	Parameters
key(,)	Global Variables B

Figure 10.130: Key Function

- 9. Place the cursor, at the first argument of key function and double-click the required key that you want to apply, from *Keys* in the Parameters Panel. This is the first argument for the key function.
- 10. Place the cursor at the second argument of key function and double click the required *local variable*, under *Local/Ancestor Variables* in the Parameters Panel. This is the second argument for the key function.
- 11. The syntax of the key function in the textual rules pane will be displayed as:

key ("key1" , \$VarEmpidSource1)

12. Append the name of the element (*Address*), of the *source2* schema, which needs to be mapped to the target element (*Address*). Now the syntax of the mapping will be displayed as:

key ("key1" , \$ VarEmpidSource1)/Address


(see Figure 10.131)



ADEPTIA - Data Mapper - EMP_Record  File View Actions Heb				
👔 Data Mapper 🕋 XSL 🥝 Debugger				
💾 🗵 🥥 🤔 🕕 Current Element : ADDRESS				
Core Schema	Copen Target Schema			
Structure_of_source_XSD     A Root (Source1)     A Roord	Structure_of_destination_XSD			
Math String Date Aggregation Conditional Axis Boolean Context XSLTemplate DB				
Imapping Rules       Imapping Rules       Imapping Rules       Imapping Rules         Key('Address_Key' , & VarEmpidSourcel )/ADDRESS         Imapping Rules       Imapping Rules         Reg       Imapping Rules	Parameters     Global Variables     Current Variables     Curtent Variables     Curtent Variables     Curtent Variables     Curtent Variables     Curtent Variables     Curtent Variables     Context Variables     Co			

Figure 10.131: Map Key Function Node to Target Element

- 13. Click **Apply Mapping** (**S**) button. This maps the key to the address element of the target schema. If you shift the focus to another target element, or click any of the *Mapping Rules, Textual Rules, Properties, Node, XSL* or *Debugger* tabs, without applying the mapping, then an alert message is displayed (refer to Figure 10.110).
- 14. Click **No** to apply the mapping and shift focus to the other object. If you click **Yes**, then the mapping activity is cleared and is replaced by the previous mapping in the Mapping Graph Area and the focus is shifted to the other object.
- 15. Apply *For Each* on element *address* of target schema from Root level of *Source2* schema. This will execute key in the context of second source schema (i.e. *Source2*).
- 16. <u>Save</u> the mapping activity and exit the Data Mapper.



# **Declaring Connection Info Variable**



Connection Info variables are used as a parameter in the DBQuery function, when extracting information from the database.

#### Steps to declare a Connection Info Variable

- 1. Ensure that the <u>source and target schemas are loaded</u> and all their elements are listed under their respective nodes.
- 2. Click **Global** tab in the Mapping Graph Area. All tabs of the Global tab are displayed.
- 3. Click **Connection Info** tab. The Connection Info Variable pane is displayed in the Mapping Graph Area (see Figure 10.132).

& ADEPTIA - Data Happer - customer			X	
Pile View Actions Help				
👔 Data Mapper 🚍 XSL 🎯 Debupper				
💾 🛿 🗭 🤁 🕕		Current Element : AGE		
Copen Source Schema		Q (	Ipen Target Schema	
Structure of source, SSD A Root (EndSorce, TextSchema) A Root (S) A NAME (Kinng) (M) A NAME (Kinng) (M) B NARLD (Kinng) (M) B NARLD (Kinng) (M) A NOTESO (Kinng) (M) A NOTESO (Kinng) (M) A NOTESO (Kinng) (M) B NARLD (Kinng) A NATEORDING (date) B SKIANT(DN (kinng)) A AGE (integer) 1		Structure_of_destruction_XSD :: A Root (GASCrot_TextSchema) ::: A Record ::: A Record :: A Record ::: A Record :: A Reco	2	
-			-	
Math String Date Aggregation Conditional Axis Boolean Context XSLTemplate DB				
Global Variables   Custom Methods   Kiey Functions   Context Variables   Connecto Context Variables   Connecton Variable Name Click there to declare variable Enclick there to declare variable	le Name O Connection Variable Value		Paramèters     B:      Global Variables     B:      Global Variables     B:      Global Variables     B:      Global Variables     B:      Global Variables	
	EvalJMSE_DBInfo	DBINO ID 192154001011112194194445000012 192154001191212A546759400009 1921540011661122991500294000003	<ul> <li>→ Krys</li> <li>⊕ Context Varables</li> <li>⊕ → Templates</li> <li>⊕ → Templates</li> <li>⊕ Global Methods</li> <li>→ Value Map</li> </ul>	

Figure 10.132: Connection Info Variable Pane

- 4. Click *Connection Variable Name* text field and enter the name of the *Connection Info* variable you want to create (e.g. Var1). Press the **Tab** or **Enter** key. This takes the control to the *Connection Variable Value* field.
- The Connection Info variable accepts a DBInfo as its value. Thus, the Connection Variable Value field displays a list of existing DBInfo Names and their IDs. Select the DBInfo name that you want to assign for the Connection Info variable (see Figure 10.133).



ADEPTIA - Data Happer - customer  File View Actions Help			X
1 Data Mapper 1 XSL Or Debugger		Research Filesen and a 197	
≝ ⊠ ⊘ ₴		Current Element : AGE	
Carl Open Source Schem	b		📲 🖓 Open Target Schema
Studture_of_source_XSD		Structure, of, destructor, XSD A Record A R	-
Math String Date Aggregation Conditional Axis Boolean Context >>	SL Template DB		
Global Vanables   Custom Methods   Kiey Punctons   Context Vanables   Co         Context Vanables   Co           Grametion Vaniable Name         Garmetion Vaniable Name         Select DBInfo	omection Info	ariable Value	Parameters     B      Global Variables     B      Cucal Variables     B      Cucal Variables     B      Custom Methods     Kers
	DBinto Name            P         EvaPr_Database/no.5QServer           C         EvaDer_Dbinto           C         EvaDer_Dbinto           EvaDer_Dbinto            Syndres         Syndres	DBInfo ID 19226600151112364945000012 19226600119811227544975400009 19216600116611219510029600003	H → Chrys H → Crempletes H → Crempletes H → Connection Info H → © Global Methods H → © Value Map

Figure 10.133: Enter Connection Variable Value



- 6. Click **Save Connection Variable** () button to save the *Connection Info* variable. This Connection Info variable is added to the list of existing variables in the *Connection Variable Name* field. It is also displayed under *Connection Info* in the Parameters Panel. If you shift the focus to another node, or click any of the *Mapping Rules, Textual Rules, Local Variables, Properties, XSL* or *Debugger* tabs, without saving the Connection Info variable, an alert message is displayed (refer to Figure 10.110).
- 7. Click **No** to save the Connection Info variable and shift the focus to the other object. If you click **Yes**, then the defined Connection Info variable is cleared and the focus is shifted to the other object.

You can rearrange the Connection Info variables by dragging it up or down in the list.

You can edit or delete a Connection Info variable from the Parameters Panel itself. For details, refer to the <u>Managing a Global Variable</u> <u>from Parameter Panel</u> section.

### **Setting Target Element Properties**

You can set various properties of a target element.



#### Steps to set target element properties

- 1. Ensure that the <u>source and target schemas are loaded</u> and all their elements are listed under their respective nodes.
- 2. Click the *target* element for which you want to set properties.
- 3. Click **Node** tab displayed in the Mapping Graph Area. All tabs of the Node tab are displayed.
- 4. Click **Properties** tab. The Properties pane is displayed (see Figure 10.134)

A ADEPTIA - Data Happer - custom	er				_ 8 ×
Ele Yew Actions Help					
👔 Data Mapper 🔄 XSL 🧐 Debug	per				
💾 🛛 🛛 🎅 🕕 📃		Current	Element : NAME		
	😭 🖓 Open Source Schema		0 G 🔁	Open Target Schema	
Structure_of_source_XS0	(M) (4) ((H) (8) (9)		Structure_of_destination_XSD		A
Math Shine Date Annenation Con	nditional Axis Boolean Context XSLTemplate DB				×
	s 🕐 Local Variables 70% Properties		-	Parameters	
Mapping Rules Textual Rules     XPath	RootRecord/NAME			Global Variables	
ForEach				B      Local Variables     Custom Methods     K      Keys     B      Context Variables	
> Sorting	Click here to	add/view Sorting Rules		Templates	
Disable-Output-Escaping	no		<b>v</b>	Giobal Methods	
Sorting     Disble-Output-Escaping     Comments			E E	Value Map	
			Save Properties		

Figure 10.134: Properties Pane

The Properties pane comprises of various properties, which are outlined in the table below.

Property	Description
XPath	Displays the XPath of the selected target element. It is a read-only field.
For Each	Sets the For Each property for the target element. It is used to repeat occurrences of a target element depending on the total occurrences of a source element in the source file. To set the For Each property refer to the section Setting the For Each Property.
Sorting	Sets the Sorting rules for the target element. It also allows you to view or remove sorting rules for the target element. To set the Sorting Rules, refer to the

Table 10.22: Properties of a Target Element



	section Setting Sorting Rules.
Disable-Output-Escaping	Sets the disable-output –escaping property for the target element. It is used to include this property under the 'value-of' element in the generated XSL. By default, this property is set as 'no'. For details on this property, refer to the section Using XSL Property.
Comments	Displays comments entered for the target element. This is a data entry field and allows you to enter comments for the target element. To enter comments, refer to the section Adding Comments for Target Element.

- 5. Enter the properties required for the selected target element.
- 6. Click **Save Properties** to save the properties entered for the target element. If you shift focus to another node, or click any of the *Mapping Rules, Textual Rules, Global Variables, Properties, XSL* or *Debugger* tabs, without saving the properties, an alert message is displayed (refer to Figure 10.110).
- 7. Click **No** to save the properties and shift focus to the other object. If you click **Yes**, then the defined properties are cleared and the focus is shifted to the other object.

### Setting For Each Property

The *For Each* property is used to repeat the occurrences of a target element or node, depending on the total occurrences of a source element or a node in the source file.

For example, an XML schema with a node customer has three elements, first\_name, last\_name, and state. This schema is used both at the source and at the target end.

Supposing, the source file has 10 occurrences of the customer. Applying the For Each property on the target node customer, for the source node customer, generates an output file containing 10 occurrences of the customer in it.

If *For Each* property is not used, an output file is generated with only one occurrence of customer in it.

For Each and Apply Template both can not be used simultaneously on one node.

### Steps to set the For Each property

- 1. Ensure that the **source and target schemas are loaded** and all their elements are listed under their respective nodes.
- 2. Click the *target* element for which you want to set the For Each property.
- 3. Click **Node** tab displayed in the Mapping Graph Area. All tabs of the Node tab are displayed.
- 4. Click **Properties** tab. The Properties pane is displayed (refer to Figure 10.134).




5. Click the *For Each* property field and then double-click the *source* element using which you want to apply the For Each property. This displays the entire path of the source element in the *For Each* field (see Figure 10.135).

& ADEPTIA - Data Happer - custo	mer				_8×
File View Actions Help					
👔 Data Mapper 🔄 XSL 🥥 Debu	oper				
💾 🛛 🗢 💐 🔍 🗌			Current Element : NAME		
	Copen Source Schema			Coper Coper	Target Schema
Structure, of, source, XSD     A Roce (BaS/cort, TestS)     A Roce (BaS/cort, TestS)     A Roce (S)     A Roce (R)     A	(4) (4) (4) (4) (4) (4) (4) (4) (4) (4)		Structure_of_destination_XSD	) (M) ) V) e)	<u>م</u> ۲
	onditional Axis Boolean Context XSL Template DB				Parameters
Mapping Rules W Textual Rules	Root/Record/NAME				🖲 ও Global Variables
> XPath ForEach	Sinput_EvalScript_TextSchema/Root/Record/NAME				E      Custom Methods     Custom Keys     E     Ocntext Variables
a Sorting		Click here to add/view Sorting Ru	des		Templates
Disable-Output-Escaping	no			¥	Connection Info     Gobal Methods
Comments				2	La Value Map
			Save Prop	rties	

Figure 10.135: Source Element in For Each Property

You can set the *For Each* property on more than one source element. You can use the | character as a separator between the XPath of each source element.

- 6. Click **Save Properties**. This applies the For Each property for the selected target element. If you shift focus to another node, or click any of the *Mapping Rules, Textual Rules, Global Variables, Properties, XSL* or *Debugger* tabs, without saving the For Each property, an alert message is displayed (refer to Figure 10.110).
- Click No to save the For Each property and shift focus to the other object. If you click Yes, then the defined For Each property is cleared and the focus is shifted to the other object.





To remove the *For Each* property from the target element, right-click *target* element and select **Remove Mappings** option. This displays the Remove Mapping Options dialog box. Select the *Remove For Each* checkbox and click **OK**.




### Adding Comments to Target Schema Elements

Comments are used to provide additional information to target nodes and elements. Comments are displayed as tool tips and are reflected in the XSL generated under the *XSL* tab.

#### Steps to add a comment to the target element

- 1. Ensure that the **source and target schemas are loaded** and all their elements are listed under their respective nodes.
- 2. Click the *target* element for which you want to add a comment.
- 3. Click **Node** tab displayed in the Mapping Graph Area. All tabs of the Node tab are displayed.
- 4. Click **Properties** tab. The Properties pane is displayed (refer to Figure 10.134).
- 5. Click the *Comments* property field and enter the comment for the selected target element (see Figure 10.136)



#### Figure 10.136: Enter Comment

- 6. Click **Save Properties**. This adds the comment and displays it next to the target element. If you shift focus to another node, or click any of the *Mapping Rules, Textual Rules, Global Variables, Properties, XSL* or *Debugger* tabs, without saving the comments, an alert message is displayed (refer to Figure 10.110).
- 7. Click **No** to save the comments and shift focus to the other object. If you click **Yes**, then the defined comments are cleared and the focus is shifted to the other object.



Once a comment is added to a target element, the letter **(CM)** is displayed next to the target element. This signifies that a comment has been created for the target element. Refer to <u>Table of Suffixes</u> for details on suffixes displayed next to a target element.

### Setting Sorting Rules

You can set sorting rules for a target element. It is used to sort value of elements in the generated output. While generating the output XML, the value of elements can be sorted either in ascending or descending order. For example, records of the employee can be sorted on the basis of their salaries. Figure 10.137 shows input XML before sorting.

```
<?xml version="1.0" encoding="UTF-8" ?>
- <employees>
employee attribute="14" attribute1="15">
 <TESTCASENO>TESTCASENO1</TESTCASENO>
 <DESCRIPTION>DESCRIPTION1</DESCRIPTION>
 <NAME>John</NAME>
 <ADDRESS>Address1</ADDRESS>
 <EMAILID>EMAILID1</EMAILID>
 <PHONENO>PHONENO1</PHONENO>
 <DOB>DOB1</DOB>
 <DEPT>DEPT1</DEPT>
 <SALARY>10000</SALARY>
 <DOJ>DOJ1</DOJ>
 <DESIGNATION>DESIGNATION1</DESIGNATION>
 <AGE>34</AGE>
 </employee>
employee attribute="14" attribute1="15">
 <TESTCASENO>TESTCASENO2</TESTCASENO>
 <DESCRIPTION>DESCRIPTION2</DESCRIPTION>
 <NAME>David</NAME>
 <ADDRESS>ADDRESS2</ADDRESS>
 <EMAILID>EMAILID2</EMAILID>
 <PHONENO>PHONENO2</PHONENO>
 <DOB>DOB2</DOB>
 <DEPT>DEPT2</DEPT>
 <SALARY>8000</SALARY>
 <DOJ>DOJ2</DOJ>
 <DESIGNATION>DESIGNATION2</DESIGNATION>
 <AGE>45</AGE>
 </employee>
 <employee attribute="14" attribute1="15">
```



<TESTCASENO>TESTCASEN3</TESTCASENO> <DESCRIPTION>DESCRIPTION3</DESCRIPTION> <NAME>Ricky</NAME> <ADDRESS>ADDRESS3</ADDRESS> <EMAILID>EMAILID3</EMAILID> <PHONENO>PHONENO3</PHONENO> <DOB>DOB3</DOB> <DEPT>DEPT3</DEPT> <SALARY>15000</SALARY> <DOJ>DOJ3</DOJ> <DESIGNATION>DESIGNATION3</DESIGNATION> <AGE>36</AGE> </employees>



Figure 10.138 shows the Output XML after sorting.

```
<?xml version="1.0" encoding="UTF-8" ?>
- <employees xmlns:java="http://xml.apache.org/xslt/java"</p>
xmlns:str="http://exslt.org/strings">
_ <employee attribute="" attribute1="">
 <TESTCASENO>TESTCASEN3</TESTCASENO>
 <DESCRIPTION>DESCRIPTION3</DESCRIPTION>
 <NAME>Ricky</NAME>
 <ADDRESS>ADDRESS3</ADDRESS>
 <EMAILID>EMAILID3</EMAILID>
 <PHONENO>PHONENO3</PHONENO>
 <DOB>DOB3</DOB>
 <DEPT>DEPT3</DEPT>
 <SALARY>15000</SALARY>
 <DOJ>DOJ3</DOJ>
 <DESIGNATION>DESIGNATION3</DESIGNATION>
 <AGE>36</AGE>
 </employee>
employee attribute="" attribute1="">
 <TESTCASENO>TESTCASENO1</TESTCASENO>
 <DESCRIPTION>DESCRIPTION1</DESCRIPTION>
 <NAME>John</NAME>
 <ADDRESS>Address1</ADDRESS>
 <EMAILID>EMAILID1</EMAILID>
```



```
<PHONENO>PHONENO1</PHONENO>
 <DOB>DOB1</DOB>
 <DEPT>DEPT1</DEPT>
 <SALARY>10000</SALARY>
 <DOJ>DOJ1</DOJ>
 <DESIGNATION>DESIGNATION1</DESIGNATION>
 <AGE>34</AGE>
 </employee>
_ <employee attribute="" attribute1="">
 <TESTCASENO>TESTCASENO2</TESTCASENO>
 <DESCRIPTION>DESCRIPTION2</DESCRIPTION>
 <NAME>David</NAME>
 <ADDRESS>ADDRESS2</ADDRESS>
 <FMAILID>FMAILID2</FMAILID>
 <PHONENO>PHONENO2</PHONENO>
 <DOB>DOB2</DOB>
 <DEPT>DEPT2</DEPT>
 <SALARY>8000</SALARY>
 <DOJ>DOJ2</DOJ>
 <DESIGNATION>DESIGNATION2</DESIGNATION>
 <AGE>45</AGE>
 </employee>
 </employees>
```

### Figure 10.138: Output XML



The Sorting rules can be set only for record where *For Each Mapping* or *Apply Template* is used. The *<xsl:apply-templates>* element applies a template to the current element or to the child nodes of the current element, when the parent elements of source and target schemas are mapped.

### Steps to set Sorting Rules

- 1. Ensure that the **source and target schemas are loaded** and all their elements are listed under their respective nodes.
- 2. Ensure that the <u>source and target elements to be mapped are selected and</u> <u>displayed</u> in the Mapping Graph Area.
- 3. To use Apply template, click *Employee* (parent) element in the source panel and drag the mouse pointer to the *Employee* (parent) element in the target panel. A line is displayed between the source and target panels indicating the mapping between source and target elements (see Figure 10.139).



Image: Contract State Structure_of_cource_XSD       Image: Cource State Structure_of_cource_XSD         Image: Structure_of_cource_XSD       Image: Cource Structure_of_cource_XSD         Image: Structure_of_cource_XSD       Image: Cource Structure_of_cource_XSD         Image: Structure_of_cource_XSD       Image: Cource_XSD         Image: Structure_of_XSD       Image: Cource_XSD	& ADEPTIA - Data Mapper - EMP_Record		_ 18 ×
Current Element : NAME         Structure_of_source_XSD         A Root (EvalScipt_TextSchema)         A Root (EvalScipt_Titt)	File View Actions Help		
Accel (evaluation of the second (M)     ADDRESS (string) (M)     ADTECPSINING (state) (M)     DESIGNATION (string) (M)     ADTECPSINING (string) (M)     ADT		Irrent Element : NAME	
Structure_of_source_XSD  A Root (EvalScript_TextSchema)  A Ro			
Math       String       Dete       Aggregation       Conditional       Axis       Boolean       Context       XSL Template       DB         Image: Imag	Structure_of_source_XSD     Acoot (EvalScript_TextSchema)     Acoot (EvalScript_TextSchema)     Acobest (EvalScript_TextSchema)     Acobest (String) (M)     Acobest (String) (M)     OATEOFERITH (date) (M)     ODATEOFERITH (date) (M)     ODATEOFERITH (date) (M)     ODEPARTMENT (string) (M)     ODATEOFINING (date) (M)     ODATEOFINING (date) (M)	Structure_of_destination_XSD A Root (EvalScript_TextSchema) A Root (EvalScript_TextSchema) A Root (M) ADDRESS (string) (M)	×
Image: The second se			-
1       Size       1       Size       0       Cooler Variables         1       NAME.       1       NAME.       0       Cooler Variables         0       Cooler Variables       0       0       Cooler Variables         0       Cooler Variables       0       0       Cooler Variables         0       Context Variables       0       0       0         0       O       0       0       0       0         0       0       0       0       0       0         0       0       0       0       0       0         0       0       0       0       0       0         0       0       0       0       0       0         0       0       0       0       0       0         0       0       0       0       0       0         0       0       0       0       0       0       0         0       0       0       0       0       0       0       0         0       0       0       0       0       0       0       0         0       0       0			

Figure 10.139: Apply Template



- 4. Click **Node** tab displayed in the Mapping Graph Area. All tabs of the Node tab are displayed.
- 5. Click **Properties** tab. The Properties pane is displayed (refer to Figure 10.134).
- 6. Click the **Click here to add/view Sorting Rules** option displayed against the Sorting property field. This displays the Add New Sorting Rules dialog box (see Figure 10.140)

🛝 Add New Sorting Rules		
Target Element :	Record	
Source Element :		
DataType :	text 💌	
Order :	ascending 💌	
	Save Close View/Remove	

Figure 10.140: Sorting Rules Dialog Box



- 7. This screen displays the name of the selected target record to be sorted. Type the name of the source element on the basis of which you want to sort output (e.g. SALARY), in the *Source Element* field.
- 8. Select the data type as either text or numeric from the *Data Type* drop-down list. This specifies how the input value is to be interpreted. By default, text is selected.
- 9. Select the sorting order as ascending or descending from the *Order* drop-down list. By default, ascending is selected.
- 10. Click **Save** to save the sorting rule.
- 11. Click Close to return the Data Mapper screen. The letter (SR) is displayed next to the sorted target element. This signifies that the target element has been sorted based on the specified source element. Refer to the <u>Table of Suffixes</u> for details on suffixes displayed next to an element.

More than one sorting can also be applied to a single target element. For example, if salary of two employees is same, they can be further sorted out based on their age.
 To delete sorting, click View/Remove button. The Remove Sorting Rules dialog box is displayed with a list of existing sorting rules. Select sorting rule and click Remove/Remove All to delete sorting rules.

Once the sorting is applied based on the set rules, the output XML is displayed as displayed in Figure 10.138.

### Filtering of Elements/Attributes in Target Data

You can filter elements or attributes from appearing in the target XML. There are two ways to filter data:

- Using IFF Condition
- Using Apply Filter checkbox from right-click popup menu

The Apply Filter checkbox method is recommended as it is easy to use and can be done individually on multiple nodes, directly from the data mapper applet.

### Using Apply Filter Checkbox

### Steps to filter using Apply Filter Checkbox

- 1. Ensure that the <u>source and target schemas are loaded</u> and all their elements are listed under their respective nodes.
- 2. Right-click the *target* element that you want to filter, and mark the *Apply Filter* checkbox as checked (see Figure 10.141). By default, this checkbox is unchecked.



& ADEPTIA - Data Mapper - EMP_Record	_8×
File View Actions Help	
Tota Mapper 🔄 XSL 🤤 Debugger	
	Current Element : DEPARTMENT
Copen Source Schema	Copen Target Schema
Structure_of_source_XSD	Structure_of_destination_XSD  A Root (EvalScript_TextSchema)  A NAME (string)  A DDRESS (string)  A DDRESS (string)  PHONENO (integer)  D ATEOFBIRTH (date)  DATEOFBIRTH (date)  A GE (int  A Sign Stream  A GE (int  A Remove Schema  A Remove Sche
	Remove Clone
Math String Date Aggregation Conditional Axis Boolean Context XSL Template DB	Copy Mapping
Begy Happing Rules Textual Rules 🕲 Local Variables 🔅 Properties	
	Custom XSL Before Custom XSL After Custom XSL After Custom XSL After Custom XSL After Custom

Figure 10.141: Checking Apply Filter Checkbox

3. This selection will filter the selected element from the target output XML data. You can uncheck this checkbox anytime to display the element in the target data.

Ø	You can apply this filtering option on the element or attribute levels.
Ø	Once the filter is applied on the target element, the letters (FL) are displayed next to each filtered target element. This signifies that the filter has been applied for the target element. Refer to <b>Table of Suffixes</b> for details on suffixes displayed next to an element.

### **Creating Clone of Target Element**

Cloning means generating replicas of the target elements or nodes. You can create clones of all target elements.

### Steps to create a clone

- 1. Ensure that the <u>source and target schemas are loaded</u> and all their elements are listed under their respective nodes.
- 2. Right-click the *target* element and select the **Duplicate Node** option.



4	Ø
- 6	4

You can create a clone of all target nodes except the root node. Thus, the *Duplicate Node* sub-option is displayed as inactive for the root node.

3. The element which is created using cloning is displayed with the suffix [1] after its name. Subsequent clones that are created for that element will have the suffix [2] and so on. You can create a maximum of 50 occurrences of an element, with one main element and 49 clones.

### Removing Clone of Target Element

### Steps to remove a clone

- 1. Ensure that the <u>source and target schemas are loaded</u> and all their elements are listed under their respective nodes.
- 2. Right-click the cloned element that you want to remove and select the **Remove Clone** option. A screen is displayed confirming the removal of the selected clone (see Figure 10.142).





Figure 10.142: Confirm Remove Clone

3. Click **Yes** to remove the clone. This removes the selected clone from the target schema.



### Removing Schema

You can remove a schema from the source or target panels. If a source or target schema is removed, everything associated with the mapping of the schema such as Mapping Graph Area, Connection Lines or For Each property is removed.

#### Steps to remove a schema



- 1. Ensure that the <u>source and target schemas are loaded</u> and all their elements are listed under their respective nodes.
- 2. Right-click the *root* element of the schema that you want to remove and select the **Remove Schema** option. A screen is displayed confirming the removal of the selected schema (see Figure 10.143).




Figure 10.143: Confirm Remove Schema

3. Click **Yes** to remove the schema. This removes the selected clone from the target schema.



A schema can be removed only from the root element. Thus, the *Remove Schema* option is displayed as active only for the root element.

### Adding Custom XSL

At times, you may want to add some additional specialized XSL to a target element, or at the top or bottom of the mapping XSL. You can do this by adding custom XSL code.

### Steps to add custom XSL code for a Target Element

- 1. Ensure that the <u>source and target schemas are loaded</u> and all their elements are listed under their respective nodes.
- 2. Right-click the *target* element and select the **Custom XSL Before** option (see Figure 10.144).



🗶 ADEPTIA – Data Mapper – EMP_Record	@_×
File View Actions Help	
Tota Mapper 🔄 XSL 🤬 Debugger	
💾 🛛 🥥 🤔 🕕 🛛 🖓 Cur	rent Element : DEPARTMENT
ି⊴ା⊋ Open Source Schema	🔄 🆓 Open Target Schema
Structure_of_source_XSD     B A Root (EvalScript_TextSchema)     A Root (EvalScript_TextSchema)     A Root (EvalScript_TextSchema)     A Roberss (string) (M)     ADDRESS (string) (M)     ADDRESS (string) (M)     DATEOFBIRTH (date) (M)     DATEOFBIRTH (date) (M)     DEPARTMENT (string) (M)     DATEOFJOINING (date) (M)     DESIGNATTN (string) (M)     AGE (integer) (M)     AGE (integer) (M)	Structure_of_destination_XSD
Math String Date Aggregation Conditional Avis Boolean Context XSLTemplate DB	Copy Mapping
	Reste Mapping
Mapping Rules Textual Rules O Local Variables Local Varia	Custom XSL Before ↓ Custom XSL After ↓ Custom XSL After ↓ Custom XSL After ↓ Methods ↓ Methods ↓ Variables ↓ Methods ↓ Variables ↓ tes ↓ Connect Matching Children ↓ Global Methods ↓ Variables ↓ Varia
4	

Figure 10.144: Select Custom XSL Before Option

3. The Add Custom XSL Before screen is displayed for the target element. Enter the custom XSL code for the target element (see Figure 10.145).



& Custom XSL Before : DEPARTMENT	×
1 <departmentbefore></departmentbefore>	
2 <xsl:vaue-of select="DEPARTMENT"></xsl:vaue-of>	
3 <departmentbefore></departmentbefore>	
	-
	►
Clear Save Cancel	

Figure 10.145: Enter Custom XSL Code

4. Click **Save** to save the XSL code and close the screen. Alternately, click **Clear** to clear the XSL code, or **Cancel** to close the screen without saving the changes.



Similarly, you can add custom XSL code after a target element, by selecting **Custom XSL After** option from the right menu (refer to Figure 10.144).

### Steps to add global custom XSL code

- 1. Ensure that the <u>source and target schemas are loaded</u> and all their elements are listed under their respective nodes.
- 2. Click the Actions menu and select Global Custom XSL Before option (see Figure 10.146).



Image: Structure Actions Help         Image: Structure Actions X3. Before         Child         Image: Structure Actions X3. Before         Image: Structure Actions X3. After         On demand (optimized) loading of XML Schema tree         Image: Structure Actions X3. After         On demand (optimized) loading of XML Schema tree         Image: Structure Actions X3. After         On demand (optimized) loading of XML Schema tree         Image: Structure Actions Ac	🙏 ADEPTIA	A – Data Mapper – EMP_Record			_ 8 ×
Add Yake Map Options       Current Element : DEPARTMENT         Manespace       Current Element : DEPARTMENT         Structure_of_destination_XSD       Structure_of_destination_XSD         Enable DBQuery caching       Current         Structure_of_destination_XSD       Structure_of_destination_XSD         Enable DBQuery caching       Current         Structure_of_destination_XSD       Structure_of_destination_XSD         Enable DBQuery caching       Current         Structure_of_destination_XSD       Structure_of_destination_XSD         Search Element       Current Structure_of_destination_XSD         Search Element       Current Structure_of_destination_XSD         Search Element       Current Structure_of_destination_XSD         Search Element       Current Structure_of_destination_XSD         Other String Others       Other String (M)         O DATECO-FORINNIC (date) (M)       O DEPARTMENT (string) (M)         O DATECO-FORINNIC (date) (M)       O DESIGNATION (string) (M)         AGE (integer) (M)       O Destignation       Structure_of Conditional Avis Boolean Context XSL Template DB         Mapping Rules       Textual Rules       Concent Variables       Parameters         Mapping Rules       Textual Rules       Properties       Parameters       Context Variables       Parameters <th>File View</th> <td>Actions Help</td> <td></td> <td></td> <td></td>	File View	Actions Help			
Global Custom XSL After     CutH4     On demand (optimized) loading of XML Schema tree     CHH4     On demand (optimized) loading of XML Schema tree     CHH4     Structure.of.destination.XSD     Structure.of.destination.XSD	📸 Data M	🥑 Validate XSL	Ctrl+V		
Global Custom XSL After     CtH+A     On demand (optimized) loading of XML Schema tree     CtH+A     On demand (optimized) loading of XML Schema tree     CtH+A     Structure_of_destination_XSD     Structure_of_destination_XSD	Ē 💾 🚺	📓 Global Custom XSL Before	Ctrl+B	urrent Element : DEPARTMENT	
Structure_of_destination_XSD     Structure_of_destination_XSD		🤤 Global Custom XSL After			1
And Carlson Auto Map Options     Chrl-B     Beake DRQuery caching     Chrl-B     Search Element     Chrl-F     Search Element     Search Element			Ctrl+E		Schema
Search Element       Ctrl+F         Set Data Viewer Record Count <ul> <li>ADDRESS (string) (M)</li> <li>ADDRESS (string) (M)</li> <li>ADDRESS (string) (M)</li> <li>ADATEOR/DINING (date) (M)</li> <li>DATEOR/DINING (date) (M)</li>         &lt;</ul>	📄 🗄 📥 F		•		
Search Element       Ctrl+F         Set Data Viewer Record Count <ul> <li>ADDRESS (string) (M)</li> <li>EMAILID (string) (M)</li> <li>EMAILID (string) (M)</li> <li>DATEOFDINING (date) (M)</li> <li< td=""><th>Ē.</th><td>Enable DBQuery caching</td><td>Ctrl+D</td><td></td><td></td></li<></ul>	Ē.	Enable DBQuery caching	Ctrl+D		
Add Custom Auto Map Options     Add Custom Auto Map Options     Add Value Map Options     Add Value Map Options     DATEOFJOINING (date) (M)     AGE (integer) (M)     DATEOFJOINING (date)     (M)     DATEOFJOINING (date)     (M)     DATEOFJOINING (date)     (M)     DATEOFJOINING (date)     (M)     AGE (integer) (M)     DATEOFJOINING (date)     (M)     AGE (integer) (M)     AGE (integer) (M)     DATEOFJOINING (date)     (M)     AGE (integer) (M)     DATEOFJOINING (date)     (M)     DATEOFJOINING     (H)     DATEO		Search Element	Ctrl+F	ADDRESS (string) (M)	
C Add Custom Auto Map Options     OATEC/FBIRTH (date) (M)     OEPARTMENT (string) (M)     OATEC/FDINNS (date) (M)     OATEC/FOINING (date) (M)     OATEC/FOI		Set Data Viewer Record Count			•
(*)* Add value Map Options       • SALARY (Integer) (M, LV)         • DATEOFJOINING (date) (M)       • ODESIGNATION (String) (M)         • DESIGNATION (String) (M)       • ODESIGNATION (String) (M)         • AGE (integer) (M)       • ODESIGNATION (String) (M)         • ODESIGNATION (String) (M)       • ODESIGNATION (String) (M)         • AGE (integer) (M)       • ODESIGNATION (String) (M)         • AGE (integer) (M)       • ODESIGNATION (String) (M)         • ODESIGNATION (String) (M)       • ODESIGNATION (String) (M)         • AGE (integer) (M)       • ODESIGNATION (String) (M)         • ODESIGNATION (String) (M)       • ODESIGNATION (String) (M)		© Add Custom Auto Map Options		DATEOFBIRTH (date)	(M)
DATEOFJOINING (date) (M)     DESIGNATION (string) (M)     AGE (integer) (M)		(v)= Add Value Map Options			
Math String Date Aggregation Conditional Axis Boolean Context XSL Template DB					(M)
Image: Second	-				V
1       DEPARTME.       0	Math Strin	ng Date Aggregation Conditional Axis Boolean Cor	ntext XSL Template DB		
Image: Contrast of the second seco			operties	· · · · · · · · · · · · · · · · · · ·	
	Data Viewer Global	Sparime <mark>, → 1 dep</mark>	ARTME.	X	Oustom Methods     Keys     Context Variables     Ornext Variables     Ornext Info     Onection Info     Olobal Methods

Figure 10.146: Select Global Custom XSL Before Option

3. The Add Global Custom XSL Before screen is displayed. Enter the global custom XSL code (see Figure 10.147).



🙏 Custom XSL Before : Global 🛛 🕺				
l <xsl:variable n<="" th=""><th>ame="varGlobalCustomerBefore"</th><th>select="'1000'"/&gt; 🔺</th></xsl:variable>	ame="varGlobalCustomerBefore"	select="'1000'"/> 🔺		
		F		
	Clear Save Cancel			

Figure 10.147: Enter Global Custom XSL Code

4. Click **Save** to save the XSL code and close the screen. Alternately, click **Clear** to clear the XSL code, or **Cancel** to close the screen without saving the changes.

Similarly, you can add global custom XSL code after mapping XSL, by selecting **Global Custom XSL After** option from the Actions menu (refer to Select Global Custom XSL Before Option screen).

5. Once you have entered the custom XSL code, it is saved in the Mapping XSL screen (see Figure 10.148).

 $\mathcal{D}$ 



1	<pre><?xml version='1.0'?></pre>
2	<xsl:stylesheet <="" version="1.1" xmlns:java="http://xml.apache.org/xslt/java" xmlns:xalan='&lt;/th&gt;&lt;/tr&gt;&lt;tr&gt;&lt;th&gt;3&lt;/th&gt;&lt;th&gt;&lt;pre&gt;&lt;xsl:output method="xml" version="1.0" encoding="ISO-8859-1" indent="yes"/&gt;&lt;/pre&gt;&lt;/th&gt;&lt;/tr&gt;&lt;tr&gt;&lt;th&gt;4&lt;/th&gt;&lt;th&gt;&lt;xsl:param name="_userName"/&gt;&lt;/th&gt;&lt;/tr&gt;&lt;tr&gt;&lt;th&gt;5&lt;/th&gt;&lt;th&gt;&lt;xsl:param name="_password"/&gt;&lt;/th&gt;&lt;/tr&gt;&lt;tr&gt;&lt;th&gt;6&lt;/th&gt;&lt;th&gt;&lt;xsl:param name=" class"/&gt;&lt;/th&gt;&lt;/tr&gt;&lt;tr&gt;&lt;th&gt;7&lt;/th&gt;&lt;th&gt;&lt;xsl:param name=" identifier"/&gt;&lt;/th&gt;&lt;/tr&gt;&lt;tr&gt;&lt;th&gt;8&lt;/th&gt;&lt;th&gt;&lt;xsl:param name=" subject"/&gt;&lt;/th&gt;&lt;/tr&gt;&lt;tr&gt;&lt;th&gt;9&lt;/th&gt;&lt;th&gt;&lt;xsl:param name=" repositoryPath"/&gt;&lt;/th&gt;&lt;/tr&gt;&lt;tr&gt;&lt;th&gt;10&lt;/th&gt;&lt;th&gt;&lt;xsl:param name=" Inputl"/&gt;&lt;/th&gt;&lt;/tr&gt;&lt;tr&gt;&lt;th&gt;11&lt;/th&gt;&lt;th&gt;&lt;xsl;variable name="Input Demo EmployeeSchema" select="document(\$ Input])"/&gt;&lt;/th&gt;&lt;/tr&gt;&lt;tr&gt;&lt;th&gt;12&lt;/th&gt;&lt;th&gt;&lt;xsl:variable name="apos"&gt;' xmlns:xsl="http://www.w3.org/1999/XSL/Transform" xsl:variable=""></xsl:stylesheet>
13	
14	<xsl:variable name="varGlobalCustomBefore" select="'1000'"></xsl:variable>
15	
16	<xs1:template match="/"></xs1:template>
17	<employees></employees>
18	<employee></employee>
19	PreCustom XSL starting for element EMPID>
20	<empidbefore></empidbefore>
21	<xs1:value-of select="EMPID"></xs1:value-of>
22	
23	<precustom element="" empid="" ending="" for="" xsl=""></precustom>
24	<pre><pre>cempid&gt;</pre></pre>
25	<pre><xsl:value-of select="%Input Demo EmployeeSchema/employees/employee/EMPID"></xsl:value-of></pre>
26	ENP ID
27	
28	<empidafter></empidafter>
29	<xs1:value-of select="EMPID"></xs1:value-of>
30	
31	
32	<firstname></firstname>
33	<xs1:value-of select="%Input Demo EmployeeSchema/employees/employee/FIRSTNAME"></xs1:value-of>
34	
35	<lastwame></lastwame>
36	<pre><xs1:value-of select="\$Input Demo EmployeeSchema/employees/employee/LASTWAME"></xs1:value-of></pre>
37	
38	
39	
40	
41	
42	<pre><xsl:variable name="varGlobalCustomBefore" select="'1000'"></xsl:variable></pre>
43	<1-Global PostCustom XSL ending>

Figure 10.148: Custom XSL Code in Mapping XSL

### Select Root

You can change the root element when XML schemas are loaded. The root element always appears as a tag in the Output section on the *Debugger* screen. You can change this tag by selecting the desired root element.

### Steps to select root element of a schema

- 1. Ensure that the **source and target schemas are loaded** and all their elements are listed under their respective nodes.
- 2. Right-click the *root element* of the schema whose root element you want to change and select the **Select Root** option.
- 3. The Select Root Element screen is displayed (see Figure 10.149). This screen displays a list of existing root elements for the selected schema in a drop-down list.



Select Roo	t		
employee			-
	ок	Cancel	

Figure 10.149: Select Root Element



All elements that are declared as global in the XSD are listed in this dropdown list.

4. Select the *root element* that you want to change from the *Select Root* drop-down list and click **OK**. A screen is displayed confirming the change of the root element (see Figure 10.150).



Figure 10.150: Confirm Change of Root Element

5. Click **Yes** to change the root element. This changes the root element and displays the selected root element.

The Select Root sub-option is displayed as active only for the root element.

### Adding Namespace Prefix

You can add a namespace prefix to a target element. This prefix is displayed next to the target element in the target schema, and is automatically displayed in the Output section on the *Debugger* screen.

### Steps to add a namespace prefix to a target element

1. Ensure that the **source and target schemas are loaded** and all their elements are listed under their respective nodes.



2. Right-click the element of the target schema for which you want to add a namespace prefix and select the **Add Namespace Prefix** option. The Add Namespace Prefix screen is displayed (see Figure 10.151).

Add Namespace Pre	fix Dial	og	×
Namespace I	Prefix:		
	Ok	Cancel	

Figure 10.151: Add Namespace Prefix

3. Enter the namepace prefix and click **OK**. This adds the prefix and displays it next to the selected target element in the target schema.




Once you add a namespace prefix for a target element, you need to add a namespace for it. To do this, refer to <u>Adding Namespace</u> section.

### Populating extension type element

If complex type of element is an extension type i.e. other complex types are extending from this type, then you have the option to load the hierarchy from the list of complex types, which are extending from original element type.

### Steps to select extension element

- 1. Ensure that the <u>source and target schemas are loaded</u> and all their elements are listed under their respective nodes.
- 2. Right-click the extension element of the schema whose element hierarchy you want to change and select the **Extension Element** option.



3. The Select Extension Element screen is displayed (see Figure 10.152). This screen displays a list of extension element type.



🛦 Select Extension Element 🛛 🔀	
Select Extension	
ens:Account 🗸	
OK Cancel	

Figure 10.152: Select Extension Element

4. Select the required extension type that you want to load from the *Select Extension Element* drop-down list and click **OK**. A screen is displayed confirming the change of extension element (see Figure 10.153).

Adeptia	a Mapper Warning!
•	Are you sure you want to change the extension node of schema?
	Yes No

Figure 10.153: Confirm Change of Extension Element

5. Click **Yes** to change the extension element. The selected hierarchy will be loaded.

# USING RECORD TO RECORD SERVICE

Record to Record Service takes inputs record by record and processes them according to the defined logic using java programming construct, and gives the output one record at a time. User can write Java logic that will be executed in this service. The Java logic has access to Record to Record script service, context of the process flow this service belongs to, input and output Stream handlers, which allow Java logic to access and manipulate input data to generate output and pass it to another service in the process flow.

In the Adeptia Suite this feature is available in:

BPM Suite	Integration Suite	ETL Suite
$\checkmark$	$\checkmark$	

### Prerequisites:

• Schema activity must be created before creating Record to Record Service. Steps to create Record to Record activity:



- 1. In the Adeptia Suite homepage menu, click **[+]** Configure to expand the tree. All the items in the Configure category are displayed.
- 2. Click [+] Services to expand the tree. All the items in the Services category are displayed.
- 3. Click [+] Data Transform to expand the tree, and then click Record to Record. The Manage Record to Record screen is displayed (see Figure 10.154).

[+] My Tasks [+] My Documents	Config	gure > Services > Data Transform >	Record to Record				
[+] My Solutions	New	Edit   Delete   Revisions   Dependencies		Select Field to Se	arch 💙		Search
[+] My Monitor [+] History							
	#	Name	Descripti	on	Owner	Perm.	Modified 🔻
[+] Design	1 ()	EvalRec_Record2Record	Record 2 Record Transformer		demouser	RWX	08/12/05 17:21
[-] Configure [+] Forms							
[+] WorkFlow							
[-] Services							
[+] Data Dictionary							
[+] Source							
[+] Schema							
[+] Target							
[+] Web Services							
[-] Data Transform							
🍫 Data Mapping							
ee Record to Record							

Figure 10.154: Manage Record to Record Service

4. Click the **New** link. The Create Record to Record screen is displayed (see Figure 10.155).



Design > Services > Data Transform > Record to	Record		
[-] Standard properties			
Name *			
Description *	I		
Description			<u>^</u>
			_
Script *			
			-
Input Format *	XML		
Schema Name (Input data) *	SELECT	•	
Output Format *	XML •		
[+] Advanced properties			
* Mandatory fields.			
Save Cancel			

Figure 10.155: Create Record to Record Service

- 5. Enter the name and description of the new Record to Record service in the *Name* and *Description* fields respectively.
- 6. Enter the sample Java script displayed in Figure 10.156 to perform the desired transformation.

### **Template Script**

Note: the complete script is executed for each record.
// setting data into process flow context
// context - This object represents the process flow context which is implicitly available to Script
context.put("Variable name", "Object value") ;
// reading data from process flow context
Object value=context.get("Variable name");
// Reading the input Record



```
// record - represents the input data record object, which is implicitly
available to Script
  String name = record.getField("name");
  String email = record.getField("email");
// Creating an Empty record
 com.adeptia.indigo.io.Record outputRecord =
com.adeptia.indigo.io.IoObjectPool.borrowRecord();
// Populating output Record
 outputRecord.addField(name);
 outputRecord.addField(email);
// Writing output record to output stream read by another activity
 // service- This is the "Record to Record" Service object which is also
available implicitly to the script.
 // "default"- this is the name of the output stream.keep this as it is.while
making process flow make sure you use the default stream only.
  service.write(outputRecord, "default");
// To wait for certain flag in process flow context so that next record
can be processed based on the value of flag
 while(true)
 {
  String isRecievedAck = (String) context.get("recievedAck");
  if(isRecievedAck == null || (isRecievedAck.equals("false")))
  {
    try
    {
     Thread.sleep(300);
    }
    catch(Exception e)
    {
    }
  }
  else
  {
   break;
  }
 } // end
```

### Figure 10.156: Sample Java Script

7. Select input and output format as either XML or Native (non XML) from the *Input Format* and *Output Format* drop-down lists respectively.



8. Select the source schema activity from the *Schema Name* drop-down list.

Ø	If any XML Schema is selected in the <i>Schema Name</i> drop-down list, then the <i>Input Format</i> must be selected as XML.
	To learn how to create Schema activity, refer to Creating Schema Activity section.
	To learn about Advanced Properties refer to <u>Changing Advanced</u> <u>Properties</u> section.

- 9. Click the **Save** button. A screen is displayed confirming that the Record-to-Record activity has been created successfully. If the comments property is enabled, then clicking Save will display a screen where you need to enter comments related to creating the Record-to-Record service (refer to Figure 3.6).
- 10. Enter the comments in the Add Comments field.



The comment should be at least 1 character in length.

11. Click **OK** to save the comments. This displays a screen confirming that the Record-to-Record service has been created successfully.



By default, the *Comments* property is disabled. To enable it, refer to the *Updating System Properties* section in *Administrator Guide*.



# **11** CREATING EXTENSIONS

This section describes

- Creating a custom plugin activity
- <u>Creating a Native Call activity</u>.

## **CREATING CUSTOM PLUGIN**

A custom plugin is a scripted service that can process data in a customized manner using javaprogramming constructs and provides an extension point for adding any customized data processing logic. It takes the input as a stream and generates the output as a stream. You can write a Java logic that will be executed in this service. Java logic has access to the script service, context of the process flow this service belongs to, input and output stream handlers that allow Java logic to access and manipulate input data to generate the output and pass it to another service in process flow.

In the Adeptia Suite this feature is available in:

BPM Suite	Integration Suite	ETL Suite
$\checkmark$	$\checkmark$	$\checkmark$

### Steps to create custom plugin activity

- 1. In the Adeptia Suite homepage menu, click **[+]** Configure to expand the tree. All the items in the Configure category are displayed.
- 2. Click [+] Services to expand the tree. All the items in the Services category are displayed.
- 3. Click **[+] Extensions** to expand the tree, and then click **Custom Plugin**. The Manage Custom Plugin screen is displayed (see Figure 11.1).

[+]	My Documents							
[+]	My Solutions	Config	jure > Services > Extensions > Cust	om Plugin				
[+]	My Monitor	1						
[+]	History	New	Edit   Delete   Revisions   Dependencies		Select Field to Se	arch 💌		Search
[+]	Design					0		Modified <b>*</b>
[-]	Configure	#	Name	Descripti		Owner	Perm.	1
	+] Forms	1 ()	EvalScript_ScriptedService	Scripted Service to Concatena	ite Employee Records	demouser	RWX	08/10/05 12:57
	+] WorkFlow							
	-] Services							
	[+] Data Dictionary							
	[+] Source							
	[+] Schema							
	[+] Target							
	[+] Web Services							
	[+] Data Transform							
	[-] Extensions							
	ee Custom Plugin							
	℃ <mark>0</mark> Native Call							





4. Click the **New** link. The Create Custom Plugin screen is displayed (see Figure 11.2).

Configure > Services > Exte	nsions > Custom Plugin	
[-] Standard properties		_
Name *		
Description *		
		<u> </u>
Script *		
[+] Advanced properties		
* Mandatory fields.		
Save Cancel		

Figure 11.2: Create Custom Plugin

- 5. Enter the name and description of the new custom plugin in the *Name* and *Description* fields respectively.
- 6. Enter the sample Java script displayed in Figure 11.3 to perform the desired transformation.

### Template Script:

```
// Setting data into process flow context
  // context - This object represents the process flow context,
which is implicitly available to Script
    context.put("Variable name", "Object value");
// Reading data from process flow context
    Object value = context.get("Variable name");
```






Figure 11.3: Sample JAVA Script



- 7. Click the **Save** button. A screen is displayed confirming that the custom plugin activity has been created successfully. If the *comments* property is enabled, then clicking **Save** will display a screen where you need to enter comments related to creating the custom plugin (refer to Figure 3.6).
- 8. Enter the comments in the *Add Comments* field.



The comment should be at least 1 character in length.

9. Click **OK** to save the comments. This displays a screen confirming that the custom plugin has been created successfully.



By default, the *Comments* property is disabled. To enable it, refer to the *Updating System Properties* section in *Administrator Guide*.



# **CREATING NATIVE CALL ACTIVITY**

Native Call is used to run the .EXE, .BAT or .SH files asynchronously during the execution of a process flow.

In the Adeptia Suite this feature is available in:

BPM Suite	Integration Suite	ETL Suite
$\checkmark$	$\checkmark$	$\checkmark$

#### Steps to create Native Call activity

- 1. In the Adeptia Suite homepage menu, click **[+]** Configure to expand the tree. All the items in the Configure category are displayed.
- 2. Click [+] Services to expand the tree. All the items in the Services category are displayed.
- 3. Click [+] Extensions to expand the tree, and then click Native Call. The Manage Native Call screen is displayed (see Figure 11.4).

[+]	My Documents	S						
[+]	My Solutions	Config	gure > Services > Extensions > Nati	ve Call				
[+]	My Monitor	1						
[+]	History	New	Edit   Delete   Revisions   Dependencies	-	-Select Field to Se	arch 💌		Search
[+]	Design					-	_	
[-]	Configure	#	Name	Description	1	Owner	Perm.	Modified <b>*</b>
	[+] Forms	1 ()	EvalXform_NativeCall	Native call to open the target Ex	cel File.	demouser	RWX	11/24/09 14:26
	[+] WorkFlow							
	[-] Services							
	[+] Data Dictionary							
	[+] Source							
	[+] Schema							
	[+] Target							
	[+] Web Services							
	[+] Data Transform							
	[-] Extensions							
	ee Custom Plugin							
	운 Native Call							

Figure 11.4: Manage Native Call

4. Click the **New** link. The Create Native Call screen is displayed (see Figure 11.5).



Configure > Services > Extensions > Native Call					
[-] Standard properties					
Name *					
Description *					
Default Extension	Select Extension 💌				
File Name(Absolute Path) *					
Argument(s) space separated					
Working Directory(Absolute Path)					
[+] Advanced properties					
* Mandatory fields.					
Save Cancel					

Figure 11.5: Create Native Call

- 5. Enter the name and description of the new Native Call activity in the *Name* and *Description* fields respectively.
- 6. Select the extension of the file i.e. .exe, .bat or .sh from the *Default Extension* drop-down list.
- 7. Enter the filename with full path in the *File Name(Absolute Path)* field.
- 8. To specify any arguments for selected batch or executable file enter the arguments in the *Argument(s) space separated* field.
- 9. Enter the path of directory, where you want the run the specified batch or executable file, in the *Working Directory (Absolute Path)* field.



All the files specified into batch or executable file must be placed on the server on which the Adeptia Server is running.

If Working Directory is not specified, the home directory of Adeptia Server, (i.e. ../../AdeptiaServer/AdeptiaeServer-4.9) becomes the working directory. All the files specified into batch or executable file will be looked into Adeptia Server home path.

For example, there is batch file *Mybatch.bat* and it is placed on C drive. The contents of batch file are *Copy File1.txt File2.txt*. *File1.txt* is placed in C drive. Since the working directory is not specified the batch file will look for *File1.txt* into *../../AdeptiaServer/AdeptiaServer-4.9* and it will cause error. So you can either specify the working directory (i.e. C:\) or specify the absolute path (e.g. *copy C: \File1.txt C: \File2.txt*) in the batch file. 10. Click **Save** button. This displays a screen confirming that the native call activity has been created successfully. If the *Comments* property is enabled, then clicking **Save** will display a screen where you need to enter comments related to creating the native call (refer to Figure 3.6).

ADEPTIA

11. Enter the comments in the *Add Comments* field.



The comment should be at least 1 character in length.

12. Click **OK** to save the comments. This displays a screen confirming that the native call activity has been created successfully.



By default, the *Comments* property is disabled. To enable it, refer to the *Updating System Properties* section in *Administrator Guide*.



When using a native call in a process flow, the *waitForEnd* property is set to *False* by default. This implies that the native call and other activities in the process flow are executed simultaneously. If you want to wait till the native call is complete, before executing the next activity in the process flow, you need to set this property to *True*.



# **12 CREATING POLLING SERVICE ACTIVITY**

Polling Services allow the process flow to 'wait' and 'listen' to a defined location, at which specific file, mail or data is to arrive or is to be modified before the execution of next activity. The Polling Services perform the 'listen' action at a frequency specified while creating the Polling activity.

There are four types of Polling Service:

- Database Polling Activity
- File Polling Activity
- FTP Polling Activity
- Mail Polling Activity

#### Polling Status

When a polling service is used in a process flow, it creates a *PollingStatus* activity variable. This variable is assigned value based on the execution of the polling service in the process flow. The Polling Status activity variable can take the following values:

- Timeout
- Aborted
- Success

## **CREATING DATABASE POLLING ACTIVITY**

The Database Polling Service activity is used to check any changes in the data stored in a database table.

In the Adeptia Suite this feature is available in:

BPM Suite	Integration Suite	ETL Suite
$\checkmark$	$\checkmark$	

#### Prerequisites:

• Database Info activity must be created before creating Database Polling Service activity.

#### Steps to create a Database Polling activity

- 1. In the Adeptia Suite homepage menu, click **[+]** Configure to expand the tree. All the items in the Configure category are displayed.
- 2. Click [+] Services to expand the tree. All the items in the Services category are displayed.



3. Click **[+] Polling** to expand the tree, and then click **Database**. The Manage Database Polling Service screen is displayed (see Figure 12.1).

[+] My Monitor	Configure > Services >	> Polling > Database			
[+] History					
[+] Design [-] Configure	New   Edit   Delete   Revis	ions   Dependencies	Select Fie	Id to Search 🔽	Search
[+] Forms	# Nam	ie	Description	Owner Perm.	Modified 🔻
[+] WorkFlow			No records found		
[-] Services					
[+] Data Dictionary					
[+] Source					
[+] Schema					
[+] Target					
[+] Web Services					
[+] Data Transform					
[+] Extensions					
[-] Polling					
♦] Database					
🗊 File					

Figure 12.1: Manage Database Polling Service

4. Click the **New** link. The Create Database Polling Service screen is displayed (see Figure 12.2).



Configure > Services > Polling > Data	base
[-] Standard properties	
Name *	
Description *	
Database Info*	SELECT
Define Database Polling Criteria	3*
SQL Query	
	V.
Check Condition	
Operator	Select 💌
Value	
O SQL Trigger	
SQL Trigger Name	
	Frequency Duration
Polling Frequency *	Select One 💌
Expiry Time *	Select One 💌
[+] Advanced properties * Mandatory fields.	
Save Cancel	

Figure 12.2: Create Database Polling Service

- 5. Enter the name and description of the new Database Polling Service in the *Name* and *Description* fields respectively.
- 6. Select the Database Info Id activity from the *Database Info Id* drop-down list.



To learn how to create Database Info activity, refer to the section *Creating Database Info* in *Administrator Guide*.



- 7. You can create the database event definition by entering an SQL Query or a database trigger command. By default, *SQL Query* option is selected. Enter the query in the *SQL Query* field. Select the operator for the query from the *Operator* drop-down list. Enter the value to be compared in the query in the *Value* field. The query should return only one record. If the query returns multiple records, then only the first record is accepted. If the query returns one record, then it will compare the value of the first field with the value specified in the *Value* field.
- 8. Alternately, enter the database trigger command in the *SQL Trigger* field.

Ø	Following is the format of SQL trigger
	<trigger text=""></trigger>
	INSERT INTO dbpollingtable VALUES ('Query = <where clause="">');</where>
	END <trigger name=""> ;</trigger>
	Edit the parts, which are within $< >$ . You can define a 'Where' clause that indicates the row that is updated. When the command is parsed, it will return the updated row from the database source.
	Do not delete the Insert query.
	<trigger name=""> after the END tag should be used for Oracle only. In case of SQL server, <trigger name=""> is not needed.</trigger></trigger>
	Following is the example of the trigger used for SQL Server :
	create trigger Trigger_test on emp for
	insert,update
	as
	declare @empname varchar(20)
	begin
	set @empname=(select empname from inserted);
	INSERT INTO dbpollingtable VALUES ('Query =WHERE empname=''
	+@empname+''');
	END ;
	Following is the example of the trigger used for Oracle:
	CREATE OR REPLACE TRIGGER Trigger_test AFTER INSERT OR UPDATE ON Emp FOR EACH ROW BEGIN INSERT INT O dbpollingtable VALUES ('Query = where rowid= '    :new.rowid ); END Trigger_test;
	Here : <i>Trigger test</i> is name of the trigger.



*Emp* is the name of the user table on which insert or update operation has to be done.

*dbpollingtable* is the name of the temporary table used. Do not change it.

- 9. Enter the name of Trigger in the SQL Trigger Name field.
- 10. Enter the time interval for Polling in the *Polling Frequency* field. Enter the digit in the *Frequency* field and select the unit of time i.e. seconds, minutes or hours etc from the *Duration* drop-down list.
- 11. Enter the expiry time in the *Expiry Time* field. After expiry time process flow does not poll for data.



Recommended minimum Polling Frequency is 30 seconds.

To learn about Advanced Properties refer to **Changing Advanced Properties** section.



When a database polling service is used in a process flow, it creates a *Polling Status activity* variable. For details, refer to **Polling Status** section.

- 12. Click **Save** button. This displays a screen confirming that the database polling service has been created successfully. If the *Comments* property is enabled, then clicking **Save** will display a screen where you need to enter comments for creating the database polling service (refer to Figure 3.6).
- 13. Enter the comments in the Add Comments field.



The comment should be at least 1 character in length.

14. Click **OK** to save the comments. This displays a screen confirming that the database polling service has been created successfully.



By default, the *Comments* property is disabled. To enable it, refer to the *Updating System Properties* section in *Administrator Guide*.

# **CREATING FILE POLLING ACTIVITY**

The Polling Service activity is used to check the arrival or modification of file(s) on the Local LAN location.

In the Adeptia Suite this feature is available in:

BPM Suite	Integration Suite	ETL Suite
$\checkmark$	$\checkmark$	



### Steps to create a File Polling Activity

- 1. In the Adeptia Suite homepage menu, click **[+]** Configure to expand the tree. All the items in the Configure category are displayed.
- 2. Click [+] Services to expand the tree. All the items in the Services category are displayed.
- 3. Click [+] Polling to expand the tree, and then click File. The Manage File Polling Service screen is displayed (see Figure 12.3).

[+] My Mor	nitor	Configure > Services > Pol	ling > File		
[+] History	/				
[+] Design		New   Edit   Delete   Revisions	Dependencies	Select Field to Search 💌	Search
[-] Configu					
[+] For	ms	# Name	Description	Owner	Perm. Modified 🔻
[+] Woi	rkFlow		No records found		
[-] Ser	rvices				
[+]	Data Dictionary				
[+]	Source				
[+]	Schema				
[+]	Target				
[+]	Web Services				
[+]	Data Transform				
[+]	Extensions				
E	Polling				
	<b>∳]</b> Database				
(	📄 File				
(	FTP				

Figure 12.3: Manage File Polling Service

4. Click the **New** link. The Create File Polling Service screen is displayed (see Figure 12.4).



Configure > Services > Polling > File						
[-] Standard properties						
Name *						
Description *						
Trigger Type *	On FileCreated					
File Include Criteria *						
File Exclude Criteria						
File Base Location *						
Use VFS *						
Secure						
User Id *						
Password						
Confirm Password						
	Frequency Duration					
Polling Frequency *	Select One 💌					
File Stable Time *	Select One 💌					
Expiry Time *	Select One 💌					
[+] Advanced properties						
* Mandatory fields.						
Save Cancel						

Figure 12.4: Create File Polling Service

- 5. Enter the name and description of the new File Polling Service in the *Name* and *Description* fields respectively.
- 6. Select the trigger type from the *Trigger Type* drop-down list. The effect on the selection is listed in the table below.

Table 12.1: Trigger Type Selection Values

Trigger Type Selection	Description



On FileCreated	To configure the File Polling service to check for the creation of a new file(s).
On FileExists	To configure the File Polling service to check for the existence of the file(s)
On FileModified	To configure the File Polling service to check for any modification in file(s)

- 7. Enter the name of file that File Polling service needs to verify, in *File Include Criteria* field.
- 8. Enter the name of file that File Polling service does not need to verify, in *File Exclude Criteria* field. For example \*.*txt* is entered in *File Include Criteria*, but two files *Gdata.txt* and *Gdata1.txt* are not required to be verified by File Polling service. Then *Gdata.txt* and *Gdata1.txt* file name need to be entered separated by comma in *File Exclude Criteria* field. You can use regular expressions listed in the table below.

Expression	Description	
*.*	For all files with some extension	
*	For all files in a directory	
a*.txt	For files starting with a and having extension txt (e.g. arch.txt)	
a?????.txt	For files starting with a and have 6 more character followed by txt extension (e.g. archive.txt)	
a[1-9]	For a1, a2 ,a3a9	
b[aiu]t	For bat, bit or but	
a.txt, a.doc	For two files named as a.txt and a.doc	

Table 12.2: Expressions used in File Include Criteria and File Exclude Criteria

9. Enter the path of file in *File Base Location*. Example c:/Gmdata.

You can also use regular expression for folders, in *File Include Criteria* and *File Exclude Criteria* fields. For example, if you enter *h\*/\*.txt* in *File Include Criteria* field and *C:/Gmdata* in *File Base Location* field, it will search for all .txt file inside all directories which starts from h under C:\Gmdata.


- 10. When Adeptia Server is installed on Windows Operating System, File Polling uses windows service to connect to remote machine to access any file. It just connects once and uses the same connection with the same User ID and Password (which is stored in the cache) every time. If you want to enforce the validation of User ID and Password every time while accessing the file on a remote machine, check *Use VFS* checkbox.
- 11. Enter username and password in the *User ID* and *Password* fields respectively. Then, reenter the password in the *Confirm Password* field.
- 12. Enter the time interval, the file polling service will check for the arrival of any file or modification of existing file in the *Polling Frequency* field. Enter the digit in the *Frequency* field and select the unit of time i.e. seconds, minutes or hours etc from the *Duration* drop-down list.



Recommended minimum Polling Frequency is 30 seconds.



- 13. Enter the file stable time in the *File Stable Time* field. This is applicable only when user selects On *FileModified* in trigger type. Polling will wait for the above specified time to become a file stable.
- 14. Enter the expiry time in the *Expiry Time* field. After expiry time process flow does not poll for the file.



When a file polling service is used in a process flow, it creates a *Polling Status activity* variable. For details, refer to <u>Polling Status</u> section.

- 15. Click **Save** button. This displays a screen confirming that the file polling service has been created successfully. If the *Comments* property is enabled, then clicking **Save** will display a screen where you need to enter comments for creating the file polling service (refer to Figure 3.6).
- 16. Enter **the** comments in the *Add Comments* field.



The comment should be at least 1 character in length.

17. Click **OK** to save the comments. This displays a screen confirming that the file polling service has been **created** successfully.



By default, the *Comments* property is disabled. To enable it, refer to the *Updating System Properties* section in *Administrator Guide*.

# CREATING FTP POLLING ACTIVITY

The FTP Polling Service activity is used to check the arrival or modification of a file(s) on a FTP location.

In the Adeptia Suite this feature is available in:

BPM Suite	Integration Suite	ETL Suite
$\checkmark$		

#### Steps to create a FTP Polling Activity

- 1. In the Adeptia Suite homepage menu, click **[+]** Configure to expand the tree. All the items in the Configure category are displayed.
- 2. Click [+] Services to expand the tree. All the items in the Services category are displayed.



3. Click **[+] Polling** to expand the tree, and then click **FTP**. The Manage FTP Polling screen is displayed (see Figure 12.5).

+] My Monitor	Configure > Services > Polling > FTP			
+] History				
+] Design -] Configure	New   Edit   Delete   Revisions   Dependencies	Select Fi	eld to Search 💌	Searc
[+] Forms	# Name	Description	Owner Perm.	Modified 🔻
[+] WorkFlow		No records found		
[-] Services				
[+] Data Dictionary				
[+] Source				
[+] Schema				
[+] Target				
[+] Web Services				
[+] Data Transform	n			
[+] Extensions				
[-] Polling				
<b>∳</b> ] Database				
📑 File				
FTP				



4. Click the **New** link. The Create FTP Polling Service screen is displayed (see Figure 12.6).



Configure > Services > Polling > FTP	)
[-] Standard properties	
Name *	
Description *	
Host name *	
Port *	21
User Id *	
Password	
Confirm Password	
Transfer Type	PASSIVE -
Trigger Type *	On FileCreated
SSH FTP (SFTP) *	
FTP Over TLS/SSL (FTPS) *	
FTPS Mode	Explicit 💌
Protection Level	Clear
Validate Server	
Keystore Name	SELECT 💌
File Include Criteria *	
File Exclude Criteria	
File Base Location *	
Polling Frequency *	Frequency Duration
File Stable Time *	Select One 💌
	Select One
Expiry Time *	
[+] Advanced properties	
* Mandatory fields.	
Save Cancel	

Figure 12.6: Create FTP Polling Service



- 5. Enter the name and description of the new FTP Polling Service in the *Name* and *Description* fields respectively.
- 6. Enter the name and port number of the FTP Server in the *Host Name* and *Port* fields respectively.
- 7. Enter username and password required to access FTP Server in the *User ID* and *Password* fields respectively. Then, re-enter the password in the *Confirm Password* field.
- 8. Select the transfer type as either *Active* or *Passive* from the *Transfer Type* drop-down list. *Active* transfer is more secure since the client only initiates communication to the Server on one port whereas in case of *Passive* transfer the client initiates communication to the Server over two ports. Passive mode is useful when you are behind a firewall or a proxy.
- 9. Select the trigger type from the *Trigger Type* drop-down list. For selection of values, refer to Table 12.1.
- 10. Check the *SSH FTP (SFTP)* checkbox if the FTP Server specified in the *Host Name* field is an FTP Server over SSH.
- 11. Check the *FTP Over TLS/SSL (FTPS)* checkbox, if the FTP Server, specified in the *Host Name* field is an FTP Server over TLS/SSL.
- 12. Incase you have selected *FTP Over TLS/SSL (FTPS)*, checkbox, then select the FTPS mode from *FTPS Mode* drop-down list. It can be *Explicit* or *Implicit* depending on FTP Server that you are accessing.
- 13. Select the protection level supported by the FTP Server, from the *Protection Level* dropdown list. It can be *Clear* or *Private*.
- 14. If you want to validate the certificate sent by the FTPS Server, check the *Validate Server* check box.
- 15. Select keystore activity from the *Keystore Name* drop-down list. This option is applicable only when you have checked the *Validate Server* checkbox.

When Validate option is unchecked, it always accepts the certificate sent by FTPS Server.
 When this option is checked, it validates the certificate sent by FTPS server against the certificate imported in Keystore.
 Keystore is repository of security certificates.
 To know how to create Keystore and import certificates, refer to *Creating Keystore* secton of *Administrator Guide*.

- 16. Enter the name of file that FTP event needs to verify in the File Include Criteria field.
- 17. Enter the name of file that file event does not need to verify in the *File Exclude Criteria* field. For example *\*.txt* is entered in *File Include Criteria*, but two files *Gdata.txt* and *Gdata1.txt* are not required to be verified by FTP Polling Service. Then *Gdata.txt* and *Gdata1.txt* file name need to be entered separated by comma in *File Exclude Criteria* field. You can use regular expressions listed in Table 12.2.
- 18. Enter the path of file in *File Base Location*. Example c:/Gmdata.



You can also use regular expression for folders, in *File Include Criteria* and *File Exclude Criteria* fields. For example, if you enter  $h^*/*.txt$  in *File Include Criteria* field and *C:/Gmdata* in *File Base Location* field, it will search for all .txt file inside all directories which starts from h under C:\Gmdata.



19. Enter the time interval, the FTP Polling Service will check for the arrival of any file or modification of existing file in the *Polling Frequency* field. Enter the digit in the *Frequency* field and select the unit of time i.e. seconds, minutes or hours etc from the *Duration* drop-down list.



Recommended minimum Polling Frequency is 30 seconds.

- 20. Enter the file stable time in the *File Stable Time* field. This is applicable only when user selects On *FileModified* in trigger type. Polling will wait for the above specified time to become a file stable.
- 21. Enter the expiry time in the *Expiry Time* field. After expiry time process flow does not poll for the file.



To learn about Advanced Properties refer to **<u>Changing Advanced</u> <u>Properties</u>** section.



When a FTP polling service is used in a process flow, it creates a *Polling Status activity* variable. For details, refer to <u>Polling Status</u> section.

- 22. Click **Save** button. This displays a screen confirming that the FTP polling service has been created successfully. If the *Comments* property is enabled, then clicking **Save** will display a screen where you need to enter comments for creating the FTP polling service (refer to Figure 3.6).
- 23. Enter the comments in the *Add Comments* field.



The comment should be at least 1 character in length.

24. Click **OK** to save the comments. This displays a screen confirming that the FTP polling service has been created successfully.



By default, the *Comments* property is disabled. To enable it, refer to the *Updating System Properties* section in *Administrator Guide*.

# CREATING MAIL POLLING ACTIVITY

The Mail Polling activity is used to 'listen' for the arrival of any mails on the mail Server.

In the Adeptia Suite this feature is available in:

BPM Suite	Integration Suite	ETL Suite
۸ N		

Steps to create a Mail Polling activity



- 1. In the Adeptia Suite homepage menu, click **[+]** Configure to expand the tree. All the items in the Configure category are displayed.
- 2. Click [+] Services to expand the tree. All the items in the Services category are displayed.
- 3. Click **[+] Polling** to expand the tree, and then click **Mail**. The Manage Mail Polling screen is displayed (see Figure 12.7).

[+] My Monitor	Configur	e > Services > Polling > Mail			
[+] History					
[+] Design	New   Edit	Delete   Revisions   Dependencies	Select Fie	ald to Search 💙	Search
[-] Configure					
[+] Forms	#	Name	Description	Owner Pe	erm. Modified 🔻
[+] WorkFlow			No records found		
[-] Services					
[+] Data Dictionary					
[+] Source					
[+] Schema					
[+] Target					
[+] Web Services					
[+] Data Transform					
[+] Extensions					
[-] Polling					
<b>⇒0</b> Database					
📑 File					
E FTP					
🖂 Mail					

Figure 12.7: Manage Mail Polling Service

4. Click the **New** link. The Create Mail Polling screen is displayed (see Figure 12.8).



Configure > Services > Polling > Mail	
[-] Standard properties	
Name *	
Description *	
Protocol *	POP3
Incoming Mail Server *	
Domain	
CDO host machine	
Enable SSL	
Port	110
User Id	
Password	
Confirm Password	
Search based on following filter crite	ria *
Sender E-mail	
Mail Subject	
Mail Content	
File Attachment	
	Frequency Duration
Polling Frequency *	Select One 💌
Expiry Time *	Select One 💌
[+] Advanced properties	
* Mandatory fields.	
Save Cancel	

Figure 12.8: Create Mail Polling Service



- 5. Enter the name and description of the new Mail Polling activity in the *Name* and *Description* fields respectively.
- 6. Select the Internet standard protocol to be used for retrieving incoming mails, from the *Protocol* drop-down list. You can select either the *POP3*, *IMAP4* or the *MAPI* protocol. Based on the selected protocol, the default port number for that protocol is displayed in the *Port* field.
- 7. Enter the address of the incoming mail server in the *Incoming Mail Server* field.

To access mails from Microsoft Exchange Server use *MAPI* in the *Protocol* drop-down list. To connect Adeptia Server with Microsoft Exchange Server, you need to buy a third party tool called *J-Integra for Exchange*. J-Integra for Exchange is a high performance middleware bridge that enables Java Exchange interoperability. If you want to retrieve mails from an Exchange Server using J-Integra, select *MAPI* in the *Protocol* drop-down list.

If MAPI is selected in the Protocol drop-down list:

- Enter name of the exchange server in *Incoming Mail Server* field
- Enter the domain name in the *Domain* field
- Enter the name of the CDO host machine in *CDO host machine* field. CDOConfig.exe is a tool that comes with the J-Integra for Exchange SDK and is used for configuring CDO. Host where CDO is configured is called CDO host machine.

For detailed information about Jintegra for Exchange, refer to <u>http://j-integra.intrinsyc.com/products/exchange/</u>.

- 8. Check the Secure checkbox, if the specified incoming mail server is SSL enabled.
- 9. The default port number of the selected protocol is displayed in the *Port* field. If you want to change this port number, enter the new port number in the *Port* field.
- 10. Enter the user Id and password of mail server in the *User ID* and *Password* fields respectively. Then re-enter the password in the *Confirm Password* field.
- 11. Select any of the following filter criteria:
  - Sender E-mail
  - Mail Subject

 $\langle n \rangle$ 

- Mail Content
- File Attachment

You may select more than one filter criteria.

- 12. Enter the sender's email address and subject of email in the *Sender Email* and *Mail Subject* fields respectively.
- 13. To define search based on mail content, enter the required content in *Mail Content* field.



You can also use asterisk and Wild Cards in *Mail Content* field.



- 14. Enter the name of the file attached with mail, in the *File Attachment* field.
- 15. Enter the time interval for Polling in the *Polling Frequency* field. Enter the digit in the Frequency field and select the unit of time i.e. seconds, minutes or hours etc from the *Duration* drop-down list.



Recommended minimum Polling Frequency is 30 seconds.

16. Enter the expiry time in the *Expiry Time* field. After expiry time process flow does not poll for the mail.



When a mail polling service is used in a process flow, it creates a *Polling Status activity* variable. For details, refer to **Polling Status** section.

- 17. Click **Save** button. This displays a screen confirming that the mail polling service has been created successfully. If the *Comments* property is enabled, then clicking **Save** will display a screen where you need to enter comments for creating the mail polling service (refer to Figure 3.6).
- 18. Enter the comments in the *Add Comments* field.



The comment should be at least 1 character in length.

19. Click **OK** to save the comments. This displays a screen confirming that the mail polling service has been created successfully.



By default, the *Comments* property is disabled. To enable it, refer to the *Updating System Properties* section in *Administrator Guide*.



# **13** CREATING DATABASE CONNECTORS

Database Connector is used to make a connection between a particular database server (e.g. SQL, Oracle and DB2 etc) and Adeptia Suite. There are several services of Adeptia Suite, which require database connector to connect to any database server. Examples of database connectors are *Database Schema, Database Source, Database Target* and *Database Events.* Database connectors consist of two parts: Database Driver and Database Info.

This chapter describes the following tasks:

- <u>Creating Database Driver</u>
- Creating Database Info
- <u>Creating JMS Provider</u>

## CREATING DATABASE DRIVER

A database driver is used to specify the type of database and driver jar files that are required to connect to that database. Database jar files are drivers, which are used to connect to database Servers. There are specific jar files for specific database server. These jar files are not provided with the Adeptia Suite. These jar files are available with the database servers. Driver jar files can also be obtained from following locations:

### Oracle Server

http://www.oracle.com/technology/software/tech/java/sqlj\_jdbc/index. html

#### SQL Server

http://www.microsoft.com/downloads/details.aspx?FamilyID=07287B11 -0502-461A-B138-2AA54BFDC03A&displaylang=en

In the Adeptia Suite this feature is available in:

BPM Suite	Workflow Suite	Integration Suite	ETL Suite
$\checkmark$		$\checkmark$	$\checkmark$

### Steps to create a database driver

- 1. Click [+] Administer to expand the tree and then click [+] Connector. All the items in the Connector category are displayed.
- 2. Click **Database Driver**. The Manage Database Driver screen is displayed (see Figure 13.1).



-] Configure [+] Forms	Config	jure > Services > Connector	> Database Driver			
[+] WorkFlow [-] Services	New	Edit   Delete   Revisions   Depend	dencies -	-Select Field to Search 💌		Search
[+] Data Dictionary						
[+] Source	#	Name	Description	Owner	Perm.	Modified <b>*</b>
[+] Schema	1 ()	Oracle_DBDriver	Oracle server driver	demouser	RWX	11/24/09 15:36
[+] Target	2 🔿	MySQLServer_DBDriver	MySQL server driver	demouser	RWX	01/25/08 12:50
[+] Web Services	3 ()	SQLServer_DBDriver	SQL server driver	demouser	RWX	01/25/08 12:49
<ul><li>[+] Data Transform</li><li>[+] Extensions</li></ul>	4 🔿	HSQL_DBDriver	Database driver for HSQL	demouser	RWX	01/22/08 21:11
[+] Polling						
[-] Connector						
<b>⇒0</b> Database Driver						
<b>⇒0</b> Database Info						
🖾 JMS Provider						

Figure 13.1: Manage Database Driver

3. Click the **New** link. The Create Database Driver screen is displayed (see Figure 13.2).

Configure > Services > Connector > D	atabase Driver	
[-] Standard properties		
Name *		
Description *		
Upload Driver Jar/Zip files		Browse Jars
Driver Main Class Name *		Get Driver Class
[+] Advanced properties		
* Mandatory fields.		
Save Cancel		

Figure 13.2: Create Database Driver

- 4. Enter the name and description of the new database driver in the *Name* and *Description* fields respectively.
- 5. Click **Browse Jars** button to upload the driver jar files for the database. The Browse Database Jar screen is displayed (see Figure 13.3).



🖉 Upload Jar File	s - Windows Internet Explorer	
🕖 Choose File		
Click on Browse b	utton to choose the file.	
Browse File	Browse	
<b>Upload File</b> Click on the "Uplo process to upload	ad File" button. Please wait till your file appears in list. Repeat the other files.	
File Names Upload File		
Olick on Finis uploaded jars.	h button to complete the process/ unload jars to unload presently	
Finish	unload ja <del>rs</del>	


Figure 13.3: Browse Database Jar

6. Click **Browse** button and select the required jar file. The path of the selected jar file is displayed in the *Browse File* field (see Figure 13.4). A list of required Jar files for different databases is displayed in the table below.

Database Server	Driver Jar Files
Oracle	Classes12.jar
	For Oracle BLOB Datatype:
	base.jar, oracle.jar and util.jar
	These Jars can be downloaded from
	http://www.datadirect.com/downloa
	<u>d/index.ssp</u>
IBM DB2 (Ver 7.1)	db2java.zip (7.1 version)
IBM DB2 (Ver 8.1)	db2jcc.jar
MS SQL	msbase.jar, mssqlServer.jar and msutil.jar
JTDS-SQL Server	Jtds.jar
HSQL DB	hsqldb-1.7.2.jar



🖉 Upload Jar File	s - Windows Internet Explorer	- X
		<u> </u>
🕖 Choose File		
Click on Browse b	outton to choose the file.	
Browse File	C:\DB_Driver\classes12.ja Browse	
<b>Oupload File</b> Click on the "Uplo process to upload	oad File" button. Please wait till your file appears in list. Repeat the 1 other files.	
File Names Upload File		
Olick on Finis uploaded jars.	sh button to complete the process/ unload jars to unload presently	
Finish	unload jars	
<u> </u>		-



7. Click **Upload File** button. The file name is displayed in the *File Names* list (see Figure 13.5).

🜈 Upload Jar Files - Windows Internet Explorer	<u> </u>
	<u> </u>
Choose File	
Click on Browse button to choose the file.	
Browse File Browse	
<b>Oupload File</b> Click on the "Upload File" button. Please wait till your file appears in list. Repeat the process to upload other files.	
File Names	
classes12.jar Upload File	
Click on Finish button to complete the process/ unload jars to unload presently uploaded jars.	
Finish unload jars	
	<b>V</b>

Figure 13.5: Jar Files Uploaded



- 8. Repeat steps 6 and 7 to upload additional jar files.
- 9. To unload jars files, click **Unload jars** button.
- 10. Click **Finish** button to return to the Manage Database Driver screen. The uploaded jar file(s) is displayed in the Upload Driver Jar files field (see Figure 13.6).

Administer > Connector > Database Driver		
[-] Standard properties		
Name *	SQLDriver	]
Description *	sql driver	]
Upload Driver Jar/Zip files	classes12.jar	Browse Jars
Driver Main Class Name *		Get Driver Class
[+] Advanced properties * Mandatory fields. Save Cancel		

Figure 13.6: Uploaded Driver Jar Files

11. Enter the Driver Main Class Name of the database in the *Driver Main Class Name* field. Driver Main Class Name is a fully qualified java class name for the main database driver class. The driver class name typically starts with a com., net. or org. followed by the company domain. For example, the JDBC driver class for mysql.com is called *com.mysql.jdbc.Driver*. Click **Get Driver Class...** button to select Driver Main Class Name from a drop-down list (see Figure 13.7).

ame ORACLE: oracle.jdbc.driver.OracleDriver

Figure 13.7: Select Database Driver Main Class Name

12. Select the Driver Main Class Name from the drop-down list and click **OK** button. A list of Driver Main Class Name of different databases is displayed in the table below.

Database Server	Driver Main Class Definition
Oracle	oracle.jdbc.driver.OracleDriver
	For Oracle BLOB Datatype:
	com.ddtek.jdbc.oracle.OracleDriver
IBM DB2 (Ver 7.1)	COM.ibm.db2.jdbc.net.DB2Driver

Table 13.2: Driver	Main Class Names	for Database Servers
--------------------	------------------	----------------------



IBM DB2 (Ver 8.1)	com.ibm.db2.jcc.DB2Driver
MS SQL	com.microsoft.jdbc.sqlServer.SQLServerDriver
JTDS-SQL Server	net.sourceforge.jtds.jdbc.Driver
HSQLDB	org.hsqldb.jdbcDriver
MS Access	sun.jdbc.odbc.JdbcOdbcDriver
MS Excel	sun.jdbc.odbc.JdbcOdbcDriver

- 13. Click **Save** button. This displays a screen confirming that the Database Driver has been created successfully. If the *Comments* property is enabled, then clicking **Save** will display a screen where you need to enter comments related to creating the Database Driver (refer to Figure 3.6).
- 14. Enter the comments in the *Add Comments* field.

		~	
1	1	2	۴.
11		e	

The comment should be at least 1 character in length.

15. Click **OK** to save the comments. This displays a screen confirming that the Database Driver has been created successfully.

M	
V	

By default, the *Comments* property is disabled. To enable it, refer to the section **<u>Updating System Properties</u>**.

# CREATING DATABASE INFO

Database Info activity is used to specify the Server URL (JDBC URL), Username and Password to access the database. Server URL points to a specific database on a specified database Server. There is no standard for Server URL. Every JDBC driver uses a slightly different syntax. For example, a Server URL for a MySQL database using the com.mysql.jdbc.Driver might look like this: *jdbc:mysql://localhost/databaseName*. Database Info uses database driver to connect to specified Database Server.

In the Adeptia Suite this feature is available in:

BPM Suite	Workflow Suite	Integration Suite	ETL Suite		
$\checkmark$		$\checkmark$			

### Prerequisites

Database Driver activity must be created before creating Database Info Activity.

### Steps to create Database Info

1. Click **[+]** Administer to expand the tree and then click **[+]** Connector. All the items in the Connector category are displayed.



2. Click **Database Info**. The Database Info screen is displayed (see Figure 13.8).

[-] Configure [+] Forms	Confi	gure > Services > Connector > Data	base Info				
<ul> <li>[+] WorkFlow</li> <li>[-] Services</li> <li>[+] Data Dictionary</li> </ul>	New	Edit   Delete   Revisions   Dependencies		Select Field to Se	arch 💙		Search
[+] Source	#	Name	Descripti	on	Owner	Perm.	Modified <b>T</b>
[+] Schema	1 ()	EvalJMSE_DBInfo	Database Info for HSQL .		demouser	RWX	11/24/09 15:37
[+] Target	2 ()	EvalXform_DbInfo	Database Info for HSQLDB.		demouser	RWX	11/24/09 15:36
[+] Web Services	3 ()	EvalPF_DataBaseInfo_SQLServer	SQL Server Microsoft Info.		demouser	RWX	11/11/09 16:52
[+] Data Transform [+] Extensions	4 ()	ConnectToSalesDatabase	connection information to Sale	es db	demouser	RWX	11/11/09 16:51
[+] Polling							
[-] Connector							
O Database Driver							
<b>⇒0</b> Database Info							
🖾 JMS Provider							

Figure 13.8: Manage Database Info

3. Click the **New** link. The Create Database Info screen is displayed (see Figure 13.9).

Configure > Services > Connector > D	atabase Info	
[-] Standard properties		
Name *		]
Description *		]
Select JDBC Driver*		
O Use Existing	SELECT	•
C Create New		Create Database Driver
Server URL *		Help
User*		]
Password		
Confirm Password		
Test Database Connect	ion	
[+] Advanced properties		
* Mandatory fields.		
Save Cancel		

Figure 13.9: Create Database Info

- 4. Enter the name and description of the Database Info in the *Name* and *Description* fields respectively.
- 5. Select the database driver activity.

(M)	То	learn	how	to	create	database	driver	activity,	refer	to	section
Ŵ	Cre	eating	Data	aba	ise Dri	ver					



- 6. To select an existing database driver activity, select the *Use Existing* radio button and select the database driver activity from the drop-down list.
- 7. To use a new database driver activity, select the *Create New* radio button and then click **Create Database Driver** button. This displays the Create Database Driver screen.
- 8. Enter the required parameters and click **Save** in the Create Database Driver screen to save the database driver activity and return to Create Database Info screen.
- 9. Click **Help** button next to the *Server URL* field to define Server URL. The Database URL Definition screen is displayed (see Figure 13.10).

Database URL Definition	<u> </u>
[-] Database Connection properties	
Database Type *	Oracle 💌
Host Name *	
Port *	
Database Name *	
Ok Cancel	

Figure 13.10: Define Server URL

- 10. Select the type of database from the Database Type drop-down list.
- 11. Enter the name of database Server, port number and name of the database in *Host Name*, *Port* and *Database Name* fields respectively.
- 12. Click **OK** button to return to the Manage Database Info screen. The defined database URL is displayed in the *Server URL* field (see Figure 13.11).



Configure > Services > Connector > Database Info > EvalPF_DataBaseInfo_SQLServer						
[-] Standard properties						
[] Standard properties						
Name *	EvalPF_DataBaseInfo_SQLServer					
Description *	SQL Server Microsoft Info.					
Select JDBC Driver*						
O Use Existing	SQLServer_DBDriver (SQL server driver)					
C Create New	Create Database Driver					
Server URL *	jdbc:jtds:sqlserver://DatabaseServer: Help					
User *						
Password						
Confirm Password						
Test Database Connecti	ion					
[+] Advanced properties						
* Mandatory fields.						
Save Save As Cancel						

Figure 13.11: Defined Database Server URL

A list of Server URL's of different databases is displayed in the table below.

Database Server	Server URL			
Oracle	jdbc:oracle:thin:@databaseServer:1521:orcl			
	For Oracle BLOB Datatype:			
	jdbc: datadirect: oracle: //databaseserver: 1521; ServiceName =test			
IBM DB2 (Ver 7.1)	jdbc:db2://databaseServer:6789/TOOLSDB			
IBM DB2 (Ver 8.1)	jdbc:db2://databaseServer:50000/TOOLSDB			
MS SQL	jdbc:microsoft:sqlServer://databaseServer:1433;DatabaseN ame=master			
SQL JTDS	jdbc:jtds:sqlserver://databaseserver:1433/master			
MS Access	jdbc:odbc:Driver={MicroSoft Access Driver (*.mdb)}; DBQ=c:/test/db1.mdb			
MS Excel	Jdbc: odbc: ExcelJDBCTest			

Table 13.3: Server URL for Database Servers



	where ExcelJDBCTest is the ODBC object that you need to create using DSN.
HSQL DB	jdbc:hsqldb:hsql://databaseserver:2476

DatabaseServer in Table 24.3 is the name of the server on which the database is running.

- 13. Enter the username that is used to connect database server in the User field.
- 14. Click **Test Database Connection** button to verify the connection between the Adeptia Suite and the database.
- 15. Enter the password in the Password and Confirm Password fields respectively, if required.
- 16. Click **Save** button. This displays a screen confirming that the Database Info activity has been created successfully. If the *Comments* option is enabled, then clicking **Save** will display a screen where you need to enter comments related to creating the Database Info activity (refer to Figure 3.6).
- 17. Enter the comments in the *Add Comments* field.



The comment should be at least 1 character in length.

18. Click **OK** to save the comments. This displays a screen confirming that the Database Info activity has been created successfully.



By default, the *Comments* option is disabled. To enable it, refer to the section **<u>Updating System Properties</u>**.

# CREATING JMS PROVIDER

JMS Provider is used to connect to JMS Server. While creating JMS Provider, you need to specify the Provider Jar files, which are used to connect to JMS Server. There are several services of Adeptia Suite, which require JMS Provider to connect to JMS Server.

In the Adeptia Suite this feature is available in:

BPM Suite	Integration Suite	ETL Suite
$\checkmark$		

#### Steps to create JMS Provider

- 1. Click **[+]** Administer to expand the tree and then click **[+]** Connector. All the items in the Connector category are displayed.
- 2. Click **JMS Provider**. The Manage JMS Provider screen is displayed (see Figure 13.12).



[-] Configure		jure > Services > Connector > JMS	Provider	Select Field to Sea	arch 💌		Search
[+] Source	#	Name	Descript	ion	Owner	Perm.	Modified 🔻
[+] Schema	1 ()	EvalJMSE_JMSProvider	JMS Provider for Open JMS		demouser	RWX	08/22/05 14:15
[+] Target	2 ()	EvalRec_JMSProvider	JMS Provider to connect oper	JMS	demouser	RWX	08/12/05 17:23
<ul> <li>[+] Web Services</li> <li>[+] Data Transform</li> </ul>							
[+] Extensions							
[+] Polling							
[-] Connector							
<b>⇒]</b> Database Driver							
Database Info							
🖾 JMS Provider							

#### Figure 13.12: Manage JMS Provider

3. Click the **New** link. The Create JMS Provider screen is displayed (see Figure 13.13).

Configure > Services > Connector > JM	S Provider	
[-] Standard properties		
Name *		
Description *		
JMS URL *		
Provider Jar Files*		Upload Jars
JNDI Factory *		
Queue Connection Factory *		
Topic Connection Factory *		
[+] Advanced properties		
* Mandatory fields.		
Save Cancel		

Figure 13.13: Create JMS Provider

- 4. Enter the name and description for the new JMS Provider in the *Name* and *Description* fields respectively.
- 5. Enter the URL of the JMS Server in the *JMS URL* field. For example, for OpenJMS running on the same server, use *rmi://localhost:2099/JndiServer*
- 6. Click **Upload Jars** button to upload the driver jar files for the JMS Server. The Browse Jar Files screen is displayed (refer to Figure 13.3).




Figure 13.14: Uploaded Provider Jar Files

- 11. Enter the JNDI Factory class name as specified by the JMS Provider in the *JNDI Factory* field. For Example, in case of OpenJMS, the value is *org.exolab.jms.jndi.rmi.RmiJndiInitialContextFactory*.
- 12. Enter the JMS Provider Queue connection Factory in the *Queue Connection Factory* field. For example, in case of OpenJMS, Queue Connection Factory is JmsQueueConnectionFactory.
- 13. Enter the JMS Provider Topic Connection Factory in the *Topic Connection Factory* field. For example, in case of OpenJMS, Topic Connection Factory is JmsTopicConnectionFactory.
- 14. Click **Save** button. This displays a screen confirming that the JMS Provider activity has been created successfully. If the *Comments* property is enabled, then clicking **Save** will display a

ADEPTIA



screen where you need to enter comments related to creating the JMS Provider (refer to Figure 3.6).

15. Enter the comments in the *Add Comments* field.

The comment should be at least 1 character in length.

16. Click **OK** to save the comments. This displays a screen confirming that the JMS Provider activity has been created successfully.



By default, the *Comments* property is disabled. To enable it, refer to the section **Updating System Properties**.

# USING MLLP

The Minimal Lower Layer Protocol (MLLP) is the most common mechanism for exchanging the HL7 data. MLLP uses the TCP/IP protocol to transfer the data in continuous stream of bytes. MLLP delimiters is used to recognize the start and the end of message.

Adeptia Suite support the transfer of data using MLLP. You can configure Adeptia Suite as MLLP Server or MLLP client.

In the Adeptia Suite this feature is available in:

BPM Suite	Integration Suite	ETL Suite
$\checkmark$	$\checkmark$	$\checkmark$

## **Configuring MLLP Server**


MLLP Server is used to receive the data. When an MLLP activity is configured in server mode, it opens the specified port and waits from the specified client to send the data.

## Steps to configure MLLP Server

- 1. Click **[+]** Administer to expand the tree and then click **[+]** Connector. All the items in the Connector category are displayed.
- 2. Click **MLLP**. The Manage MLLP screen is displayed (see Figure 13.15Figure 13.12).



[+] My Tasks	Configure	Services > Connector > MLLP			
[+] My Documents	configure >	Services > Connector > MEEP			
[+] My Solutions				to Search 💌	
[+] My Monitor	New   Edit   De	elete   Revisions   Dependencies	Select Field	to Search 💌	Search
[+] History	Activate				
	#	Name	Description	Owner Perm.	Modified 🔻
[+] Design			No records found		
[-] Configure					
[+] Forms					
[+] WorkFlow					
[-] Services					
[+] Data Dictionary					
[+] Source					
[+] Schema					
[+] Target					
[+] Web Services					
[+] Data Transform					
[+] Extensions					
[+] Polling					
[-] Connector					
♦) Database Driver					
♦] Database Info					
JMS Provider					



3. Click the **New** link. The Create MLLP screen is displayed (see Figure 13.16).



Name * Description * [-] TCP Connection Host name * Port *	
[-] TCP Connection Host name *	
Host name *	
Port *	
	0
Mode Type *	Server 💌
Connection Retry Count	* 0
	Frequency Duration
Interval between retry *	Select One 💌
[-] MLLP	
Start Text Char *	0B
End Text Char *	1C
Last Text Char *	0D
	Frequency Duration
Data time out *	Select One 💌
	Frequency Duration
Data Polling Frequency	Frequency Duration
Ack time out *	Select One
	Frequency Duration
Ack Polling Frequency *	Select One 💌
File Base Location *	
Process Flow Name *	None
Advanced properties	
Advanced properties	

Figure 13.16: Create MLLP Activity

4. Enter the name and description for the new MLLP activity in the *Name* and *Description* fields respectively.

- 5. Expand the *TCP Connection* properties. TCP connection properties are displayed.
- 6. In *Host Name* field, enter the IP address of the host from where, the MLLP server is supposed to receive the data.

ADEPTIA

- 7. In *Port* field, enter the port at which the MLLP Server will allow the MLLP client to be connected.
- 8. Select *Server* from the *Mode Type* drop-down list.
- 9. In *Connection Retry Count* field, enter the maximum number of retries, the adapter attemps to connect to a specific TCP/IP connection before giving up.
- 10. In Interval between retry field, enter the duration between the retries.
- 11. Expand the *MLLP* Properties. The MLLP properties are displayed.
- 12. Enter start, end and last text character in *Start Text Character, End Text Character* and *Last Text Character* respectively.
- 13. Enter the data time out duration in *Data Time Out* field.
- 14. Enter the data polling frequency in the *Data Polling Frequency* field. This is time interval between successive polls for data.
- 15. Enter the acknowledgment timeout duration in Ack Time Out field.
- 16. Enter acknowledgment polling frequency in *Ack Polling Frequency*. This is time interval between successive polls for acknowledgemt.
- 17. Enter location where you want to store the received data, in the *File Base Location* field. The received data is stored in the file named as Message\_<yyyy-MM-dd-hh-mm-ss-SSS>. This file doesn't have any extension.
- 18. If you want to trigger a process flow, when any data is received, you can select the process flow, from *Process Flow Name* drop-down list.
- 19. Click **Save** button. This displays a screen confirming that the MLLP activity has been created successfully. If the *Comments* property is enabled, then clicking **Save** will display a screen where you need to enter comments related to creating MLLP Activity (refer to Figure 3.6).
- 20. Enter the comments in the Add Comments field.

The comment should be at least 1 character in length.

21. Click **OK** to save the comments. This displays a screen confirming that the JMS Provider activity has been created successfully.



By default, the *Comments* property is disabled. To enable it, refer to the section **<u>Updating System Properties</u>**.

## Configuring MLLP Client

MLLP Client is used to send the data to the specified MLLP server. While creating the MLLP Client, you need to define the data location. As soon as any data is stored, it starts sending the data to the specified MLLP Server.

### Steps to configure MLLP Client



- 1. Click **[+]** Administer to expand the tree and then click **[+]** Connector. All the items in the Connector category are displayed.
- 2. Click **MLLP**. The Manage MLLP screen is displayed (see Figure 13.17).

[+] My Tasks	Configure >	Services > Connector > MLLP			
[+] My Documents					
[+] My Solutions	New   Edit   D	elete   Revisions   Dependencies	Select Field	to Search 💌	Search
[+] My Monitor					
[+] History	Activate				
[+] Design	# 🔅	Name	Description	Owner Pern	n. Modified 🔻
[-] Configure			No records found		
[+] Forms [+] WorkFlow					
[+] WorkFlow [-] Services					
· · · ·					
[+] Source [+] Schema					
[+] Target					
[+] Web Services					
[+] Data Transform					
[+] Extensions					
[+] Polling					
[-] Connector					
→] Database Driver					
♦0 Database Info					
🖂 JMS Provider					
MLLP					

Figure 13.17: Manage MLLP Activity

3. Click the **New** link. The *Create MLLP* screen is displayed (see Figure 13.18).



	rd properties	
	Description *	
[-] 1	CP Connection	
	Host name *	
	Port *	0
	Mode Type *	Server 💌
	Connection Retry Count *	0
		Frequency Duration
	Interval between retry *	Select One 💌
[-]	<b>NLLP</b>	
	Start Text Char *	0B
	End Text Char *	1C
	Last Text Char *	0D
		Frequency Duration
	Data time out *	Select One 💌
		Frequency Duration
	Data Polling Frequency *	Select One
		Frequency Duration
	Ack time out *	Frequency Duration
	Ack Polling Frequency *	Frequency Duration Select One
	File Base Location *	
	Process Flow Name *	None
Advand	ed properties	

Figure 13.18: Create MLLP Activity

4. Enter the name and description for the new MLLP activity in the *Name* and *Description* fields respectively.

- 5. Expand the *TCP Connection* properties. TCP connection properties are displayed.
- 6. In *Host Name* field, enter the IP address of the host to which the MLLP Client will send the data.

ADEPTIA

- 7. In *Port* field, enter the port at which the MLLP client will connect the MLLP Server.
- 8. Select *Client* from the *Mode Type* drop-down list.
- 9. In *Connection Retry Count* field, enter the maximum number of retries, the adapter attemps to connect to a specific TCP/IP connection before giving up.
- 10. In Interval between retry field, enter the duration between the retries.
- 11. Expand the *MLLP* Properties. The MLLP properties are displayed.
- 12. Enter start, end and last text character in *Start Text Character, End Text Character* and *Last Text Character* respectively.
- 13. Enter the data time out duration in *Data Time Out* field.
- 14. Enter the data polling frequency in the *Data Polling Frequency* field. This is time interval between successive polls for data.
- 15. Enter the acknowledgment timeout duration in *Ack Time Out* field.
- 16. Enter acknowledgment polling frequency in *Ack Polling Frequency*. This is time interval between successive polls for acknowledgemt.
- 17. Enter location where from where data is picked and sent to the MLLP server. The data which you want to send to the MLLP server should be kept in this location.
- 18. Click **Save** button. This displays a screen confirming that the MLLP activity has been created successfully. If the *Comments* property is enabled, then clicking **Save** will display a screen where you need to enter comments related to creating the MLLP activity (refer to Figure 3.6).
- 19. Enter the comments in the *Add Comments* field.

The comment should be at least 1 character in length.

20. Click **OK** to save the comments. This displays a screen confirming that the JMS Provider activity has been created successfully.



By default, the *Comments* property is disabled. To enable it, refer to the section <u>Updating System Properties</u>.

# Activating MLLP Activity

Once you create the MLLP server or client, you need to activate it in order to receive or send the data.

## Steps to activate MLLP Activity

- 1. Click **[+]** Administer to expand the tree and then click **[+]** Connector. All the items in the Connector category are displayed.
- 2. Click **MLLP**. The Manage MLLP screen is displayed (see Figure 13.19).



С	onfig	ure	> Services >	Connector > M	ILLP					
Ne	w	Edit	Delete   Revisi	ons   Dependenci	es	Select Field	to Search 💌			Search
Ac	tivate	2								
#		- (j):		Name		Description	Owner	Perm.	Modif	fied 🔻
1	$^{\circ}$	۵	MLLP_Server		MLLP Server		admin	RWX	08/30/10	12:05

Figure 13.19: Manage MLLP Activity

3. Select the MLLP activity that you want to activate and click *Activate* link. The selected MLLP activity is activated and a confirmation is screen is displayed. (see Figure 13.20).

MLLPConfiguration activity "MLLP\_Server(192168001005128315012904600002)" activated successfully.

Figure 13.20: Manage MLLP Activity



# 14 MISCELLANEOUS

This section allows you to create the following activities:

- <u>Context Download</u>
- Context Upload
- <u>Stored Procedure</u>
- Mail Notification

# **CREATING CONTEXT DOWNLOAD ACTIVITY**

Context Download activity is used to generate XML from a context variable. This is required when the context variable's information is to be stored in some target. This information can be passed as stream to other activities. For example, if you want to store variables and their values present in the context as per schema defined to any target activity like database target, file target, then context download activity can be used. It will generate XML of context variables and their values, which can be further used.

In the Adeptia Suite this feature is available in:

BPM Suite	Integration Suite	ETL Suite
$\checkmark$		$\checkmark$

### Steps to Create Context Download activity

- 1. In the Adeptia Suite homepage menu, click **[+]** Configure to expand the tree. All the items in the Configure category are displayed.
- 2. Click [+] Services to expand the tree. All the items in the Services category are displayed.
- 3. Click **[+]** Miscellaneous to expand the tree, and then click Context Download. The Manage Context Download screen is displayed (see Figure 14.1)



[+] My Monitor	Configure > Services > Polling > Ma	il		
[+] History				
[+] Design	New   Edit   Delete   Revisions   Depender	Select F	ield to Search 💌	Search
[-] Configure				
[+] Forms	# Name	Description	Owner Perm.	Modified 🔻
[+] WorkFlow		No records found		
[-] Services				
[+] Data Dictionary				
[+] Source				
[+] Schema				
[+] Target				
[+] Web Services				
[+] Data Transform				
[+] Extensions				
[+] Polling				
[+] Connector				
[-] Miscellaneous				
📴 Context Download				
🛃 Context Upload				

Figure 14.1: Manage Context Download

4. Click **New** link. The Create Context Download screen is displayed (see Figure 14.2).


Configure > Services > Miscellaneous	> Context Download
[-] Standard properties	
Name *	
Description *	
Schema Name *	SELECT
	Define Context Variable(s)
[+] Advanced properties	
* Mandatory fields.	
Save Cancel	

Figure 14.2: Create Context Download

- 5. Enter the name and description for Context Download in the *Name* and *Description* fields respectively.
- 6. Select the schema activity from the *Schema Name* drop-down list.
- 7. To define the context variable, click **Define context variable(s)** button. The Map Context Variable screen is displayed (see Figure 14.3).



chema Elements	Variable Name	e	Variable Value	N	ullab
E-Root				*	
				*	
				*	
				*	
				*	
		Add Vari	able		




8. Expand the selected schema by clicking [+]. All fields of selected schemas are displayed (see Figure 14.4).



Мар (	Context Variable		_
Schema Elements	Variable Name	Variable Value	Nullable
<sup>Ģ</sup> "Root			
<sup>⊟</sup> "Record ●Action			
□ NAMEINSURED □ ADDRESS			
DDOB			
DTELEPHONENO DEXPIRYDATE DPREMIUMMEDICAL DPREMIUMDENTAL DSECURITYCODE	Ad	d Variable	
Ok Cancel			

Figure 14.4: Expand Schema

9. Enter a name for the context variable in the Variable Name field (see Figure 14.5).





10. Select the schema element, which you want to map with the above defined variable. The XPath of the selected element is displayed in the Mapping field (see Figure 14.6).







Figure 14.6: Map Schema Element with Variable

11. Click **Apply** button. Value of the selected schema element is displayed in the *Variable Value* field (see Figure 14.7).



### Figure 14.7: Apply Map

- 12. Repeat steps from 8 to10 to map the context variable with other elements.
- 13. Check the *Nullable* checkbox in case you want this variable to allow blank value.
- 14. Click **OK** button to return to the Create Context Download screen.





To learn about Advanced Properties refer to Changing Advanced Properties section.

- 15. Click **Save** button. This displays a screen confirming that the Context Download activity has been created successfully. If the *Comments* property is enabled, then clicking **Save** will display a screen where you need to enter comments related to creating the context download activity (refer to Figure 3.6).
- 16. Enter the comments in the *Add Comments* field.



The comment should be at least 1 character in length.

17. Click **OK** to save the comments. This displays a screen confirming that the Context download activity has been created successfully.



By default, the *Comments* property is disabled. To enable it, refer to the *Updating System Properties* section in *Administrator Guide*.

# CREATING CONTEXT UPLOAD ACTIVITY

Context Upload is used to map any field of a schema to the Process Flow Context Variable. Once the variable is set in process flow context, it can be used by any activity in the Process Flow.

Context Upload variables can be created for all types of schemas. In case of XML Schema, only those XML schemas, which are created by uploading XSD file, or DTD file (with Convert to XSD option enabled) can be used to create Context Upload variables.

In the Adeptia Suite this feature is available in:

BPM Suite	Integration Suite	ETL Suite
$\checkmark$	$\checkmark$	$\checkmark$

#### Steps to Create Context Upload activity

- 1. In the Adeptia Suite homepage menu, click **[+]** Configure to expand the tree. All the items in the Configure category are displayed.
- 2. Click [+] Services to expand the tree. All the items in the Services category are displayed.
- 3. Click **[+]** Miscellaneous to expand the tree, and then click Context Upload. The Manage Context Upload screen is displayed (see Figure 14.8)



[+] My Monitor	Configure > Services > N	Aiscellaneous > Context Upload		
[+] History				
[+] Design	New   Edit   Delete   Revision	ns   Dependencies	Select Field to Search 💌	Search
[-] Configure				
[+] Forms	# Name	Description	Owner	Perm. Modified <b>*</b>
[+] WorkFlow		No records found		
[-] Services				
[+] Data Dictionary				
[+] Source				
[+] Schema				
[+] Target				
[+] Web Services				
[+] Data Transform				
[+] Extensions				
[+] Polling				
[+] Connector				
[-] Miscellaneous				
📴 Context Download				
Context Upload				

Figure 14.8: Manage Context Upload

4. Click **New** link. The Create Context Upload screen is displayed (see Figure 14.9).

Configure > Services > Miscellaneous	> Context Upload
[-] Standard properties	
Name *	
Description *	
Schema Name *	SELECT
	Define Context Variable(s)
[+] Advanced properties	
* Mandatory fields.	
Save Cancel	

Figure 14.9: Create Context Upload

- 5. Enter the name and description for Context Upload in the *Name* and *Description* fields respectively.
- 6. Select the schema activity from the *Schema Name* drop-down list.
- 7. To define the context variable, click **Define context variable(s)** button. The Map Context Variable screen is displayed (refer to Figure 14.3).
- 8. Expand the selected schema by clicking [+]. All fields of selected schemas are displayed (refer to Figure 14.4).
- 9. Enter a name for the context variable in the Variable Name field (refer to Figure 14.5).
- 10. Select the schema element, which you want to map with the above defined variable. The XPath of the selected element is displayed in the Mapping field (refer to Figure 14.6).



The Context Upload variable accepts only string and list as parameters. When it is used in a process flow, then you need to specify the XPath value. If you select 'String' as the Data Type property, then the first XPath value



is used.

- 11. Click **Apply** button. Value of the selected schema element is displayed in the *Variable Value* field (refer to Figure 14.7).
- 12. Repeat step 8 to11 to map the context variable with other elements.
- 13. Click **OK** button to return to the Create Context Upload screen.

To learn about Advanced Properties refer to <u>Changing Advanced</u> <u>Properties</u> section.

- 14. Click **Save** button. This displays a screen confirming that the Context Upload activity has been created successfully. If the *Comments* property is enabled, then clicking **Save** will display a screen where you need to enter comments related to creating the context upload activity (refer to Figure 3.6).
- 15. Enter the comments in the Add Comments field.



The comment should be at least 1 character in length.

16. Click **OK** to save the comments. This displays a screen confirming that the Context Upload activity has been created successfully.



By default, the *Comments* property is disabled. To enable it, refer to the *Updating System Properties* section in *Administrator Guide*.

### **CREATING STORED PROCEDURE**

A stored procedure is a group of SQL statements that form a logical unit and perform a particular task. Stored procedures are used to encapsulate a set of operations or queries to execute on a database server. Stored procedures can be compiled and executed with different parameters and they may have any combination of input, output, and input/output parameters.

Using Adeptia Server's Stored Procedure activity, you can execute a database stored procedure. Stored Procedure activity takes IN parameters from process flow context. So you need to set the value of IN parameters in the process flow context. For Example if the selected stored procedure has IN parameters as *empid*, you have to set an input variable in process flow context with the name *Service. ActivityName>.InParams.empid*, where *Activity Name>* is the name of the stored procedure activity, which is used in the process flow. You can set this input variable using put-context-var, Process flow Variable or custom plugin.

Similarly OUT parameters of the stored procedure are set to process flow context. For example if the selected stored procedure has OUT parameters as *salary*, the output variable is set in the process flow context as *Service. ActivityName>.OutParams.salary*, where *Activity Name>* is the name of the activity, which is used to execute the process flow. You can further use this variable and its value is the process flow. Value of output variable set by stored procedure activity, is always in string format. You need to type cast it in required format. Stored procedure



doesn't generate a stream. So you have to use context source activity after stored procedure activity. To know how to create a context source, refer to the section <u>Using Context Source</u> and <u>Context Target</u>.

Variable name for INOUT parameter will be *Service.* <*ActivityName*>.*InOutParams.count*, where <*Activity Name*> is the name of the activity, which is used to execute the process flow and count is the INOUT parameter of the stored procedure.

#### Limitation:

Adeptia Server stored procedure activity is supported for MS SQL, Oracle and Sybase version 9.0.2.

In the Adeptia Suite this feature is available in:

BPM Suite	Integration Suite	ETL Suite
$\checkmark$	$\checkmark$	$\checkmark$


#### Prerequisites:

• Database Info activity must be created before creating Stored Procedure activity.

#### Steps to create Stored Procedure activity

- 1. In the Adeptia Suite homepage menu, click **[+]** Configure to expand the tree. All the items in the Configure category are displayed.
- 2. Click [+] Services to expand the tree. All the items in the Services category are displayed.
- 3. Click **[+]** Miscellaneous to expand the tree, and then click Stored Procedure. The Manage Stored Procedure screen is displayed (see Figure 14.10).


[+]	My Monitor	Configure	> Services > Miscellaneous > Store	d Procedure			
[+]	History						
[+]	Design	New   Edit	Delete   Revisions   Dependencies	Select Fiel	d to Search 💙		Search
[-] <sup>–</sup>	Configure						
[+	] Forms	#	Name	Description	Owner	Perm.	Modified 🔻
[+	] WorkFlow			No records found			
[-]	Services						
	[+] Data Dictionary						
	[+] Source						
	[+] Schema						
	[+] Target						
	[+] Web Services						
	[+] Data Transform						
	[+] Extensions						
	[+] Polling						
	[+] Connector						
	[-] Miscellaneous						
	📴 Context Download						
	🛃 Context Upload						
	Stored Procedure						





Design > Services > Miscellaneous > Stored Pro	ocedure
[-] Standard properties	
Name *	
Description *	
Database Info	SELECT
Stored Procedure Name *	Browse Stored Procedures
Stored Procedure Parameters	
In Params	
Out Params	
InOut Params	
[+] Advanced properties * Mandatory fields.	
Save Cancel	

4. Click the **New** link. The Create Stored Procedure screen is displayed (see Figure 14.11).



- 5. Enter the name and description for new stored procedure activity in the *Name* and *Description* fields respectively.
- 6. Select the *database* info activity from the *Database Info Id* drop-down list.

1	To learn how to create Database Info activity, refer to the section Creating	1
Ø	Database Info in Administrator Guide.	1

7. To select the database stored procedure, click **Browse Stored Procedure** button. The Select Stored Procedure screen with list of stored procedure is displayed (see Figure 14.12)





Figure 14.12: Select Stored Procedure

8. Select the required stored procedure and click **Get Parameters** button. The stored procedure parameter screen is displayed with list of parameters (see Figure 14.13).






Figure 14.13: View Parameters

9. Click **OK** to return to Stored Procedure activity screen. Parameters of the selected procedure are populated in *Stored Procedure Parameters* field (see Figure 14.14).

Services > Miscellaneous > Stored Procedure				
[-] Standard properties				
Name *	StoredProcedure			
Description *	StoredProcedure			
Database Info	dbi_sql (dbi_sql)			
Stored Procedure Name *	db0.sp_proc2 Browse Stored Procedures			
Stored Procedure Parameters				
In Params	@rolino varchar			
Out Params	@name char			
InOut Params				
[+] Advanced properties * Mandatory fields. Save Cancel				

Figure 14.14: Manage Stored Procedure

- 10. In the Stored Procedure activity screen click **Save** button. This displays a screen confirming that the Stored Procedure activity has been created successfully. If the *Comments* property is enabled, then clicking **Save** will display a screen where you need to enter comments related to creating the database schema (refer to Figure 3.6).
- 11. Enter the comments in the *Add Comments* field.



The comment should be at least 1 character in length.



12. Click **OK** to save the comments. This displays a screen confirming that the Stored Procedure activity has been created successfully.



By default, the *Comments* property is disabled. To enable it, refer to the *Updating System Properties* section in *Administrator Guide*.



# **CREATING NOTIFICATION ACTIVITY**

This section covers the following topics:

- Creating Mail Notification activity
- Creating Notification to send User Defined Message
- Creating Notification to send Process Flow Summary

### **Creating Mail Notification Activity**

In the Adeptia Suite, Notification is used to send mail to users about the execution status of a process flow. You can add the Mail Notification activity anywhere in the process flow. You can add more than one Mail Notification activities in a process flow.

The Mail Notification activity is of two types:

- User Defined Message: This type of mail notification is used to send custom email message to any user during execution of a process flow. Any file can be attached to the mail.
- **Process Flow Summary:** This type of mail notification is used by the Adeptia Server to dynamically send summary of a process flow execution.

In the Adeptia Suite this feature is available in:

BPM Suite	Integration Suite	ETL Suite
$\checkmark$	$\checkmark$	$\checkmark$

### **Creating Notification to Send User Defined Message**

Steps to create User Defined Message Notification

- 1. In the Adeptia Suite homepage menu, click **[+]** Configure to expand the tree. All the items in the Configure category are displayed.
- 2. Click [+] Services to expand the tree. All the items in the Services category are displayed.
- 3. Click **[+]** Notification to expand the tree, and then click Mail Notification. The Manage Mail Notification screen is displayed (see Figure 14.15).



-] My Monitor -] History	Config	ure > Services > Miscellaneous >	Mail Notification			
] Design	New   E	dit   Delete   Revisions   Dependencies	Select Field to	Search 💙		Searc
Configure [+] Forms	#	Name	Description	Owner	Perm.	Modified <b>*</b>
[+] WorkFlow	1 ()	PurchaseOrderProcessingNotify	notify when transaction finishes	demouser	RWX	09/01/09 12:29
[-] Services	2 ()	FulfillmentErrorNotify	notify when web service call fails	demouser	RWX	09/01/09 12:29
[+] Data Dictionary	3 0	NotifyPurchaseDepartment	notify puchase dept of new order	demouser	RWX	09/01/09 12:29
[+] Source [+] Schema	4 ()	EvalRec_MailNotification	Mail Notification to acknowledge the record processed	demouser	RWX	08/22/05 15:17
[+] Target						
[+] Web Services						
[+] Data Transform						
[+] Extensions						
[+] Polling						
[+] Connector						
[-] Miscellaneous						
📴 Context Download						
된 Context Upload						
Stored Procedure						
🖂 Mail Notification						

Figure 14.15: Manage Mail Notification

4. Click the **New** link. The Create Mail Notification screen is displayed (see Figure 14.16).



Configure > Services > Miscellaneou	s > Mail Notification		
[-] Standard properties			
Name *			
Description *			
Notification Type*	User Defined Message 💌		
Mail Subject*			
To User(s)	admin (Default Administrator) demo_manager (demo manager) demo_supervisor (demo supervisor) demouser (Demo User)		
To Email-Id(s) (comma separated)			
Message			
Notification Criteria	Running or Executed Successfully		
Attachment			
File Path			
File Name			
[+] Advanced properties			
* Mandatory fields.			
Save Cancel			

#### Figure 14.16: Create Mail Notification

- 5. Enter the name of the new Mail Notification in the *Name* field. Then, enter the description for the Mail Notification in the *Description* field.
- 6. Select User Defined Message from the *Notification Type* drop-down list.
- 7. Enter subject for the email message in the *Mail Subject* field.
- 8. Select the user(s) to whom you want to send the notification email from *To Adeptia user(s)* field.
- 9. Enter the recipient(s) email address in *To Email Id(s) (comma separated)* field.



You can select the recipient of the notification mail either by selecting user from *To Adeptia user(s)* or by specifying email address in *To Email Id(s) (comma separated)* field.

When you select user, the notification mail is sent to the email address specified while creating the user.

- 10. Enter the email message in the *Message* field.
- 11. To send a file as attachment, check the *Attachment* checkbox and enter the file path and file name in the *File Path* and *File Name* fields respectively.



To learn about Advanced Properties refer to section Changing Advanced Properties section.

- 12. Click **Save** button. This displays a screen confirming that the mail notification activity has been created successfully. If the *Comments* property is enabled, then clicking **Save** will display a screen where you need to enter comments related to creating the mail notification (refer to Figure 3.6).
- 13. Enter the comments in the *Add Comments* field.



The comment should be at least 1 character in length.

14. Click **OK** to save the comments. This displays a screen confirming that the mail notification activity has been created successfully.



By default, the *Comments* property is disabled. To enable it, refer to the *Updating System Properties* section in *Administrator Guide*.

### **Creating Notification to Send Process Flow Summary**

#### Steps to create Process Flow Summary Notification

- 1. In the Adeptia Suite homepage menu, click **[+]** Configure to expand the tree. All the items in the Configure category are displayed.
- 2. Click [+] Services to expand the tree. All the items in the Services category are displayed.
- 3. Click **[+]** Notification to expand the tree, and then click Mail Notification. The Manage Mail Notification screen is displayed (refer to Figure 14.15).
- 4. Click the **New** link. The Create Mail Notification screen is displayed (refer to Figure 14.16).
- 5. Enter the name of the new mail notification in the *Name* field. Then, enter the description for the mail notification in the *Description* field.
- 6. Select Process Flow Summary from the *Notification Type* drop-down list.
- 7. Enter subject for the email message in the *Mail Subject* field.
- 8. Select the user(s) to whom you want to send the notification email from *To Adeptia user(s)* field.
- 9. Enter the recipient(s) email address in *To Email Id(s) (comma separated)* field.



You can select the recipient of the notification mail either by selecting user from *To Adeptia user(s)* or by specifying email address in *To Email Id(s)* (comma separated) field.

When you select user, the notification mail is sent to the email address specified while creating the user.

10. Select one of the criteria from the *Notification Criteria* drop-down list. All criteria are explained in the table below.

Notification Criteria	Description
Running or Executed Successfully	Email is sent only when the process flow is running or executed successfully.
Failure	Email is sent only when the process flow execution is failed. However, if any activity before the mail notification fails, then all activities (including Mail Notification activity) are skipped and no email is sent.
	Thus, it is recommended to use the Mail Notification activity with the End Event of process flow. To know how to use Mail Notification Activity with End Event of the Process Flow, refer to <u>Attaching End</u> <u>Process (Mail Notification) to Process</u> <u>Flow</u> section.
Always	Email is sent whether the process flow execution is successful or failed. However, if any activity before the mail notification fails, then all activities (including Mail Notification activity) are skipped and no email is sent.
	Thus, it is recommended to use the Mail Notification activity with the End Event of process flow. To know how to use Mail Notification Activity with End Event of the Process Flow, refer to <u>Attaching End</u> <u>Process (Mail Notification) to Process</u> Flow section.

Table 14.1: Notification Criteria

To learn about Advanced Properties refer to **Changing Advanced Properties** section.

- 11. Click **Save** button. A screen is displayed where you need to enter comments related to creating the mail notification (refer to Figure 3.6).
- 12. Enter comments in the *Add Comments* field.



Ø

The comment should be at least 1 character in length.



13. Click **OK** to save the comments. This displays a screen confirming that the mail notification activity has been created successfully.



By default, the *Comments* property is disabled. To enable it, refer to the *Updating System Properties* section in *Administrator Guide*.

# 15 USING REPORTS & DASHBOARD

DashBoard collects data from various data sources, even outside Adeptia Server. As a user executes DashBoard, it displays the results in a graphical format with four different components clubbed together to form a single DashBoard. Monitoring DashBoard provides Adeptia Server user with real-time visibility into the performance of decisive services.

Monitoring DashBoard enables Administrator to analyze discrepancies between expected and actual performance and to monitor compliance with IT operational best practices in real-time.

DashBoard enables the user to represent data in the form of *PIE chart, Bar Chart, String chart* and *Table chart.* 

DashBoard applet represents data using the four components:

- Bar Chart
- String Chart
- Table Chart
- PIE Chart

DashBoard enables business users to view business level information like the number of orders received per customer (Bar Chart), Orders processed per business users (Bar Chart), Orders received per item (PIE Chart), List of new customers today (Table Chart), maximum order of the day (String Chart).

Using DashBoard can be broadly classified into three parts:

- Creating DashBoard Component
- Designing DashBoard
- Executing DashBoard

### Prerequisites

- To create any DashBoard activity, *Database Driver* and *Database Info* should be already created and table used for selection of columns for customized DashBoard creation should exist.
- JRE 1.5 needs to be installed on your system to open the Dashboard applet.



• The *Pop-up Blocker* needs to be disabled in the web browser, to open the Dashboard applet. By default, the *Pop-up Blocker* is enabled.

# **CREATING CUSTOM REPORT**

A Custom Report can be used to generate customize report of any set of data. Using Custom Report, you can also generate report for already executed or running process flows.

A custom report activity is created using the custom report template (jrxml file), which is generated by the *iReport* software. This custom report activity is further used to select the process flow and generate reports into PDF, XLS, CSV, TXT and HTML format.

*iReport* is a third party software which provides a graphical tool to design report template. For detailed information about iReport software refer to following website.

http://www.jasperforge.org/jaspersoft/opensource/business\_intelligence/ireport/

In the Adeptia Suite this feature is available in:

BPM Suite	Integration Suite	ETL Suite
$\checkmark$		

#### Steps to create a custom report activity

- 1. In the Adeptia Suite homepage menu, click **[+]** Configure to expand the tree. All the items in the Configure category are displayed.
- 2. Click [+] Reports & Dashboards to expand the tree and then click Custom Report. The Manage Custom Report screen is displayed (see Figure 15.1).

[+]	My Tasks	Config	ure > Reports & Dashboards > Cust	om Report			
[+]	My Documents						
[+]	My Solutions	New   E	dit   Delete   Revisions   Dependencies		Select Field to Search 💙		Search
[+]	My Monitor						
[+]	History	Execute					
		#	Name	Descripti	on Owner	Perm.	Modified 🔻
[+]	Design	1 ()	StandardProcessflowReport	StandardProcessflowReport	admin	RWX	07/26/06 13:14
[-]	Configure						
1	+] Forms						
1	+] WorkFlow						
1	+] Services						
1	-] Reports & Dashboards						
	Custom Report						
	🍫 DashBoardComponent						
	🍫 DashBoardDesign						

Figure 15.1: Manage Custom Report

3. Click the **New** link. The Create Custom Report screen is displayed (see Figure 15.2).



Configure > Reports & Dashboards	> Custom Report
[-] Standard properties	
Name *	
Description *	
Database Info Id	None
Upload Jrxml Files *	Upload Jrxml Files
	User Defined Parameter
Report Type *	PDF 💌
Note: Saving of activity will take tin	ne incase multiple Jrxml files are uploaded.
[+] Advanced properties	
* Mandatory fields.	
Save Cancel	

Figure 15.2: Create Custom Report Activity

- 4. Enter the name of Custom Report in the *Name* field. Then, enter the description for the Custom Report in the *Description* field.
- 5. Select the Database Info activity which points to the database Server to fetch the data, from the *Database Info ID* drop-down list.

\$	To learn how to create Database Info activity, refer to Creating Database
Ø	To learn how to create Database Info activity, refer to <i>Creating Database</i> <i>Info</i> section in the <i>Administrator Guide</i> .

6. To upload the Jrxml file (custom report template) generated using *iReport* software, click **Upload Jrxml File** button. The Upload Jrxml File screen is displayed (see Figure 15.3).

🖉 Upload Jrxml Files - Windows Internet Explorer	
	<b>A</b>
1 Choose File	
Click on Browse button to choose the file.	
Browse File Browse Upload File	
2 Click on Finish button to complete the process.	
Finish	

Figure 15.3: Select Jasper File

7. Click **Browse** button and select the Jrxml file. The path of the Jrxml file is displayed in the *Browse* File field (see Figure 15.4).



Upload Jr	kml Files - Microsoft Internet Explorer	
🕖 Choose I	File	
Click on Bro	wse button to choose the file.	
Browse File	C:\Jrxml\report.jrxml Browse	Upload File
2 Click on	Finish button to complete the process.	
Finish		

Figure 15.4: Select Jasper File

8. Click **Upload File** button. The file name is displayed in the *File Names* list (see Figure 15.5).

🚰 Upload Jrxml Files - Microsoft Internet Explorer	
Choose File	<u> </u>
Click on Browse button to choose the file. Browse File Upload File Upload File	
Select All   Unload File(s) report.jrxml	
Click on Finish button to complete the process.	

Figure 15.5: Jasper File Uploaded

9. Click **Finish** button. The uploaded *iReport* file is displayed in the *Upload Jrxml files* field (see Figure 15.6).



Configure > Reports & Dashboards >	Custom Report > StandardProcessflowReport			
[-] Standard properties				
Name *	StandardProcessflowReport			
Description *	StandardProcessflowReport			
Database Info Id	EvalXform_DbInfo (Database Info for HSQLDB.)			
Upload Jrxml Files *	StandardReportTemplate.j Upload Jrxml Files			
	User Defined Parameter			
Report Type *	PDF 💌			
Note: Saving of activity will take time incase multiple Jrxml files are uploaded.				
[+] Advanced properties				
* Mandatory fields.				
Save Save As Cancel				

Figure 15.6: Uploaded Jasper Files in Create Custom Report

10. To change value of user defined Parameter defined in the Jrxml file, click **User Defined Parameter** button. The Jasper Report Parameter screen is displayed with list of parameters defined in the Jrxml file (see Figure 15.7).

Jasper Rep	ort Parameters	
StandardReportTem	plate.jrxml	
Parameter Name	Parameter Value	
sucessCount		
totalCount		
activityNames		
sqlQuery		
activityPieChart		

Figure 15.7: Define Jasper Report Parameters

11. Enter the value of the parameter in the Parameter Value field.



In *Parameter Value* field you can enter any constant value or any value which is set in context. To enter the constant value, directly enter the value in the *Parameter Value* field. To enter the value from the context, enter the name of the context variable starting and ending with \$\$. For example \$\$Eid\$\$.

- 12. Click **OK** to close the Jasper Report Parameter screen.
- 13. Select the format in which the custom report is to be generated, from the *Report Type* dropdown list.

ADEPTIA

- 14. Click **Save** button. This displays a screen confirming that the custom report activity has been created successfully. If the *Comments* property is enabled, then clicking **Save** will display a screen where you need to enter comments related to creating the custom report (refer to Figure 3.6).
- 15. Enter the comments in the *Add Comments* field.

The comment should be at least 1 character in length.

16. Click **OK** to save the comments. This displays a screen confirming that the custom report activity has been created successfully.



By default, the *Comments* property is disabled. To enable it, refer to the *Updating System Properties* section in *Administrator* Guide.



A custom report can be used as a service in a process flow. For details, refer to the section **Using Custom Report in Process Flow**.

A custom report activity named *StandardprocessflowReport* comes precreated with the Adeptia Server. You can use that activity to generate the report for a Process Flow.

# **CREATING DASHBOARD COMPONENT ACTIVITY**

A DashBoard Component activity can be created using one of the following:

- Bar Chart
- String Chart
- Table Chart
- PIE Chart

In the Adeptia Suite this feature is available in:

BPM Suite	Integration Suite	ETL Suite
$\checkmark$		

### **Creating Bar Chart Activity**

#### Steps to create Bar Chart

1. In the Adeptia Suite homepage menu, click **[+]** Configure to expand the tree. All the items in the Configure category are displayed.



2. Click [+] Reports & Dashboards to expand the tree and then click Dashboard Component. The Manage DashBoard Component screen is displayed (see Figure 15.8).

[+]	My Tasks	Configure > Reports & Dashboards > I	DashBoardComponent		
[+]	My Documents		· · · · · · · · · · · · · · · · · · ·		
[+]	My Solutions	New   Edit   Delete   Revisions   Dependenci	esSelect Eie	ld to Search 💙	Search
[+]	My Monitor	New   Lait   Delete   Kevisions   Dependenti	es Select He		Jearch
[+]	History				
		# Name	Description	Owner Perm.	Modified 🔻
[+]	Design		No records found		
[-]	Configure				
	[+] Forms				
	[+] WorkFlow				
	[+] Services				
	[-] Reports & Dashboards				
	Custom Report				
	🍫 DashBoardComponent				
	🍫 DashBoardDesign				

Figure 15.8: Manage Dashboard Component

3. Click the New link. The Create DashBoard Component screen is displayed (see Figure 15.9).

Configure > Reports & Dashboards > D	)ashBoardComponent
[-] Standard properties	
Name *	
Description *	
DashBoard Components *	BarChart 💌
Database Info Id *	SELECT Select Tables
[+] Advanced properties	
* Mandatory fields.	
Save Cancel	

Figure 15.9: Create Dashboard Component

- 4. Enter the name and description of the new DashBoard Component in the *Name* and *Description* fields respectively.
- 5. Select Bar Chart from the *DashBoard Component* drop-down list.
- 6. Select the appropriate Database Info, depending on the database you want to use, from the *Database Info Id* drop-down list.
- 7. Click **Select Tables** button. The Select Table screen is displayed (see Figure 15.10).



 Select Table
C system_aliases
O SYSTEM_ALLTYPEINFO
C SYSTEM_AUTHORIZATIONS
O SYSTEM_BESTROWIDENTIFIER
C SYSTEM_CACHEINFO
C SYSTEM_CATALOGS
O SYSTEM_CHECK_COLUMN_USAGE
O SYSTEM_CHECK_CONSTRAINTS
C SYSTEM_CHECK_ROUTINE_USAGE
C SYSTEM_CHECK_TABLE_USAGE
C SYSTEM_CLASSPRIVILEGES
C SYSTEM_COLLATIONS
C SYSTEM_COLUMNPRIVILEGES
O SYSTEM_COLUMNS
C SYSTEM_CROSSREFERENCE
C SYSTEM INDEXINFO

Figure 15.10: Select Table


8. Select the required table and click **Get Columns** button. The Columns in Bar Chart screen is displayed (see Figure 15.11).



Table name is : SYSTEM_ALL4 • Table Selection	ASES
X-Axis Column	OBJECT_TYPE
Y-Axis Column [Integer type only]	OBJECT_TYPE
O Table Query HELP: Valid Quer	У

Figure 15.11: Select Columns for Bar Chart

9. Select the X-Axis and Y-Axis components for the Bar Chart from the X-Axis Column and Y-Axis Column [Integer type only] drop-down lists respectively.



- 10. Click **Save** button to save the Bar Chart information. A screen is displayed confirming that the DashBoard Component activity has been created successfully. If the *Comments* property is enabled, then clicking **Save** will display a screen where you need to enter comments related to creating the dashboard component (refer to Figure 3.6).
- 11. Enter comments in the *Add Comments* field.



The comment should be at least 1 character in length.

- 12. Click **OK** to save the comments and return to the Create Dashboard Component screen.
- 13. Click **Save** button. A screen is displayed confirming that the DashBoard Component activity has been created successfully.



```
Ø
```

By default, the *Comments* property is disabled. To enable it, refer to the *Updating System Properties* section in *Administrator* Guide.

### Creating String Chart Activity

### Steps to create String Chart

- 1. In the Adeptia Suite homepage menu, click **[+]** Configure to expand the tree. All the items in the Configure category are displayed.
- 2. Click **[+] Reports & Dashboards** to expand the tree and then click **Dashboard Component**. The Manage DashBoard component screen is displayed (refer to Figure 15.8).
- 3. Click the **New** link. The Create DashBoard Component screen is displayed (refer to Figure 15.9).
- 4. Enter the name and description for the new DashBoard Component in the *Name* and *Description* fields respectively.
- 5. Select String Chart from the *DashBoard Components* drop-down list.
- 6. Select the appropriate Database Info, depending on the database user wants to use, from the *Database Info Id* drop-down list.
- 7. Click **Select Tables** button. The Select Tables screen is displayed (refer to Figure 15.10).
- 8. Click Get Columns button. The Select Fields screen is displayed (see Figure 15.12).



ashboard Component [String Chart]	
Select Fields:	
Table name is : SYSTEM_ALIASES         Select All (Click on Select all to select all the Columns from specified table) or click on individual column name and write the simple Select query with Comma (,) Seprated Column names.         OBJECT_TYPE (VARCHAR)         OBJECT_CAT (VARCHAR)         OBJECT_SCHEM (VARCHAR)         OBJECT_NAME (VARCHAR)         ALIAS_CAT (VARCHAR)         ALIAS_SCHEM (VARCHAR)         ALIAS_(VARCHAR)	
Ok Back	

Figure 15.12: Select Fields

- 9. Click **Select All** to select all the columns from specified table or click individual column name and write the simple Select query with Comma (,) Separated Column names and click **OK** button to return to the Create Dashboard Component screen.
- 10. Click **Save** button. This displays a screen confirming that the DashBoard Component activity has been created successfully. If the *Comments* property is enabled then clicking **Save** will display a screen where you need to enter comments related to creating the dashboard component (refer to Figure 3.6).
- 11. Enter the comments in the Add Comments field.



The comment should be at least 1 character in length.

12. Click **OK** to save the comments. This displays a screen confirming that the DashBoard Component activity has been created successfully.



By default, the *Comments* property is disabled. To enable it, refer to the *Updating System Properties* section in *Administrator* Guide.

### **Creating Table Chart Activity**

Steps to create a Table Chart



- 1. In the Adeptia Suite homepage menu, click **[+]** Configure to expand the tree. All the items in the Configure category are displayed.
- 2. Click **[+]** Reports & Dashboards to expand the tree and then click Dashboard Component. The Manage DashBoard component screen is displayed (refer to Figure 15.8).
- 3. Click the **New** link. The Create DashBoard Component screen is displayed (refer to Figure 15.9).
- 4. Enter the name and description for the new DashBoard Component in the *Name* and *Description* fields respectively.
- 5. Select Table Chart from the *DashBoard Components* drop-down list.
- 6. Select the appropriate Database Info, depending on the database user wants to use, from the *Database Info Id* drop-down list.
- 7. Click Select Tables button. The Select Table screen is displayed (refer to Figure 15.10).
- 8. Click **Get Columns** button. The Select Fields screen is displayed (refer to Figure 15.12)
- 9. Click **Select All** to select all the columns from specified table or click individual column name and write the simple Select query with Comma (,) Separated Column names and click **OK** button to return to the Create Dashboard Component screen.
- 10. Click **Save** button. This displays a screen confirming that the DashBoard Component activity has been created successfully. If the *Comments* property is enabled, then clicking **Save** will display a screen where you need to enter comments related to creating the dashboard component (refer to Figure 3.6).
- 11. Enter the comments in the *Add Comments* field.



The comment should be at least 1 character in length.

12. Click **OK** to save the comments. This displays a screen confirming that the DashBoard Component activity has been created successfully.



By default, the *Comments* property is disabled. To enable it, refer to the *Updating System Properties* section in *Administrator* Guide.

### **Creating PIE Chart Activity**

#### Steps to create a PIE Chart

- 1. In the Adeptia Suite homepage menu, click **[+]** Configure to expand the tree. All the items in the Configure category are displayed.
- 2. Click [+] Reports & Dashboards to expand the tree and then click Dashboard Component. The Manage DashBoard component screen is displayed (refer to Figure 15.8).
- 3. Click the **New** link. The Create DashBoard Component screen is displayed (refer to Figure 15.9).
- 4. Enter the name and description for the new DashBoard Component in the *Name* and *Description* fields respectively.

- 5. Select PIE Chart from the *DashBoard Components* drop-down list.
- 6. Select the appropriate Database Info, depending on the database user wants to use, from the *Database Info Id* drop-down list.

ADEPTIA

- 7. Click **Select Tables** button. The Select Table screen is displayed (refer to Figure 15.10).
- 8. Click Get Columns button. The Select Columns screen is displayed (refer to Figure 15.11).
- 9. Select the X-Axis and Y-Axis for the PIE Chart from the *X-Axis Column* and *y-Axis Column* [*Integer type only*] drop-down lists respectively.

In PIE Chart Y-Axis Column can take only integer values or values which could be evaluated to an integer e.g. a string with value "2". Any other value will cause erroneous behavior.

You can write, SQL query to define columns of PIE chart. To write SQL query, click Table Query radio button and enter your query in the Table Query field.

- 10. Click **Save** button. This displays a screen confirming that the DashBoard Component activity has been created successfully. If the *Comments* property is enabled, then clicking **Save** will display a screen where you need to enter comments related to creating the dashboard component (refer to Figure 3.6).
- 11. Enter the comments in the *Add Comments* field.

The comment should be at least 1 character in length.

- 12. Click **OK** to save the comments and return to the Create Dashboard Component screen.
- 13. Click **Save** button. A screen is displayed confirming that the DashBoard Component activity has been created successfully.



By default, the *Comments* property is disabled. To enable it, refer to the *Updating System Properties* section in *Administrator* Guide.

# **CREATING DASHBOARD DESIGN ACTIVITY**

In the Adeptia Suite this feature is available in:

BPM Suite	Integration Suite	ETL Suite
$\checkmark$		

#### Steps to create a DashBoard Design activity

1. In the Adeptia Suite homepage menu, click **[+]** Configure to expand the tree. All the items in the Configure category are displayed.



2. Click **[+]** Reports & Dashboards to expand the tree and then click Dashboard Design. The Manage DashBoard Design screen is displayed (see Figure 15.13).

[+]	My Tasks	Configure > Reports & Dashboards > Das	shBoardDesign			
[+]	My Documents		•			
[+]	My Solutions	New   Edit   Delete   Revisions   Dependencies	Sele	ct Field to Search 💌		Search
[+]	My Monitor	new   zak   belete   Kensions   bependences	0010			ocorcii
[+]	History	Execute				
		# Name	Description	Owner	Perm. M	odified 🔻
[+]	Design		No records found			
[-]	Configure					
	[+] Forms					
	[+] WorkFlow					
	[+] Services					
	[-] Reports & Dashboards					
	Custom Report					
	💁 DashBoardComponent					
	💁 DashBoardDesign					

Figure 15.13: Manage Dashboard Design

3. Click the **New** link. The Create DashBoard Design screen is displayed (see Figure 15.14).

Configure > Reports & Dashboards	> DashBoardDesign
[-] Standard properties	
Name *	
Description *	
Bar Chart	None 💌
PIE Chart	None 💌
Table Chart	None 💌
String Chart	None 💌
[+] Advanced properties	
* Mandatory fields.	
Save Cancel	

Figure 15.14: Creating Dashboard Design

- 4. Enter the name and description of the new DashBoard Design in the *Name* and *Description* fields respectively.
- 5. Then select any of the components from the *Bar Chart, PIE Chart, Table Chart* and *String Chart* drop-down lists. You may select one component from each chart and any number of charts.
- 6. Click **Save** button. This displays a screen confirming that the DashBoard Design activity has been created successfully. If the *Comments* property is enabled then clicking **Save** will



display a screen where you need to enter comments related to creating the dashboard design (refer to Figure 3.6).

7. Enter the comments in the *Add Comments* field.



The comment should be at least 1 character in length.

8. Click **OK** to save the comments. This displays a screen confirming that the DashBoard Design activity has been created successfully.



By default, the *Comments* property is disabled. To enable it, refer to the *Updating System Properties* section in *Administrator* Guide.

# EXECUTING DASHBOARD DESIGN

Steps to execute a DashBoard Design activity

- 1. In the Adeptia Suite homepage menu, click **[+]** Configure to expand the tree. All the items in the Configure category are displayed.
- 2. Click **[+] Reports & Dashboards** to expand the tree and then click **Dashboard Configure**. The Manage DashBoard Design screen is displayed (refer to Figure 15.13).
- 3. Select the radio button adjacent to required dashboard design activity that you want to execute and then click **Execute** link.
- 4. A DashBoard applet appears displaying the component that was chosen while creating the DashBoard Design activity (see Figure 15.15).






Figure 15.15: View Dashboard

5. To configure the refresh time, select the refresh time from the *Select refresh delay (in seconds)* drop-down list.



# **16 MANAGING ACTIVITIES**

Managing activities involves creating new activities, editing or deleting the existing activities, and saving another instance of those activities. It also includes viewing a revision history of activities and a list of related activities associated with an activity. Creation of various Adeptia Server activities has been covered in previous sections.

This section allows you to perform the following tasks related to an activity:

- Search an Activity
- View an Activity
- Edit an Activity
- Delete an Activity
- View Revision History of an Activity
- <u>View Dependant Activities of an Activity</u>
- Change Advanced Properties of an Activity

For editing, deleting and saving another instance of activities, viewing revision history and list of related activities, refer to the sections below.

### **SEARCHING AN ACTIVITY**

An activity can be searched by its name or description from the list of activities.

#### Steps to search an activity (for example Text Schema activity)

- 1. In the Adeptia Suite homepage menu, click **[+]** Configure to expand the tree. All the items in the Configure category are displayed.
- 2. Click [+] Services to expand the tree. All the items in the Services category are displayed.
- 3. Click **[+]** Schema to expand the tree, and then click **Text**. The Manage Text Schema screen is displayed (see Figure 16.1).

Configure     (+) Forms     (+) WorkFlow     (-) Services     (+) Data Dictionary	Configure > Services > Sche		Field to Search 🔽	Search
<ul> <li>[*] Source</li> <li>[*] Source</li> <li>[-] Schema</li> <li>[#] Adv. Database</li> <li>28 Adv. Positional</li> <li>28 Adv. Text</li> <li>(#] Database</li> <li>28 Excel</li> <li>29 Excel</li> <li>20 Festional</li> <li>20 Text</li> <li>30 Text</li> <li>31 Text</li> </ul>	#     Name       1     InventoryItemsCSVSchema       2     EvalScript_TextSchema       3     EvalJMSE_TextSchema	Description text schema for CSV file Text Schema for Employee data Text Schema for Stock Quotes	Owner Perm. demouser RWX demouser RWX demouser RWX	Modified ▼ 08/08/09 09:06 08/22/05 22:03 08/22/05 17:46





- 4. Select the field to search from *Select Field* drop-down list.
- 5. Enter the search criteria in the *Search* field. For example, if Name is selected in *Select Field* drop-down list then enter the name of the *Search* field.



Figure 16.2: Enter Search Criteria

6. Click **Search** button. The searched activity is displayed.

### **Using Wild Cards in Search**

If you do not remember the entire name or description of the activity, you can use Wild Card characters to search the activity. Once you select the option from the *Select Search Option* drop-down list, you can use a Wild Card character in the *Criteria* field. The Wild Card characters supported by Adeptia are described in the table below.

Wild Card Character	Description	Example
?	Signifies one character in the string	• Eval?MSE_TextSchema Searches for a string which has a character between Eval and MSE_TextSchema. Thus it displays EvalJMSE_TextSchema.
		• Eval???E?TextSchema Searches for a string which has three characters after Eval and one character after E. Thus it displays EvalJMSE_TextSchema.

Table 16.1:	Wild (	Card	characters	supported	hv	Adentia
	vvnu c	Jaru	characters	supporteu	ωy	лисрпа



*	Signifies mu	ultiple • Eval*E TextSchema
	.,	ultiple • Eval*E_TextSchema
	characters in a string	Searches for a string which has
		one or more characters after
		Eval and before E TextSchema.
		Thus, it displays EvalJMSE_Text
		Schema.
		Schema.
		<ul> <li>Eval *</li> </ul>
		Searches for a string which has
		one or more characters after
		Eval. In such a case, it can
		display more than one strings
		such as <i>EvalJMSE TextSchema</i> ,
		EvalScript_TextSchema
		EvalXForm_ExcelSchema, etc.
		You can select the string that
		you want from this list.
		jou want norn this list.

### **VIEWING ACTIVITY PROPERTIES**

### Steps to View Activity Properties (for example Text Schema activity)

- 1. In the Adeptia Suite homepage menu, click **[+]** Configure to expand the tree. All the items in the Configure category are displayed.
- 2. Click [+] Services to expand the tree. All the items in the Services category are displayed.
- 3. Click **[+]** Schema to expand the tree, and then click **Text**. The Manage Text Schema screen is displayed (refer to Figure 16.1).
- 4. Click the activity name. A screen is displayed displaying the properties of the selected activity (see Figure 16.3).



Properties					Value	
Description	Text Schema I	for Employee data				
Data Header Present	Yes					
Quotes Handling On	No					
		FieldName	Type DateForma	TimeFormat		
	1 [NA	WE	string 💽 mmddyyyy	* hh.mm.əə	1	
2 ADDRESS string mmddyyyy Mhhmmiss M						
	3 EN	AUD	string mmddyyyy	💌 hh.mm.sa	1	
	4 PH	IONENO	number 💌 mmddyyyy	hh:mm:ss	1	
Field Definition	5 DA	ATEOFBIRTH	date 💌 mm/dd/yy	*	1	
	6 DE	PARTMENT	string 💽 mmddyyyy	📧 hh.mm.ss	1	
	7 SA	LARY	number 🚬 mmddyyyy	hh:mm:ss	*	
	8 DA	ATEOFJOINING	date dd-mm-yy	×	10	
	9 [DE	SIGNATION	string 💌 mmddyyyy	📧 hh.mm.as	<u>×</u>	
	10 AG	3E	number 💽 mmddyyyy	hh:mm.ss	1	
XSD	W3C Se<br <xs:scheme< td=""><td>a xmlns:xs="http://v nt name="Root"&gt; otation&gt;</td><td>"ISO-8859-1"?&gt; v Adeptia Editor&gt; vwww.w3.org/2001/XMLScherr</td><td>a"&gt;</td><td></td><td></td></xs:scheme<>	a xmlns:xs="http://v nt name="Root"> otation>	"ISO-8859-1"?> v Adeptia Editor> vwww.w3.org/2001/XMLScherr	a">		
Entity Id	1921680010	0611553768421400	0004			
Owner	evalUser					
Owner's Group	evalGroup					
Dreation Date	08/12/2006 1	15:30:42				
ast Modified Date	08/22/2005 2	22:03:43				
est Modified By	admin					
Permissions	Owner(R,W,X)	Group(R.X)				

Figure 16.3: View Activity Properties

5. Click **Close** button to return to the Manage Activity screen.

### **EDITING AN ACTIVITY**

#### Steps to edit an activity (for example Text Schema Activity)

- 1. In the Adeptia Suite homepage menu, click **[+]** Configure to expand the tree. All the items in the Configure category are displayed.
- 2. Click [+] Services to expand the tree. All the items in the Services category are displayed.
- 3. Click **[+]** Schema to expand the tree, and then click **Text**. The Manage Text Schema screen is displayed (refer to Figure 16.1).
- 4. Select the radio button adjacent to the activity, which you want to edit and then click the **Edit** link. A screen is displayed that allows you to change the properties of the selected activity (see Figure 16.4).



Services > Schema > Text > EvalJMSE_TextSchema [·] Standard properties				
	ame * EvalJMSE_TextSchema			
	escription * Text Schema for Stock Quotes			
	ata Header Present			
	ecord Separator* \n			
	eld Separator*			
Download Schema Definition File Download				
	reate Schema Definition*			
C Use Definition File Data V Upload File				
	Enter the Fields Sequentially			
	# FieldName Type DateFormat TimeFormat			
	1 Symbol string r mmddyyyy r hh:mm:ss r			
	2 CompanyName string mmddyyyy mhh:mm:ss			
	3 LastTradePrice number mmddyyyy rhh:mm:ss r			
	4 TradeTime date  mm/dd/yy  hh:mm:ss			
Number of Rows 1 at Position 10 Add Row Remove Row				
[+] Advanced properties				
* Mandatory fields.				
Save Save As Cancel Test				

Figure 16.4: Edit Activity

You can edit only those activities,	in which you have write permission

- 5. After changing the properties, click **Save** button to save the changes. This displays a screen confirming that the activity has been updated successfully. If the *Comments* property is enabled, then clicking **Save** will display a screen where you need to enter comments related to editing the activity (refer to Figure 3.6).
- 6. Enter the comments in the *Add Comments* field.



7. Click **OK** to save the comments. This displays a screen confirming that the activity has been updated successfully.

Ø



By default, the *Comments* property is disabled. To enable it, refer to the *Updating System Properties* section in *Administrator* Guide.

To save another instance of the edited activity with different name, change the activity name in the *Name* field and then click **Save As** button. A screen is displayed confirming that the activity has been created successfully.



You can verify a source or target activity at design time. For this, click **Test**. This verifies the values in the fields of the activity and checks whether the source or target actually exists in the specified location. The verifications on the fields vary with each activity.

# DELETING AN ACTIVITY

### Steps to delete an activity

- 1. In the Adeptia Suite homepage menu, click **[+]** Configure to expand the tree. All the items in the Configure category are displayed.
- 2. Click [+] Services to expand the tree. All the items in the Services category are displayed.
- 3. Click **[+]** Schema to expand the tree, and then click **Text**. The Manage Text Schema screen is displayed (refer to Figure 16.1).
- Select the radio button adjacent to the activity that you want to delete and then click the Delete link. A screen is displayed asking for the confirmation to delete an activity (see Figure 16.5).




Figure 16.5: Delete an Activity

- 5. Click **OK** button if you are sure to delete the activity. If the *Comments* property is enabled, then clicking **OK** will display a screen where you need to enter comments related to deleting the activity (refer to Figure 3.6).
- 6. Enter the comments in the *Add Comments* field.



The comment should be at least 1 character in length.

7. Click **OK** to save the comments. This displays a screen confirming that the activity has been deleted successfully.



(M)	
Ý	

By default, the *Comments* property is disabled. To enable it, refer to the *Updating System Properties* section in *Administrator* Guide.

# VIEWING REVISION HISTORY

The Revision History of an activity displays a log of actions that have been performed on the activity.

#### Steps to view Revision History of an activity (for example Text Schema activity)

- 1. In the Adeptia Suite homepage menu, click **[+]** Configure to expand the tree. All the items in the Configure category are displayed.
- 2. Click [+] Services to expand the tree. All the items in the Services category are displayed.
- 3. Click **[+]** Schema to expand the tree, and then click **Text**. The Manage Text Schema screen is displayed (refer to Figure 16.1).
- 4. Select the radio button adjacent to the activity whose revision log you want to view, and then click the **Revisions** link. A screen is displayed that shows a list of actions performed on the selected activity, in descending order (see Figure 16.6).

# 🔻	Date	User	Group		Comments
1	03/24/2007 12:26:54	admin	administrators	Changed record separator	
2	03/24/2007 12:26:29	admin	administrators	Added Age Field	
3	03/24/2007 12:19:37	admin	administrators		
3	12:19:37	aunin	aummistrators		

Figure 16.6: View Revision History

- 5. This screen displays the date and time of the action, the User's name and group of the user who performed the action and also the comments (if any) entered for an action.
- 6. Click **Back** to go to the Manage Text Schema screen.

8	The					dependent			
Ø	"abpr	n.appmanag	gement.log	gRetainTil	ne".	For example,	to c	heck I	ast year's
	histor	y of activiti	es, you ne	ed to cha	ange	the system da	ate ai	nd ther	n click the
	Revis	sion Histor	<b>y</b> option.						

# VIEWING DEPENDENT ACTIVITIES

The Dependent Activities of an activity displays a list of activities that are using or are dependent on the activity. It includes activities that are directly or indirectly dependent upon the selected activity. If an activity is edited, then all the related activities will, in turn, be affected.



For example, there is a database driver namely DBDriver1. This driver is used by the database info DBInfo. The database info DBInfo is further used by the database schema DBSchema. The DBSchema is loaded while mapping source and target elements.

When the mapping activity is used in a process flow, it extracts the elements from the DBSchema. This implies that the mapping activity uses the DBSchema directly and the process flow indirectly. The DBSchema further extracts information from the DBInfo. This implies that the DBSchema uses the DBInfo directly and the process flow indirectly. The DBInfo further locates the driver DBDriver1. This implies that the DBInfo uses the DBDriver1 directly and the process flow indirectly.

The Dependent Activities will display the process flow and a list of all activities that are directly related to the selected activity. In the above example, the related activities for DBDriver1 will display the process flow and DBInfo. The related activities for DBInfo will display the process flow and DBSchema. The related activities of DBSchema will further include the process flow and the mapping activity.

#### Steps to view Dependent Activities of an activity (for example Text Schema activity)

- 1. In the Adeptia Suite homepage menu, click **[+]** Configure to expand the tree. All the items in the Configure category are displayed.
- 2. Click [+] Services to expand the tree. All the items in the Services category are displayed.
- 3. Click [+] Schema to expand the tree, and then click **Text**. The Manage Text Schema screen is displayed (refer to Figure 16.1).
- Select the radio button adjacent to the activity, whose list of dependant activities you want to view, and then click the **Dependencies** link. A screen is displayed that shows a list of activities directly and indirectly dependent on the selected activity (see Figure 16.7).

De	Dependent activities for Text 'EvalJMSE_TextSchema'							
# 🔺	Activity Name	Activity Type	Description	Action				
1	EvalJMSE_Mapping	Data Mapping	Text to Database Mapping	View Dependencies Edit				
2	customer	Process Flow	cust	View Dependencies Edit				
3	EvalJMSE_ProcessFlow	Process Flow	Process Flow for JMS Event demo	View Dependencies Edit				
	_							
Back								

Figure 16.7: View Dependant Activities

5. This screen displays the name and type of the activity that is using this activity. It also displays the activity description. In addition to the View link, it also shows a Dependencies Edit link, against each activity which further have activities dependent upon them. For example, click Dependencies Edit against the activity. A screen is displayed which lists all activities dependent upon the activity (see Figure 16.8).

De	Dependent activities for Data Mapping 'EvalJMSE_Mapping'								
# <b>^</b> 1	Activity Name EvalJMSE_ProcessFlow	Activity Type Process Flow	Description Process Flow for JMS Event demo	Action View Dependencies Edit					
Back									

Figure 16.8: View Related Activities

6. Click **Back** to go to the Manage Text Schema screen.



A	Related Activities cannot be viewed for Process Flows, WebDAV Folder and the Dashboard. It is also not displayed for the Users and Groups as all				
Ŵ	the Dashboard. It is also not displayed for the Users and Groups as all				
	activities are dependent upon Users and Groups.				

## CHANGING ADVANCED PROPERTIES

Advanced properties of an activity show the name of the Owner, Creation Date, Last Modified Date, Modified By and Permissions.

The advanced properties vary for each activity. However, the process of changing advanced properties is similar for all activities. The process of changing advanced properties for a Text schema is explained below.

#### To change the permission of an activity:

- 1. In the Adeptia Suite homepage menu, click **[+]** Configure to expand the tree. All the items in the Configure category are displayed.
- 2. Click [+] Services to expand the tree. All the items in the Services category are displayed.
- 3. Click **[+]** Schema to expand the tree, and then click **Text**. The Manage Text Schema screen is displayed (refer to Figure 16.1).
- 4. Select the radio button adjacent to the activity that you want to edit and then click the **Edit** link. The Edit Text Schema screen is displayed in edit mode. (refer to Figure 16.4).
- 5. To change the advance properties, click **[+]** Advanced Properties. All the fields of advance properties are displayed (see Figure 16.9).



[-] Advanced properties	
Quotes Handling On	
Allow Less Fields	
Filter Invalid XML Characters	
Handle Enclosing Character	
Owner*	evalUser (Default user for eval FI)
Creation Date	08/12/2006 15:30:42
Last Modified Date	08/22/2005 22:03:43
Last Modified By	admin
	Read Write Execute
	Owner 🔽 🔽
Permissions*	Group 🔽 🗖
	Other
* Mandatory fields.	
Save Save As Cancel Test	

Figure 16.9: View Advanced Properties

6. To change the ownership of the activity, select the owner from the *Owner* drop-down list.

1	A user	can	select	another	user	within	its	group	only	as	the	owner	of	the
	activity	•												

- 7. The Creation Date, Last Modified Date and Last Modified By fields are non editable. A user cannot change the values of these fields.
- 8. To change the permissions, check the required checkboxes beside Permissions according to the following tables.

	Owner
Read	Read permission allows the owner user to view the activity. The Read checkbox is pre-selected and cannot be unchecked.
Write	Write permission allows the owner user to Edit the activity.
Execute	Execute permission allows the owner user to Execute the activity.

Table 16.2: Owner Permissions



#### Table 16.3: Group Permissions

	Group
Read	Read permission allows the other users of the owner's group to view the activity.
Write	Write permission allows the other users of the owner's group to Edit the activity.
Execute	Execute permission allows the other users of the owner's group to Execute the activity.

	Other
Read	Read permission allows the users of the other group to view the activity.
Write	Write permission allows the users of the other group to Edit the activity.
Execute	Execute permission allows the users of the other group to Execute the activity.

- 9. After changing the properties, click **Save** button to save the changes. This displays a screen confirming that the activity has been updated successfully. If the *Comments* property is enabled, then clicking **Save** will display a screen where you need to enter comments related to editing the activity (refer to Figure 3.6).
- 10. Enter the comments in the Add Comments field.



The comment should be at least 1 character in length.

11. Click **OK** to save the comments. This displays a screen confirming that the activity has been updated successfully.



By default, the *Comments* property is disabled. To enable it, refer to the *Updating System Properties* section in *Administrator* Guide.

# **17 WORKING WITH PROCESS FLOW**

A process flow is a set of activities arranged in a sequence to perform a specific task(s). Combining various activities i.e. Source, Target, Schema or Transformer etc. creates a process flow. The execution of a process flow is controlled by the Process Engine. The Process Engine starts the execution of process flow instances and all the activities present in a process flow. When the process flow is executed, data from the source is converted to the intermediate form and then it is dispatched to the target. The transformer does the conversion of data. In the Adeptia Server two types of transformers are used:



- Stream2XMLStream/XMLStream2stream: This transformer converts the source data to XML (i.e. Stream2XMLStream) and then XML to target data (i.e. XMLStream2Stream).
- SchemaStream2Record/SchemaRecord2Stream: This transformer converts source data to intermediate format (i.e. SchemaStream2Record) and then intermediate format to target data (i.e. SchemaRecord2Stream).

In the Adeptia Suite this feature is available in:

BPM Suite	Integration Suite	ETL Suite
$\checkmark$	$\checkmark$	$\checkmark$

#### Repository

When the process flow is executed, data from the source is converted to the intermediate form and then it is dispatched to the target. The intermediate data is stored in a repository folder. The path of the repository folder is .../../AdeptiaServer-5.1/ServerKernel/web/repository. Another folder is created representing the group which executed the process flow. All files that are created during the activity, design and running of the process flow, are stored in the group folder and this group folder is stored inside the repository folder. While creating a process flow, the user can specify whether to keep or delete the repository folder.

Activities of a process flow are executed in two ways:

- **Synchronous Activity:** If an activity is synchronous, process flow initiates the execution of that activity and waits for its completion. The execution of subsequent activity is initiated only after the completion of first activity.
- Asynchronous Activity: If an activity is asynchronous, process flow initiates the execution of that activity and subsequent activities as defined in the process flow without waiting for the completion of the first activity.

A	Repository	file	is	not	generated	for	the	activities	which	are	used	in
Ø	Asynchron	ious	mc	de.								

#### Controlling Synchronization

In a process flow, if an activity is synchronous, no signal is required to acknowledge the Process Engine about its completion as it runs in the main thread. If an activity is asynchronous, running parallel to main thread, some mechanism is required to notify the Process Engine about its completion. This is achieved by signaling.

#### Signaling



Signaling facilitates coordination of asynchronous activities in a process flow. A signal is raised as an asynchronous activity completes. The Synch Node in the process flow waits for signal and ensures that all the activities raising that signal are completed before control moves further in the process flow. This is done using the Synch Node option while defining a process flow.

#### Time Out

When an activity is used as asynchronous, a new property TimeOut is added to it. By default, its value is 300 seconds. If an asynchronous activity cannot connect to the next activity within this time limit, it gets aborted. To know how to use an activity in asynchronous mode and to changes its property, refer to the section <u>Creating Process Flow</u>.

## UNDERSTANDING PROCESS DESIGNER

Process Designer allows users to design business processes and business rules. It enables comprehensive designing of a process flow by the simple *Point and Click* method. The Business Process Modeling Notation (BPMN) standard is used to graphically depict business processes. The Process Designer is easy to use and enables both technical and non-technical users to design processes. The Process Flow Designer applet is displayed in Figure 17.1.




Figure 17.1: Process Designer Applet



The Process Flow Designer window is divided into eight sections:

- Menu Bar
- Tool Bar
- Palette
- Repository View
- Graph Canvas
- Bottom Pane
- PF XML (Process Flow XML)
- Preferences

#### Menu Bar

Options of the Menu Bar are listed in the table below.

Menu Option	Sub-Option	Function
	New	Open new Graph Canvas to create a new process flow.
	Open locally saved Process Flow	Open a process flow saved to a local machine.
File	Save to Server	Save process flow to the Adeptia Server.
THE	Save Process Flow locally	Save process flow to a local machine.
	Import Process Model	Import a process model and create the process flow based on that model
	Exit	Close the Process Designer applet.
	Undo	Undo the previous action.
Edit	Redo	If you later decide you didn't want to undo an action, click the Redo button
Euit	Zoom In	Zoom and magnify the current selection.
	Zoom Out	Zoom and minimize the current selection.

Table 17.1:	Menu Bai	<sup>r</sup> Options
-------------	----------	----------------------



	Synchronize PD with Server	Synchronize the process flow with a list of Adeptia Server objects such as activities and process flow.
	Enter Login Information	Enter login information for accessing process designer.
	Maximize Graph Canvas	Maximize the Graph Canvas workspace.
	Show Properties Tab	Display and activate the Properties tab at the bottom pane of the Graph Canvas.
Actions	Show Exception Handler Tab	Display and activate the On- Exception Scripts tab at the bottom pane of the Graph Canvas.
	Show Alerts Tab	Display and activate the Alerts tab at the bottom pane of the Graph Canvas.
	Show Process Flow Variables Tab	Display and activate the Process Flow Variables tab at the bottom pane of the Graph Canvas.
	Show Comments Tab	Display and activate the Comments tab at the bottom pane of the Graph Canvas.
	Process Flow Attributes	Allow you to enter the properties of the process flow.
Modes	Online/Offline	Toggle between online and offline mode.
	Show Flow Object Labels	Display labels of process flow objects.
	Show Connectivity Object Labels	Display labels while connecting objects.
View	Show Artifacts and Associations	Display artifacts and associations.
	Show Control Flows	Display control flows.
	Grid	Display grid in Graph Canvas.
Help	Help	Displays help for the Process Designer applet.



The sub-options of the File, Edit, Actions and Help menus can also be accessed by their keyboard shortcuts. To view a list of the defined shortcuts, refer to the **Keyboard Shortcuts** section.



#### Tool Bar

Options of the Tool bar are explained in the table below.

Button	Name	Function
	New Process Flow	Open new graph canvas to create a process flow
	Open Locally Saved Process Flow	Open process flow file saved on local hard disk.
в	Save Process Flow to Adeptia Server	Save Process flow to the Adeptia Server.
陷	Save process Flow Locally	Save process flow on local hard disk.
T <u>a</u>	Generate PDF	Generate PDF file of the process flow diagram. You can generate a <i>Graph PDF</i> , <i>Summary PDF</i> or <i>Entire Flow PDF</i> . A <i>Graph PDF</i> includes all the rules applied on all activities in the process flow. A <i>Summary PDF</i> includes only the activity details. The <i>Entire</i> <i>Flow PDF</i> includes all details of the process flow.
0	Synchronize with Adeptia Server	Synchronize a list of Adeptia Server objects i.e. activities and process flow from the Adeptia Server.
+	Maximize/Restore Flow Canvas	Maximize and restore graph canvas.
	Show Properties Panel	Show the Properties panel in the bottom pane.
0	Show Exception Handler Panel	Show the Exception Handler Script in the bottom pane.
۲	Show Error Panel	Show the Error panel in the bottom pane.
	Show Process Flow Variable Panel	Show the Process Flow Variable Panel in the bottom pane
	Show Comments Panel	Show the Comments panel in the bottom pane.
5	Undo	Undo the last action.

Table 17.2:	Tool Bar Options
-------------	------------------



3	Redo	If you later decide you didn't want to undo an action, click the Redo button.
۹,	Zoom In	Zoom In the Graph Canvas area.
্	Zoom Out	Zoom Out the Graph Canvas area.

#### Palette

The Palette contains a list of BPMN graphical elements. BPMN graphical elements are used to define the flow of business processes. These BPMN graphical elements are listed in five different panels, listed in the table below.

Element	Description	Notation
Events	An event is something that "happens" during the course of a business process. Events influence the flow of the process and usually have a cause (trigger) or an impact (result).	Start End
Activities	An activity is work that is performed within a business process. The rectangle image displayed in the next column is used to depict an Activity in a Process Flow.	Activity
Gateways	A Gateway is used to control the divergence and convergence of a sequence flow. Thus it determines branching, forking, merging, and joining of paths.	Gateway
Flows	A flow (control flow) is used to show the order that activities are performed in a business process. There are four types of flows: Sequence flow Default Sequence flow	Sequence Flow Default Sequence Flow
	<ul><li>Association flow</li><li>Directional Association</li></ul>	Association Flow

#### Table 17.3: BPMN Graphical Elements



Artifacts	Artifacts do not have any direct effect on the sequence flow or message flow of the process. They are used to provide additional information for the reader of the Process flow diagram. You can add any amount of information in this element. However, you cannot add any color to the text. To view the information, you can resize the frame in all directions.	Data Object
-----------	--	-------------



All the BPMN Graphical Elements can be resized.

To know more details about BPMN (Business Process Modeling Notations) visit the site: http://www.bpmn.org/Documents/BPMN\_V1-0\_May\_3\_2004.pdf

#### **Repository View**

The Repository View lists the Adeptia Server objects, such as Activities, Process flows, Context variables and Actions.



The Activities Panel has been renamed to Repository View. It is not reflected in the screenshots of this section.

#### Graph Canvas

The Graph Canvas is the area where a process flow is drawn. BPMN specification and Adeptia Server activities are dragged onto the Graph Canvas and arranged in a sequence in order to create a process flow. The Graph Canvas can also be resized if an activity is dragged beyond the default size.

#### Bottom Pane

The Bottom Pane is used to view properties of the activities, add comments to the activities, view error in a process flow and to create context variables. There are five panels in the Bottom Pane:

- Properties
- On Exception Script
- Errors
- Process Flow Variable
- Comments



#### PF XML (Process Flow XML)

The Process Flow window displays Process Flow XML that is generated while designing a process flow. To view the XML of a process flow click **PF XML** tab (see Figure 17.2).




Figure 17.2: View Process Flow XML

#### Preferences

The Preferences window allows you to select the background color of graph canvas and labels etc. To view the Preferences window, click **Preferences** tab (see Figure 17.3).






Figure 17.3: Preferences

You can modify various preferences. These are listed in the table below.

Table	17.4:	Edit	Preferences
Iabio		Louit	1101010110000

Preferences	Description
Background Colors	Change the background color of the Graph Canvas, BPMN Events Panel or Activities Panel.
Label Colors	Change the colors of labels of activities displayed in the Graph Canvas.
Validation	Verifies that the process flow created in the Graph Canvas is correct as per the BPMN standard and Adeptia Server. You can enable/disable Validation in the Preferences window. By default, it is enabled.
Undo Redo	Reverts the action done by the user in the Graph Canvas. You can enable/disable Validation in the Preferences



	window. By default, it is disabled.
Set Undo and Redo Limit	Set the number of actions that you can undo or redo.
BPMN Palette Colors	Change colors of Events, Activities, Gateway and Artifacts.

### **Keyboard Shortcuts**

Menu Option	Sub-Option	Keyboard Shortcut
	New	<ctrl> + <n></n></ctrl>
File	Open locally saved Process Flow	<ctrl> + &lt;0&gt;</ctrl>
The	Save to Server	<ctrl> + <s></s></ctrl>
	Save Process Flow locally	<ctrl> + <b></b></ctrl>
	Undo	<ctrl> + <z></z></ctrl>
Edit	Redo	<ctrl> + <y></y></ctrl>
Lan	Zoom In	<ctrl> + <numpad +=""></numpad></ctrl>
	Zoom Out	<ctrl> + <numpad -=""></numpad></ctrl>
	Synchronize PD with Server	<f5></f5>
	Enter Login Information	<ctrl> + <l></l></ctrl>
	Maximize Graph Canvas	<ctrl> + <m></m></ctrl>
Actions	Show Properties Tab	<ctrl> + <r></r></ctrl>
	Show Exception Handler Tab	<ctrl> + <g></g></ctrl>
	Show Alerts Tab	<ctrl> + <e></e></ctrl>
	Show Process Flow Variables Tab	<ctrl> + <f></f></ctrl>
	Show Comments Tab	<ctrl> + <h></h></ctrl>
Help	Help	<f1></f1>



# **CREATING PROCESS FLOW**

#### Prerequisites:

- JRE 1.6 needs to be installed on your system to open the Process Designer applet.
- The *Pop-up Blocker* needs to be disabled in the web browser, to open the Process Designer applet. By default, the *Pop-up Blocker* is enabled.
- The windows user must have Administrative rights on the PC, where Process Designer will be opened.

The Process Flow Creation using Process Designer comprises of two parts:

- Designing Process Flow using BPMN Graphical Elements
- <u>Attaching Adeptia Server activities with the BPMN elements</u>

### **Designing Process Flow using BPMN Graphical Elements**

#### Steps to draw a Process Flow using Process Designer

- 1. In the Adeptia Suite homepage menu, click **[+] Design** to expand the tree. All the items in the **Design** category are displayed.
- 2. Click [+] **Process Flow** to expand the tree and then click **Process Flow**. The Manage Process Flow screen is displayed (see Figure 17.4).

[+]	MyTasks	De	Design > Process Flow						
[+]	My Documents								
[+]	My Solutions	New	New   Edit   Delete   Revisions   DependenciesSelect Field to Search V Search						
[+]	My Monitor	nev	•	ine (	belete   Kevisions   bependencies	Select Heid to Search			Search
[+]	History	Acti	Activate   Execute   BindEvent   ViewEvents						
		#		<pre>())</pre>	Name	Description	Owner	Perm.	Modified 🔻
[-]	Design	1	0	৾	PurchaseRequisition	purchase requisition approval workflow	demouser	RWX	09/01/09 12:47
	🖈 Process Model	2	0	ંટ	EmployeeBenefitsConversion	ETL example: Convert Excel data files into XML.	demouser	RWX	09/01/09 12:46
[+]	X Process Flow Configure	з	0	ં	PurchaseOrderProcessing	Integration example: Convert and load data from XML files to a target Database. Email user when flow finishes.	demouser	RWX	09/01/09 12:46
[+] [+]	Deploy Administer	4	0	ં	PurchaseOrderProcessing_extended	Integration example: Flow includes a rule that notifies sales if the purchase qty is greater than 100.	demouser	RWX	09/01/09 12:46
		5	$\circ$	٢	OrderFulfillment	Integration Example: Fulfill customer orders by calling a Web Service.	demouser	RWX	09/01/09 12:46

Figure 17.4: Manage Process Flow

3. Click **New** link. The Create Process Flow screen is displayed (see Figure 17.5).



Design > Process Flow > Process Flow					
[-] Standard properties					
Name*					
Description *					
Logging Level *	ERROR 💌				
Repository File Retention *	DONT DELETE				
	Process Flow Designer				
[+] Advanced properties * Mandatory fields.					
Save Cancel					

Figure 17.5: Create Process Flow

4. Enter the name and description of the new process flow in the *Name* and *Description* fields respectively.



Description of the process flow can be overridden during execution of the process flow. To know how to override the process flow description, refer to the section **Overriding Process Flow Description at Runtime**.

5. Select the logging level from the *Logging Level* drop-down list. The various logging levels are depicted in the table below.

Level	Description			
DEBUG	The DEBUG level logs are fine-grained informational events that are most useful to debug any problem. Debug level is useful for programmers.			
INFO	The INFO level logs are informational messages that highlight the progress of Process flow execution. In INFO, status (successful or failure) of each activity is displayed.			
ERROR	In ERROR, possible cause of failure of an activity is displayed. By default <i>Error</i> is selected in the <i>Logging Level</i> .			

Table 17.6: Types of Logging Levels

6. Select repository file retention from the *Repository File Retention* option. During execution, the process flow creates a temporary repository file to store intermediate data. These repository files can cause unnecessary disk space usage and you may want to delete them after execution of the process flow. On the other hand sometime these repository files can be helpful in case of the failure of the process flow execution. For each instance of the process flow execution a unique repository folder



is created that contains Source, intermediate XML data files and target formatted data. By default, repository files are being stored in the repository folder of the Adeptia Server. You can also choose an option to delete them or to archive them in a different location. Options for Repository File Retention are outlined in the table below.

Retention Description	
Option	
DONTDELETE	Repository files are not deleted after execution of Process flow.
DELETE	Repository files are deleted after the process flow is executed.
ARCHIVE	Repository files are moved to another location. By default repository files are archived in C:/repo folder. To change the location where archived file is stored, refer to the section to any other folder or to WebDAV repository, you need to change <i>abpm.transaction.repository.archive.server</i> property. Refer to the Administrator Guide for details.
DELETE ON SUCCESS	Repository files are deleted only when the process flow is executed successfully and there is no error record.

Table 17.7: Options for Repository File Retention

7. Click [+] to expand the **Advanced Properties**. Advanced properties of process flow are displayed (see Figure 17.6).



[-]	Advanced properties	
	Retain Process Variable Xml	
	Recoverable Process Flow	
	Priority	NORMAL 🗸
	Process Flow Definition *	
	Owner*	admin (Default Administrator) 🔽
	Permissions*	Read Write Execute         Owner       Image: Component of the secure of the

Figure 17.6: Process Flow's Advanced Properties

8. To make this process flow implicitly recoverable, check the *Recoverable Process Flow* checkbox.

Recoverable Process Flows are those Process flows, whose execution can be resumed in case the kernel is restarted due to some reason during Process Flow execution. For details of recoverable process flows refer to Recovery section.

9. Select the priority from the *Priority* drop-down list. This property is applicable when Queue Processor is enabled. Table 17.8 lists the priorities and their description.

Priority	Description			
NORMAL	When a process flow with <i>Normal</i> priority is executed, it first get queued to the Queue Processor and then get executed based on the availability of the queue			

Ø




	processor.
IMMEDIATE	When a process flow with <i>Immediate</i> priority is executed, it by passes the Queue Processor and gets executed immediately, even if the queue processor is busy.

For more details about Queue Processor, refer to *Load Management* section of *Admin Guide*.

10. Click **Process Flow Designer** button. The Process Designer window is displayed (see Figure 17.7).



If you are starting the Process Designer on your system for the first time, then a warning message is displayed that prevents you from starting this application. Just ignore this message and click **Start** to continue.



#### Figure 17.7: Process Designer

11. Click **Activity** element in the Palette and drag it to the Graph Canvas. The dragged activity element is displayed in the Graph Canvas (see Figure 17.8).



Start Event	End Event
-------------	-----------

Figure 17.8: Dragging BPMN Activity into Graph Canvas

12. By default, all BPMN elements except Event objects are blank. You can add a label to the BPMN element, once you drag it to the Graph Canvas. You can do this by doubleclicking the element. This displays the properties associated with the element in the Properties Panel in the Bottom Pane. Alternately, you can right-click the element and select **View Properties** option (see Figure 17.9).





Figure 17.9: Right-Clicking an Activity

13. The Properties Panel is displayed in the Bottom Pane. Type the name of the element in the *Value* column of the *Label* field. Click the element again in the Graph Canvas to display the name in the element (see Figure 17.10).



-75 100 -125 -150 -150 -200 -225 -225 -225 -275 -300 -325 -350	Start Event	End Event	
SES PI	roperties 🚫 OnException Scripts 🐼 Alerts 🛐 Process Flow Va	ariables 🗊 Comments	
	Name		Value
Label			Task1


Figure 17.10: Displaying Name of Activity



- 14. Repeat steps 9 and 10 to add more activities in Graph Canvas.
- 15. Click **Gateway** element and drag it to desired location in the Graph Canvas. The Gateway element is displayed in the Graph Canvas area (see Figure 17.11).



Figure 17.11: Dragging BPMN Gateway into Graph Canvas



Once the required BPMN elements are dragged to the Graph Canvas and proper labeling is done using the Properties Panel, it is necessary to connect them in order to design a business flow.

- 16. Click required flow in the Palette. The control flow is selected.
- 17. Drag the cursor between two BPMN elements. Both BPMN elements are connected with the selected flows (see Figure 17.12).






Figure 17.12: Connecting BPMN Elements

18. Connect all BPMN elements with appropriate control flow (see Figure 17.13).





Figure 17.13: Connecting BPMN Elements



Once designing of business process is completed it is necessary to attach the Adeptia Server activities to BPMN elements of the business process.

### Attaching Adeptia Server activities with the BPMN elements

#### Prerequisites

• Adeptia Server activities must be created before attaching them with BPMN elements in the Process flow.

#### Steps to attach Adeptia Server activities with BPMN elements

1. Expand the **Repository View** panel. All the items in the Server Entities category are displayed (see Figure 17.14).



A Process Designer [customer][Server]	الافتر
File Edit Actions Modes View Help	
3 Designer 2 PF XML & Preferences	
🕒 🖴 🖻 🔁 🖏 +	
Palette ¥	្លាំ និននិងម៉ាន់ ទោះសំនេះ ទោះភ្លាំ អា
Repository View 🕆	53 59 75
Server Entities	
Activities     Action	
🗈  ExistingPF	
	Start Event End Event
	200
	28
	207
	Properties 🚫 OnException Scripts 😢 Alerts 🔯 Process Flow Variables 🐊 Comments
	Name Value Value
	1.000 [1994.2
	<u> </u>
Statusi Online	Adeptis BPM Suite 5.0 - Windows Internet Explorer

Figure 17.14: Selecting Adeptia Server Activity

2. Further expand the type of activities e.g. Human Workflow, Schema, Source, etc until you find the required activity (see Figure 17.15).



A Process Designer [customer][Server]	
File Edit Actions Modes View Help	
🏂 Designer 🤾 PF XML 🐉 Preferences	
🕒 🐸 🔁 🔁 🗮 +	
Palette ¥	
Repository View	25
🌉 Server Entities 📃	
Activities     Activities     CompressionService	100 Taski Task2
B B ESCOLC	
Economicana Economicana	E <sup>B0</sup>
HumanWorkFlow      Miscellaneous	05
E- Native Service	
D     Notification	
E- 🔂 Poling	E-250
RecordQueueProducer	205
RecordQueueReceiver      AppenderNode	
E Reports	
E- 2 Schema	E <sup>125</sup>
Adv. Text	E-30 4
- T Adv. Positional	
	Properties 🚫 Griduception Scripts 😮 Alerts 🔯 Process Flow Yanables 🐊 Comments
EvalPF_ExcelSchem	Name Value
EvalPF_EcelSchem	Lobel Task2
EvalScript_ExcelSch	
Eval/form_ExcelSch	
Positional     Positional	
E 40 304.	
Status: Online	

Figure 17.15: Selecting Adeptia Server Activity

3. Select the required activity, drag it to the Graph Canvas and drop it on the BPMN element with which you want to attach the activity. A small image of the activity is displayed at the top left corner of the BPMN element (see Figure 17.16).




Figure 17.16: Attaching Adeptia Server activity

An activity can also be attached by right-clicking the BPMN element. Rightclick BPMN element and select **Attach Server Entity**. List of activities is displayed. Select the required activity and click **Ok** button. You can change the label of the element if desired. If you attach an activity to a blank BPMN element, then the activity name is displayed in the BPMN element (see Figure 17.17).






Figure 17.17: Adeptia Server activity name in BPMN element

4. Repeat step 1 to 3 to attach activities to other BPMN elements (see Figure 17.18).





Figure 17.18: Attaching Adeptia Server activity

5. To view or edit the properties of the Adeptia Server activity attached with the BPMN elements, right-click activity and then select **View Properties**. The properties of the attached activity are displayed in the Properties Panel (see Figure 17.19).

50 75 100 125 55 art Event 150 55 art Event 150 55 art Event 150 55 art Event 150 55 art Event 150 55 art Event	End Event	
	Y	
📰 Properties 🚫 OnException Scripts 🚫 Alerts 🔄 Process Flow Variables 🗒 Comments		
Name	Value	
Activity Maximum Retries on Failure	0	
Activity Wait Time(in seconds) between Retries	60	
Character Set Encoding	ISO-8859-1	
dataAction	No Action	
Error Records	Fie	
D 19216800101111219404004900006		
abel Task1		
EvaIPF_ExcelSchema_Format1		
source Sour		
streamVames EvaPF_ExcelSchema_Format1		
Synch	true	
Transformer	Stream2XmlStreamTransformer	
ype ExcelSchema		

Figure 17.19: Edit Activity Properties





- Right-click target schema activity and select View Properties. *Transformer* property must be *XMLStream2Stream*.
   For details on Transformer types and changing from one type to another, refer to the section Changing Transformer Type.
- 6. By default activities are *Synchronous*. If you want to make the activity *asynchronous*, go to the **Properties Panel**, change the value of *Synch* from *true* to *false*.
- 7. Click **File** menu and then select **Save to Adeptia Server**, to save the process flow on the Adeptia Server. This displays a screen confirming that the process flow has been created successfully. If the comments property is enabled, then clicking **Save to Adeptia Server** will display a screen where you need to enter comments related to creating the process flow (see Figure 17.20).

Enter Comments X			
į,	Specify comments for process flow EvalPD_ProcessFlow		
	OK Cancel		

Figure 17.20: Enter Comments (Process Flow)

8. Enter the comments in the *Specify Comments for process flow* field.



The comment should be at least 1 character in length. If you enable/disable the *Comments* property in the middle of a process flow, you need to restart the process flow applet.

9. Click **OK** to save the comments. This displays a screen confirming that the process flow has been created successfully.



By default, the *Comments* property is disabled. To enable it, refer to the *Updating System Properties* section in *Administrator Guide*.

### Save Process Flow on Local Hard Disk

#### Steps to save the Process Flow on local hard disk

1. Select **Save Process Flow Locally** from the **File** menu. The Save window is displayed (see Figure 17.21).



🖆 Save		
Save in:	繴 My Computer	🗾 🤌 💌 🖽
My Recent Documents Desktop My Documents	<ul> <li>31/2 Floppy (A:)</li> <li>Local Disk (C:)</li> <li>Shared Documents</li> <li>Local Disk (D:)</li> <li>DVD/CD-RW Drive (E:)</li> </ul>	
My Network	File name: customer	Save
Places	Files of type: xml	Cancel

Figure 17.21: Save Process Flow

2. Enter the name of the file in *File Name* field and click **Save** button. The process flow is saved in XML format in the specified location.

€	To create a Process flow, an IT user can simply drag the required Adeptia Server activities to the Graph Canvas and connect them using flow controls. In other words, an IT user does not need to draw process flow using BPMN elements and then attach Adeptia Server activities to the BPMN elements.
Ø	You can view details of an event associated with a process flow, by clicking the event displayed under Associated Events on the Manage Process Flow screen.

If a process flow is opened in **Read-Only** mode, you can view and modify it, but you cannot save the changes, as all Save options are disabled. However, if you open a process flow that has write permissions, from the Process Designer applet, then Save options become activated.

### Changing Transformer Type

In the Adeptia Server two types of transformers are used:



- Stream2XMLStream/XMLStream2stream: This transformer converts the source data to XML (i.e. Stream2XMLStream) and then the XML to target data (i.e. XMLStream2Stream). This transformer is used when a mapping activity is used in the process flow. In this case, the Stream2XMLStream is used in the source schema and the XMLStream2stream is used in the target schema.
- SchemaStream2Record/SchemaRecord2Stream: This transformer converts the source data to intermediate format (i.e. SchemaStream2Record) and then the intermediate format to target data (i.e. SchemaRecord2Stream). This transformer is used when record to record process of the data is required.

#### Steps to change the transformer type

1. Right-click the schema activity in the Graph Canvas Area, and select **View Properties**. Properties of the selected schema activity are shown in the Properties Panel (see Figure 17.22).

150 175 175 175 175 175 175 175 175	End Event	
-350 4	P	
👿 Properties 🚫 OnException Scripts 🚫 Alerts 🛐 Process Flow Variables 🗐 Comments		
Name	Value	
Activity Maximum Retries on Failure	0 ***	
Activity Wait Time(in seconds) between Retries		
Character Set Encoding	ISO-8859-1	
dataAction	No Action	
Error Records	File	
ID	192168001166112200685798400006	
Label	EvalXform_ExcelSchema	
Name	EvalXform_ExcelSchema	
source	EvalXform_Mapping	
streamNames	EvalXform_ExcelSchema	
Synch	true	
Transformer	XmlStream2StreamTransformer	
Type	ExcelSchema	

Figure 17.22: Changing Transformer Type

2. Select the required transformer type (e.g. *Stream2XMLStream* in case of source schema and *XMLStream2Stream* in case of target schema) from the *Transformer* drop-down list.

## ACTIVATING/DE-ACTIVATING PROCESS FLOW

Process flows can be in activated or de-activated state. You cannot execute a process flow, which is in de-activated state. If you want to execute a de-activated process flow, you have to first activate it. When a process flow is created, it is in activated state, if number of activated process flows is less than maximum allowed by license. Otherwise process flow is created in de-activated state.

#### Steps to activate/de-activate a process flow



- 1. In the Adeptia Suite homepage menu, click **[+] Design** to expand the tree. All the items in the **Design** category are displayed.
- 2. Click [+] Process Flow to expand the tree and then click Process Flow. The Manage Process Flow screen is displayed.
- 3. If the process flow is in activated state, a **De-activate** link is highlighted when select the radio button adjacent to it.
- 4. To de-activate the process flow, click the **De-activate** link.
- 5. Similarly to activate a de-activated process flow, select the radio button adjacent to it and click **Activate** link.

# **TESTING A PROCESS FLOW**

Process flow can be tested, before executing it. By testing a process flow you will be able to know the behavior of the process flow, right before executing it in production environment. Testing is useful especially for those process flows, in which decision nodes are used. When you test a process flow, you can give values of different process flow variables used in the process flow and check its behavior. The values of process flow variables are given using a XML file.

#### Steps to test a process flow

1. In the Manage Process Flow screen, click the radio button against the process flow that you want to edit. This selects the process flow and activates the *Edit* link. Clicking the **Edit** link displays the Edit Process Flow screen (see Figure 17.23).

Design > Process Flow > Process Flow > EvalPD_ProcessFlow			
[-] Standard properties			
Name*	EvalPD_ProcessFlow		
Description *	purchase order processing		
Logging Level *	ERROR 💌		
Repository File Retention *	DONT DELETE		
	Process Flow Designer		
[+] Advanced properties			
* Mandatory fields.           Save         Save As         Cancel         Test			

Figure 17.23: Edit Process Flow



2. Click the **Test** button. The Test Process Flow screen is displayed. (see Figure 17.24).

🧯 Upload XML to test	Process Flow - Windows Internet Explorer		_ 🗆 ×
Design > Process Flow > Process Flow > Test EvalPD ProcessFlow			
This tast feature is an	slicable for Drocoss Flow baying variables where va	ue will be over-ridden by value provided in XML file.	
This test reature is app	nicable for Process now having variables whose va	de win de over-nuden dy vane provided in Ant. The,	
Process Flow Nan	e EvalPD_ProcessFlow		
Process Flow Id	192168001006115571166220300005		
File Name	Browse		
Upload XML			
Uploaded XML Fil	es		

Figure 17.24: Test Process Flow

3. Click **Browse** and select the required XML files. Following is the sample of XML file used to test the process flow. (see Figure 17.25).

xml version="1.0"?	
<variables></variables>	
<variable name="Data" value="55000"></variable>	

Figure 17.25: Sample XML

4. Once the required file is selected, click **Upload XML** button. The uploaded file is show in the Test Process Flow screen. (see Figure 17.26).



Design > Process Flow > Process Flow > Test EvalPD_ProcessFlow				
This test feature is app	icable for Process Flow having variables whose value will be over-ridden by value provided in XML file.			
Process Flow Name EvalPD ProcessFlow				
Process Flow Id	192168001006115571166220300005			
File Name	Browse			
Upload XML				
Uploaded XML Files				
C employees1.xml				
Select any Uploaded XML File to Unload it or Execute Process Flow				

Figure 17.26: Select XML File



You can upload more than one file.

5. Select the uploaded XML file and click the **Execute** button (the *Execute* link changes to a button when a file is selected). The following screen is displayed. (see Figure 17.27).

Request submitted for EvalPD\_ProcessFlow execution at Tue Aug 25 23:55:43 IST 2009. See the Process Flow Logs for execution details.

Figure 17.27: View Process Flow Log

6. Click **Process Flow Logs** link, to check the status of the process flow.

## **UNDERSTANDING VALIDATION**

Validation is a mechanism, which ensures that the process flow created in Graph Canvas is correct as per the BPMN standard and Adeptia Server. If the process flow is not correct, a message is displayed in the Alerts Panel of Bottom Pane (see Figure 17.28).






Figure 17.28: Validation

In Figure 17.28 shown above, you can see that *Task1* and *Task2* are properly connected with the incoming and outgoing sequence flow but *Task3* has an incoming sequence but no outgoing sequence flow. The validation message is displayed in the Alerts Panel. There are two categories of validations:

- BPMN Server specific Validation: This includes Adeptia Server validation like file target has no input source stream, etc. This is displayed with "BPMServer" category in the Alerts Panel.
- **BPMN Specific Validation:** This includes BPMN specific validation like end event cannot have outgoing sequence flow, etc. This is displayed with "BPMN" category in the Alerts Panel.

Validation messages are further divided into two types:

- **Error:** These are displayed in the Alerts Panel with type (<sup>⊗</sup>) along with error message and the corresponding user action is reverted if possible. If revert action takes place successfully then a warning message is displayed explaining the reason of revert operation. For example, start event cannot have incoming sequence flow, hence removed.
- Warning: These are displayed the Errors Panel with type (<sup>(a)</sup>) and the corresponding warning message is displayed. For example, start event has no outgoing sequence flow.

By default, *Validation* is enabled and *Revert Action* is disabled. Revert action specifies reverting (if possible) wrong user action automatically by Process Designer.

### **Disabling Validation**



#### Steps to disable Validation

1. Click **Preferences** tab in Process Designer screen. The Change Preferences screen is displayed (see Figure 17.29).

File Edit Actions Modes View Help			
3 Designer & PF 304, & Preferences			
Preferences			
Badiground Colors			
Label Colors			
- Valdaton			
Undo Redo			
🗟 🧰 BMMI Palette Colors			
r	Cardy designs of Largery		estore Default
	Apply changes Save of	onfiguration R	estore Default

Figure 17.29: Changing Preferences

2. Click **Validation** under the **Preferences** Menu. The Validation Options screen is displayed (see Figure 17.30).



File Edit Actions Modes	View Heb	Π
🍪 Designer 🗼 PF XML 🛔	w Preferences	j
a Malidation	Enable or Daable validation Enable  Enable Broadbe Revert Action	
Colors     DPMN Palette Colors		
	Apply changes Save configuration Restore Default	
	Appry changes bave compguration Kestore behaut	1

Figure 17.30: Disable Validation

- 3. Select **Disable** from *Enable or Disable Validation* drop-down list.
- 4. Click **Apply Changes** button and then click **Save Configuration** button.



Similar steps need to be done to change the status of Revert Action.

# USING UNDO REDO

This feature allow user to perform UNDO and REDO operations. This can be done either through

the **Undo** and **Redo** submenu under **Edit** menu or by clicking the **Undo** () and **Redo** () buttons in the toolbar.

- **Undo:** This action will replace the user current action with the previous action. For example, moving the BPMN Element to its previous position.
- **Redo:** This action will replace the user recent action with his undone action. For example, moving the BPMN Element to its previous position where undo action took place.

# USING MULTIPLE SELECTIONS

User can select multiple BPMN Elements from the Flow Canvas and move them to other location in the Flow Canvas. Multiple BPMN Elements will be selected with the combined event of left



mouse click and **<CTRL>** key or drawing selection rectangle on flow canvas. A selection rectangle is a virtual rectangle drawn as the user press right mouse button and drag over the flow canvas. On release of mouse button the rectangle becomes invisible and the entities inside the drawn rectangle will be selected. An example of multiple selections is displayed in Figure 17.31.





Figure 17.31: Multiple Selections



# USING ZOOM IN AND ZOOM OUT

This feature allow user to perform ZOOM IN and OUT operations on the canvas. This can be done either through the **Zoom In** and **Zoom out** submenu under Edit menu or by clicking the **Zoom** 

In (<sup>1</sup>) and **Zoom out** (<sup>1</sup>) buttons in the toolbar.

In Zoom In/Zoom Out mode, all activities in the Graph Canvas will be resized. Additionally, all connecting sequence flows will be also redrawn. A process flow can be zoomed in to any limit. However when zooming out, it has to conform to certain limits. It will stop in the listed cases:

- Any element location becomes (0,0) coordinates
- Any element dimension becomes less than its minimum dimension

You can drag and move existing activities or add new activities in zoom mode, but when saving the process flow to server, they are resized and relocated to the default proportions. If any error event is attached to an activity, it will also be zoomed in the same proportion. The zoomed size is never saved to the server. When the process flow is reloaded, it will display in normal mode.



When a process flow is zoomed, the size of images inside a BPMN element will not be zoomed. Additionally, the size of an arrow head will also not change.



# **USING ACTIONS IN PROCESS FLOW**

Actions enable necessary control over a process flow. Lists of actions that can be used to control a process flow are displayed in the table below.

Action	Description			
Call:	This action is used to call another process flow (sub-flow) synchronously. Users need to specify the following properties while adding the Call action to a process flow:			
	flowId: Name of the process flow (sub-flow).			
	You can override its value dynamically during execution of the process flow. To override the flowId you can use custom plugin activity or put-context-var before call action.			
	Following is the code which is used in custom plugin activity to override the flow id:			
	context.setActivityParameter("Call1","flowId", "192168001158117188341381200001");			
	where <i>Call1</i> is the name of the call activity and <i>192168001158117188341381200001</i> is ID of the child process flow.			
	Label: The label displayed for the call action.			
	Name: Name for the call action			
	<i>resultCtxVarName:</i> Name of the context variable that contains the status of the sub-flow. Its value is Boolean.			
	Using <i>Call</i> action you can select Parent Process flow itself to be executed as child process flow. In this case the process flow will run in infinite loop. You should use some condition, which is use to stop the process flow after certain recursion. If the condition fails, you can kill the process flow from System Monitoring.			
Checkpoint:	This action is used to resume the execution of a process flow from its current status if kernel stops unexpectedly. The Checkpoint action saves process flow state (context variable, checkpoint info, state name etc) in a file. When the Adeptia Server kernel is restarted it checks for the recoverable process flow by scanning all the existing process flow files and starts the particular process flow from its last checkpoint. Checkpoint should not be used within JTA block. It should be used before or after the JTA block.			



	Label: The label displayed for the Checkpoint action.			
	Name: Name for the Checkpoint action.			
Delay:	This action is used to pause the propagation of process flow for a given time. The Delay action pauses the propagation of process flow but the asynchronous activities, which were started earlier, keep running in parallel. Users need to specify the following properties while adding the Delay action to a process flow:			
	Label: The label displayed for the Delay action.			
	Name: Name for the Delay action.			
	<i>Time:</i> Specify the time in seconds till which the execution of process flow is paused.			
JTA-Begin/ JTA-End:	These actions are used to create a JTA block. JTA block is used to create a set of activities within a process flow. When all the activities in a JTA block are completed successfully, the data is committed, and the process flow control can move beyond the JTA block to the next activity. If any of the activities in the JTA block fails to complete successfully, the rollback function is called and the whole process flow is stopped and error is logged. JTA is applicable only when source or target is a database.			
	<i>Label:</i> The label displayed for the JTA-Begin/End action. <i>Name:</i> Name for the JTA-Begin/End action.			
	Name. Name for the STA Degin/End action.			
JTA-RollBack:	This action is used to call the rollback function at any point in a process flow. The JTA–RollBack function is always used within a JTA block.			
	Label: The label displayed for the JTA-Rollback action. Name: Name for the JTA-Rollback action.			
Put-Context- Var:	This action is used to declare one or more context variables with values assigned to it at any point in the process flow. A context variable is declared when this action is executed while running the process flow. Put-Context-Var is generally used to set the value of any field of an activity used in a process flow, during execution of the process flow. For example you can set/overwrite the subject of mail source activity during execution of process flow. Another example can be appending current date stamp at the end of the name of a file, created as target, during a process flow execution. User needs to specify the following properties while adding the Put-Context-Var action to a process flow:			



	<ul> <li>Edit Context: Displays a condition screen which allows you to add a new context variable or edit or delete existing context variables.</li> <li>Label: The label displayed for the Put-Context-Var action.</li> <li>Name: Name for the Put-Context-Var action.</li> <li>Type: Displays the type of action selected. This is a readonly field.</li> </ul>	
Set-Child- Context	This action is used to set the value of Process Flow Context Variable or Activity Context Variable from parent process flow to child process flow. Set-child-Context must be used before Call action. User needs to specify the following properties while adding the Set-Child-Context action to a process flow:	
	<ul> <li>Activity: Name of activity in parent process flow, whose 'Activity Context Variable' value will be used to set to the child context variable specified by Child Key. If name of the activity is not specified, then the 'Process Flow Context Variable' specified by Key will be used.</li> <li>ChildActivityName: Name of activity of child process flow whose value will be set. If name of the activity is not specified, then the 'Process Flow Context Variable' specified by Child Key will be set.</li> <li>Childkey: Name of Context Variable of the child process flow whose value will be set.</li> <li>ChildName: Name of the Call or Spawn action, which is used to call or spawn child process flow. Set-child-context uses the ChildName to find out the call or spawn action and the corresponding process flow to set the context variable.</li> <li>Key: Name of the context variable of the parent process flow whose value will be used to set the child context variable.</li> <li>Key: Name of the context variable of the parent process flow whose value will be used to set the child context variable.</li> <li>Key: The label displayed for the Set-Child-Context action.</li> <li>Name: Name for the Set-Child-Context action.</li> </ul>	
Set-Parent- Context:	This action is used to set the value of 'Process Flow Context Variable' or 'Activity Context Variable' from child process flow to the 'Process Flow Context Variable' or 'Activity Context Variable' of the parent process flow, which initiated the child process flow by call/spawn action. User needs to specify the following properties while adding the Set-Parent-Context action to a process flow:	



Activity: Name of activity of the child process flow, whose 'Activity Context Variable' value specified by Key will be used to set the parent process flow variable specified by Parent key. If name of the activity is not specified, then the 'Process Flow Context Variable' specified by Key will be used.Key: Name of the context variable of the child process flow whose value will be used to set the parent context variable specified by Parent Key.Label: The label displayed for the Set-Parent-Context action.Name: Name of Set-Parent-Context action ParentActivityName: Name of activity of parent process flow whose 'Activity Context Variable' specified by Parent Key will be set. If name of the activity is not specified, then the 'Process Flow Context Variable' specified by Parent Key will be set.ParentKey: Name of Context Variable of parent process flow whose value will be set.ParentKey: Name of Context Variable of parent process flow whose value will be set.
Spawn:       This action is used to call another process flow (sub-flow) asynchronously. Users need to specify the following properties while adding the Spawn action to a process flow:
flowId: Name of the process flow (sub-flow).
You can override its value dynamically during execution of the process flow. To override the flowId you can use custom plugin activity or put-context-var before spawn action. Following is the code which is used in custom plugin activity
to override the flow id:
context.setActivityParameter("Spawn1","flowId", "192168001158117188341381200001");
where <i>Spawn1</i> is the name of the spawn activity and <i>192168001158117188341381200001</i> is ID of the child process flow.
Label: The label displayed for the Spawn action.
Name: Name for the Spawn action.
<i>resultCtxVarName:</i> Name of the context variable that contains the status of the sub-flow. Its value is Boolean.
Signal: Name for the signal that is generated after the
asynchronous process flow (sub-flow) is completed. This property is applicable only when Wait for Child property is



set to true. Wait for Child: Specify whether the parent process flow's end event will wait for the completion of child process flow or not. If this property is set to true, the parent process flow end event will wait till the child process flow is completed. During this period, parent process flow will be in running state. Once the child process flow is completed, it raises the signal specified in the Signal property and then the end event is executed. If the value of Wait for Child property is set to false, the parent process flow does not wait for the child process flow to be completed. The child process flow to be completed. The child process flow to be completed. The base to raise a signal to process engine when an synchronous activity is completed. The following properties eed to be specified while adding the Synch action in a process fow: <i>Label:</i> The label displayed for the Synch action. <i>Name:</i> Name for the Synch action. <i>Signal:</i> Name of the signal that is specified in the signal properties of the Synch action. Signal: Name of the signal that is specified in the signal properties of the Synch action. Mais action is used to log a message, which can be used later for formation, debugging, or error log purposes. User can check the	
<ul> <li>end event will wait for the completion of child process flow or not. If this property is set to true, the parent process flow end event will wait till the child process flow is completed. During this period, parent process flow will be in running state. Once the child process flow is completed, it raises the signal specified in the Signal property and then the end event is executed. If the value of Wait for Child property is set to false, the parent process flow does not wait for the child process flow to be completed.</li> <li>In this action is used to raise a signal to process engine when an synchronous activity is completed. The following properties event to be specified while adding the Synch action in a process flow:</li> <li>Label: The label displayed for the Synch action. Name: Name for the Synch action.</li> <li>Signal: Name of the signal that is specified in the signal properties of the Synch action.</li> </ul>	
Synchronous activity is completed. The following properties         eed to be specified while adding the Synch action in a process         bewein         Label: The label displayed for the Synch action.         Name: Name for the Synch action.         Signal: Name of the signal that is specified in the signal properties of the Synch action.         nis action is used to log a message, which can be used later for	
Synchronous activity is completed. The following properties         eed to be specified while adding the Synch action in a process         bw:         Label: The label displayed for the Synch action.         Name: Name for the Synch action.         Signal: Name of the signal that is specified in the signal properties of the Synch action.         nis action is used to log a message, which can be used later for	
Name: Name for the Synch action. Signal: Name of the signal that is specified in the signal properties of the Synch action.	
Name: Name for the Synch action. Signal: Name of the signal that is specified in the signal properties of the Synch action.	
Signal: Name of the signal that is specified in the signal properties of the Synch action.	
properties of the Synch action.	
information, debugging, or error log purposes. User can check the values of variable at run time in a process flow. This action uses Adeptia Server logging framework. Users need to specify the following properties while adding the Trace action to a process flow:	
Label: The label displayed for the Trace action.	
<i>Log Level:</i> Log Level is the level at which the message is to be logged. It can be logged at DEBUG, INFO or ERROR levels. Logging level for trace action should not be higher than the logging level of the Process Flow. For example if you have selected 'INFO' logging level in the process flow, you should select 'INFO' or 'ERROR' in trace action. If you select 'DEBUG' logging level in trace action, the trace message will not be logged in process flow log. Similarly while viewing the process flow log, if you select logging level, lower than the logging level of trace action, you	



Wait:	his action waits for certain variable value to be changed in a process flow 'context' to a predefined value for a given timeout. Basically process engine waits for some event to happen then it noves forward. This action is related to polling of a variable and etting some variable in context. Users need to specify the ollowing properties while adding the Wait action to a process low:		
	Label: The label displayed for the Wait action.		
	Name: Name for the Wait action.		
	pollinginterval: Time interval in seconds the wait action will poll for the above specified variable value.		
	<i>resultCtxVarName</i> : Name of the context variable that contains the status of the Wait action. Its value is Boolean		
	timeout: Timeout duration in seconds		
	value: Value of the context variable.		
	<i>var:</i> Name of the context variable for which the Wait action 'waits'.		

#### Steps to add Actions to a Process Flow

1. Click tree structure in the **Repository View** panel. Expand the **Action** list of the Adeptia Server. The list of Adeptia Server actions is displayed (see Figure 17.32).

Palette	★ E 0 25 50 75 100 125 150 +175 200 225 250 275 300 325 350 375 400 425 450 475 500 525 550 575 600 625 650 675 700 725 750 775 80
Repository View	
Server Entities  Server Entities  Control Control  Contr	Start Event
	Properties 🚳 OnException Scripts 🙆 Alerts 🔄 Process Flow Variables 🗒 Comments
	Type Category Error Message
	BPMN End Event has no incoming sequence flow.     BPMN Start Event should have one outgoing sequence flow.
	premi premi prant event should have one outgoing sequence now.

### Figure 17.32: List of Actions in Adeptia Server

2. Select the required action and drag it to the Graph Canvas area. The dragged action is displayed in the Graph Canvas (see Figure 17.33).



	Call 1	
Start Event		End Event

Figure 17.33: Dragging Action to Graph Canvas

3. Right-click **Action** element and select **View Properties**. The properties of the action element are displayed in the Properties Panel in the Bottom Pane (see Figure 17.34).

459 295 295 296 295 296 5 Start Event 495 495		End Event	*		
4			<u>&gt;</u>		
🖂 Properties 🚫 On Exception Scripts 🔀 Alerts 🛅 Process Row Variables 📄 Connents					
Name Yalue					
flowId			<u>×</u>		
Label		Call Call			
Name resultCtxVarName	ame Call				
Туре		Call			

Figure 17.34: Action's Properties

4. Change the required properties and then click the action element in the Graph canvas area.

# **CREATING PROCESS FLOW VARIABLE**

Process Flow Variable are created and used throughout the execution of a process flow.

#### Steps to create a Process Flow Variable

1. Click **Process Flow Variable** tab in the bottom pane. The Process Flow Variables Panel is displayed with the list of existing variables (see Figure 17.35).






Figure 17.35: Process Flow Variable Panel

2. Click **New Process Flow Variable** () button in the Process Flow Variable Panel. The Process Flow Variable Entry screen is displayed (see Figure 17.36).

A Process flow variable entry			
Please enter variable name and value			
Variable name			
Variable value			
	Ok Cancel		

Figure 17.36: Create Process Flow Variable

- 3. Enter the name for the process flow variable in the *Variable Name* field.
- 4. Enter the value of process flow variable in the *Variable Value* field.
- 5. Click **OK** button to save the process flow variable and return to the Graph Canvas.
- 6. Once a new process flow variable is created, it is added to the list in the Process Flow Variables tab (see Figure 17.37).






Figure 17.37: Process Flow Variable created



To track all changes made on the process flow variable, check the *Track* checkbox against the process flow variable.

# **CREATING CONTEXT VARIABLE**

You can create multiple context variables in a process flow using the *PutContextVar* action. Once they are created, you can use these context variables in the context of the process context as and when required.

#### Steps to create a Context Variable

1. Click tree structure in the **Repository View** panel. Expand the **Action** list and select the **Put-Context-Var** action. Drag it to the Graph Canvas area. The Put-Context-Var action is displayed in the Graph Canvas (see Figure 17.38).



Figure 17.38: Drag Put-Context-Var action in Graph Canvas

2. Right-click **Put-Context-Var** action and select **View Properties**. The properties of the *Put-Context-Var* action are displayed in the Properties Panel in the Bottom Pane (see Figure 17.38).



	200 225 250 275 300 325 350 375 400 425 450 475	Start Event	CrusipD_F Bigsurr •	E Evalpor trape	End Event	
Name         Value           Content Variables         Edit           Label         PutContent/VarTag4           Name         PutContent/VarTag4		4				
Context Variables Edd Context Variables Dated PutContextVariag4 Norm PutContextVariag4	Pr	🗟 Propertiles 🚫 CinException Scripts 🚫 Alerts 🔄 Process Flow Variables 🗒 Comments				
Label PutContextWarTag4 Name PutContextWarTag4		Name Value				
Name PutContextVarTag4						
nype Put-Context-Var	Type	pe Put-Context-Var				

Figure 17.39: Properties of Put-Context-Var action

 Click Edit button. The Edit Context Variables screen is displayed (see Figure 17.40). This screen displays a list of existing context variables and the Add Variable (), Edit Variable () and Delete Variable () buttons.



	Edit Context Variables				
Conte	ext Variable Information T	able			
D					
	Activity Name	Variable Name	Variable Value		
			Done Cance	:	

Figure 17.40: Edit Context Variables



The **Edit Variable** and **Delete Variable** buttons appear as disabled if no context variables have been created or no existing context variables have been selected.

4. Click **Add Variable** () button to create a new context variable. The Context Variable Information screen is displayed (see Figure 17.41).



🛦 Context Variable Information	X
Activity Name :	
Variable Name :	•
Variable Value :	
	Done Cancel

Figure 17.41: Context Variable Information

5. Select the name of the activity for which you want create the context variable, from the *Activity Name* drop-down list. This drop-down lists all the activities that are currently present on the Graph Canvas. Once you select the activity, all the attributes of the selected activity, are listed in the Variable Name drop-down list.



If the Activity Name field is left blank, then a new context variable is declared.

6. Select the attribute for which you want to create the context variable, from the *Variable Name* drop-down list. For example, you can select the File Path field in case of a File Source or File Target activity.



If the *Activity Name* field is blank, then the current context variables will be listed in the Variable Name drop-down list.

7. Enter the value that you want to set for the attribute/context variable, in the *Variable Value* field.

You can even append the current date or time stamp with the name of the file in the Variable Value field. To do this, click in the Variable Value field, and press <CTRL> + <Space Bar>. A list of the date and time format is displayed. Selecting a format from this list, displays it in the Variable Value field. Alternately, you can enter the required file path with the file name as in the example: C:\target\File\_target%%yyyy-mm-dd%%.txt

The Variable Value field does not support '&' and '<' symbols.

8. Click **Done**. This adds the context variable and takes the control back to the Edit Context Variables screen, where the new context variable is added to the list of existing context variables (see Figure 17.42).




Edit Context Variables					
Context Variable Information Table					
Activity Name	Variable Name	Variable Value			
EvalPD_FileSource	fileName	customer			
		Done Cancel			

Figure 17.42: Context Variable Added



You can add multiple context variables (up to a maximum of 100) for the process flow.

9. Click **Done** on the Edit Context Variables screen to add all the displayed context variables to the context of the process flow.



context variables on the Edit Context Variables screen. You can select multiple context variables to delete, by pressing **<CTRL>** and the context variables. This selection(s) will enable the **Delete Variable** button. Clicking this button will delete the selected context variable(s).

ADEPTIA

# **USING CONTEXT SOURCE AND CONTEXT TARGET**

Process Flow keeps it data in memory called Process Flow Context, which is used by the process flow during its execution. When process flow takes any data from the context, it uses the context source activity. Context Source is used to read a variable and stream it out to other activities of the process flow. In addition to that Context Source can also read file from repository (WebDAV or File) and pass it to other activities. Similarly, when process flow sends any data to the context, it uses the context target activity.

#### Steps to create a Context Source/Target activity

- 1. Click tree structure in the **Repository View** panel. Expand the **Activities** list and click **Source**. A list of source activities is displayed.
- 2. Select **Context Source**. Drag the Context Source to the Graph Canvas Area. A small image of the activity is displayed in the Graph Canvas Area (see Figure 17.43).



Figure 17.43: Drag Context Source

3. In the Graph Canvas area, right click the **Context Source** and select **View Properties**. This displays all properties for the context source in the Bottom Pane (see Figure 17.44).



250						
275						
275 300 328 350 375 400		Context				
-300	Start Event	Source a	$\bigcirc$			
-325			End Event			
-350						
375						
-400						
425						
-450						
470						-
						×
-175						¥ 1
	🚫 OnException Scripts 🔞	Alerts Drocess Flow Variables	ments			× 1
	🚫 OnException Scripts 🛛 👸	Alerts SProcess Flow Variables	ments		Value	×
Properties			ments	99	Value	¥
Properties	kory				Value	×
Properties	kory		fal		Value	× ×
Properties	kory		fai fai	se AIN_TYPE	Value	2 
Properties Document Repose eventContextEn Format	kory		fai fai	58	Value	× × ×
Properties Document Repos eventContextEn Format ID Label	kory		fai Fai PL	se AIN_TYPE	Value	× ×
Properties Document Repose eventContextEnc Format D Lobel Name	kory		fai Fai PL	se AIN_TYPE ntextSource	Value	× * * *
Properties     Properties     Document Repose eventContextEn Format ID     Lobel Name parameterName	kory		fai Fai PL	se AIN_TYPE ntextSource	Value	× × × ×
Properties     Properties     Document Repos     eventContextEn     Format     D     Label     Name     parameterName     source	kory		fai Fai PL	se AIN_TYPE ntextSource	Value	× × ×
<u> </u>	kory		fai Fai PL	66 AIN_TYPE ntextSource ntextSource	Value	× × × ×

### Figure 17.44: Properties of Context Source

4. A list of properties and their descriptions are displayed in the table below.

Properties	Description
Document Repository	This property specifies whether the data to be taken from the value of process flow variable, or from the document repository. If it is set to false, the data is taken from the Process Flow variable, specified by the Parameter Name property. If it is set to true, the source data is taken from the repository file specified by the File Name (with full Path) Property. Specify the path of the document repository and the name of the repository file, from which the data is to be taken, in this field. Repository can be WebDAV repository or file repository. To know more about repository, refer to the <i>Administrator Guide</i> .
eventContextEnabled	By default it is set to <b>NO</b> . If you want to pass any data from event, select <b>Yes</b> . For example, if you are triggering the process flow using Mail Event and you want to pass the content of the mail to the process flow, set this property to yes. To know about events, refer to the <b>Creating Trigger and</b> <b>Events</b> section.
Format	Data Format; whether Plain Type or Record Type. Select Plain Type, if data is in Byte Stream. Select Record type, if data is in record format.
Label	Label of the Context Source Activity displayed in the Graph Canvas area.
Name	Name of the Context Source activity. By default, it is same as the Process Variable name.
Repository Folder	Name and path of the WebDAV folder. This property is displayed only if the <b>Document Repository</b> property is set to <i>True</i> .
parameterName	Select the name of the Process Flow Variable, whose value is to be taken as context source. This property

### Table 17.10: Context Source/Target Activity Properties




	is applicable only when the <b>Document Repository</b> Property is set to <i>False</i> .
Source	Name of the stream being consumed by this activity. This property is applicable only for Context Target. It is non-editable.
streamNames	Name of the output stream name. This property is applicable only for Context Source. It is non-editable.
Synch	Specifies whether the activity will be executed in Synch mode or Asynch mode.
Туре	Activity Type; whether Context Source or Context Target. By Default Context Source is selected. If you want to use it as Context Target, select Context Target from the drop-down list.
Version Control	It specifies whether versions are to be maintained for the repository file, which is created by context target. This property is displayed only if the <b>Document Repository</b> property is set to <i>True</i> . If this property is set to false, then the versions are not maintained. If it is set to True, then all versions are tracked.

# **OVERRIDING PROCESS FLOW DESCRIPTION AT RUNTIME**

You can override the description of process flow during execution. To override the description put-context-var action is used. If the description of a process flow is overridden, in process flow log, new description is shown.

#### Steps to override Process Flow Description


1. Click tree structure in the **Repository View** panel. Expand the **Action** list and select the **put-context-var** action and drag it to the Graph Canvas area anywhere within the process flow.



2. Connect the put-context-var action as shown in Figure 17.45 .

Figure 17.45: Connect Put-Context-Var to activity





3. Right-click **put-context-var** and select **View Properties**. Its properties are displayed in the Properties Panel in the Bottom Pane (see Figure 17.46).

Figure 17.46: Properties of Put-Context-Var

- 4. Click **Edit** button to edit the value of context variable. The Edit Context Variables dialog box is displayed.
- 5. Click **Add Variable** () to add new context variable. The Context Variable Information screen is displayed.
- 6. Leave the Activity Name field blank.
- 7. Select ProcessFlowDescription from *Variable Name* drop-down list.
- 8. Enter the new description of the process flow in the *Variable Value* field.
- 9. Click **Done** to close Context Variable Information screen. This takes the control back to the Edit Context Variables screen. The newly created variable is added to the list of existing context variables.
- 10. Click **Done** to close Edit Context Variables screen and return to Process Designer.
- 11. Save the process flow and exit from Process Designer.

# **OVERRIDING ACTIVITY OF A PROCESS FLOW AT RUNTIME**

An activity of a process flow can be overridden by another activity during execution of the process flow. For example lets assume the following process flow:






Figure 17.47: Usage Scenario

In Figure 17.47 the process flow uses the EvalXform\_ExcelSchema. You can override this activity with any other schema activity (for example, EvalXform\_Text Schema) during the execution of the process flow. In this case, EvalXform\_TextSchema is executed during the execution of the process flow.

This functionality is used when the actual activity to be executed is decided at execution time, not at design time of the process flow. For example, in a process flow that handles data coming in various formats, you have to first add the schema activity for each data format and then route the data to appropriate format using decision node. This results in the process flow being bulky and unmanageable. At times, you may even need to design one process flow for each data format. Now, this problem can be overcome by using the same process flow with a different schema activity. You can simply override the EvalXform\_ExcelSchema with any other schema of your choice. For details on the type of activities that can be overridden refer to the <u>Activities that can be overridden</u> section.

There are two ways of overriding an activity in a process flow. They are outlined as:

- Overriding an activity using Custom Plugin
- Overriding an activity using put-context-var

## Overriding an activity using Custom Plugin

You can override an activity by using a custom plugin activity just before the activity, which needs to be overridden by another activity.




Figure 17.48: Overriding an Activity using Custom Plugin

As shown in Figure 17.48, the *EvalXform\_CustomPlugin* activity is used just before the *EvalXform\_ExcelSchema* activity.

The **setActivityParameter ( ) API** is used to override the activity.



The sample Java code, which is used to override a schema activity, is displayed in Figure 17.49.

context.setActivityParameter(ActivityName,"schemaTypedId", activityType + ":" + dynamicActivityID);

Figure 17.49: Sample Java Code used to Override a Schema Activity

For all other activities the overriding is done using the Java code displayed in Figure 17.50.

context.setActivityParameter(activityName,"TypedId",activityType
":" + dynamicActivityID);

Figure 17.50: Sample Java Code used to Override Activities

#	Name	Description	Example
1	activityName	Name of the activity, which is to be overridden	EvalXfrom_ExcelSchema
2	activityType	Activity Type of the activity, which will override the existing activity. To know the Activity Type of the activity refer to the <u>Activities that can be</u> <u>overridden</u> section.	TextSchema
3	dynamicActivityID	Entity Id of the activity, which will override the existing activity. To know the Entity Id of an activity, in Manage activity screen, click on the activity.	192168001006115537684214000004

Table 17.11:	Arguments	used in	Java	Code
--------------	-----------	---------	------	------

### Overriding an activity using put-context-var

You can override an activity using put-context-var action just before the activity, which needs to be overridden by another activity.

#### Steps to override an activity using put-context-var

- 1. Click tree structure in the **Repository View** panel. Expand the **Action** list and select the **put-context-var** action and drag it to the Graph Canvas area just before the activity, which is to be overridden.
- 2. Connect the put-context-var action to the activity (see Figure 17.51).






Figure 17.51: Connect Put-Context-Var to activity

3. Right-click **put-context-var** and select **View Properties.** Its properties are displayed in the Properties Panel in the Bottom Pane (see Figure 17.52).




Figure 17.52: Properties of Put-Context-Var

- 4. Click **Edit** button to edit the value of context variable. The Edit Context Variables dialog box is displayed.
- 5. Click Add Variable () to add new context variable. The Context Variable Information screen is displayed.
- 6. Select the activity, which is to be overridden (for example, *EvalXform\_ExcelSchema*) from *Activity Name* drop-down list.
- 7. Select SchemaTypedId (for Schema activity) or *TypedId* (for all other activities) from Variable Name drop-down list.
- 8. Enter the *Activity Type* and the *Entity Id* of the activity, which will override the existing activity in following format, in the *Variable Value* field.

Format	:	Activity Type: EntitiyID
For Example	:	TextSchema: 192168001006115537684214000004



To know the Entity Id of an activity, in Manage activity screen, click the activity.

The entered information is displayed as shown in Figure 17.53.



<u> Context</u> ¥ariable Information	X
Activity Name :	EvalXform_ExcelSchema
Variable Name :	schemaTypedId 🗾 👻
Variable Value :	TextSchema:1921680010061155376842
	Done Cancel

Figure 17.53: Context Variable Details for Overriding an Activity

- 9. Click **Done** to close Context Variable Information screen. This takes the control back to the Edit Context Variables screen. The newly created variable is added to the list of existing context variables.
- 10. Click **Done** to close Edit Context Variables screen and return to Process Designer.
- 11. Save the process flow and exit from Process Designer.

## Activities that can be overridden

You can override many types of activities in a process flow. These are outlined as:

- Source Activity
- <u>Target Activity</u>
- Schema Activity
- Polling Activity
- Other Activities

### Source Activity

Any type of source activity can be overridden by another type of source activity. For example, a file source activity can be overridden by an FTP source activity. The types of source activities, that can be overridden and their TypedId are listed in the table below.

Source Type	Activity Type
Advanced Database Source	AdvancedDatabaseSource
Database Source	DatabaseSource
File Source	FileSource
FTP Source	FtpSource

Table 17.12: Source Types that can be Overridden



HTTP Source	HttpSource
JMS Source	JmsSource
LAN File Source	LanFileSource
Mail Source	MailSource
WebDAV Source	WebdavSource

## Target Activity

Any type of target activity can be overridden by another type of target activity. For example, a file target activity can be overridden by an FTP target activity. The types of target activities, that can be overridden and their TypeId are listed in the table below.

Target Type	Activity Type
Advanced Database Target	AdvancedDatabaseTarget
Database Target	DatabaseTarget
File Target	FileTarget
FTP Target	FtpTarget
HTTP Target	HttpPost
JMS Target	JmsTarget
LAN File Target	LanFileTarget
Mail Target	MailTarget
WebDAV Target	WebdavTarget

Table 17.13: Target Types that can be Overridden

### Schema Activity

Any type of schema activity can be overridden by another type of schema activity. For example, a text schema activity can be overridden by an excel schema activity. The types of schema activities, that can be overridden and their schemaTypedId are listed in the table below.

Table 17.14: Schema Types that can be Overridden
--

Schema Type	Schema Activity Type
-------------	----------------------



Excel Schema	ExcelSchema
Text Schema	TextSchema
XML Schema	XMLSchema
EDI Schema	EDISchema
Advanced Positional Schema	AdvancePositionalSchema
Positional Schema	PositionalSchema

## **Polling Activity**

Any type of polling activity can be overridden by another type of polling activity. For example, a file polling activity can be overridden by a mail polling activity. The types of polling activities, that can be overridden and their TypeId are listed in the table below.

Possible Polling Type	Activity Type
Database Polling	DatabasePollingService
File Polling	FilePollingService
FTP Polling	FtpPollingService
Mail Polling	MailPolling

Table 17.15: Polling Types that can be Overridden

## Other Activities

All other types of activity can be overridden by exactly the same type of activity. For example, a Custom Plugin activity can be overridden by another Custom Plugin activity only. Similarly, a Data Mapper activity can be overridden by another Data Mapper activity only. All other types of activities, that can be overridden and their TypeId are listed in the table below.

Activity	Activity Type
Data Mapping	DataMapping
Record to Record	ScriptedRecord2RecordTransformer
Custom Plugin	CustomPlugin
Human Workflow	HumanInteraction
Context Download	ContextDownload

Table 17.16: Other Activity Types that can be Overridden



Context Upload	ContextUpload
MIME Message:	
Decoder	MessageExtractor
Encoder	MessageComposer
Custom Report	IndigoReport
Native Call	NativeCall
Mail Notification	MailNotification
Web Service:	
WsMessage Call	WsMessageCall
WsRpc Call	WsRpcCall

## Overriding subject and body of email sent for a Human Workflow Task

The subject of emails sent when a Human Workflow task is created/updated, is already predefined in the code. Now, you can override this subject by using *put-context-var* action.

#### Steps to override email subject using put-context-var

- 1. Click tree structure in the **Repository View** panel. Expand the **Action** list and select the **put-context-var** action and drag it to the Graph Canvas area before the human work flow task whose email subject is to be overridden.
- 2. Connect the *put-context-var* action to the task (see Figure 17.54).




Figure 17.54: Connect put-context-var to Human Workflow task

- 3. Right-click **put-context-var** and select **View Properties**. Its properties are displayed in the Properties Panel in the Bottom Pane.
- 4. Click **Edit** button to edit the value of context variable. The Edit Context Variables dialog box is displayed.
- 5. Click **Add Variable** () to add new context variable. The Context Variable Information screen is displayed.
- 6. Select the task, which is to be overridden (for example, Customer\_HWF) from *Activity Name* drop-down list. All variables of this task are listed in the Variable Name drop-down list.



- 7. Select **emailSubject** from *Variable Name* drop-down list.
- 8. Enter the new email subject that you want to display, in the *Variable Value* field. You can also define the subject as extracted from a variable, by entering \$\$ variable name \$\$ in the *Variable Value* field.

The entered information is displayed as shown in Figure 17.55.

<b>A</b> Context Variable Information	×
Activity Name :	Customer_HWF
Variable Name :	emailSubject 🔹
Variable Value :	This is a new task
	Done Cancel

Figure 17.55: Context Variable Details for Overriding email subject

- 9. Click **Done** to close Context Variable Information screen. This takes the control back to the Edit Context Variables screen. The newly created variable is added to the list of existing context variables.
- 10. Click **Done** to close Edit Context Variables screen and return to Process Designer.
- 11. Save the process flow and exit from Process Designer. When you execute this process flow, and an email for a new task is sent, then 'New Task' is appended in the email subject. This is pre-defined in the code and is displayed when you override the email subject. It is subject to change, based on the action performed. If an existing task is deferred, then 'Deferred Task' is appended.



Similarly, you can dynamically override the first line of the email subject.

## **Overriding Assignee User of a Human Workflow Task**

You can dynamically override the assignee (user to whom task is assigned) of a Human Workflow activity, during the execution of a process flow using *put-context-var* action.

#### Steps to override assignee using put-context-var

- 1. Click tree structure in the **Repository View** panel. Expand the **Action** list and select the **put-context-var** action and drag it to the Graph Canvas area before the Human Work flow task assignee is to be overridden.
- 2. Connect the *put-context-var* action to the task (refer to Figure 17.54).
- 3. Right-click **put-context-var** and select **View Properties**. Its properties are displayed in the Properties Panel in the Bottom Pane.



- 4. Click **Edit** button to edit the value of context variable. The Edit Context Variables dialog box is displayed.
- 5. Click **Add Variable** () to add new context variable. The Context Variable Information screen is displayed.
- 6. Select the task, which is to be overridden (for example, *Customer\_HWF*) from *Activity Name* drop-down list. All variables of this task are listed in the *Variable Name* drop-down list.
- 7. Select *hiReceiverUsers* from *Variable Name* drop-down list.
- 8. Enter the User Id of the user to whom you want to assign the Human Workflow task, in the *Variable Value* field. The entered information is displayed as shown in Figure 17.56.

🙏 Context Variable Information	X
Activity Name :	Customer_HWF
Variable Name :	hiReceiverUsers 🗾
Variable Value :	John
	Done Cancel

Figure 17.56: Context Variable Details for Overriding email subject

- 9. Click **Done** to close Context Variable Information screen. This takes the control back to the Edit Context Variables screen. The newly created variable is added to the list of existing context variables.
- 10. Click **Done** to close Edit Context Variables screen and return to Process Designer.
- 11. Save the process flow and exit from Process Designer. When you execute this process flow, the process will be assigned to user (for example *John* instead of *Administrator*) to whom it was originally assigned.

## PROCESSING RECORD QUEUE

By default, during the execution of process flow, the entire input data is processed at a time. Adeptia allows you to process the input data record-by-record. To process the data record-by-record, Record Queue Processor is used. Using Record Queue Processor, you can:

- Process the input data record-by-record
- Specify the number of records to be processed

#### How Record Queue Processor works?

Record Queue processor consists of *Record Queue Producer* and *Record Queue Receiver*. *Record Queue Producer* is an asynchronous activity, which sets records one by one in a queue and waits



for it to get consumed by *Record Queue Receiver*. *Record Queue Receiver* consumes the record from the queue and produces a stream. This stream can be further processed by other activities of the process flow. Once the record is consumed by *Record Queue Receiver*, *Record Queue Producer* sets the next record and waits for it to get consumed by *Record Queue Receiver*. This loop continues until all the records are queued and processed. Once all the records are processed, the loop is broken and the process flow stops.

The usage of the Record Queue Processor is explained in Figure 17.57.




Figure 17.57: Using Record Queue Processor

As shown in the figure above, data from *File\_Source* is consumed by *Text\_Schema*, which further passes it to Record Producer. Record Producer takes the first record and sets it into Queue as specified by Record Queue Producer properties. Gateway is used to check availability of records. Following is the code, which is used at Gateway to check the availability of the record in queue.

```
String queue = context.get("Service.queueName.nextRecord");
if(queue.equals("true")){
  return true;
}
return false;
```

Where queueName is the name of the queue specified in *Record Queue Producer*. "*nextRecord*" is a variable which is used to decide whether the record is available in the queue or not. Value of the variable *NextRecord* can be true or false. When *Record Queue Producer* sets a record in the queue, the value of *nextRecord* variable become true. If the value is true, it means the next record is available in queue for processing. In this case *Record Queue Receiver* takes the record from queue, changes the value of *nextRecord* variable to false and passes the record to file target. In the meantime *Record Queue Producer* again sets the record in the queue and changes the value of *nextRecord* to true and waits for it to get consumed by *Record Queue Receiver*. If the value of *NextRecord* variable is not changed to true, it means there is no record available for processing and the record queue processor is stopped.

Steps to process records using Record Queue Producer and Record Queue Receiver



- 1. Click tree structure in the **Repository View** panel. Expand the **Activities** list of the Adeptia Server and select and drag the *File source* and *Text schema* activities to the Graph Canvas area.
- 2. Select the **RecordQueueProducer** activity and drag it to the Graph Canvas area.
- 3. Drag a gateway element to the Graph Canvas area.
- 4. Drag a *File target* to the Graph Canvas area.
- 5. Select the **RecordQueueReceiver** activity and drag it to the Graph Canvas area.
- 6. Connect all the activities as shown in Figure 17.57.
- 7. Right-click **RecordQueueProducer** and select **View Properties**. Its properties are displayed in the Properties Panel in the Bottom Pane (see Figure 17.58).




Figure 17.58: Properties of RecordQueueProducer

8. Set the appropriate properties for the RecordQueueProducer. For details on the properties and their description, refer to the table below.

Table 17.17:	Record Queu	e Producer P	roperties
--------------	-------------	--------------	-----------

Properties	Description
Character Set Encoding	Character set encoding that is used for parsing, incase input data is XML. By default it is ISO- 8851-1
InputFormat	Format of the input data. It can be XML or Native.
Label	Label of the Record Queue Producer activity displayed in the Graph Canvas area.
Name	Name of the Record Queue Producer activity. By default, it is Record Queue Producer.
OutputFormat	Format of the output record. It can be XML or



	Native.
schemaTypedId	TypedId and the 30 digit activity ID of the source schema separated by colon (:). For example TextSchema: 19216800115811719672980930000 3 To know the TypedID of Schema refer to Table 17.14. To know the 30 digit activity, click the activity name from the manage page. The 30 digit activity Id along with other properties are shown.
Source	Name of the Activity, which is passing the record to Record Queue Producer. By default this field is populated. You cannot edit this field.
streamNames	Record Queue Producer doesn't produce any stream. This field remains blank.
queueName	Enter any queue name. This will be the queue name in which records are set. QueueName must be same as sourceQueueName of Record Queue Receiver activity used in the process flow.
Synch	Specifies whether the activity will be executed in Synch mode or Asynch mode. Record Queue Producer is always executed in asynch mode. This field is non editable. To know more about Synch and Asynch mode of execution, refer to the section Working with Process Flow.
Туре	Type of the activity. By default this field is populated. This field is non editable.

9. Right-click **RecordQueueReceiver** and select **View Properties**. Its properties are displayed in the Properties Panel in the Bottom Pane (see Figure 17.59).



100 125 150 5tart Event 200 225 200 225 200 225 200 225 200 200					
	F				
🐨 Properties 🔞 OnException Scripts 🕺 Alerts 🔊 Process Flow Variables 🗐 Comments					
Name	Value				
Character Set Encoding	ISO-8859-1				
ID					
inputFormat	XML 🗾				
Label	RecordQueueProducer				
Name	RecordQueueProducer				
outputFormat	XML I				
queueName					
maTypedId null					
Signal	SignalComplete TextSchema				
source streamNames	TextSchema				
	false				
Synch					
Time out (in seconds)	300 🛨 💌				

Figure 17.59: Properties of RecordQueueReceiver

10. Set the appropriate properties for the *RecordQueueReceiver*. For details on the properties and their description, refer to the table below.

1	
Properties	Description
Label	Label of the Record Queue Producer activity displayed in the Graph Canvas area.
Name	Name of the Record Queue Producer activity. By default, it is Record Queue Producer.
Source	Record Queue Receiver does not consume any stream. This field remains blank.
streamNames	Name of the stream produced by Record Queue Receiver.
SourceQueueName	Enter the name of the queue from which Record Queue Receiver will fetch the record. sourceQueueName must be same as QueueName of Record Queue Producer activity used in the process flow.
Synch	Specifies whether the activity will be executed in Synch mode or Asynch mode. Record Queue receiver can be executed in Asynch or Synch mode. To know more about Synch and Asynch mode of execution, refer to the section <u>Working with</u> <u>Process Flow</u> .
Туре	Type of the activity. By default this field is populated. You cannot edit this field.



Based on the selected properties for the *RecordQueueProducer* and *RecordQueueReceiver*, and the code specified for the Gateway element, the records are processed.



Record processing can be stopped based on specified conditions. If the condition is met, then the signal is set by the *RecordQueueReceiver* to stop further processing of records.

# Adding Conditions in Process Flow

Conditions determine whether a certain transition is executed in a process flow. Conditions are used to change the direction of the process flow based on a decision. There are three types of conditions:

- Process Flow Variable Condition
- Java Condition
- Expression Condition Builder

## **Process Flow Variable Condition**

A transition can have condition based on the value of the context variable present in the current process flow. Once the condition is met, transition takes place. The Process Flow Variable Condition can be of two types:

- <u>Activity Attributes Condition</u>: Activity Attribute Condition is used to define condition based on the value activity specific context variable in a process flow.
- <u>Other Condition</u>: Other Condition is used to define condition using pre-created context variables.



Process Designer allows Conditions to be added only for uncontrolled or default flow having gateway as its source. User cannot enter Condition for Association and Direction association flow under any circumstances.

## Adding Condition Using Process Flow Activity Attributes

Steps to add a Condition in a Process Flow using Activity Attributes

1. Select the **Gateway** ( ) element in the Palette and drag it to required place in the Graph canvas area. The Gateway element is displayed in the Graph canvas area (see Figure 17.60).



Start Event	<b></b>	End Event
-------------	---------	-----------

Figure 17.60: Drag Gateway Element to Graph Canvas Area

2. Connect the activities with the Gateway element using uncontrolled or default control flow (see Figure 17.61).





Figure 17.61: Connecting Elements



3. To add Condition, right-click control flow and select **View Properties**. The properties of the control flow are displayed in the Properties Panel in the Bottom Pane (see Figure 17.62).




Figure 17.62: Change Gateway Element Properties

4. Click **Edit Condition** button. The Condition Wizard screen is displayed (see Figure 17.63).



🛦 Condition Wizard				×
Condition type				
Choose the condition type:				
O Process Flow Variable Condition				
🔿 Java Condition				
O Expression Condition				
	Back	Next	Done	Cancel

Figure 17.63: Condition Wizard

5. Select the **Process Flow Variable Condition** and click **Next** button. The Choose Process Flow Variable Condition Type screen is displayed (see Figure 17.64).




Figure 17.64: Select Process Flow Condition Type

6. Select **Activity Attribute Condition** and then click **Next** button. The Activity Attributes Condition screen is displayed (see Figure 17.65).

A Condition Wizard			
Activity attributes condition			1
Please select required activity attribute and	desired value:		
Existing Activities :		~	
Activity Attributes :		~	
Operands Type :	Text	~	
Operators :	=	~	
Value :		~	
Decimal Precision :		0 😂	
L		_	
		Bac	k Next Done Cancel

Figure 17.65: Activity Attributes Condition

7. Select the activities of the process flow from the Existing Activities drop-down list.



- 8. Select the attribute of the selected activity from the *Activity Attributes* drop-down list.
- 9. Select the data types of the value contained by the above specified attribute from *Operand Type* drop-down list. The data types supported for the value are listed in the table below.

Data Type	Description			
Number	This data type is selected if the specified activity attribute contains numeric value. For example, 1, 12.			
Text	This data type is selected if the specified activity attribute contains text value. For example, abc, xyz.			
Decimal	This data type is selected if the specified activity attribute contains decimal value. For example, 10.211, 100.50. The decimal precision can be defined under the decimal precision text field.			

- 10. Select the operator's type from the *Operators* drop-down list. The operators supported are "=", "! =", ">", "<", ">=", "<=".
- 11. Enter or select the value of the above specified attribute from *Value* drop-down list.
- 12. Specify the decimal precision (only if operand type is "Decimal") under the *Decimal Precision* text field.
- 13. Click **Done** button to close the Condition Wizard and return to the Graph Canvas.
- 14. Repeat steps 4 to 14 to add condition on another control flow.

### Adding Condition Using Process Flow Variable Other Condition

Using Process Flow Variable we specify that if the value of a specified variable is equal to the defined value, the transition will execute.

#### Pre-Requisite:

 Process Flow variable must be created. To learn how to create process flow variable, refer to the <u>Creating Process Flow Variable</u> section.

#### Steps to add a Condition in a process flow using Process Flow Variable

- 1. Select the **Gateway** ( )element in the Palette and drag it to required place in the Graph canvas area. The Gateway element is displayed in the Graph Canvas area (refer to Figure 17.60).
- 2. Connect the activities with the Gateway element using uncontrolled or default control flow (refer to Figure 17.61).





To learn how to connect activities, refer to Creating Process Flow section.

- 3. To add Condition, right-click control flow and select **View Properties**. The properties of the control flow are displayed in the Properties Panel in the Bottom Pane (refer to Figure 17.62).
- 4. Click **Edit Condition** button. The Condition Wizard screen is displayed (refer to Figure 17.63).
- To use Condition using Process Flow Variable, select the Process Flow Variable Condition and click Next button. The Select Process Flow Condition Type screen is displayed.
- 6. Select Other Condition and then click Next button. The Other Condition Process Details screen is displayed (see Figure 17.66).

A Condition Wiza	rd		
Other Condition			
Please enter arbitrary r	iame-value:		
Name :		~	
Operands Type :	Number	~	
Operators :	=	~	
Value :			
Decimal Precision :		0 🗇	
			Back Next Done Cancel

Figure 17.66: Other Condition Process Details

- 7. Select the Process Flow Variable from the *Name* drop-down list and enter the Value in the *Value* field.
- 8. Select the data types of the value contained by the above specified context variable from *Operand Type* drop-down list. For information regarding data types supported for the value refer to Table 17.19.
- 9. Select the operator's type from the *Operators* drop-down list. The operators supported are "=", "! =", ">", "<", ">=", "<=".
- 10. Enter the value of the above specified context variable in the Value field.
- 11. Specify the decimal precision (only if operand type is "Decimal") under the *Decimal Precision* field.
- 12. Click **Done** button to apply the condition and return to the Graph Canvas.

## Java Condition

A transition can have condition, which can be in form of script. Once the condition is met, transition takes place. Java Condition is a part of transition.



The sample conditional transition is given as below:

```
<transition from="state.2" to="state.4">
        <guard>
        <indigo:scripted-guard>
        <![CDATA[
                      ..script
        ]]>
        </indigo:scripted-guard>
        </guard>
</transition>
```

A State in Process XML either has normal transition(s) and/or conditional transition(s). If there are more than one transition from a State, only one transition takes place at a time and it depends upon the order of their occurrence and condition satisfaction (in case conditional transition). Conditional transition takes place based on appropriate condition defined in form of java code. When the condition is met, transition takes place. A Condition is satisfied when java code script returns true. The Java code script should return true or false otherwise exception is raised.

### Adding Condition Using Java Condition

#### Steps to add a Condition in a process flow using Java Condition

- 1. Select the **Gateway** ( )element in the Palette and drag it to required place in the Graph canvas area. The Gateway element is displayed in the Graph canvas area (refer to Figure 17.60).
- 2. Connect the activities with the Gateway element using uncontrolled or default control flow (refer to Figure 17.61).



To learn how to connect activities, refer to Creating Process Flow section.

- 3. To add Condition, right-click control flow and select **View Properties**. The properties of the control flow are displayed in the Properties Panel in the Bottom Pane (refer to Figure 17.62).
- 4. Click Edit Condition under the Properties tab. The Condition Wizard screen is displayed.
- 5. To define Condition using Java Condition, select the **Java Condition** and click **Next** button. The Java Condition screen is displayed (see Figure 17.67).



Condition Wizard	
Java condition (Press CTRL + SPACE for template)	
	2
Back Next Done Ca	ncel

Figure 17.67: Enter Java Condition

6. Enter the Java Code in the *Java Condition* field and click **Done** button to return to the Graph Canvas area.



You can use **<CTRL>+<Space Bar>** to view pre-defined template of Java Code, which can be used in creating Java Condition. You can select any of them and edit it according to your requirement.

7. Similarly, repeat steps 4 to 7 to add Condition to another control flow.

### **Expression Condition Builder**

A transition can have condition based on an expression. This expression is built using the Activity Attributes or the Process Flow variable with the 'AND' & 'OR' condition.

### Adding Condition Using Expression Builder

Using Activity Attributes and Process Flow variables, and the 'AND' or 'OR' conditions, you can generate an expression.

#### Steps to add a Condition in a process flow using Expression Builder



1. Select the **Gateway** ( ) element in the Palette and drag it to required place in the Graph canvas area. The Gateway element is displayed in the Graph Canvas area (refer to Figure 17.60).

2. Connect the activities with the Gateway element using uncontrolled or default control flow (refer to Figure 17.61).



To learn how to connect activities, refer to Creating Process Flow section.

- 3. To add Condition, right-click control flow and select **View Properties**. The properties of the control flow are displayed in the Properties Panel in the Bottom Pane (refer to Figure 17.62).
- 4. Click Edit Condition button. The Condition Wizard screen is displayed.
- 5. To use Condition using Expression Builder, select the **Expression Condition** and click **Next** button. The Condition Wizard screen is displayed (see Figure 17.68).

Condition Wizard			×
Rule	Operator:	-	
Rule Information Table			
(#)			
Rule Name	Expression	F	lule Reason
		Back Next	Done Cancel

#### Figure 17.68: Condition Wizard

For defining expressions you need to define rules. A rule supports multiple expressions. You can link the multiple expressions using the rule operator.

6. Click Add Rule ()) to add a new rule. This displays the Rule Information screen (see Figure 17.69).



A Rule Information			X
Rule Name:	Rule Reason:		
Declaring Activity Attribute/Variable to build I	Expression		
Please select Activity Attribute/Variable and o	lesired value to build expression:		
Existing Activities :		~	
Activity Attribute/Variable :		~	
Operand Type :	Number	~	
Operator :	=	~	
Value :		~	
	1	Ir	isert Variable
Declaring Operator to build Expression			
Please select required Operator to build Expre	ession:		
Select Operator:	8.8	~	
		In	ert Operator
Expression			
L			1
		Done	Cancel

Figure 17.69: Rule Wizard

- 7. Enter the name of the Rule (for example, Rule 1) in the *Rule Name* field.
- 8. Enter the reason on the basis of which the rule will be evaluated as true or false (for example, Rule 1 is valid), in the *Rule Reason* field. This is set in the context.
- 9. To build the expression, you first need to select the Activity Attribute or Process Flow variable to be used in the expression. Select the activity to be used, from the *Existing Activities* drop-down menu. This drop-down is populated with the current activities. Alternately, if you select a blank value, then a process flow variable is selected.
- 10. Select the activity attribute or the process flow variable, from the *Activity Attribute/Variable* drop-down menu. This drop-down is populated with values based on the selection in the *Existing Activities* field. If an activity is selected, then this drop-down lists all attributes of the selected activity. If a process flow variable is selected, then this drop-down lists the currently available process flow variables.
- 11. Select the data type of the selected activity attribute or process flow variable, from the *Operand Type* drop-down menu. This drop-down is populated with values of *Number, Text (String)* and *Decimal.* These are description are outlined in the table below.

Data Type	Description
Number	This data type is selected if the specified activity attribute contains numeric value. For example, 1, 12.

Table 17.20: Data Types Supported for Operand Type Value



Text	This data type is selected if the specified activity attribute contains text value. For example, abc, xyz.
Decimal	This data type is selected if the specified activity attribute contains decimal value. For example, 10.211, 100.50. The decimal precision can be defined under the decimal precision text field.

12. Select the operator to be applied on the activity attribute or process flow variable, from the *Operator* drop-down menu. This drop-down is populated with values based on the selection in the *Operand Type* field. The possible Operator values for various Operands are listed in the table below.

Operand	Possible Operators		
Number	=, !=, <, >, <=, >=		
Decimal	=, !=, <, >, <=, >=		
Text	Equal, Not Equal, Equal Ignore Case and Not Equal Ignore Case		

- 13. Select the value for the activity attribute or process flow variable that needs to be verified, from the *Value* drop-down menu. This drop-down is editable. The *Number* Operand type should be of data type *Long*. The *Decimal* Operand type should be of *Double* data type.
- 14. Click **Insert Variable** to insert the defined condition (comprising of activity attribute or process flow variable) into the *Expression* text area, displayed at the bottom of the screen.
- 15. Once the activity attributes or process flow variable is inserted, you can create another condition for building the expression. Select the condition to be used for building the expression, from the *Select Operator* drop-down menu. This drop-down is populated with values of *&&* (AND) and // (OR).
- 16. Click **Insert Operator** to insert the selected operator into the *Expression* text area.
- 17. Both the conditions are displayed in the *Expression* text area. You can edit this expression for evaluation based on certain rules. These rules are outlined in the table below.

Object	Rule
Activity Attribute/Process Flow Variable	It is to be displayed between \$\$. For example, Activity Attribute will be displayed as \$\$ Service. Activity. <i>Activity</i> <i>Attribute</i> \$\$ Process Flow variable will be displayed as \$\$ <i>var1</i> \$\$
Operand Text	<ul> <li>All values are enclosed within double quotes. For example, ("text").</li> <li>Values having '\' are replaced by</li> </ul>

Table	17.22:	Rules	for	Evaluation



	<ul> <li>'\\'.</li> <li>Values having double quotes (") are replaced by single quotes (').</li> </ul>		
Operator Equal	The condition is replaced as (\$\$var\$\$.equals ("text")).		
Operator Not Equal	The condition is replaced as! (\$\$var\$\$.equals ("text")).		
Operator Equal Ignore Case	The condition is replaced as (\$\$var\$\$.equalsIgnoreCase ("text")).		
Operator Not Equal Ignore Case	The condition is replaced as! (\$\$var\$\$.equalsIgnoreCase ("text")).		



If an invalid expression is entered in the Expression text area, the transaction will abort.

The information is displayed in the Rule Information screen as in Figure 17.70.

A Rule Information				×
Rule Name:	Rule 1	Rule Reason	Rule 1 is valid	
Declaring Activity Attribute/Variable to bu	ild Expression			
Please select Activity Attribute/Variable and	nd desired value	to build expressi	on:	- 10 - 10 - 10 - 10 - 10 - 10 - 10 - 10
Existing Activities :	EvalPD_F	FileSource	-	]
Activity Attribute/Variable :	fileName			]
Operand Type :	Text		+	]
Operator :	Equal		-	]
Value :	SupplyOrd	der.xls		]
				Insert Variable
Declaring Operator to build Expression				
Please select required Operator to build E	xpression:			
Select Operator:	&&		*	
				Insert Operator
Expression				
(\$\$Service.EvalPD_FileSo	urce.fileN	ame\$\$.equa	als("SupplyO	rder.xls"))
				Done Cancel

#### Figure 17.70: New Rule Information

18. Click **Done** button. This returns the control to the Condition Wizard screen with the newly added rule. Similarly, you can add more rules. They are displayed in the Condition Wizard screen (see Figure 17.71).



Condition Wizard		<u>×</u>
	Rule Operator:	1
Rule Information Table		
i#i		
Rule Name	Expression	Rule Reason
Rule 1	(\$\$Service.EvalPD_FileSource.fileName\$\$.equal	Rule 1 is valid
Rule 2	(\$\$Service.EvalPD_FileSource.filePath\$\$.equals(	
Rule3	(\$\$Service.EvalPD_FileSource.deleteOnSuccess	Rule3 is valid
	Back	Next Done Cancel

Figure 17.71: Added Rules



You can edit the Rule Name and Rule Reason from this screen.

19. Select the operator on the basis of which you want to evaluate these rules, from the *Rule Operator* drop-down list. The various rule operators are outlined in the table below.

Table 17.23:	Rule O	perators
--------------	--------	----------

Rule Operator	Description
11	This evaluates the rules based on the OR operator. If any of the listed rules is true, then the decision value in the process flow will be executed as true.
&&	This evaluates the rules based on the AND operator. If all the listed rules are true, then only the decision value in the process flow will be executed as true. If any of the listed rules is false, then the decision value will be executed as false.

- 20. You can evaluate the rules using one operator at a time. For example, if you select ||, then all rules will be evaluated on the basis of the OR operator. You cannot evaluate two rules (for example, Rule 1 and Rule 2) based on OR operator and two rules (for example Rule 2 and Rule3) based on the AND operator.
- 21. Click **Done**. This closes the Condition Wizard screen and returns to the Graph Canvas.



Once you execute the process flow, all the listed rules will be evaluated in top to bottom sequential order.

If they are evaluated using the *OR* (//) rule operator, then if any of the listed rules is true, then the decision value will be true and the process flow will be executed in the True path. The reason for all rules that are evaluated as True, will be added as comma separated values and set as a single value in the context variable *ruleReason* in the format *ruleName* (*ruleReason*).

If the rules are evaluated using the *AND* (&&) rule operator, then only if all the listed rules are true, then the decision value will be true and the process flow will be executed in the True path. Even if one rule is evaluated to false, then the decision value will be false and process flow will execute in the False path. The reason for all rules that are evaluated as True, will be added as comma separated values and set as a single value in the context variable *ruleReason* in the format *ruleName* (*ruleReason*). The rules that are evaluated as False, will appear as an empty value in the *ruleReason* context variable.

### **DEFINING SEQUENCE FLOW ORDERING**

When more than one sequence flow is attached with an activity, the transition that was dragged first will be executed before the transition dragged later. You can specify the ordering of the execution of the transitions.

#### Steps to define sequence flow ordering

1. Right-click the activity in the Graph Canvas to which more that one sequence flow is attached and select Sequence Flow Ordering (see Figure 17.72).




Figure 17.72: Define Sequence Flow Ordering

2. The Sequence Flow Ordering screen is displayed (see Figure 17.73).



Sequence flow Orderi	ng	×
Sequence Flows		
Sequence Flow Label	Destination Label	Û
Sequence Flow1	ExcelSchema	0
Sequence Flow 2	Target	
	Done	Cancel

Figure 17.73: Sequence Flow Ordering

- 3. Select the required activity and move it using **Up** ( $\widehat{\mathbf{b}}$ ) and **Down** ( $\frac{1}{\mathbf{b}}$ ) arrow buttons to define the sequence.
- 4. Click **Done** button to return to the Graph Canvas.

### **CREATING MULTIPLE STREAMS**

Stream represents the flow of data in a process flow. Multiple streams are used when the output of an activity needs to be sent to two or more activities in a process flow.

#### Steps to create multiple streams for an activity

1. Right-click the activity in the Graph Canvas from which multiple streams are to be generated and then select **Multiple Streams**. The Multiple Stream Dialog screen is displayed (see Figure 17.74).



Multiple Stream Dialo	g				×
Stream Name Entry					
Stream name :				Add Stre	eam
Stream And Activity Ma	pping				
Streams Activities	EvalScript_Text 💌 EvalPD_FileSource 💌		Ma	ар	
Stream Information Tab					
🔊 💦 🍭					
Stream Name	Error Stream	Stream Consum		Explici	it Stream
EvalScript_TextSche		EvalXform_Map	ping		
				Done	Cancel

Figure 17.74: Multiple Stream Dialog Box

- In the Stream Information Table, the existing stream is displayed. If you want to delete the existing stream, click on the stream to select it and then click **Delete** Stream (<sup>10</sup>) button. The selected stream is deleted.
- 3. To create a new stream, enter the name for the Stream in the *Stream Name* field and then click **Add Stream** button. The name of the added Stream is displayed in the *Streams* drop-down list (see Figure 17.75).



Multiple Stream Dialo	g		×
-Stream Name Entry-			
Stream name :			Add Stream
Stream And Activity Ma	pping		
Streams Activities	Data1	Ma	ap
Stream Information Tab			J.
🛞 💦 🍭			
Stream Name	Error Stream	Stream Consumer A	
Data1			
			Done Cancel

Figure 17.75: New Stream Added

- 4. The Activity which will consume the stream currently selected in the *Streams* dropdown list is already displayed, however to change it, select the activity from the *Activities* drop-down list, and then click **Map** button. The mapped stream and the activity are displayed in the *Stream Information Table* (see Figure 17.76).
- 5. Ensure that the *Explicit Stream* checkbox is checked.



Multiple Stream Dialo	g			×
Stream Name Entry				
Stream name :				Add Stream
-Stream And Activity Ma	pping			
Streams Activities	Data1 💌 EvalXform_Map 💌		Ma	ар
Stream Information Tab				
19 N Q	~			
Stream Name	Error Stream	Stream Consum		Explicit Stream
Data1		EvalXform_Map	ping	
				Done Cancel

#### Figure 17.76: Stream Created



If you are creating an error stream check the Error Stream checkbox.

- 6. Repeat steps 4 to 6 to create another stream.
- 7. Click **Done** button to return to the Graph Canvas. The created streams are displayed in the Graph canvas by data objects Artifact (see Figure 17.77).






Figure 17.77: Showing Multiple Streams in Process Flow

The Artifacts are only to show the flow of streams therefore it is necessary to add the activities with appropriate flows. If user deletes a stream from the Multiple Stream Dialog box, then the corresponding Artifacts are also deleted. If an Artifact representing a stream is deleted then the stream is also deleted. Process Designer asks user if he/she wants to delete the underlying stream.

To hide the Artifacts, click **View** in the menu bar and uncheck the *Show Artifacts and Associations* option.

The Multiple Stream feature can be used in three scenarios:

Creating more than one Stream

When data from one stream is sent to more than one activity, you can create more than one stream. However, more than one stream can be created only with the selected activities. These activities are Mapping Transformation, Scripted Service, Repeater Service, XML Validator and Decoder.



A Mapping activity does not always generate multiple streams. It is based on the schemas used in the mapping activity.

Creating Error Stream

If a source or target schema is not compliant with the corresponding source or target data, then the process flow execution will generate error records. Sometimes these error records are useful for users and user may want to store them for debugging. In such a case, error stream is created along with data stream. This error stream can be mapped to some other activity for further processing. For example, user may want to store the error records in a file target. To specify a stream as an error stream, check the *Error Stream* checkbox in the Multiple Stream Dialog Box. Error stream can be generated for Schema, Database source, Database target, Advanced Database target and XML Validator only.

Creating Default Stream



Sometimes an action, for example the Delay action, is used between two activities. In such type of situation data from the first activity does not pass to another activity because the action Delay does not consume data from the first activity and hence cannot pass it to another. To avoid this condition default stream is used.

#### Steps to create a default stream

- 1. Right click the first activity and select **Multiple Stream**. The Multiple Stream dialog box appears (refer to Figure 17.74).
- 2. Delete the existing stream.
- 3. Select another activity from the *Activities* drop-down list.
- 4. Click **Default Stream** ( ) button and then click **Map** button (see Figure 17.74).
- 5. Ensure that the *Explicit Stream* checkbox is checked.



Multiple Stream Dialo	g		×
-Stream Name Entry-			
Stream name :			Add Stream
Stream And Activity Ma	pping		
Streams	EvalScript_Text 💌		ap
Activities	EvalPD_FileSource 💌		°P
Stream Information Tab	ble		
🔅 💦 🍭			
Stream Name	Error Stream	Stream Consumer A	Explicit Stream
EvalScript_TextSche		EvalPD_FileSource	
			Done Cancel

Figure 17.78: Creating Default Stream

6. Click **Done** button to save the stream and return to Process Designer screen.

If you map a stream from a source activity to multiple activities (for example, Schema or Target activities) using the Multiple Stream option, only one target activity can get the stream from the source activity. The other target activities do not get the stream from the source activity and thus get aborted. This in turn aborts the process flow. It will only work if a gateway element is used in a process flow. This element will include a condition, on the basis of which one target activity can be selected at runtime. Another way is to use a Repeater Node to pass the stream to more than one activity. For details on using a Repeater Node, refer to the <u>Using</u>



Repeater Node section.

## USING STREAM SELECTOR

When more than one input stream is connected to an activity, Stream Selector is used to specify the input stream to be consumed by the activity. To understand the use of Stream Selector consider the following scenario (see Figure 17.79).




Figure 17.79: Scenario

In this process flow, you can see that two input streams are passed to the File Target. The desirable execution sequence is that first *File Source* will be executed then *File Target* and there after the *Gateway*. Now, if the condition specified at the *Gateway* is satisfied, the process flow will be finished. If the condition specified at *Gateway* is not satisfied, the control will be passed to the *File Source1* and further to *File Target*. Practically, when this process flow will be executed, the *File Target* activity will get confused whether to take input from *File Source or from File Source1*. Thus, this process flow will fail.

To avoid such a situation, **Stream Selector** is used. Streams from *File Source* and *File Source1* are passed to Stream Selector and then from Stream Selector to the *File Target*. The use of Stream Selector is displayed in Figure 17.80.




Figure 17.80: Stream Selector

Stream Selector takes input from the activity, which has just executed. If *File Source* has executed before the execution of stream selector, it will take input from *File Source*. If *File Source1* has just executed, it will take input from *File Source1*.

#### Steps to use a Stream Selector



- 1. Click tree structure in the **Repository View** panel. Expand the **Activities** list of the Adeptia Server and select **Selector**. A list of selector activities is displayed.
- 2. Click **Stream Selector Service** and drag it to the Graph Canvas. The Stream Selector Service node is displayed in the Graph Canvas area (see Figure 17.81).




Figure 17.81: Drag Stream Selector to Graph Canvas

3. Connect the required activities with the Stream Selector Service node (see Figure 17.82).




Figure 17.82: Connect Activities with Stream Selector Node

### **USING REPEATER NODE**

Repeater node is used when output of one activity is sent to more than one activity. For example, data from a file source is sent to two file targets.

#### Steps to use a Repeater Node

- 1. Click tree structure in the **Repository View** panel. Expand the **Activities** list of the Adeptia Server and select the **Repeater Node**. A list of repeater node activities is displayed.
- 2. Select the **Repeater Service** under Repeater Node and drag it to the Graph Canvas. A Repeater Service node is displayed in the graph canvas (see Figure 17.83).



Start Event	FileSource	Repeate rServic e	FileTarget	End Event
			FileTarg et1	

Figure 17.83: Repeater Service Node

3. Connect all activities with appropriate control flows in the Graph Canvas (see Figure 17.84).





Figure 17.84: Connect Activities



- 4. To create multiple streams, right click **Repeater Service** and select **Multiple Stream**. The Multiple Stream Dialog Box is displayed.
- 5. Enter number of streams in the *Enter Stream Count* field and click **Add Stream** button. Since we have two outputs from repeater node, enter 2 in the *Enter Stream Count* field.
- 6. Select 1 from the *Stream* drop-down list and select the first activity, which will consume the stream from the *Repeater Node*, from the *Activities* drop-down list.
- 7. Click **Map** button. The stream created is displayed in the *Stream Information Table*.
- 8. To create second stream, select 2 from the *Stream* drop-down list and select another activity, which will consume another stream from *Repeater Node* from *Activities* drop-down list.
- 9. Click **Map** button. The second stream is displayed in the *Stream Information Table* (see Figure 17.85).



Multiple Stream Dialo	g				×
-Stream Count Entry					
Enter stream count(1 to	100):			Add Stre	am
Stream And Activity Ma	pping				
Streams Activities	2 💌		Ma	β	
Stream Information Tab	ble				
ی 🔧 🛞					
Stream Name	Error Stream	Stream Consum	er A	Explici	t Stream
1		EvalPD_FileTarg			
2		EvalPD_FileTarg	jeti		
				Done	Cancel

Figure 17.85: Create Second Stream

10. Click **Done** button to save the streams created and return to the Graph Canvas. The created streams are displayed in the Graph Canvas by Artifact (see Figure 17.86).




Figure 17.86: Repeater Node with Multiple Stream



### **USING ERROR INTERMEDIATE EVENT**

Error Intermediate Event is used to redirect Process Flow execution to an alternate path in case of failure of any activity during process flow execution. To understand the use of Error Intermediate Event consider the following scenario:




Figure 17.87: Scenario

In this process flow, data from a text file is converted to an excel file using schema and mapping activities. Now if the Mapping activity is critical for your business, you may want be notified, if mapping activity fails during process flow execution.

To handle this situation you can attach **Error Intermediate Event** with mapping activity so that, in case mapping activity fails, a notification activity is executed and sends an email to the specified email address. Use of Error Intermediate Event is displayed in the Figure 17.88




Figure 17.88: Use Error Intermediate Event

#### Steps to use Error Intermediate Event

1. Right-click the activity with which you want to attach the intermediate event and select **Add Intermediate Event** option (see Figure 17.89).




Figure 17.89: Select Add Intermediate Event

2. This attaches the Intermediate Event to the selected activity (see Figure 17.90).





Figure 17.90: Error Immediate Event Attached

3. Drag another activity, which needs to be executed in case of failure of Mapping activity, to the Graph Canvas Area (see Figure 17.91).




Figure 17.91: Drag Another Activity

4. Connect the Error Intermediate Event to Mail Notification activity and then Mail Notification activity to End Event (see Figure 17.92).



Figure 17.92: Connect Activities

While connecting Error Intermediate Event with Mail Notification activity, please ensure that you are connecting Error Event with Mail Notification not the Mapping activity with Mail Notification.

## **CREATING EXCEPTION HANDLER SCRIPT**

Exception Handler scripts are basically Java code, which is invoked, if any exception or error occurred during execution of a process flow. There are three types of Exception Handler Scripts:

- Service Exception
- Process Flow Exception
- Invalid Data Exception

These Exception Handler Scripts can be created at a global level (for all the activities in the Process Flow) or at the activity level (for a specific activity). If an exception or errors during the execution of a process flow, the activity level exception handler script is invoked first. If the activity level exception handler script is not created for that activity, then only the global level exception handler script is invoked.

These Exception Handlers are invoked at different stages of the process flow. These are depicted in the table below.



<b>T</b>     <b>1T 0 1</b>				D =
Table 17 24	Exception	Handlers	in a	Process Flow
	EXCODUTION	rianaroro		1100000011010

Service Exception	This exception handler script is invoked when any error related service (activity) occurs. For example: File not found, Stream closed etc.
Process Flow Exception	This exception handler script is invoked when any error occurs at Process Flow level. The Exception can only be declared at global level. For example: JMX not found, Repository not found etc.
Invalid Data Exception	This exception handler script is invoked when any error related to processing of data occurs. For example: Incorrect record format etc.

### **Creating Global Exception Handler Script**

#### Steps to create a Process Flow (Global) Exception Handler Script

1. Click **On Exception Scripts** tab (<sup>(S)</sup>) in the Bottom Pane. The Create Exception Handler screen is displayed (see Figure 17.93).





Figure 17.93: Creating Exception Handler Script

2. Click **Edit Service Exception**. The Service Exception dialog box is displayed (see Figure 17.94).



A ServiceException Dialog	×
Enter the exception handler java code (Press CTRL + SPACE for template):	
1	<u> </u>
	Done Cancel

Figure 17.94: Service Exception Dialog Box



3. Enter the Java code in the *Service Exception* dialog box and click **Done** button.

### Creating Activity Exception Handler Script

#### Steps to create an Activity Exception Handler Script

- 1. Right-click the activity in the Graph Canvas and select **Service Exception Dialog**. The Service Exception Dialog Box is displayed (see Figure 17.94).
- 2. Enter the Java code in the *Service Exception* field and click **Done** button.



You can use **<CTRL>+<Space Bar>** to view examples of Java Condition. **<CTRL>+<Space Bar>** show lists of example. You can select any of them



and edit it according to your requirement.

If you want to create Invalid Data Handler script, right-click the activity and select **Invalid Data Exception Dialog**.

## USING COMPRESSION/DECOMPRESSION

Compression is used to compress any file into ZIP, RAR or JAR file. Similarly, Decompression is used to extract file from a ZIP, RAR or ZAR file. This feature supports Compression or Decompression of only one file.

#### Steps to use Compression/Decompression

- 1. Drag the required file source activity in the Graph Canvas area.
- 2. Click tree structure in the **Repository View** panel. Expand the **Activities** list of the Adeptia Server and select **Compression Service**. A list of compression service activities is displayed.
- 3. Select **Compression** and drag it to the Graph Canvas area (see Figure 17.95).

Start Event	FileSource	Compres sion	End Event
-------------	------------	--------------	-----------

Figure 17.95: Drag Compression Activity

- 4. Drag the required target activity to the Graph Canvas area.
- 5. Connect all activities in Graph Canvas with **Unconditional Control flow** as displayed in Figure 17.96.



Figure 17.96: Connect Activities

6. Right-click the **Compression** activity and select **View Properties**. Properties of the Compression activity are displayed in the Properties Panel (see Figure 17.97).



250       250       255       255       255       255       265       265       265       265       265       265       265       265       265       265       265       275       265       275       265       275   <						
Name	Value					
FieName						
10						
	Compression					
	Compression					
ource EvaPO_PileSource						
streamNames	Compression					
	true 🗸					
Type	Compression					

Figure 17.97: Compression Activity Properties

7. Enter the name of the file, which will be within the compressed file, in the *Filename* field.




Name specified in the File Target activity will be the name of the compressed target file.

Similarly you can use Decompression feature.

### USING CUSTOM REPORT IN PROCESS FLOW

A custom report is used to send generated report (in PDF or HTML formats) to a file based target (in PDF or HTML formats).





In this process flow, data from a text file is converted to an excel file using the schema and mapping activities. The data generated in the excel file is converted to PDF/HTML format using a custom report and sent to a file target.

#### Steps to use a Custom Report

- 1. Click tree structure in the **Repository View** panel. Expand the **Activities** list of the Adeptia Server and select **Reports**. A list of reports is displayed.
- 2. Select the **Custom Report** and expand it to view the custom reports. Select the desired custom report and drag it to the Graph Canvas. The Custom Report node is displayed in the graph canvas (see Figure 17.99).





Figure 17.99: Custom Report Node

3. Connect all activities with appropriate control flows in the Graph Canvas as displayed below (see Figure 17.100).




Figure 17.100: Connect Activities

4. Executing this process flow will send generated report to the file target.

## ATTACHING END PROCESS (MAIL NOTIFICATION) TO PROCESS FLOW

Attaching End Process adds a Mail Notification activity at the end of the process flow. Mail Notification is used to send e-mail to appropriate users at the certain point in process flow.

#### Steps to Attach a Mail Notification at the end of Process Flow

1. In the Graph Canvas, right-click at the **End BPMN** element and then select the **View Properties**. The properties of the End BPMN element are displayed in the Properties Panel (see Figure 17.101).




Figure 17.101: Attaching End Process

2. Click **End Process Value** column and select *True* from the drop-down list. The Select Notification screen is displayed with list of mail notification activities (see Figure 17.102).



Select Notification	×
Mail Notification	
EvalRec_MailNotification	
select cancel	

Figure 17.102: Selecting Mail Notification

3. Select the required mail notification activity and click **Select** button. The selected mail notification activity is attached at the end of the process flow.



To know, how to create Mail Notification activity, refer to the <u>Creating</u> <u>Mail Notification activity</u> section.

## **GENERATING PDF FILE OF PROCESS FLOW**

The process flow information can be saved into a PDF file for documentation purposes. There are three types of PDF files that can be generated from Process Designer.

- **Graph PDF:** Graph PDF only contains the screen shot of the Process Flow created in Graph Canvas area.
- **Summary PDF:** Summary PDF contains activity details of the Process Flow. It is implemented only for mapping and schema.
- Entire Flow PDF: Entire Flow PDF contains information regarding each and every activities of the Process Flow. List of information contained in the Entire Flow PDF is as below.

#### Process Flow Details



- Process Flow Name
- Process Flow ID
- Process Flow Description
- Creation Date
- Modification Date
- Debug Level
- Group Owner

#### Process Variable Details

- Key or Name of the Variable
- Initial Value
- Type (Global or Activity)
- Activity Name (If the Type is activity)
- Activity Label used in Process Designer
- Activity Type

#### Graph Canvas Entity

- Name
- Description
- User Owner
- Group Owner
- Creation Date
- Modification Date
- Permission
- Comment
- Label
- Inbound Connecting Objects
- Outbound Connecting Objects
- Activity Specific Information

For example, path of the source file in case of File Source activity, information of fields in case of Schema Activity or mapxmlfile in case of Mapping Activity.

#### Process Flow Graph

#### Steps to generate a PDF file of a Process Flow

1. In Process Designer, click **Generate PDF** (<sup>1</sup>/<sub>2</sub>) button. The PDF Generation dialog box is displayed (see Figure 17.103).



PDF Generation					
Select PDF Type?					
Graph PDF	Summary PDF	Entire Flow PDF	Cancel		

Figure 17.103: Select PDF Type

2. Select the type of PDF file to be generated. A *Graph PDF* includes all the rules applied on all activities in the process flow. A *Summary PDF* includes only the activity details, and is implemented only on mapping and schema. The *Entire Flow PDF* includes all details of the process flow. The Save box appears to select the path, where PDF file will be saved (see Figure 17.104).

🛓 Save		×
Save in:	Ay Documents	💌 🤌 🔛 📰
My Recent Documents Desktop My Documents My Computer	<ul> <li>Acrobat 6 Pro</li> <li>Address Book</li> <li>Adobe Photoshop CS 8.0</li> <li>Downloads</li> <li>My Albums</li> <li>My Art</li> <li>My DVDs</li> <li>My Google Gadgets</li> <li>My Music</li> <li>My Pictures</li> <li>My Received Files</li> <li>My Scans</li> <li>My Shapes</li> </ul>	My Sharing Folders My Videos Outlook Express 1 Outlook Express_backup PageMaker 7.0 Picture Motion Browser SnagIt Catalog Software SunJava Symantec Antivirus Corporate Editio Signapointment letter.pdf Signapointment letter.pdf Signapointment letter.pdf Signapointment letter.pdf
- <b>S</b>	File name: customer	Save
My Network Places	Files of type: pdf	▼ Cancel

Figure 17.104: Save Box

- 3. Select the path and enter the name of the file in the *File Name* field.
- 4. Click **Save** button. The generated PDF file is saved in the specified folder.

## WORKING WITH PROCESS DESIGNER IN OFFLINE AND ONLINE MODES

The Adeptia Server Process Designer allows user to work in offline mode. A user can design a process flow even if he/she is not connected with the Adeptia Server. At any moment user can



switch from Offline mode to Online and vice versa. The Online mode or Offline mode status is displayed in the bottom left side of the Process Designer window.

#### Steps to switch to the Offline mode

1. Click **Modes** menu and then click **Online** option. The checkmark displayed next to the Online mode is removed and you will be shifted to the Offline mode (see Figure 17.105).

File Edit Actions Modes View Smulls	9201 Help	
😸 Designer 😸 s Online 🖡 xet.		
🕒 🗰 🖻 🖓 🔘 🗔	○ ◆ ◆ C 元 ○ + 0 □ ○ ○ ○ □ □ ○ ○ ○ ○ ○ ○ ○ ○ ○ ○ ○ ○ ○	
BPHIN Activities Panel	ត្រួម ខ្លាំង អាមេរិយនៃ អាមេរិយន៍ អាមេរិយនេះ អ	k.
		-
		_
	E-100	
J		
Activities Panel		
Native Service      Notification	and fare from	
🖲 🔩 Poling	Event Event	
RecordQueaeProducer     RecordQueaeProducer	239	
E- 🥐 Repeaterfiede		
8 🔐 Scherna 8 🛟 Salactor		
B C Source		٤
		ſ
ContextTarget     E -40 Database Target	Conservations 🚫 Creditionaphilon Strates 💫 Alerts 🛅 Process Row Variables 📃 Comments	
File Target     File Target     FileTarget	Pad Process False	
EvalVF_FileTarget_E	Label End Event	
EvaPF_FileTarpet_1     EvaPF_FileTarpet_1		
EvalSolpt_FileTarget     EvalSolpt_FileTarget     EvalSolen_FileTarget		
- C FTP Target		
HTTP Target		
WebdavTarpet 💌		
Status: Offline		-

Figure 17.105: Changing Mode

While working in the Offline mode, you cannot save the Process Flow on the Adeptia Server. You can save the Process Flow on your local hard disk.
 Users working in the Offline mode cannot see objects e.g. activities and process flows etc that other users create on Adeptia Server. To view those objects, shift to the Online mode. Click the Actions menu and then select Synchronize PD with Adeptia Server.

When switching to Online mode, you need to login again.

#### Steps to switch to the Online mode

1. Click **Modes** menu and then click **Online** option. The Process Designer Login screen is displayed (see Figure 17.106).



Process Designer Login Screen 🛛 🗙						
Enter user id:	admin					
Enter password:	1; ****					
Enter host:	adeptia1					
Enter port:	8080					
Submit Cancel						

Figure 17.106: Process Designer Login

2. Enter the User ID and the password in their respective fields and click **Submit**. This activates the online mode for the Process Designer screen. If the user belongs to more than one group, then the Select Group screen is displayed (see Figure 17.107).

Select Group					
Select Group Select the group for the entered u Transport OK Cancel					

Figure 17.107: Select User Group



The *Group* drop-down list is populated with only those groups of which the logged in user is a member.

3. Select the group from the *Group* drop-down list and click **OK**. This activates the online mode for the selected user.

## **EXECUTING A PROCESS FLOW**

Once you have created a process flow, you can execute it, in order to process the data. You can execute a process flow in two ways:

- Manually
- Automatically

### **Executing a Process Flow Manually**

Steps to execute a Process Flow manually



- 1. In the Adeptia Suite homepage menu, click **[+] Design** to expand the tree. All the items in the **Design** category are displayed.
- 2. Click [+] Process Flow to expand the tree and then click Process Flow. The Manage Process Flow screen is displayed (refer to Figure 17.4).
- 3. Select the radio button adjacent to the required process flow and click **Execute** link. The process flow execution screen is displayed (see Figure 17.108).

Request submitted for EvalRec\_ProcessFlow execution at Tue Apr 06 18:14:28 IST 2010. See the <u>Process Flow Logs</u> for execution details.

#### Figure 17.108: Process Flow Executed

4. To view the status of execution of the process flow, click **Process Flow Logs** link. The Process Flow Log screen is displayed (see Figure 17.109).

Refresh   View Process flow log								
Activity Name	Activity Type	Status	UserID	Start Time	2	End Time	Ac	tion
EvalRec_JMSTarget	JmsTarget	Running	demouser	04/06/2010 15:	53:23 N	IA.	Details	Diagnostic
EvalRec_PositionalSchema1	SchemaIntermediate2StreamTransformer	Executed	demouser	04/06/2010 15:	53:22 0	4/06/2010 15:53:23	Details	Diagnostic
RecordData	ContextSource	Executed	demouser	04/06/2010 15:	53:22 0	4/06/2010 15:53:22	Details	Diagnostic
Scripted-Guard	Condition	Executed	demouser	04/06/2010 15:	53:22 0	4/06/2010 15:53:22	Details	Diagnostic
Scripted-Guard	Condition	Executed	demouser	04/06/2010 15:	53:22 0	4/06/2010 15:53:22	Details	Diagnostic
EvalRec_Record2Record	ScriptedRecord2RecordTransformer	Running	demouser	04/06/2010 15:	53:22 N	A	Details	Diagnostic
EvalRec_PositionalSchema	SchemaStream2IntermediateTransformer	Executed	demouser	04/06/2010 15:	53:21 0	4/06/2010 15:53:22	Details	Diagnostic
EvalRec_FileSource	FileSource	Executed	demouser	04/06/2010 15:	53:20 0	4/06/2010 15:53:20	Details	Diagnostic
EvalRec_ProcessFlow	Transaction	Running	demouser	04/06/2010 15:	53:20 N	IA.	Details	Diagnostic

Figure 17.109: View Process Flow Log

- If the process flow is still running you can click *Refresh* to view the updated information of the process flow execution.
  - To view the process flow log of other process flows, click *View Process Log* link. The process flow log page is displayed.
  - To learn more about Process Flow Log refer to the *Viewing Process Flow Logs* section in the *Business User Guide*.

### **Executing a Process Flow Automatically**

You can execute a process flow automatically based on some events. For example, when you receive an email in your mailbox, the process flow can be executed. For this, you need to bind an event (for example, a mail event) with the process flow. You can either bind an existing event or create a new event and then bind it with a process flow.

#### Steps to execute a process flow automatically



- 1. In the Adeptia Suite homepage menu, click **[+] Design** to expand the tree. All the items in the **Design** category are displayed.
- 2. Click [+] Process Flow to expand the tree and then click Process Flow. The Manage Process Flow screen is displayed (refer to Figure 17.4).
- 3. Select the radio button adjacent to the required process flow and click **BindEvent** link. The Create Event Registry screen is displayed (see Figure 17.110).

Design > Events & Triggers > Event Registry					
[-] Standard properties					
Name *					
Description *					
Select Event Info*					
O Use Existing	SELECT				
C Create New	SELECT Create Event				
Process Flow Name *	EvalXform_ProcessFlow (Process Flow to transfer)				
[+] Advanced properties					
* Mandatory fields.					
Save Cancel					

Figure 17.110: Create Event Registry

- 4. Enter the name and description of the event registry in their respective fields.
- 5. To bind an existing event to the process flow, select the *Use Existing* radio button, and select the event from the drop-down list. Else, to bind a new event to the process flow, select the *Create New* radio button. Select the event type from the drop-down list, and then click **Create Event** button. This displays the Create Event screen for the selected event type. For example, if you select Mail Event from the drop-down list, then clicking Create Event button, displays the Create Mail Event screen.
- 6. Enter the required parameters and click **Save** in the Create Event screen to save the event activity and bind it to the process flow and return the control to Manage Process Flow screen.

For details, on creating an event, refer to **Events and Triggers** section.

### USAGE RECOMMENDATION

Following points should be kept in mind while working in Process Designer:



- User can View or change Process Flow properties from Process Flow Attribute in Actions menu.
- While working in Process Designer, user can login with different username or can switch to other Adeptia Server. To login with other username or switch to other Adeptia Server, select Enter Login Information from Actions menu. If you switch to another Adeptia Server, you must have an account to another Adeptia Server and that account must have permission to use Process Designer.



For details, on different user types, refer to the User section in the Administrator Guide.

• Process Designer allows multiple object deletion. More than one activity can be selected by dragging mouse pointer and deleted collectively.



# **18** CREATING TRIGGER AND EVENTS

Trigger Events are used to schedule and trigger a process flow. Trigger Events enable you to specify when and how frequently the process flow should be executed on a recurring basis. The types of trigger events are outlined as:

- Calendar Event
- Database Event
- Event Registry
- File Event
- FTP Event
- HTTP Trigger
- JMS Event
- Mail Event
- Timer Event
- Web Service Trigger

By default, a trigger event remains deactivated after its creation. To trigger a process flow using the trigger events, you must bind it with appropriate trigger events and then activate those events.

### **CREATING CALENDAR EVENT**

This service enables you to specify the recurring execution of process flow between the specified dates in conjunction with a specified calendar.

In the Adeptia Suite this feature is available in:

BPM Suite	Integration Suite	ETL Suite
$\checkmark$		$\checkmark$

#### Steps to create a Calendar Event

- 1. In the Adeptia Suite homepage menu, click **[+] Deploy** to expand the tree. All the items in the **Deploy** category are displayed.
- 2. Click [+] Events & Triggers to expand the tree and then click Calendar. The Manage Calendar Event screen is displayed (see Figure 18.1).



[+]	My Tasks	Deploy > Events	& Triggers > Calendar					
[+]	My Documents							
[+]	My Solutions	New   Edit   Delete	Revisions   Dependencies		Select Field to Search			Search
[+]	My Monitor	New   coit   Delete	Revisions   Dependencies		select Field to search			Search
[+]	History	Activate   Trigger No	w					
		#	Name	Description	n PF	Owner	Perm.	Modified 🔻
[+]	Design			No records found				
[+]	Configure							
[-]	Deploy							
	[-] Events & Triggers							
	🗊 Calendar							
	<b>⇒0</b> Database							

Figure 18.1: Manage Calendar Event

3. Click the **New** link. The Create Calendar Event screen is displayed (see Figure 18.2).

Deploy > Events & Triggers > Calendar				
[-] Standard properties				
Name *				
Description *				
Event Start Date (mm/dd/yyyy)				
Time (hh:mm)	Hours  Mins			
Event Expiry Date (mm/dd/yyyy)				
Time (hh:mm)	Hours V Mins V			
Firing Days *	AllDays			
Firing Schedule* (* - No Constraint)	Sec Mins Hrs DOM Mon DOW Year			
[+] Advanced properties				
* Mandatory fields.				
Save Cancel				

Figure 18.2: Create Calendar Event

- 4. Enter the name and description of the new Calendar Event activity in the *Name* and *Description* fields respectively.
- 5. Enter the date from which Calendar event will start triggering; in the *Event Start Date* field. The date must be in *mm/dd/yyyy* format. Click the calendar icon to select the required date from the calendar.
- 6. Enter the start time from the *Time* drop-down list.
- 7. Enter the date on which Calendar event will stop triggering, in the *Event Expiry Date* field. The date must be in *mm/dd/yyyy* format. Click the calendar icon and select the required date from the calendar.
- 8. Enter the expiry time from the *Time* drop-down list.
- 9. Select the days of week on which the event should fire from the *Firing Days* drop-down list.



Types of firing days are described in the table below.

Table	18.1:	Types	of	Firina	Davs
1 abio		1,000	0.	1 11 11 19	Days

Days	Description
All Days	The event will fire on all days (Mon to Sun) of the week.
Business Days	The event will fire from Monday to Friday excluding holidays. To know how to specify holidays, refer to the <i>Business Calendar</i> section of <i>Appendix A</i> in <i>Administrator Guide</i> .
Week Days	The event will fire from Monday to Friday even if there are any holidays.

10. Define the frequency of execution in the *Firing Schedule* fields.




- 11. Click Save button. This displays a screen confirming that the Calendar event has been created successfully. If the *Comments* property is enabled, then clicking **Save** will display a screen where you need to enter comments for creating the calendar event (refer to Figure 3.6).
- 12. Enter the comments in the Add Comments field.

Ø
V

The comment should be at least 1 character in length.

13. Click **OK** to save the comments. This displays a screen confirming that the calendar event has been created successfully.

By default, the Comments property is disabled. To enable it, refer to the Updating System Properties section in Administrator Guide.



You can view details of a process flow associated with a calendar event, by clicking the process flow displayed under Associated Process Flows on the Manage Calendar Event screen.

## CREATING DATABASE EVENT

The Database Event enables you to schedule a process flow to be triggered when a record is inserted, updated or deleted in a database table.

In the Adeptia Suite this feature is available in:

BPM Suite	Integration Suite	ETL Suite
-----------	-------------------	-----------



$\checkmark$	$\checkmark$	
--------------	--------------	--

#### Prerequisites:

• Database Info activity must be created before creating Database Event activity.

#### Steps to create a Database Event

- 1. In the Adeptia Suite homepage menu, click **[+] Deploy** to expand the tree. All the items in the **Deploy** category are displayed.
- 2. Click **[+] Events & Triggers** to expand the tree and then click **Database**. The Manage Database Event screen is displayed (see Figure 18.3).

Ŀ	· · · · · · · · · · · · · · · · · · ·	Deploy > Ev	ents & Triggers > Databas	se				
Ŀ	+] My Documents							
Ŀ	+] My Solutions	New   Edit   D	elete   Revisions   Dependenci	esSelect Field to S	Search	~		Search
ŀ	+] My Monitor	incer   cont   b	elete   Kethiolis   Sependenci					ocurcii
ŀ	+] History	Activate   Trig	ger Now					
		#	Name	Description	PF	Owner	Perm.	Modified 🔻
ŀ	+] Design			No records found				
ŀ	+] Configure							
ŀ	] Deploy							
	[-] Events & Triggers							
	🗈 Calendar							
	Database							
	Event Registry							
	📑 File							

Figure 18.3: Manage Database Event

3. Click the **New** link. The Create Database Event screen is displayed (see Figure 18.4).



Deploy > Events & Triggers > Databas	56
[-] Standard properties	
Name *	
Description *	
Database Info*	SELECT
Define Database Polling Criteria	<b>_</b>
Denne Database Ponnig Chtena	
SQL Query	<b>X</b>
Trigger For All Records	
Check Condition	
Operator	Select -
Value	
O SQL Trigger	
SQL Trigger Name*	
Event Start Date (mm/dd/yyyy)	
Time (hh:mm)	Hours 🔽 Mins 💌
Event Expiry Date (mm/dd/yyyy)	
Time (hh:mm)	Hours V Mins V
Polling Frequency *	Frequency Duration Select One
[+] Advanced properties	
* Mandatory fields.	
Save Cancel	
Save Callcel	

Figure 18.4: Create Database Event

4. Enter the name and description of the new Database Event activity in the *Name* and *Description* fields respectively.



5. Select the Database Info Id activity from the *Database Info Id* drop-down list.

Ø

To learn how to create Database Info activity, refer to the section *Creating Database Info* in *Administrator Guide*.

6. You can create the database event definition by entering an SQL Query or a database trigger command. By default, *SQL Query* option is selected. Enter the query in the *SQL Query* field. Mark the *Check Condition* checkbox as checked, if you want to trigger the process flow based on a condition. The result of the query will be compared with a conditional value, and the process flow will be triggered, if the values match. Select the operator for the query from the *Operator* drop-down list. Enter the value to be compared in the query returns multiple records, then only the first record is accepted. If the query returns one record, then it will compare the value of the first field with the value specified in the *Conditional Value* field. If the value matches, then the process flow is triggered. If the value does not match, then the system simply logs an error. It does not trigger the process flow.

Ø

If the *Check Condition* checkbox is marked as unchecked, then the process flow is triggered each time a row is returned.

In case *Trigger for All Record* checkbox is checked, then for all the records, only one process flow is trigger and it processes all the records.

7. Alternately, enter the database trigger command in the *SQL Trigger* field.

Ø	Following is the format of trigger used to trigger the process flow:
	<trigger text=""></trigger>
	INSERT INTO dbeventtriggertable VALUES ('Query = <where clause="">');</where>
	END <trigger name=""> ;</trigger>
	Edit the parts, which are within < >. You can define a 'Where' clause that indicates the row that is updated. When the command is parsed, it will return the updated row from the database source.
	Do not delete the Insert query.
	<trigger name=""> after the END tag should be used for Oracle only. In case of SQL server, <trigger name=""> is not needed.</trigger></trigger>
	Following is the example of the trigger used for SQL Server :
	create trigger Trigger_test on emp for
	insert,update
	as
	declare @empname varchar(20)
	begin
	set @empname=(select empname from inserted);
	INSERT INTO dbeventtriggertable VALUES ('Query =WHERE empname=''' +@empname+'''');



END ;
Following is the example of the trigger used for Oracle:
CREATE OR REPLACE TRIGGER Trigger\_test
AFTER INSERT OR UPDATE ON Emp FOR EACH ROW BEGIN INSERT INTO dbeventtriggertable VALUES ('Query = where rowid= ' || :new.rowid ); EN D Trigger\_test;
Here :
Trigger\_test is name of the trigger.
Emp is the name of the user table on which insert or update operation has to be done.
dbeventtriggertable is the name of the temporary table used. Do not change it.

- 8. Enter the name of Trigger in the *SQL Trigger Name* field.
- 9. Enter the date from which Database event will start triggering; in the *Event Start Date* field. The date must be in *mm/dd/yyyy* format. Click calendar icon and select the required date from the calendar.
- 10. Enter the start time from the *Time* drop-down list.
- 11. Enter the date on which Database event will stop triggering, in the *Event Expiry Date* field. The date must be in *mm/dd/yyyy* format. Click the calendar icon and select the required date from the calendar.
- 12. Enter the expiry time from the *Time* drop-down list.
- 13. Enter the time interval, the database event checks the database Server in the *Polling Frequency* field. Enter the digit in the Frequency field and select the unit of time i.e. seconds, minutes or hours etc from the *Duration* drop-down list.



Recommended minimum Polling Frequency is 30 seconds. To learn about Advanced Properties refer to <u>Changing Advanced</u> <u>Properties</u> section.

- 14. Click **Save** button. This displays a screen confirming that the database event has been created successfully. If the *Comments* property is enabled, then clicking **Save** will display a screen where you need to enter comments for creating the database event (refer to Figure 3.6).
- 15. Enter the comments in the *Add Comments* field.



The comment should be at least 1 character in length.

16. Click **OK** to save the comments. This displays a screen confirming that the database event has been created successfully.



By default, the *Comments* property is disabled. To enable it, refer to the *Updating System Properties* section in *Administrator* Guide.



Ø

You can view details of a process flow associated with a database event, by clicking the process flow displayed under *Associated Process Flows* on the Manage Database Event screen.

# **CREATING EVENT REGISTRY**

In the Adeptia Suite this feature is available in:

BPM Suite	Integration Suite	ETL Suite
$\checkmark$	$\checkmark$	$\checkmark$

#### Steps to Register a Process Flow with a Trigger Event

- 1. In the Adeptia Suite homepage menu, click **[+] Deploy** to expand the tree. All the items in the **Deploy** category are displayed.
- 2. Click [+] Events & Triggers to expand the tree and then click Event Registry. The Manage Event Registry screen is displayed (see Figure 18.5).

[+]	My Tasks	D	eplo	y > Events & Triggers > Event Regis	stry				
[+]	My Documents								
[+]	My Solutions	Ne	ew I F	Edit   Delete   Revisions   Dependencies		Select Field to Se	arch 🗙		Search
[+]	My Monitor								
[+]	History								
		#		Name	Descript	ion	Owner	Perm.	Modified 🔻
[+]	Design	1	0	InventoryItemsEventRegister	register to inventory items pa	rt 2	demouser	RWX	08/08/09 11:34
[+]	Configure	2	0	PurchasOrderEventRegister	register file event to purchase	e order flow	demouser	RWX	08/07/09 16:30
[-]	Deploy	з	0	OrderFulfillmentEventRegister	register email event to fulfillm	ent flow	demouser	RWX	08/07/09 14:51
	[-] Events & Triggers	4	~	EmployeeBenefitEventRegister	register file event to benefits		demouser	RWX	08/07/09 14:42
	p Calendar	4	0	EmployeeBenefitEventKegister	•		demouser	RWA	08/07/09 14:42
	<b>⇒0</b> Database	5	0	EvalJMSE_EventRegistry	Event Resigtry to bind EvalJM EvalJMSE_ProcessFlow	ISE_JMSEvent and	demouser	RWX	08/16/05 19:39
	R Event Registry	6	$\bigcirc$	EvalPF_MailEventRegistry_Format1	mail event registry for format:	1	demouser	RWX	07/26/05 15:43
	📑 File	7	0	EvalPF_MailEventRegistry_Format2	mail event registry for format	2	demouser	RWX	07/23/05 17:42
	FTP								
	¦≇ НТТР								
	🖾 JMS								

Figure 18.5: Manage Event Registry

3. Click the **New** link. The Create Event Registry screen is displayed (see Figure 18.6).



Design > Events & Triggers > Event Registry		
[-] Standard properties		
Name *		
Description *		
Select Event Info*		
O Use Existing	SELECT	
C Create New	SELECT 💌	Create Event
Process Flow Name *	customer (cust)	•
[+] Advanced properties		
* Mandatory fields.		
Save Cancel		

Figure 18.6: Create Event Registry

- 4. Enter the name and description of the new Event Registry activity in the *Name* and *Description* fields respectively.
- 5. Select the required Events activity.

To learn how to create event activity, refer to <u>Creating Trigger and</u> <u>Events</u> section.

- 6. To select an existing event activity, select the *Use Existing* radio button and select the event activity from the drop-down list.
- 7. To create a new event activity, select the *Create New* radio button, select the event type from the drop down list and then click **Create Event** button. This displays the selected *Create Event* screen.
- 8. Enter the required parameters and click **Save** in the Create Event screen to save the event activity and return to Create Event Registry screen.
- 9. Select the required Trigger Event from the *Event Name* drop-down list.
- 10. Select the required process flow from the Process Flow Name drop-down list.

To learn about Advanced Properties refer to section Changing Advanced Properties section.

- 11. Click **Save** button. This displays a screen confirming that the event registry has been created successfully. If the *Comments* property is enabled, then clicking **Save** will display a screen where you need to enter comments for creating the event registry (refer to Figure 3.6).
- 12. Enter the comments in the *Add Comments* field.



The comment should be at least 1 character in length.

13. Click **OK** to save the comments. This displays a screen confirming that the event registry has been created successfully.



0	By default, the Comments property is disabled. To enable it, refer to the
Ø	Updating System Properties section in Administrator Guide.

# **CREATING FILE EVENT**

The File Event enables you to specify when and how frequently a process flow should be executed based on either creation of a new file, or existence of a file(s) in a pre-defined location or upon its modification.

In the Adeptia Suite this feature is available in:

BPM Suite	Integration Suite	ETL Suite
$\checkmark$		$\checkmark$

#### Steps to create a File Event

- 1. In the Adeptia Suite homepage menu, click **[+] Deploy** to expand the tree. All the items in the **Deploy** category are displayed.
- 2. Click [+] Events & Triggers to expand the tree and then click File. The Manage File Event screen is displayed (see Figure 18.7).

[+]	My Tasks	Deploy > Ev	ents & Triggers > File					
[+]	My Documents							
[+]	My Solutions	New   Edit   De	elete   Revisions   Dependencies	Select Field to Sea	rch 💌			Search
[+]	My Monitor	incli   cole   be	liete   Kensions   Bependendes					ocurcii
[+]	History	Activate   Trigg	ger Now					
		#	Name	Description	PF	Owner	Perm.	Modified <b>*</b>
[+]	Design	1 🔿 🔞 Cheo	ckForPurchaseOrderFiles	check for new purchase order files	View	demouser	RWX	11/24/09 14:27
[+] [-]	Configure Deploy	2 🔿 🔞 Cheo	ckForEmployeeBenefitFiles	check for new benefits file	View	demouser	RWX	11/24/09 14:26
	[-] Events & Triggers							
	Calendar							
	<b>⇒0</b> Database							
	R Event Registry							
	🗊 File							
	E FTP							

Figure 18.7: Manage File Event

3. Click the **New** link. The Create File Event screen is displayed (see Figure 18.8).



Deploy > Events & Triggers > File	
[-] Standard properties	
Name *	
Description *	
Trigger Type *	On FileCreated 💌
File Include Criteria *	
File Exclude Criteria	
File Base Location *	
Use VFS *	
Secure	
User Id *	
Password	
Confirm Password	
Event Start Date (mm/dd/yyyy)	
Time (hh:mm)	Hours V Mins V
Event Expiry Date (mm/dd/yyyy)	
Time (hh:mm)	Hours 💌 Mins 💌
	Frequency Duration
Polling Frequency *	Select One 💌
File Stable Time *	Select One 💌
[+] Advanced properties	
* Mandatory fields.	
Save Cancel	

Figure 18.8: Create File Event

4. Enter the name and the description of the new File Event activity in the *Name* and *Description* fields respectively.



5. Select the trigger type from *Trigger Type* drop-down list. The effect on the selection is listed in the table below.

Trigger Type Selection	Description
On FileCreated	To configure the file event to check for the creation of a new file(s).
On FileExists	To configure the file event to check for the existence of the file(s)
On FileModified	To configure the file event to check for any modification in file(s)

- 6. Enter the file name that the file event needs to verify, in the *File Include Criteria* field.
- 7. Enter the name of file that file event does not need to verify, in the *File Exclude Criteria* field. For example \*.txt is entered in *File Include Criteria*, but two files *Gdata.txt* and *Gdata1.txt* file are not required to be verified by File Event. Then *Gdata.txt* and *Gdata1.txt* file name need to be entered separated by comma in *File Exclude Criteria* field. To specify more than one file in *File Include Criteria* and *File Exclude Criteria*, you can use regular expressions listed in the table below.

Table 18.3: Expressions used in File Include Criteria and File Exclude Criteria

Expression	Description
* *	For all files with some extension
*	For all files in a directory
a*.txt	For files starting with a and having extension txt (e.g. arch.txt)
a?????.txt	For files starting with a and have 6 more character followed by txt extension (e.g. archive.txt)
a[1-9]	For a1, a2 ,a3a9
b[aiu]t	For bat, bit or but
a.txt, a.doc	For two files named as a.txt and a.doc



If more than one file is specified in the *File Include Criteria* field, process flow will triggered for each file.

#### 8. Enter the path of file in File Base Location field. Example c:/Gmdata



You can also use regular expression for folders, in *File Include Criteria* and *File Exclude Criteria* field. For example, if you enter  $h^*/*.txt$  in *File Include Criteria* field and *C:/Gmdata* in *File Base Location* field, it will search for all .txt file inside all directories which starts from h under C:\Gmdata.

9. When Adeptia Server is installed on Windows Operating System, File Event uses windows service to connect to remote machine to access any file. It just connects once and uses the



same connection with the same User ID and Password (which is stored in the cache) every time. If you want to enforce the validation of User ID and Password every time while accessing the file on a remote machine, check *Use VFS* checkbox.

- 10. If the File Event is secured i.e. username and password are required to access it, then check the *Secure* checkbox and enter the username and password required to access the file in the *User ID* and *Password* fields respectively. This option is applicable only when the file specified is located on a remote machine.
- 11. Enter the date from which file event will start triggering, in the *Event Start Date* field. The date must be in *mm/dd/yyyy* format. Click calendar icon and select the required date from the calendar.
- 12. Enter the start time from the *Time* drop-down list.
- 13. Enter the date on which file event will stop triggering, in the *Event Expiry Dat*e field. The date must be in *mm/dd/yyyy* format. Click calendar icon and select the required date from the calendar.
- 14. Enter the expiry time from the *Time* drop-down list.
- 15. Enter the time interval for which file event will check for the arrival of any file or upon modification of existing file in the *Polling Frequency* field. Enter the digit in the *Frequency* field and select the unit of time i.e. seconds, minutes or hours etc from the *Duration* drop-down list.



Recommended minimum Polling Frequency is 30 seconds.

16. Enter the file stable time in the *File Stable Time* field. This is applicable only when user selects On FileCreated or On FileModified in trigger type. Trigger will wait for the specified time for the file to become stable.



To learn about Advanced Properties refer to <u>Changing Advanced</u> <u>Properties</u> section.

- 17. Click **Save** button. This displays a screen confirming that the file event has been created successfully. If the *Comments* property is enabled, then clicking **Save** will display a screen where you need to enter comments for creating the file event (refer to Figure 3.6).
- 18. Enter the comments in the *Add Comments* field.



The comment should be at least 1 character in length.

19. Click **OK** to save the comments. This displays a screen confirming that the file event has been created successfully.



By default, the *Comments* property is disabled. To enable it, refer to the *Updating System Properties* section in *Administrator* Guide.



You can view details of a process flow associated with a file event, by clicking the process flow displayed under *Associated Process Flows* on the Manage File Event screen.



## **CREATING FTP EVENT**

The FTP Event enables you to specify when and how frequently a process flow should be executed based on either creation of a new file, or existence of a file(s) on a FTP Server or upon its modification.

In the Adeptia Suite this feature is available in:

BPM Sui	ite Integratio	on Suite ETL Suite
$\checkmark$	$\checkmark$	

#### Steps to create a FTP Event

- 1. In the Adeptia Suite homepage menu, click **[+] Deploy** to expand the tree. All the items in the **Deploy** category are displayed.
- 2. Click [+] Events & Triggers to expand the tree and then click FTP. The Mange FTP Event screen is displayed (see Figure 18.9).

[+]	My Tasks	Deploy > Eve	nts & Triggers > FTP					
[+]	My Documents							
[+]	My Solutions	New   Edit   Del	ete   Revisions   Dependencies	Select F	ield to Search 🔽			Search
[+]	My Monitor	new prote poet	ete   Revisions   Dependencies	Delecci				ocurci
[+]	History	Activate   Trigge	er Now					
		# 🎲	Name	Description	PF	Owner	Perm.	Modified <b>*</b>
[+]	Design	1 🔘 🔞 FTP_E	ivent	Test	None	demouser	RWX	07/20/10 11:19
[+]	Configure	2 🔿 🙆 Check	ForInventoryItemsFiles	check for inventory csv files	View	demouser	RWX	09/01/09 12:31
[-]	Deploy							
	[-] Events & Triggers							
	🗈 Calendar							
	<b>⇒0</b> Database							
	Event Registry							
	🕞 File							
	E FTP							
	🏗 НТТР							

#### Figure 18.9: Manage FTP Event

3. Click the **New** link. The Create FTP Event screen is displayed (see Figure 18.10).



Deploy > Events & Triggers > FTP		
[-] Standard properties		
Name *		
Description *		
Host name *		
Port *	21	
User Id *		
Password		
Confirm Password		
Transfer Type *	PASSIVE -	
Trigger Type *	On FileCreated	
SSH FTP (SFTP) *		
FTP Over TLS/SSL (FTPS) *		
FTPS Mode	Explicit 💌	
Protection Level	Clear 💌	
Validate Server	<b>—</b>	
Keystore Name	SELECT 💌	
File Include Criteria *		Define List
File Exclude Criteria		
File Base Location *		
Event Start Date (mm/dd/yyyy)		
Time (hh:mm)	Hours 💌 Mins 💌	
Event Expiry Date (mm/dd/yyyy)		
Time (hh:mm)	Hours 💌 Mins 💌	
	Frequency Duration	
Polling Frequency *	Select One 💌	
File Stable Time *	Select One 💌	
[+] Advanced properties		
* Mandatory fields.		
Save Cancel		

Figure 18.10: Create FTP Event



- 4. Enter the name and description of the new FTP Event in the *Name* and *Description* fields respectively.
- 5. Enter the name and port number of the FTP Server in the *Host Name* and *Port* field respectively.
- 6. Enter username and password required to access FTP Server in the *User ID* and *Password* fields respectively. Then, re-enter the password in the Confirm Password field.
- 7. Select the transfer type as either *Active* or *Passive* from the *Transfer Type* drop-down list. Active transfer is more secure since the client only initiates communication to the server on one port whereas in case of Passive transfer the client initiates communication to the Server over two ports. Passive mode is useful when you are behind a firewall or a proxy.
- 8. Select the trigger type from the *Trigger Type* drop-down list. For details of the selection, refer to Table 18.2.
- 9. Check the *SSH FTP (SFTP)* checkbox if the FTP Server specified in the *Host Name* field is an FTP Server over SSH.
- 10. Check the *FTP Over TLS/SSL (FTPS)* checkbox, if the FTP Server, specified in the *Host Name* field is an FTP Server over TLS/SSL.
- 11. Incase you have selected *FTP Over TLS/SSL (FTPS)*, checkbox, then select the FTPS mode from *FTPS Mode* drop-down list. It can be *Explicit* or *Implicit* depending on FTP Server that you are accessing.
- 12. Select the protection level supported by the FTP Server, from the *Protection Level* dropdown list. It can be *Clear* or *Private*.
- 13. If you want to validate the certificate sent by the FTPS Server, check the *Validate Server* check box.
- 14. Select keystore activity from the *Keystore Name* drop-down list. This option is applicable only when you have checked the *Validate Server* checkbox.

When *Validate* option is unchecked, it always accepts the certificate sent by FTPS Server.
When this option is checked, it validates the certificate sent by FTPS server against the certificate imported in Keystore.
Keystore is repository of security certificates.
To know how to create Keystore and import certificates, refer to *Creating Keystore* secton of *Administrator Guide*.

15. Enter the name of file that FTP event needs to verify, in the File Include Criteria field.

In File Include Criteria and File Exclude Criteria you can also give the folder name along with the file name. For example suppose you have entered *C:\Gmdata* in *File Base Location* field. There are two sub-folders *Purchase* and *Purchase1* in *Gmdata* folder. Now suppose you don't know whether the file is in *Purchase* or *Purchase1* folder. To handle this scenario you can define File Include Criteria as defined below:
 Purchase/\*.txt,Purchase1/\*.txt.
 You can also use regular expression in the folder name as given below:



Pur\*/\*.txt This path includes both the folder *Purchase* and *Purchase1*. If you have large number of paths that need to be define, you can also use *Define List* option.

16. To define path in *File Include Criteria*, click *Define List* button. The *File Include Criteria List* screen is displayed (see Figure 18.11).

٢	🖇 Add/Remove File	Include Criteria - Windows Internet Explorer	_ 0	X
		File Include Criteria List		1
	File Include Criteria		Add to List	
		Save Cancel		

Figure 18.11: Add Include Criteria List

17. To add path enter the path in *File Include Criteria* field and click *Add to List* button. The added path are shown in *File Include Criteria List* (see Figure 18.12).

¢	Add/Remove File Include Criteria - Microsoft Internet Explorer	IX
Г		-
L	File Include Criteria List	
	File Include Criteria Add to List	
L	File Include Criteria List (Select checkbox to remove file include criteria from list)	
	C:\Purchase\Stationary\DVD\*.txt	
	C:\Purchase\Stationary\*.txt	
L	C:\Purchase\Systems\*.xls	
L	C:\Purchase\Systems\LCD\*.xls	
	Save Cancel	

- Figure 18.12: File Include Criteria List
- 18. Click *Save* button to save the added path in *File Include Criteria* field. The added paths are populated in the *File Include Criteria Field* in the *Create FTP Event* page.



If you want to remove some path form the *File Include Criteria*, Check the checkbox adjacent to the required path and then click *Save*. The selected path is not populated in the *File Include Criteria* field of the *Create FTP Event* page.

19. Enter the name of file that file event does not need to verify, in the *File Exclude Criteria* field. For example \*.*txt* is entered in *File Include Criteria*, but two files *Gdata.txt* and *Gdata1.txt* file are not required to be verified by FTP Event. Then *Gdata.txt* and *Gdata1.txt* file name need to be entered separated by comma in *File Exclude Criteria* field. To specify more than one file in *File Include Criteria* and *File Exclude Criteria*, you can also use regular expressions. These are listed in Table 18.3



If more than one file is specified in the *File Include Criteria* field, process flow will triggered for each file.

- 20. Enter the path of file in *File Base Location* field. Example c:/Gmdata.
- 21. Enter the date from which FTP event will start triggering, in the *Event Start Date* field. The date must be in *mm/dd/yyyy* format. Click calendar icon and select the required date from the calendar.
- 22. Enter the start time from the *Time* drop-down list.
- 23. Enter the date on which FTP event will stop triggering, in the *Event Expiry Date* field. The date must be in *mm/dd/yyyy* format. Click the calendar icon and select the required date from the calendar.
- 24. Enter the expiry time from the *Time* drop-down list.
- 25. Enter the time interval for which FTP event will check for the arrival of any file or modification of existing file in the *Polling Frequency* field. Enter the digit in the Frequency field and select the unit of time i.e. seconds, minutes or hours etc from the *Duration* drop-down list.




Recommended minimum Polling Frequency is 30 seconds.

26. Enter the file stable time in the *File Stable Time* field. This is applicable only when user selects On FileModified in trigger type. Trigger will wait for the specified time for the file to become stable.



To learn about Advanced Properties refer to <u>Changing Advanced</u> <u>Properties</u> section.

- 27. Click **Save** button. This displays a screen confirming that the FTP event has been created successfully. If the *Comments* property is enabled, then clicking **Save** will display a screen where you need to enter comments for creating the FTP event (refer to Figure 3.6).
- 28. Enter the comments in the *Add Comments* field.



29. Click **OK** to save the comments. This displays a screen confirming that the FTP event has been created successfully.



Ø
---

By default, the *Comments* property is disabled. To enable it, refer to the *Updating System Properties* section in *Administrator* Guide.

You can view details of a process flow associated with a FTP event, by clicking the process flow displayed under *Associated Process Flows* on the Manage FTP Event screen.

# CREATING HTTP TRIGGER

The HTTP trigger enables you to schedule a process flow to be triggered when an HTTP request is made to Adeptia Server. It also allows the request to pass the data to the process flow. The trigger can be used by a HTTP client application to integrate with process flow, deployed on the Adeptia Server.


In the Adeptia Suite this feature is available in:

BPM Suite	Integration Suite	ETL Suite
$\checkmark$		$\checkmark$

#### Steps to create a HTTP Trigger

- 1. In the Adeptia Suite homepage menu, click **[+] Deploy** to expand the tree. All the items in the **Deploy** category are displayed.
- 2. Click [+] Events & Triggers to expand the tree and then click HTTP. The Manage HTTP Trigger screen is displayed (see Figure 18.13).

[+]	My Tasks	Deploy > Eve	ents & Triggers > HTTP					
[+]	My Documents							
[+]	My Solutions	New   Edit   De	elete   Revisions   Dependencies	Select Field	to Search	~		Search
[+]	My Monitor							
[+]	History	Activate   Trigg	jer Now					
		#	Name	Description	PF	Owner	Perm.	Modified 🔻
[+]	Design			No records found				
[+]	Configure							
[-]	Deploy							
	[-] Events & Triggers							
	🖻 Calendar							
	<b>⇒()</b> Database							
	Event Registry							
	📑 File							
	☐ FTP							
	🏗 НТТР							
	🖂 JMS							



3. Click the **New** link. The Create HTTP Trigger screen is displayed (see Figure 18.14).



Deploy > Events & Triggers > HTTP	
[-] Standard properties	
Name *	
Description *	
[+] Advanced properties	
* Mandatory fields.	
Save Cancel	

Figure 18.14: Create Http Trigger

4. Enter the name and description of the new HTTP Trigger activity in the *Name* and *Description* fields respectively.

- 5. Click **Save** button. This displays a screen confirming that the HTTP event has been created successfully. If the *Comments* property is enabled, then clicking **Save** will display a screen where you need to enter comments for creating the HTTP event (refer to Figure 3.6).
- 6. Enter the comments in the *Add Comments* field.

The comment should be at least 1 character in length.

7. Click **OK** to save the comments. This displays a screen confirming that the HTTP event has been created successfully.



By default, the *Comments* property is disabled. To enable it, refer to the *Updating System Properties* section in *Administrator* Guide.

You can view details of a process flow associated with a HTTP event, by clicking the process flow displayed under *Associated Process Flows* on the Manage HTTP Event screen.

### Usage Recommendation

To read the context variable, within a process flow following steps are required:

1. While creating the process flow, create a process flow variable. To know, how to create Process Flow Variable, refer to the section <u>Creating Process Flow Variable</u>.



- Use this process flow variable as Context Source within process flow. To know, how to use a Process Flow Variable as Context Source, refer to the section <u>Using Context Source</u> and Context Target.
- 3. Change the value of the Property Event Context Enabled to yes.
- 4. Post the data using your HTTP client application to the following URL:

http:// <servername>:<serverport>/adeptia/receiveservlet?activityID</serverport></servername>
<pre>=<entityid>&amp;userID=<loginname>&amp;password=<loginpassword>&amp;grou</loginpassword></loginname></entityid></pre>
p=IndigoGroup: <group id=""></group>

where

ServerName	: Name of the server where Adeptia Server is running
ServerPort	: Port at which Adeptia Server is running. By default, it
	is 8080.
EntityID	: 30 digit ID of the HTTP Trigger activity. To view
	Entity ID of the HTTP Trigger, click View in the HTTP
	Trigger Page.
LoginName	: User ID of the Adeptia Server
LoginPassword	: Password of the Adeptia Server
Group ID	: 30 digit ID of the group, the user belongs to. To view
	Group ID of the group, click View in the Manage group
	page.

### **CREATING JMS EVENT**

The JMS Event enables you to specify when and how frequently the process flow should be executed if any message is updated in a queue or topic of a JMS Server.

In the Adeptia Suite this feature is available in:

BPM Suite	Integration Suite	ETL Suite
$\checkmark$	$\checkmark$	

#### Prerequisites:

• *JMS Provider* activity must be created before creating *JMS Event* activity.

#### Steps to create a JMS Event

- 1. In the Adeptia Suite homepage menu, click **[+] Deploy** to expand the tree. All the items in the **Deploy** category are displayed.
- 2. Click [+] Events & Triggers to expand the tree and then click JMS. The Manage JMS Event screen is displayed (see Figure 18.15).



[+]	My Tasks	Deploy > Events & Trigger	s > JMS						
[+]	My Documents								
[+]	My Solutions	New   Edit   Delete   Revisions	Dependencies		Select Field to Sear	ch 🔽	1		Search
[+]	My Monitor History	Activate   Trigger Now							
[+]	nistory	# 💮 Nar		Descrip	tion	PF	Owner	Dorm	Modified <b>*</b>
[+]	Design								
[+]	Configure	1 🔘 🔞 EvalJMSE_JMSEvent		JMS Event to trigger Process	s Flow	view	demouser	KWX	10/04/05 13:23
[-]	Deploy								
	[-] Events & Triggers								
	11 Calendar								
	<b>⇒</b> ] Database								
	Exent Registry								
	📑 File								
	E FTP								
	🏗 НТТР								
	🖾 JMS								

- Figure 18.15: Manage JMS Event
- 3. Click the **New** link. The Create JMS Event screen is displayed (see Figure 18.16).

Deploy > Events & Triggers > JMS	
[-] Standard properties	
Name *	
Description *	
JMS Provider*	EvalRec_JMSProvider (JMS Provider to connect)
Connection Type*	TOPIC
Durable Subscriber	
SubscriberID	
Queue Or Topic Name *	
MessageSelector	
UserName	
Password	
Confirm Password	
[+] Advanced properties	
* Mandatory fields.	
Save Cancel	

Figure 18.16: Create JMS Event

4. Enter the name for the new JMS Event in the *Name* field. Then, enter the description for the JMS Event in the *Description* field.



5. Select the JMS Provider activity from the *JMS Provider* drop-down list.



To learn how to create JMS Provider activity, refer to the section *Creating JMS Provider* in *Administrator Guide*.

- 6. Select the Connection Type as either *Topic* or *Queue* from the *Connection Type* drop-down list.
- 7. Check the *Durable Subscriber* check box if the JMS Subscriber is durable. If a client needs to receive all the messages published on a topic, including the ones published while the subscriber is inactive, it uses a Durable Subscriber. This is applicable only when the connection type is Topic.
- 8. Enter the subscriber ID in the *Subscriber ID* field.
- 9. Enter the name of queue or topic as configured in the JMS Server in the *Queue Or Topic Name* field.
- 10. If you want to select a specific message from the JMS Server, enter the message selector in the *Message Selector* field.

The message selector is used to specify the filter criterion to receive a message that the user is interested in. The messages can be filtered based on only header references and properties references of the message. The message selector uses SQL92 query syntax to define the filter criteria. SQL92 is widely used to query the entire standard databases i.e. Oracle, SQL Server. The only difference between the database query and the message selector query is that the message selector uses, only a part of the query which is after the where clause.
 The following message selector selects messages with a message type of car and color of blue and weight greater than 2500 pounds:
 JMSType = 'car' AND color = 'blue' AND weight > 2500
 The following message selector selects message with the property Sport has value either as Basketball or Football.
 Sport in ('Basketball', 'Football')

11. Enter the username and password required to connect to JMS Server in the *UserName* and *Password* fields respectively. Then, re-enter the password in the *Confirm Password* field.



To learn about Advanced Properties refer to <u>Changing Advanced</u> <u>Properties</u> section.

- 12. Click **Save** button. This displays a screen confirming that the JMS event has been created successfully. If the *Comments* property is enabled, then clicking **Save** will display a screen where you need to enter comments for creating the JMS event (refer to Figure 3.6).
- 13. Enter the comments in the Add Comments field.



The comment should be at least 1 character in length.



14. Click **OK** to save the comments. This displays a screen confirming that the JMS event has been created successfully.



By default, the *Comments* property is disabled. To enable it, refer to the *Updating System Properties* section in *Administrator* Guide.



You can view details of a process flow associated with a JMS event, by clicking the process flow displayed under *Associated Process Flows* on the Manage JMS Event screen.

## CREATING MAIL EVENT

The Mail Event allows you to schedule a process flow to be triggered when a specified mail arrives on the mail Server.

In the Adeptia Suite this feature is available in:

BPM Suite	Integration Suite	ETL Suite
$\checkmark$		

#### Steps to create a Mail Event

- 1. In the Adeptia Suite homepage menu, click **[+] Deploy** to expand the tree. All the items in the **Deploy** category are displayed.
- 2. Click [+] Events & Triggers to expand the tree and then click Mail. The Manage Mail Event screen is displayed (see Figure 18.17).

[+]	My Tasks	Deploy > Eve	ents & Triggers > Mail						
[+]	My Documents								
[+]	My Solutions	New   Edit   De	lete   Revisions   Dependencies		Select Field to Sear	ch 🔽	1		Search
[+]	My Monitor								
[+]	History	Activate   Trigg	er Now						
		# 🌼	Name	Descrip	otion	PF	Owner	Perm.	Modified 🔻
[+]	Design	1 🔘 🍓 Trigge	erOrderFulfillment	look for new emails		View	demouser	RWX	09/01/09 12:33
[+]	Configure	2 🔘 🔞 EvalP	PF_MailEvent_Format1	Mail event for format1		View	demouser	RWX	09/01/06 15:03
[-]	Deploy	3 O G EvalP	PF_MailEvent_Format2	Mail event for format2		View	demouser	RWX	09/01/06 15:03
1	<ul> <li>Events &amp; Triggers</li> </ul>								
	📁 Calendar								
	Database								
	Event Registry								
	🗊 File								
	FTP								
	🏗 НТТР								
	🖾 JMS								
	🖂 Mail								

#### Figure 18.17: Manage Mail Event

3. Click the **New** link. The Create Mail Event screen is displayed (see Figure 18.18).



[-] Standard properties Name * Description * Protocol *	POP3 V	]
Description *	POP3	] ]
	POP3	]
Protocol *	POP3 -	
Incoming Mail Server *		]
Domain		
CDO host machine		
Enable SSL		
Port	110	
UserId		]
Password		
Confirm Password		
Search based on following filter crite	ria *	
Sender E-mail		🗖 ignoreCase
Mail Subject		🗹 ignoreCase
Mail Content		]
File Attachment		🗖 ignoreCase
Event Start Date (mm/dd/yyyy)		
Time (hh:mm)	Hours 💌 Mins 💌	
Event Expiry Date (mm/dd/yyyy)		
Time (hh:mm)	Hours 💌 Mins 💌	
Polling Frequency *	Frequency Duration Select One	
[+] Advanced properties		
Mandatory fields.		
Save Cancel		

Figure 18.18: Create Mail Event



- 4. Enter the name and description of the new Mail Event activity in the *Name* and *Description* fields respectively.
- 5. Select the Internet standard protocol to be used for retrieving incoming mails, from the *Protocol* drop-down list. You can select the POP3 protocol, IMAP4 protocol or the MAPI protocol. Based on the selected protocol, the default port number for that protocol is displayed in the Port field. The MAPI protocol is used to access mails on the Microsoft Exchange Server. It uses J-Integra as a bridge and uses a domain for exchanging mails, instead of a port. Thus, if the MAPI protocol is selected, then the port number field appears as disabled.
- 6. Enter the address of the incoming mail server in the *IncomingMail Server* field.
- 7. Enter the domain name that is configured for the Microsoft Exchange Server in the *Domain* field. This field appears as enabled only when the MAPI protocol is selected in the *Protocol* drop-down list.
- 8. Enter the host machine name on which CDO is installed and configured, in the *CDO Host Machine* field. This field appears as enabled only when the MAPI protocol is selected in the Protocol drop-down list. When Java applications use J-Integra to exchange mails on Micorosoft Exchange Server, then CDO serves as the intermediary between the Java application and Microsoft Exchange Server.
- 9. Check the *Secure* checkbox, if the specified incoming mail server is SSL enabled.
- 10. The default port number for the selected protocol is displayed in the Port field. If you want to change this port number, enter the new port number in the *Port* field. If MAPI protocol is selected, then the port number field appears as disabled.
- 11. Enter the username and password required to access the mail Server in the *User ID* and *Password* fields respectively. Then, re-enter the password in the Confirm Password field.
- 12. Select any of the following filter criteria:
  - Sender E-mail
  - Mail Subject
  - Mail Content
  - File Attachment

You may select more than one filter criteria.

13. Enter the sender's email address and subject of email in the *Sender Email* and *Mail Subject* fields respectively.



In *Sender E-Mail* field, you can define more than one email ids seprated by comma (,).

14. To define search based on mail content, enter the required content in *Mail Content* field.



You can also use asterisk and Wild Cards in Mail Content field.

15. Enter the name of the file attached with mail, in the *File Attachment* field.



Ø

You can define the *Sender E-Mail, Mail Subject* and *File Attachement* as case sensitive or insensitive by checking/unchecking the *Ignore Case* checkbox displayed next to the *Mail Subject* field.

- 16. Enter the date from which Mail event will start triggering; in the *Event Start Date* field. The date must be in *mm/dd/yyyy* format. Click calendar icon and select the required date from the calendar.
- 17. Enter the start time from the *Time* drop-down list.
- 18. Enter the date on which the Mail event will stop triggering; in the *Event Expiry Date* field. The date must be in *mm/dd/yyyy* format. Click the calendar icon and select the required date from the calendar.
- 19. Enter the expiry time from the *Time* drop-down list.
- 20. Enter the time interval, the Mail event will check for the existence of the mail, in the *Polling Frequency* field. Enter the digit in the *Frequency* field and select the unit of time i.e. seconds, minutes or hours etc from the *Duration* drop-down list.



[]]

Recommended minimum Polling Frequency is 30 seconds.

21. To specify maximum number of emails to be processed at a time, click **[+]** to expand Advanced Properties and enter the required value in the *Mail Process Concurrency* field.

If there is large number of emails in the mailbox, which meet the search criteria of the mail event, all the mails will be processed at a time. If you want to limit the number of emails to be process at a time with this event, enter the appropriate value in the *Mail Process Concurrency* field. Now mail event will process only the specified number of emails at a time. Remaining emails will be processed at the next polling frequency. Mails are processed on First In First Out (FIFO) basis.

To learn about Advanced Properties refer to <u>Changing Advanced</u> <u>Properties</u> section.

- 22. Click **Save** button. This displays a screen confirming that the mail event has been created successfully. If the *Comments* property is enabled, then clicking **Save** will display a screen where you need to enter comments for creating the mail event (refer to Figure 3.6).
- 23. Enter the comments in the Add Comments field.



The comment should be at least 1 character in length.

24. Click **OK** to save the comments. This displays a screen confirming that the mail event has been created successfully.



By default, the *Comments* property is disabled. To enable it, refer to the *Updating System Properties* section in *Administrator* Guide.



If a mail event is deactivated and then activated again, it will trigger an event for an existing email.

You can view details of a process flow associated with a mail event, by



clicking the process flow displayed under *Associated Process Flows* on the Manage Mail Event screen.

A mail event can trigger multiple process flows at a time. Each process flow uses a mail source. When multiple process flows use a mail source at a time, errors can occur. Thus it is advisable to limit the number of process flows triggered by a mail event. You can also set the number of retries and the sleep time between each retry, in case an error occurs when using a mail box. For details on these settings, refer to Appendix A in Administrator Guide.

# **CREATING TIMER EVENT**

The Timer Event enables you to specify the date, time and frequency at which a process flow should be executed.

In the Adeptia Suite this feature is available in:

BPM Suite	Integration Suite	ETL Suite
$\checkmark$		$\checkmark$

#### Steps to create a Timer Event

- 1. In the Adeptia Suite homepage menu, click **[+] Deploy** to expand the tree. All the items in the **Deploy** category are displayed.
- 2. Click [+] Events & Triggers to expand the tree and then click Timer. The Manage Timer Event screen is displayed (see Figure 18.19).

[+]	My Tasks	Deploy > Eve	ents & Triggers > Timer			
[+]	My Documents					
[+]	My Solutions	New   Edit   De	elete   Revisions   Dependencies	Select	Field to Search 💙	Search
[+]	My Monitor	New   Luit   De	nete   Revisions   Dependencies	Select		Search
[+]	History	Activate   Trigg	er Now			
		#	Name	Description	PF Owner Perr	n. Modified 🔻
[+]	Design			No records found		
[+]	Configure					
[-]	Deploy					
	[-] Events & Triggers					
	🗈 Calendar					
	<b>⇒</b> ] Database					
	Ex Event Registry					
	🕒 File					
	E FTP					
	🏗 НТТР					
	🖾 JMS					
	🖾 Mail					
	🐌 Timer					

#### Figure 18.19: Manage Timer Event

3. Click the **New** link. The Create Timer Event screen is displayed (see Figure 18.20).



Deploy > Events & Triggers > Timer	
[-] Standard properties	
Name *	
Description *	
Event Start Date (mm/dd/yyyy) *	
Time (hh:mm)	Hours 💌 Mins 💌
Expiry Criteria *	
Run only Once	
C Repeat Count	(number)
C Expiry By Date/Time	
Date (mm/dd/yyyy)	
Time (hh:mm)	Hours V Mins V
Frequency *	Count Duration Select One
[+] Advanced properties	
* Mandatory fields.	
Save Cancel	

Figure 18.20: Create Timer Event

- 4. Enter the name and description of the new Timer Event activity in the *Name* and *Description* fields respectively.
- 5. Enter the date from which the Timer event will start triggering, in the *Event Start Date* field. The date must be in *mm/dd/yyyy* format. Click the calendar icon to select the required date from the calendar.
- 6. Enter the start time from the *Time* drop-down list.
- 7. Select one of the *Expiry Criteria* displayed in the table below.


Table	18.4:	Expiry	Criteria
-------	-------	--------	----------

Expiry Criteria	Description
Run Only Once	Select this option if the process flow needs to be triggered only once.



Repeat Count	Select this option if the process flow needs to be triggered for given number of times. Enter the required number in the Repeat Count field. Progress flow is triggered Repeat Count + 1 times.
Expiry By Date/ Time	Select this option if the process flow needs to be triggered up to the given date and time on a given interval. To select the expiry date click on the calendar and select the required date. Select the expiry time using Hours and Mins drop-down list.

8. If *Repeat Count* or *Expiry By Date/Time* option is selected as expiry criteria, enter the time interval in the *Frequency* field.



- 9. Click **Save** button. This displays a screen confirming that the timer event has been created successfully. If the *Comments* property is enabled, then clicking **Save** will display a screen where you need to enter comments for creating the timer event (refer to Figure 3.6).
- 10. Enter the comments in the Add Comments field.



The comment should be at least 1 character in length.

11. Click **OK** to save the comments. This displays a screen confirming that the timer event has been created successfully.



By default, the *Comments* property is disabled. To enable it, refer to the *Updating System Properties* section in *Administrator* Guide.



You can view details of a process flow associated with a timer event, by clicking the process flow displayed under *Associated Process Flows* on the Manage Timer Event screen.

## TRIGGERING PROCESS FLOW USING WEB SERVICE TRIGGER

Web Service Trigger is an interface, which allows a Web Service client to trigger any process flow in Adeptia Server. The Web Service client needs to pass the ID of the process flow and any input parameters that need to be passed into the Process Flow.

To trigger a Process Flow, the Web Service client needs to know details of the Web Service published and format in which input parameter can be passed.

In the Adeptia Suite this feature is available in:

BPM Suite Integra	ion Suite ETL Suite
-------------------	---------------------



√ √	
-----	--

#### Steps to get the information required by Web Service Client to trigger a Process Flow

- 1. In the Adeptia Suite homepage menu, click **[+] Deploy** to expand the tree. All the items in the **Deploy** category are displayed.
- 2. Click [+] Events & Triggers to expand the tree and then click Web Service. The Web Service Trigger screen is displayed (see Figure 18.21).

[+]	My Tasks	Deploy > Events & Tri	aaers > Web Service
[+] [+]	My Documents My Solutions	Web Service Trigger allows	s triggering of any BPM Suite 5.1 process flow through Web Service client.
[+] [+]	My Monitor History	Web Service Trigger has fo	Ilowing details:
		WSDL URL:	http://127.0.0.1:8080/wsx/services/WsTrigger?wsdl
[+]	Design	Port Name:	WsTransactionTrigger
[+]	Configure	Service Name:	WsTrigger
[-]	Deploy	End Point:	http://127.0.0.1:8080/wsx/services/WsTrigger
	[-] Events & Triggers	Style:	document
	🗈 Calendar	Operation:	trigger
	<ul> <li>O Batabase</li> <li>k Event Registry</li> <li>F FIP</li> <li>FTP</li> <li>HTTP</li> <li>JMS</li> <li>Mail</li> <li>Timer</li> <li>Web Service</li> </ul>	Input XSD:	<pre><?xml version="1.0" encoding="UTF-8" ?><!-- W3C Schema generated by<br-->Adeptia Editor-&gt;<xsd:schema <br="" xmlns:xsd="http://www.w3.org/2001/XMLSchema">&gt;<xsd:element name="request"&gt;<xsd:complextype><xsd:sequence><xsd:element name="Transactionid" type="xsd:string" /&gt;<xsd:element maxOccurs="unbounded" minOccurs="0" name="Map"&gt;<xsd:complextype><xsd:sequence><xsd:element <br="" name="key">type="xsd:string" /&gt;<xsd:element <br="" name="value">type="xsd:string" /&gt;<xsd:element <br="" name="value">equence&gt;</xsd:element></xsd:element></xsd:element></xsd:sequence></xsd:complextype>equence&gt;</xsd:element </xsd:element </xsd:sequence></xsd:complextype></xsd:element </xsd:schema></pre>
[+]	Administer	Sample Input Document:	<pre><?xml version="1.0" encoding="ISO-8859-1"?><request xmlns:xsi="http://www.w3.org/2001/XMLSchema- instance"><transactionid>192168001138109626945685900003</transactionid><m ap="">name<value>Adeptia</value></m></request> </pre>
		Body Name space:	
		SOAP Action URI:	
		Schema Namespace URI:	xsd=http://www.w3.org/2001/XMLSchema

Figure 18.21: Web Service Trigger

- 3. This screen shows the details of the Web Service published. All the parameters needed by the Web Service client to invoke the service are displayed in this screen.
- 4. Use the WSDL URL and Sample Input Document displayed in the Figure 18.21 to trigger the Process Flow.
- 5. A Sample Input Document which is to be used to trigger the process flow is displayed below (see Figure 18.22).

```
<?xml version="1.0" encoding="ISO-8859-1"?><request
xmlns:xsi='http://www.w3.org/2001/XMLSchema-
instance'><Transactionid>192168001138109626945685900003</Transactionid>
<Map><Key>name</Key><value>Adeptia</value></Map></request>
```

Figure 18.22: Sample Input Document used to Trigger Process Flow


6. Make sure to replace the Transaction ID with the ID of the Process Flow, which is to be triggered.



Ø	

While creating the Web Service trigger, you need to ensure that Transport security type is selected, as this trigger does not support Message security type.

7. To pass the parameter to the process flow, enter the key(name) and the value of the parameter in the *Map* tag of the XML shown above.



### ACTIVATING TRIGGER EVENTS

#### Steps to Activate a Trigger Event

- 1. In the Adeptia Suite homepage menu, click **[+] Deploy** to expand the tree. All the items in the **Deploy** category are displayed.
- 2. Click [+] Events & Triggers to expand the tree and then click File. The Manage File Event screen is displayed with the list of existing events (see Figure 18.23).

Deploy > Ev	vents & Triggers > File					
New   Edit   D	elete   Revisions   Dependencies	Select Field t	o Search 🔽			Search
Activate   Trig	ger Now					
#	Name	Description	PF	Owner	Perm.	Modified 🔻
1 🔘 🌀 Che	ckForPurchaseOrderFiles	check for new purchase order files	View	demouser	RWX	11/24/09 14:27
2 🔘 🔞 Che	ckForEmployeeBenefitFiles	check for new benefits file	View	demouser	RWX	11/24/09 14:26



3. To activate the trigger event, select the radio button adjacent to the event and click **Activate**. A screen is displayed confirming the trigger event activity has been activated successfully.

### **TRIGGERING PROCESS FLOWS IN SEQUENCE**

Process Flows, which are binded with any event, are executed at every polling frequency irrespective of the fact that the process flow(s) triggered at the previous polling frequency still may be running.

Also there could be possibility that at each polling frequency, multiple process flows are executed. For Example a Process flow may be binded with a File Event, and at each polling frequency multiple files fulfill the trigger criteria. In this case for each file the binded process flow will be executed concurrently.

An advanced property *Trigger Process Flows in Sequence* is provided in all events to execute the prcess flows in sequence. You can check this checkbox, to allow process flows to be triggered in



sequence. For Example if a Process Flow is binded with a File Event, and at each polling frequency, suppose five files are fulfilling the trigger criteria. In this case the process flow is executed five times or you can say five instance of this process flow are executed in parallel. When *Trigger Process Flows in Sequence* is checked, then the process flow is executed five times, but in sequence. Means, when the execution of first instance will be completed, then only the execution of second instance will start. Now incase the next polling frequency comes before the completion of all the instances of the process flow triggered at the previous polling, then the process flow is completed, then the misfired event. Once the execution of all the instances of the process flow is fired. This should be noted that even if an event goes misfired multiple times, only one misfired event is fired at the completion of the previous execution.

#### Steps to enable "Trigger Process Flow in Sequence" property

1. Click [+] to exapnd the Advanced Properties of the Event. Advanced Properties of Event are displayed (See Figure 18.24).

[-] A	dvanced properties				
	Trigger Process Flows in Sequence				
	Owner*	admin (	Defau	lt Admi	nistrator) 💽
			Read	Write	Execute
Permissions*		Owner	$\checkmark$	✓	•
		Group	$\checkmark$		<b>V</b>
		Other			
* Mandat	* Mandatory fields.				
Save	Cancel				

Figure 18.24: Event's Advanced Properties

- 2. Check the Trigger Process Flow in Sequence checkbox.
- 3. Click *Save* to save the event.



# **19 RECOVERY**

Adeptia Suite has a recovery feature to automatically recover process flows, which are not executed completely due to Kernel shutdown. Kernel shutdown can occur due to following reasons:

- System is shutdown
- Kernel is stopped

When kernel restarts, all incomplete process flows which are recoverable are recovered.

## **RECOVERABLE PROCESS FLOWS**

You can make a process flow as **recoverable process flow** using one of the following options:

- Enabling Implicit Recovery
- Using Checkpoints
- Using Human Workflow activity

### Enabling Implicit Recovery

Implicit Recovery is a unique feature which means that the execution state of the process flow is recovered automatically in case the process flow is not executed completely due to some reasons. Now, when the kernel restarts, the process flow resumes execution from the point where it leaves.

Ø	•	Only, Synchronous activities are implicitly recoverable in the process flow. If asynchronous activities are used in process flow, they are made recoverable explicitly using check points. To know how to add checkpoint refer to the section <b>Using Actions in Process Flow</b>
	•	Actions such as Delay, Put Context Var do not have Implicit Recovery Implementation.
		Implicit recovery is supported for any level of parent-child relationship in the process flow. For a recoverable parent process flow, all its child process flows are implicitly made recoverable irrespective of whether the child process flow is configured as recoverable or not.

### Using Checkpoints

Process flows, which have checkpoints, are recoverable. Checkpoint is an action which can be used in a process flow during it creation. There can be any number of checkpoints in a process flow. Checkpoints should not be used after an asynchronous activity which is generating a source stream. Otherwise after recovery the source stream generated by asynchronous activity



will not available for the target activity which will be consuming this stream. To know how to add checkpoint refer to the section <u>Using Actions in Process Flow</u>.

### Using Human Workflow Activity

Process flows which use Human Work Flow activities, are recoverable. Human work flow activity itself acts as a checkpoint. To know how to add Human Workflow Activity in the process flow, refer to the section **<u>Creating Workflow Task</u>**.

### How Recovery Works

During execution of a process flow, at every checkpoint BPM Server stores the current state of the process flow in a recovery file. There is one recovery file for each execution of a process flow. These recovery files are stored in a recovery folder defined in the property *abpm.recovery.repository.root*. If kernel goes down during execution of process flow, recovery file will have the state of the process flow till the last checkpoint. If no checkpoint is reached, no recovery file is created and the process flow can never be recovered after failure. In the recovery file only state of the process flow is saved. Intermediate data of the process flows are stored in the repository folder. Once system is restarted and if recovery is enabled, BPM Server looks for the state of the uncompleted process flow in the recovery file, picks up the intermediate data from the repository file and resumes the process flow.

The recovery file, remains in the recovery folder unless the process flow execution is completed. The recovery of process flows cannot be completed if intermediate data are not available in repository folder. Intermediate data gets deleted automatically by Data Cleanup or user can delete it manually to free disk space. To know more about data cleanup, refer to the section **Data Cleanup**.

Even if recovery is not enabled, the recovery files created during execution of the process flows are stored in the recovery folder. But in this case recovery of the uncompleted process flows are not done. Later on if you want to recover those process flows, you need to enable recovery and restart the kernel. After Kernel is restarted, the uncompleted process flows are recovered.

### **ENABLING RECOVERY**

By default recovery is disabled. To enable the recovery, change the value of the property *abpm.transaction.recovery.enable* from no to yes. To know how to change the property, refer to the section **Updating BPM Server Properties**.

If Queue Processor is enabled, Queue Processor does the recovery. The property *abpm.transaction.recovery.enable* will not have any effect on recovery process. Queue processor tracks all the jobs (request for execution of process flows). If jobs are not completed in previous run, then queue processor will recover them automatically. To know more about Queue Processor, refer to the section <u>Load Management</u>.



# **20** ABOUT ADEPTIA INC.

Adeptia, an enterprise software company headquartered in Chicago, Illinois, provides a business process integration technology to easily and quickly automate business processes using industry-specific standards. Adeptia's unique product combines business process management with business-to-business integration. Adeptia's reusable and highly scalable technology has been deployed by Fortune 1000 companies. For more information, visit <u>http://www.adeptia.com</u>.

Adeptia Headquarters 443 North Clark St, Suite 350 Chicago, IL 60654 USA Email: info@adeptia.com

Adeptia India R&D Centre D-74, Sector 63, Noida, U.P. - 201301 India



# 21 TABLE OF FIGURES

Figure 3.1: Manage Web Forms	.15
Figure 3.2: Create Web Form	.15
Figure 3.3: Add/Remove Files	.17
Figure 3.4: Added File(s)	.17
Figure 3.5: Uploaded File(s)	.18
Figure 3.6: Enter Comments	.19
Figure 3.7: Design Form using Template	.21
Figure 3.8: Define Header	.21
Figure 3.9: Define Form	.22
Figure 3.10: Design Form Manually	.23
Figure 3.11: Sample HTML Code	.25
Figure 3.12: Sample Code for "review" Function	.26
Figure 3.13: Adeptia Rich Form	.27
Figure 3.14: Style Properties	.28
Figure 3.15: Sample Rich Form	.29
Figure 3.16: Activated Web Form	.30
Figure 4.1: Manage Workflow Task	.33
Figure 4.2: Create Workflow Task	
Figure 4.3: Advanced Properties of Workflow Task	.37
Figure 4.4: Task Manager	.39
Figure 4.5: Comments	.40
Figure 4.6: Re-assign Task	.41
Figure 4.7: Workflow Task	.42
Figure 4.8: File Upload	.42
Figure 4.9: File Uploaded	.43
Figure 4.10: View Attached File	.43
Figure 5.1: Manage Positional Data Dictionary	.46
Figure 5.2: Create Positional Data Dictionary	.46
Figure 5.3: Data Dictionary Record Builder	
Figure 5.4: Records created for the Positional Data Dictionary	.48
Figure 5.5: Edit Positional Data Dictionary	.49
Figure 5.6: Print Positional Data Dictionary Definition	.49
Figure 5.7: Download Positional Data Dictionary Definition	.50
Figure 5.8: Manage EDI Data Dictionary	
Figure 5.9: Create EDI Data Dictionary	.51
Figure 6.1: Manage Advanced Database Source	
Figure 6.2: Create Advanced Database Source	.54
Figure 6.3: Edit Query	.55
Figure 6.4: Manage Database Source	
Figure 6.5: Create Database Source	
Figure 6.6: Manage File Source	
Figure 6.7: Create File Source	.59
Figure 6.8: Manage FTP Source	
Figure 6.9: Create FTP Source	
Figure 6.10: Manage HTTP Source	
Figure 6.11: Create HTTP Source	



Figure 6.12: Manage JMS Source	
Figure 6.13: Create JMS Source	
Figure 6.14: Manage LAN File Source	
Figure 6.15: Create LAN File Source	.69
Figure 6.16: Manage Mail Source	
Figure 6.17: Create Mail Source	
Figure 6.18: Manage WebDAV Source	
Figure 6.19: Create WebDAV Source	
Figure 7.1: Manage Advance Database Schema	
Figure 7.2: Create Advance Database Schema	
Figure 7.3: Select Schema	
Figure 7.4: Select Tables	
Figure 7.5: Select Columns and Primary Key	
Figure 7.6: Generate Query	
Figure 7.7: Create Child Table	
Figure 7.8: Select Column, Primary and Related Keys	
Figure 7.9: Add Related Key	
Figure 7.10: Manage Advance Positional Schema	
Figure 7.11: Create Advance Positional Schema	
Figure 7.12: Select Data Dictionary	
Figure 7.13: Create Record Definition using Data Dictionary	
Figure 7.14: Create Record Definition	.94
Figure 7.15: Skipped and Unskipped Fields in the Data File	.96
Figure 7.16: Create Record Hierarchy Definition	.97
Figure 7.17: Create Root Record	
Figure 7.18: Create Child Record	.99
Figure 7.19: Create another Child Record	.99
Figure 7.20: Change Advanced Properties	100
Figure 7.21: Defining Field Positions Non-Sequentially	102
Figure 7.22: Edit Advance Positional Schema	
Figure 7.23: Print-Friendly Page	104
Figure 7.24: Sample Advanced Text File	105
Figure 7.25: Manage Advance Text Schema	
Figure 7.26: Create Advance Text Schema	106
Figure 7.27: Create Record Definition	
Figure 7.28: Create Record Hierarchy Definition	110
Figure 7.29: Create Root Record	111
Figure 7.30: Create Child Record	112
Figure 7.31: Create another Child Record	112
Figure 7.32: Manage Database Schema	113
Figure 7.33: Create Database Schema	114
Figure 7.34: Create Database Info	
Figure 7.35: Select Schema	
Figure 7.36: Select Tables	116
Figure 7.37: Select Table Column(s)	
Figure 7.38: Advanced Properties of Database Schema	
Figure 7.39: Manage EDI Schema	
Figure 7.40: Create EDI Schema	
Figure 7.41: Select EDI Specification	



Figure 7.42: Populated Create EDI Schema screen	
Figure 7.43: Edit EDI Schema	
Figure 7.44: Tree Representation of Schema XSD	125
Figure 7.45: Expand Root Node	126
Figure 7.46: Expand Parent Node	127
Figure 7.47: Remove Child Node	128
Figure 7.48: Saved Manipulation	129
Figure 7.49: Manage Excel Schema	130
Figure 7.50: Create Excel Schema	131
Figure 7.51: Upload file	132
Figure 7.52: Specify Start Row and Start Column No	132
Table 7.3: Currencies Supported by Excel Schema	134
Figure 7.53: View Advanced Properties of Excel Schema	135
Figure 7.54: View Advanced Properties of Excel Schema	137
Figure 7.55: Policy Details	138
Figure 7.56: XML to map Field Name with Data Header	
Figure 7.57: Sample Process Flow	
Figure 7.58: Context Target Properties	
Figure 7.59: PutContextVar Properties	
Figure 7.60: Edit Context Variables	
Figure 7.61: Context Variable Information	
Figure 7.62: Manage Positional Schema	
Figure 7.63: Create Positional Schema	
Figure 7.64: Uploaded File	
Figure 7.65: Advanced Properties of Positional Schema	
Figure 7.66: Manage Text Schema	
Figure 7.67: Create Text Schema	
Figure 7.68: Uploaded File	
Figure 7.69: Manage Word Schema	
Figure 7.70: Create Word Schema	
Figure 7.71: Download Word Schema Definition File	
Figure 7.72: Manage XML Schema	
Figure 7.73: Create XML Schema	
Figure 7.74: Advanced Properties of XML Schema	
Figure 7.75: Edit Text Schema	
Figure 7.76: Test Schema	
Figure 7.77: Test Schema	
Figure 7.78: Manage XML Validator	
Figure 7.79: Create XML Validator	
Figure 8.1: Manage Advanced Database Target	
Figure 8.2: Create Advanced Database Target	
Figure 8.3: Manage Database Target	
Figure 8.4: Create Database Target	
Figure 8.5: Manage File Target	
Figure 8.6: Create File Target	
Figure 8.7: Manage FTP Target	
Figure 8.8: Create FTP Target	
Figure 8.9: Manage HTTP Target	
Figure 8.10: Create HTTP Target	
	0



Figure 8.11: Manage JMS Target	179
Figure 8.12: Create JMS Target	180
Figure 8.13: Manage LAN File Target	182
Figure 8.14: Create LAN File Target	182
Figure 8.15: Manage Mail Target	184
Figure 8.16: Create Mail Target	185
Figure 8.17: Manage WebDAV Target	187
Figure 8.18: Create WebDAV Target Activity	188
Figure 9.1: Manage Security Policy	191
Figure 9.2: Create Security Policy	191
Figure 9.3: Define Message Level Security for Outgoing Message	193
Figure 9.4: Define Message Level Security for Incoming Message	195
Figure 9.5: Manage Web Service Consumer Activity	197
Figure 9.6: Create Web Service Consumer Activity	197
Figure 9.7: Search a Web Service	198
Figure 9.8: Web Service search result	198
Figure 9.9: Select Web Service Operation	199
Figure 9.10: Enter Input XML	200
Figure 9.11: Select Security Policy	202
Figure 9.12: Locate WSDL	204
Figure 9.13: Upload WSDL File	204
Figure 9.14: Uploaded WSDL File	205
Figure 9.15: Select Web Service Operation	206
Figure 9.16: Enter Input and Output Parameters	207
Figure 9.17: Define WS-Addressing Parameter	209
Figure 9.18: Manage Web Service Provider Activity	211
Figure 9.19: Create Web Service Provider Activity	211
Figure 9.20: Manage Web Service Provider (asynchronous web service)	213
Figure 10.1: Manage Data Mapping	215
Figure 10.2: Create Data Mapping	215
Figure 10.3: Data Mapper Applet	217
Figure 10.4: Select Schema	223
Figure 10.5: Source and Target Schema Elements	225
Figure 10.6: Select Search Element from Actions Menu	226
Figure 10.7: Element Search Dialog Box	226
Figure 10.8: Enter Parameters in Element Search Dialog Box	227
Figure 10.9: Element Match Found	227
Figure 10.10: Multiple Matches Found	228
Figure 10.11: Warning Message	
Figure 10.12: Map Source and Target Element using Drag and Drop Approach	
Figure 10.13: Map Source and Target Elements	230
Figure 10.14: Map Multiple Source and Target Schema Elements	
Figure 10.15: Same Hierarchy and Element Names	
Figure 10.16: Auto Mapper Options	
Figure 10.17: Mapped Elements using Auto Mapper	234
Figure 10.18: Remove Options	
Figure 10.19: Same Hierarchy and Element Names	
Figure 10.20: Select Add Custom Map Options	
Figure 10.21: Custom Auto Map Options Dialog box	238



Figure 10.22:	Add Data Dialog box	238
Figure 10.23:	Added Entry for Custom Auto Map	239
Figure 10.24:	Select Connect Matching Children	240
	Connect Matching Children Options	
	Source and Target elements are mapped	
	Elements of Source and Target Schema	
-	Select Add Value Map Option	
	Value Map Options Dialog box	
	Add Value Map	
	Paste Mapping Options	
	Elements of Source and Target Schema	
	Select Import Mapping Option	
0	Import Mapping Dialog	
	Mapping Imported	
•	Select Target Element	
	Select Source Element	
	Select Second Source Element	
	Add Comments (Mapping)	
•	Exit from Data Mapper	
•	Save Mapping Object	
	Mapping XSL	
0	View Mapping XML	
•	Debugger screen	
	Generate Mockup Data	
	Output XSL	
	Data Viewer	
	Attach Source	
	Source records in Grid View	
	Pop-up message	
	Tree View	
	Records in Tree View	
	Error Record	
	Target Records in Grid View	
Figure 10.55:	Target Panel in expanded mode	264
	Mapping Information Document	
0	Schema Information	
0	Detailed Mapping Information	
0	View Data Mapping	
	Data Mapper in Read-Only Mode	
	Advanced Properties	
•	Splitter XPath Details	
	Splitter Xpath Details(Enable Quick Splitting)	
	Splitter XPath in Mapping XML	
	Remove Splitter XPath Details	
	Merger XPath Details	
	Remove Merger XPath Details	
	Assign Streams	
•	Remove Options (Particular Element)	
Figure 10.70:	Create Context Schema	.279



Figure 10.71: Add Variables
Figure 10.72: Import Context Variables
Figure 10.73: Load Context Variable
Figure 10.74: Map elements
Figure 10.75: Change streaming
Figure 10.76: Add a Constant Node
Figure 10.77: Enter Constant Value
Figure 10.78: Add Div Sub-Function Node
Figure 10.79: Create Links between Nodes for Mapping Elements using Div Function287
Figure 10.80: Add Concat Sub-Function Node
Figure 10.81: Create Links between Nodes for Mapping Elements using Concat Function
Figure 10.82: Add Date-Difference Sub-Function Node
Figure 10.83: Create Links between Nodes for Mapping Elements using Date-Difference
Function
Figure 10.84: Add Sum Sub-Function Node
Figure 10.85: Create Links between Nodes for Mapping Elements using Sum Function
Figure 10.86: Add Greater Than or Equal To Boolean Function Node
Figure 10.87: Create Links between Nodes for Mapping Elements using Greater Than
Equal To Function
Figure 10.88: Add IF Conditional Function Node
Figure 10.89: Creating Links between Nodes for Mapping Elements using IF Conditional
Function
Figure 10.90: Create Local Variable
Figure 10.91: Mapping Set-Context to Local Variable
Figure 10.92: Context Variables Pane
Figure 10.93: Enter Context Variable Value
Figure 10.94: Set-Context Node
Figure 10.95: Create Links between Nodes for Mapping Set-Context Function to Target
Element
Figure 10.96: Add DBQuery Sub-Function Node
Figure 10.97: Connection Info Variable in Mapping Graph Area
Figure 10.98: Create Links between Nodes for Mapping DBQuery Function to Target
Element
Figure 10.99: Syntax for Concat Sub-Function
Figure 10.100: Parameters of the Concat Syntax
Figure 10.101: Adding Namespace
Figure 10.102: Select Namespace
Figure 10.103: Manage XSL Template
Figure 10.104: Parameter Dialog Box
Figure 10.105: Parameters Added in XSL Template
Figure 10.106: Call XSL Template Node
Figure 10.107: Create Links between Nodes for Mapping Elements using XSL Template
Figure 10.108: Global Variable Pane
Figure 10.109: Enter Name, Value and Comments of Global Variable
Figure 10.110: Alert Message
Figure 10.111: Comment in Mapping XSL



Figure 10.112:	Right-Click Menu of Elements in Parameter Panel	337
Figure 10.113:	Confirm Delete of Global Variable	337
Figure 10.114:	Add Global Variable Node	338
Figure 10.115:	Local Variable Pane	340
Figure 10.116:	Enter Name, Value and Comment for Local Variable	341
	Add Local Variable Node	
Figure 10.118:	Custom Methods Pane	345
Figure 10.119:	Add Custom Method	346
Figure 10.120:	Warning for Adding more than 4 Parameters	346
	Custom Method added to Parameters Panel	
Figure 10.122:	Add Custom Method Node	348
Figure 10.123:	Create Links between Nodes	349
	Global Methods Node	
Figure 10.125:	List of Class Files in Custom Classes Folder	351
	Custom Methods in a Custom Class	
Figure 10.127:	Key Functions Tab	354
Figure 10.128:	Key Added to Parameters Panel	355
	Map Source and Target Elements	
	Key Function	
Figure 10.131:	Map Key Function Node to Target Element	358
	Connection Info Variable Pane	
	Enter Connection Variable Value	
	Properties Pane	
	Source Element in For Each Property	
	Enter Comment	
	Sample Input XML	
	Output XML	
	Apply Template	
	Sorting Rules Dialog Box	
	Checking Apply Filter Checkbox	
	Confirm Remove Clone	
•	Confirm Remove Schema	
	Select Custom XSL Before Option	
•	Enter Custom XSL Code	
	Select Global Custom XSL Before Option	
	Enter Global Custom XSL Code	
0	Custom XSL Code in Mapping XSL	
	Select Root Element	
•	Confirm Change of Root Element	
•	Add Namespace Prefix	
	Select Extension Element	
0	Confirm Change of Extension Element	
•	Manage Record to Record Service	
	Create Record to Record Service	
0	Sample Java Script	
0	anage Custom Plugin	
	eate Custom Plugin	
0	ample JAVA Script	
•	anage Native Call	
<u> </u>	<b>.</b>	



Figure 11.5: Create Native Call	
Figure 12.1: Manage Database Polling Service	. 392
Figure 12.2: Create Database Polling Service	. 393
Figure 12.3: Manage File Polling Service	. 396
Figure 12.4: Create File Polling Service	. 397
Figure 12.5: Manage FTP Polling Service	. 400
Figure 12.6: Create FTP Polling Service	. 401
Figure 12.7: Manage Mail Polling Service	. 404
Figure 12.8: Create Mail Polling Service	. 405
Figure 13.1: Manage Database Driver	. 409
Figure 13.2: Create Database Driver	. 409
Figure 13.3: Browse Database Jar	. 410
Figure 13.4: Select Jar File	. 411
Figure 13.5: Jar Files Uploaded	. 411
Figure 13.6: Uploaded Driver Jar Files	. 412
Figure 13.7: Select Database Driver Main Class Name	. 412
Figure 13.8: Manage Database Info	. 414
Figure 13.9: Create Database Info	. 414
Figure 13.10: Define Server URL	. 415
Figure 13.11: Defined Database Server URL	. 416
Figure 13.12: Manage JMS Provider	. 418
Figure 13.13: Create JMS Provider	. 418
Figure 13.14: Uploaded Provider Jar Files	. 419
Figure 13.15: Manage Manage MLLP Activity	
Figure 13.16: Create MLLP Activity	. 422
Figure 13.17: Manage MLLP Activity	. 424
Figure 13.18: Create MLLP Activity	. 425
Figure 13.19: Manage MLLP Activity	. 427
Figure 13.20: Manage MLLP Activity	. 427
Figure 14.1: Manage Context Download	. 429
Figure 14.2: Create Context Download	
Figure 14.3: Map Context Variable	. 430
Figure 14.4: Expand Schema	. 431
Figure 14.5: Enter Variable Name	. 431
Figure 14.6: Map Schema Element with Variable	. 432
Figure 14.7: Apply Map	. 432
Figure 14.8: Manage Context Upload	. 434
Figure 14.9: Create Context Upload	. 434
Figure 14.10: Manage Stored Procedure	. 436
Figure 14.11: Create Stored Procedure	. 437
Figure 14.12: Select Stored Procedure	. 438
Figure 14.13: View Parameters	. 439
Figure 14.14: Manage Stored Procedure	. 439
Figure 14.15: Manage Mail Notification	. 442
Figure 14.16: Create Mail Notification	
Figure 15.1: Manage Custom Report	. 447
Figure 15.2: Create Custom Report Activity	
Figure 15.3: Select Jasper File	
Figure 15.4: Select Jasper File	. 449



Figure 15.5: Jasper File Uploaded	449
Figure 15.6: Uploaded Jasper Files in Create Custom Report	450
Figure 15.7: Define Jasper Report Parameters	
Figure 15.8: Manage Dashboard Component	452
Figure 15.9: Create Dashboard Component	
Figure 15.10: Select Table	453
Figure 15.11: Select Columns for Bar Chart	454
Figure 15.12: Select Fields	456
Figure 15.13: Manage Dashboard Design	459
Figure 15.14: Creating Dashboard Design	459
Figure 15.15: View Dashboard	461
Figure 16.1: Manage Activity	462
Figure 16.2: Enter Search Criteria	463
Figure 16.3: View Activity Properties	465
Figure 16.4: Edit Activity	466
Figure 16.5: Delete an Activity	467
Figure 16.6: View Revision History	
Figure 16.7: View Dependant Activities	469
Figure 16.8: View Related Activities	469
Figure 16.9: View Advanced Properties	471
Figure 17.1: Process Designer Applet	474
Figure 17.2: View Process Flow XML	
Figure 17.3: Preferences	481
Figure 17.4: Manage Process Flow	483
Figure 17.5: Create Process Flow	484
Figure 17.6: Process Flow's Advanced Properties	486
Figure 17.7: Process Designer	
Figure 17.7: Process Designer Figure 17.8: Dragging BPMN Activity into Graph Canvas	487
	487 488
Figure 17.8: Dragging BPMN Activity into Graph Canvas	487 488 488
Figure 17.8: Dragging BPMN Activity into Graph Canvas Figure 17.9: Right-Clicking an Activity	487 488 488 489
Figure 17.8: Dragging BPMN Activity into Graph Canvas Figure 17.9: Right-Clicking an Activity Figure 17.10: Displaying Name of Activity	487 488 488 489 489
Figure 17.8: Dragging BPMN Activity into Graph Canvas Figure 17.9: Right-Clicking an Activity Figure 17.10: Displaying Name of Activity Figure 17.11: Dragging BPMN Gateway into Graph Canvas	487 488 488 489 489 489
Figure 17.8: Dragging BPMN Activity into Graph Canvas Figure 17.9: Right-Clicking an Activity Figure 17.10: Displaying Name of Activity Figure 17.11: Dragging BPMN Gateway into Graph Canvas Figure 17.12: Connecting BPMN Elements	487 488 488 489 489 489 490 490
Figure 17.8: Dragging BPMN Activity into Graph Canvas Figure 17.9: Right-Clicking an Activity Figure 17.10: Displaying Name of Activity Figure 17.11: Dragging BPMN Gateway into Graph Canvas Figure 17.12: Connecting BPMN Elements Figure 17.13: Connecting BPMN Elements	487 488 488 489 489 489 490 490 491
Figure 17.8: Dragging BPMN Activity into Graph Canvas Figure 17.9: Right-Clicking an Activity Figure 17.10: Displaying Name of Activity Figure 17.11: Dragging BPMN Gateway into Graph Canvas Figure 17.12: Connecting BPMN Elements Figure 17.13: Connecting BPMN Elements Figure 17.14: Selecting Adeptia Server Activity	487 488 488 489 489 490 490 491 492
<ul> <li>Figure 17.8: Dragging BPMN Activity into Graph Canvas</li> <li>Figure 17.9: Right-Clicking an Activity</li> <li>Figure 17.10: Displaying Name of Activity</li> <li>Figure 17.11: Dragging BPMN Gateway into Graph Canvas</li> <li>Figure 17.12: Connecting BPMN Elements</li> <li>Figure 17.13: Connecting BPMN Elements</li> <li>Figure 17.14: Selecting Adeptia Server Activity</li> <li>Figure 17.15: Selecting Adeptia Server Activity</li> </ul>	487 488 488 489 489 490 490 491 492 492
Figure 17.8: Dragging BPMN Activity into Graph CanvasFigure 17.9: Right-Clicking an ActivityFigure 17.10: Displaying Name of ActivityFigure 17.11: Dragging BPMN Gateway into Graph CanvasFigure 17.12: Connecting BPMN ElementsFigure 17.13: Connecting BPMN ElementsFigure 17.14: Selecting Adeptia Server ActivityFigure 17.15: Selecting Adeptia Server ActivityFigure 17.16: Attaching Adeptia Server activity	487 488 488 489 489 490 490 491 492 492 493
Figure 17.8: Dragging BPMN Activity into Graph CanvasFigure 17.9: Right-Clicking an ActivityFigure 17.10: Displaying Name of ActivityFigure 17.11: Dragging BPMN Gateway into Graph CanvasFigure 17.12: Connecting BPMN ElementsFigure 17.13: Connecting BPMN ElementsFigure 17.14: Selecting Adeptia Server ActivityFigure 17.15: Selecting Adeptia Server ActivityFigure 17.16: Attaching Adeptia Server activityFigure 17.17: Adeptia Server activity name in BPMN element	487 488 488 489 489 490 490 490 491 492 492 493 493
Figure 17.8: Dragging BPMN Activity into Graph CanvasFigure 17.9: Right-Clicking an ActivityFigure 17.10: Displaying Name of ActivityFigure 17.11: Dragging BPMN Gateway into Graph CanvasFigure 17.12: Connecting BPMN ElementsFigure 17.13: Connecting BPMN ElementsFigure 17.14: Selecting Adeptia Server ActivityFigure 17.15: Selecting Adeptia Server ActivityFigure 17.16: Attaching Adeptia Server activityFigure 17.17: Adeptia Server activityFigure 17.18: Attaching Adeptia Server activity	487 488 488 489 489 490 490 490 491 492 493 493 493
<ul> <li>Figure 17.8: Dragging BPMN Activity into Graph Canvas</li> <li>Figure 17.9: Right-Clicking an Activity</li> <li>Figure 17.10: Displaying Name of Activity</li> <li>Figure 17.11: Dragging BPMN Gateway into Graph Canvas</li> <li>Figure 17.12: Connecting BPMN Elements</li> <li>Figure 17.13: Connecting BPMN Elements</li> <li>Figure 17.14: Selecting Adeptia Server Activity</li> <li>Figure 17.15: Selecting Adeptia Server Activity</li> <li>Figure 17.16: Attaching Adeptia Server activity</li> <li>Figure 17.17: Adeptia Server activity name in BPMN element</li> <li>Figure 17.18: Attaching Adeptia Server activity</li> <li>Figure 17.19: Edit Activity Properties</li> </ul>	487 488 488 489 489 490 490 490 491 492 492 493 493 494
<ul> <li>Figure 17.8: Dragging BPMN Activity into Graph Canvas</li> <li>Figure 17.9: Right-Clicking an Activity</li> <li>Figure 17.10: Displaying Name of Activity</li> <li>Figure 17.11: Dragging BPMN Gateway into Graph Canvas</li> <li>Figure 17.12: Connecting BPMN Elements</li> <li>Figure 17.13: Connecting BPMN Elements</li> <li>Figure 17.14: Selecting Adeptia Server Activity</li> <li>Figure 17.15: Selecting Adeptia Server Activity</li> <li>Figure 17.16: Attaching Adeptia Server activity</li> <li>Figure 17.18: Attaching Adeptia Server activity</li> <li>Figure 17.19: Edit Activity Properties</li> <li>Figure 17.20: Enter Comments (Process Flow)</li> </ul>	487 488 488 489 489 490 490 490 491 492 493 493 493 493 495
Figure 17.8: Dragging BPMN Activity into Graph CanvasFigure 17.9: Right-Clicking an ActivityFigure 17.10: Displaying Name of ActivityFigure 17.11: Dragging BPMN Gateway into Graph CanvasFigure 17.12: Connecting BPMN ElementsFigure 17.13: Connecting BPMN ElementsFigure 17.14: Selecting Adeptia Server ActivityFigure 17.15: Selecting Adeptia Server ActivityFigure 17.16: Attaching Adeptia Server activityFigure 17.17: Adeptia Server activityFigure 17.18: Attaching Adeptia Server activityFigure 17.19: Edit Activity PropertiesFigure 17.20: Enter Comments (Process Flow)Figure 17.21: Save Process Flow	487 488 488 489 490 490 490 491 492 492 493 493 493 495 496
Figure 17.8: Dragging BPMN Activity into Graph Canvas Figure 17.9: Right-Clicking an Activity Figure 17.10: Displaying Name of Activity Figure 17.11: Dragging BPMN Gateway into Graph Canvas Figure 17.12: Connecting BPMN Elements Figure 17.13: Connecting BPMN Elements Figure 17.14: Selecting Adeptia Server Activity Figure 17.15: Selecting Adeptia Server Activity Figure 17.16: Attaching Adeptia Server activity Figure 17.17: Adeptia Server activity Figure 17.18: Attaching Adeptia Server activity Figure 17.19: Edit Activity Properties Figure 17.20: Enter Comments (Process Flow) Figure 17.21: Save Process Flow Figure 17.22: Changing Transformer Type	487 488 488 489 489 490 490 491 492 492 493 493 493 494 495 496 497
Figure 17.8: Dragging BPMN Activity into Graph Canvas Figure 17.9: Right-Clicking an Activity Figure 17.10: Displaying Name of Activity Figure 17.11: Dragging BPMN Gateway into Graph Canvas Figure 17.12: Connecting BPMN Elements Figure 17.13: Connecting BPMN Elements Figure 17.14: Selecting Adeptia Server Activity Figure 17.15: Selecting Adeptia Server Activity Figure 17.16: Attaching Adeptia Server activity Figure 17.17: Adeptia Server activity name in BPMN element Figure 17.18: Attaching Adeptia Server activity Figure 17.19: Edit Activity Properties Figure 17.20: Enter Comments (Process Flow) Figure 17.22: Changing Transformer Type Figure 17.23: Edit Process Flow	487 488 488 489 490 490 490 491 492 493 493 493 494 495 496 497 498
Figure 17.8: Dragging BPMN Activity into Graph Canvas Figure 17.9: Right-Clicking an Activity Figure 17.10: Displaying Name of Activity Figure 17.11: Dragging BPMN Gateway into Graph Canvas Figure 17.12: Connecting BPMN Elements Figure 17.13: Connecting BPMN Elements Figure 17.14: Selecting Adeptia Server Activity Figure 17.15: Selecting Adeptia Server Activity Figure 17.16: Attaching Adeptia Server activity Figure 17.17: Adeptia Server activity name in BPMN element Figure 17.18: Attaching Adeptia Server activity Figure 17.19: Edit Activity Properties Figure 17.20: Enter Comments (Process Flow) Figure 17.21: Save Process Flow Figure 17.23: Edit Process Flow Figure 17.24: Test Process Flow	487 488 488 489 490 490 490 490 491 492 493 493 493 493 494 495 496 498 498
Figure 17.8: Dragging BPMN Activity into Graph Canvas Figure 17.9: Right-Clicking an Activity Figure 17.10: Displaying Name of Activity Figure 17.11: Dragging BPMN Gateway into Graph Canvas Figure 17.12: Connecting BPMN Elements Figure 17.13: Connecting BPMN Elements Figure 17.14: Selecting Adeptia Server Activity Figure 17.15: Selecting Adeptia Server Activity Figure 17.16: Attaching Adeptia Server activity Figure 17.17: Adeptia Server activity name in BPMN element Figure 17.18: Attaching Adeptia Server activity Figure 17.19: Edit Activity Properties Figure 17.20: Enter Comments (Process Flow) Figure 17.21: Save Process Flow Figure 17.23: Edit Process Flow Figure 17.24: Test Process Flow Figure 17.25: Sample XML	487 488 488 489 490 490 490 490 491 492 493 493 493 493 493 495 496 497 498 498 499
Figure 17.8: Dragging BPMN Activity into Graph Canvas Figure 17.9: Right-Clicking an Activity Figure 17.10: Displaying Name of Activity Figure 17.11: Dragging BPMN Gateway into Graph Canvas Figure 17.12: Connecting BPMN Elements Figure 17.13: Connecting BPMN Elements Figure 17.14: Selecting Adeptia Server Activity Figure 17.15: Selecting Adeptia Server Activity Figure 17.16: Attaching Adeptia Server activity Figure 17.17: Adeptia Server activity name in BPMN element Figure 17.18: Attaching Adeptia Server activity Figure 17.19: Edit Activity Properties Figure 17.20: Enter Comments (Process Flow) Figure 17.21: Save Process Flow Figure 17.23: Edit Process Flow Figure 17.24: Test Process Flow Figure 17.25: Sample XML Figure 17.26: Select XML File	487 488 488 489 490 490 491 492 492 493 493 493 493 493 495 495 496 497 498 499 499 500



Figure 17.30:	Disable Validation	. 502
Figure 17.31:	Multiple Selections	. 503
Figure 17.32:	List of Actions in Adeptia Server	. 509
Figure 17.33:	Dragging Action to Graph Canvas	. 510
	Action's Properties	
Figure 17.35:	Process Flow Variable Panel	. 511
	Create Process Flow Variable	
Figure 17.37:	Process Flow Variable created	. 512
Figure 17.38:	Drag Put-Context-Var action in Graph Canvas	. 512
Figure 17.39:	Properties of Put-Context-Var action	. 513
Figure 17.40:	Edit Context Variables	. 514
Figure 17.41:	Context Variable Information	. 515
Figure 17.42:	Context Variable Added	. 516
Figure 17.43:	Drag Context Source	. 517
Figure 17.44:	Properties of Context Source	. 518
Figure 17.45:	Connect Put-Context-Var to activity	. 519
Figure 17.46:	Properties of Put-Context-Var	. 520
Figure 17.47:	Usage Scenario	. 521
Figure 17.48:	Overriding an Activity using Custom Plugin	. 521
	Sample Java Code used to Override a Schema Activity	
Figure 17.50:	Sample Java Code used to Override Activities	. 522
	Connect Put-Context-Var to activity	
Figure 17.52:	Properties of Put-Context-Var	. 523
Figure 17.53:	Context Variable Details for Overriding an Activity	. 524
	Connect put-context-var to Human Workflow task	
Figure 17.55:	Context Variable Details for Overriding email subject	. 528
Figure 17.56:	Context Variable Details for Overriding email subject	. 529
	Using Record Queue Processor	
Figure 17.58:	Properties of RecordQueueProducer	. 531
Figure 17.59:	Properties of RecordQueueReceiver	. 533
Figure 17.60:	Drag Gateway Element to Graph Canvas Area	. 535
Figure 17.61:	Connecting Elements	. 535
	Change Gateway Element Properties	
	Condition Wizard	
Figure 17.64:	Select Process Flow Condition Type	. 536
Figure 17.65:	Activity Attributes Condition	. 536
Figure 17.66:	Other Condition Process Details	. 538
Figure 17.67:	Enter Java Condition	. 540
Figure 17.68:	Condition Wizard	. 541
Figure 17.69:	Rule Wizard	. 542
Figure 17.70:	New Rule Information	. 544
Figure 17.71:	Added Rules	. 545
Figure 17.72:	Define Sequence Flow Ordering	. 546
Figure 17.73:	Sequence Flow Ordering	. 547
Figure 17.74:	Multiple Stream Dialog Box	. 548
Figure 17.75:	New Stream Added	. 549
	Stream Created	
Figure 17.77:	Showing Multiple Streams in Process Flow	. 551
Figure 17.78:	Creating Default Stream	. 553



Figure 17.79: Scenario	. 554
Figure 17.80: Stream Selector	. 554
Figure 17.81: Drag Stream Selector to Graph Canvas	. 555
Figure 17.82: Connect Activities with Stream Selector Node	. 555
Figure 17.83: Repeater Service Node	. 556
Figure 17.84: Connect Activities	. 556
Figure 17.85: Create Second Stream	
Figure 17.86: Repeater Node with Multiple Stream	
Figure 17.87: Scenario	
Figure 17.88: Use Error Intermediate Event	
Figure 17.89: Select Add Intermediate Event	
Figure 17.90: Error Immediate Event Attached	
Figure 17.91: Drag Another Activity	
Figure 17.92: Connect Activities	
Figure 17.93: Creating Exception Handler Script	
Figure 17.94: Service Exception Dialog Box	
Figure 17.95: Drag Compression Activity	
Figure 17.96: Connect Activities	
Figure 17.97: Compression Activity Properties	
Figure 17.98: Scenario	
Figure 17.99: Custom Report Node	
Figure 17.100: Connect Activities	
Figure 17.101: Attaching End Process	
Figure 17.102: Selecting Mail Notification	
Figure 17.103: Select PDF Type	
Figure 17.104: Save Box	
Figure 17.105: Changing Mode	
Figure 17.106: Process Designer Login	
Figure 17.107: Select User Group.	
Figure 17.108: Process Flow Executed	
Figure 17.109: View Process Flow Log	
Figure 17.110: Create Event Registry	
Figure 18.1: Manage Calendar Event	
Figure 18.2: Create Calendar Event	
Figure 18.3: Manage Database Event	
Figure 18.4: Create Database Event	
Figure 18.5: Manage Event Registry	
Figure 18.6: Create Event Registry	
Figure 18.7: Manage File Event	
Figure 18.8: Create File Event	
Figure 18.9: Manage FTP Event	
Figure 18.10: Create FTP Event	
Figure 18.11: Add Include Criteria List	
Figure 18.12: File Include Criteria List	
Figure 18.13: Manage HTTP Trigger	
Figure 18.14: Create Http Trigger	
Figure 18.15: Manage JMS Event	
Figure 18.16: Create JMS Event	
Figure 18.17: Manage Mail Event	. 370



Figure 18.18:	Create Mail Event	
Figure 18.19:	Manage Timer Event	600
Figure 18.20:	Create Timer Event	601
Figure 18.21:	Web Service Trigger	603
Figure 18.22:	Sample Input Document used to Trigger Process Flow	603
Figure 18.23:	Manage File Event	604
Figure 18.24:	Event's Advanced Properties	605



# 22 TABLE OF TABLES

Table 3.1: Form Types	16
Table 7.1: Definition File Methods used for Creating Schemas	78
Table 7.2: Supported Datatypes	133
Table 7.4: Selection Process of Value for Upload XSD/DTD/XML from Field	156
Table 8.1: Record Count Type Values	
Table 8.2: Effect on Database based on the selected Database Operation	
Table 9.1: Web Services	196
Table 9.2: Value for WS Consumer Activity	201
Table 9.3: Input Parameter Value for WS Consumer Activity	208
Table 10.1: Options of Menu Bar	217
Table 10.2: Options of Tabs Panel	219
Table 10.3: Options of Tool Bar	219
Table 10.4: Tabs of Mapping Graph Area	220
Table 10.5: Buttons of Mapping Graph Area	221
Table 10.6: Parameters Listed in the Parameters Panel	222
Table 10.7: Legends of Elements	225
Table 10.8: Suffixes of Source and Target Elements	250
Table 10.9 : Options of the Debugger Screen	
Table 10.10: List of schema whose records can be shown in Data Viewer	258
Table 10.11: Fields of Assign Streams Screen	276
Table 10.12: Sub-Functions of Math Mapping Function	285
Table 10.13 : Sub-Functions of String Mapping Function	287
Table 10.14: Sub-Functions of Date Mapping Function	291
Table 10.15: Sub-Functions of Aggregation Mapping Function	294
Table 10.16: Sub-Functions of Conditional Mapping Function	
Table 10.17: Conditional Functions ('If' and 'When')	299
Table 10.18: Sub-Functions of Axis Mapping Function	307
Table 10.19: Sub-Functions of Boolean Mapping Function	
Table 10.20: Sub-Functions of Context Mapping Function	311
Table 10.21: Sub-Function of DB Mapping Function	321
Table 10.22: Properties of a Target Element	
Table 12.1: Trigger Type Selection Values	
Table 12.2: Expressions used in File Include Criteria and File Exclude Criteria	
Table 13.1: Jar Files for Database Servers	410
Table 13.2: Driver Main Class Names for Database Servers	
Table 13.3: Server URL for Database Servers	
Table 14.1: Notification Criteria	
Table 16.1: Wild Card characters supported by Adeptia	463
Table 16.2: Owner Permissions	
Table 16.3: Group Permissions	
Table 16.4: Other Permissions	472
Table 17.1: Menu Bar Options	
Table 17.2: Tool Bar Options	
Table 17.3: BPMN Graphical Elements	
Table 17.4: Edit Preferences	
Table 17.5: Keyboard Shortcuts	482



Table 17.6: Types of Logging Levels	484
Table 17.7: Options for Repository File Retention	485
Table 17.8: List of Priorities and their Description	486
Table 17.9: Actions for a Process Flow	
Table 17.10: Context Source/Target Activity Properties	518
Table 17.11: Arguments used in Java Code	522
Table 17.12: Source Types that can be Overridden	524
Table 17.13: Target Types that can be Overridden	525
Table 17.14: Schema Types that can be Overridden	525
Table 17.15: Polling Types that can be Overridden	526
Table 17.16: Other Activity Types that can be Overridden	526
Table 17.17: Record Queue Producer Properties	531
Table 17.18: Record Queue Receiver Properties	533
Table 17.19: Data Types Supported for Operand Type Value	537
Table 17.20: Data Types Supported for Operand Type Value	542
Table 17.21: Possible Operators for Operands	543
Table 17.22: Rules for Evaluation	
Table 17.23: Rule Operators	545
Table 17.24: Exception Handlers in a Process Flow	560
Table 18.1: Types of Firing Days	575
Table 18.2: Trigger Type Selection Values	
Table 18.3: Expressions used in File Include Criteria and File Exclude Criteria	
Table 18.4: Expiry Criteria	